

Lynwood Quarry Independent Environmental Audit 2023

Audit Report

Prepared for Holcim

March 2024

Lynwood Quarry Independent Environmental Audit 2023

Audit Report

Holcim

E231253 RP#1

March 2024

Version	Date	Prepared by	Approved by	Comments
V1	26 March 2023	Thomas Frankham	Thomas Frankham	Final

Approved by



Thomas Frankham

Associate Environmental Scientist (Lead Auditor Certification No. 207528) 27 March 2024

Level 3 175 Scott Street Newcastle NSW 2300

This report has been prepared in accordance with the brief provided by Holcim and has relied upon the information collected at the time and under the conditions specified in the report. All findings, conclusions or recommendations contained in the report are based on the aforementioned circumstances. The report is for the use of Holcim and no responsibility will be taken for its use by other parties. Holcim may, at its discretion, use the report to inform regulators and the public.

© Reproduction of this report for educational or other non-commercial purposes is authorised without prior written permission from EMM provided the source is fully acknowledged. Reproduction of this report for resale or other commercial purposes is prohibited without EMM's prior written permission.

TABLE OF CONTENTS

1	Intro	duction	2
	1.1	Background	2
	1.2	Audit team	4
	1.3	Audit objectives	4
	1.4	Audit scope	4
	1.5	Audit period	5
2	Audi	t methodology	6
	2.1	Selection and endorsement of audit team	6
	2.2	Audit scope development	6
	2.3	Compliance evaluation	6
	2.4	Site interviews	6
	2.5	Site inspection	7
	2.6	Consultation	7
	2.7	Compliance status descriptors	8
3	Audi	t findings	g
	3.1	Approval and document list	g
	3.2	Compliance performance	g
	3.3	Summary of agency notices, orders, penalty notices or prosecutions	10
	3.4	Non compliances	10
	3.5	Previous audit recommendations	22
	3.6	EMP, sub-plans and compliance documents	28
	3.7	Consultation outcomes	28
	3.8	Complaints	33
	3.9	Incidents	33
	3.10	Actual verses predicted environmental impacts	37
	3.11	Site inspection	37
	3.12	Site interviews	39
	3.13	Opening and closing meetings	40
	3.14	Improvement opportunities	40
	3.15	Key strengths	40
4	Reco	mmendations	42
	4.1	Non-compliances	42

	4.2 Oppor	tunities for improvement	42
5	Conclusion		44
Ap	pendices		
Ар	pendix A	DPHI authorisation of lead auditor	A.1
Ар	pendix B	Consultation records – public authorities	B.1
Ар	pendix C	Consultation records – community	C.1
Ар	pendix D	Audit compliance tables	D.1
Ар	pendix E	Site Inspection Photographs	E.1
Ta	bles		
	ole 1.1	IEA team	4
	ole 2.1	Lynwood Quarry site personnel interviews	7
	ole 2.2	Compliance status descriptors	8
	ole 3.1	Compliance performance	9
	ole 3.2	Non-compliances	11
Tak	ole 3.3	Previous audit recommendations	22
Tak	ole 3.4	Consultation	29
Tak	ole 3.5	Summary of complaints	33
Tak	ole 3.6	Incidents	34
Tak	ole 3.7	Site interviews summary	39
Tak	ole 3.8	Opening and closing meeting attendance	40
Tak	ole 4.1	Recommendations	42
- 1.			
	gures	Lucius ad automorphis laurant	2
	ure 1.1	Lynwood quarry site layout	3
Fig	ure 3.1	Compliance performance	10
Ph	otographs		
Pho	otograph E.1	Water fill point	E.2
Pho	otograph E.2	Water cart in operation	E.2
Pho	otograph E.3	IPC located outside of bunded areas	E.2
Pho	otograph E.4	Pump station	E.2
Pho	otograph E.5	Visual amenity wall	E.3
Pho	otograph E.6	Water supply dam	E.3
Pho	otograph E.7	Excess product stockpile	E.3
Pho	otograph E.8	Amenity bund	E.3
Pho	otograph E.9	Water supply dam	E.3

Photograph E.10	Granite Pit	E.4
Photograph E.11	Granite Pit	E.4
Photograph E.12	Amenity bund plant establishment	E.4
Photograph E.13	Sediment Dam G1 - Spillway	E.4
Photograph E.14	Sediment Dam G1	E.5
Photograph E.15	Water supply dam	E.5
Photograph E.16	Depositional Dust Guage	E.5
Photograph E.17	Sprayed black berry bush	E.5
Photograph E.18	Joarmin Creek	E.6
Photograph E.19	Joarmin Creek	E.6
Photograph E.20	Sediment Dam F	E.6
Photograph E.21	Workshop facilities	E.6
Photograph E.22	Excavator	E.7
Photograph E.23	Bunded oil container	E.7
Photograph E.24	Bunded oil container	E.7
Photograph E.25	Refuelling facilities	E.8
Photograph E.26	Sump	E.8
Photograph E.27	Sump oily water separator	E.8
Photograph E.28	Bunded hydrocarbon storage	E.8
Photograph E.29	Bunded container storages for hydrocarbons	E.9
Photograph E.30	Spill kits	E.9
Photograph E.31	Processing area	E.9
Photograph E.32	Workshop facilities	E.10
Photograph E.33	Administration area	E.10
Photograph E.34	Processing plant and stacker	E.10
Photograph E.35	Conveyors	E.10
Photograph E.36	Processing plant	E.10
Photograph E.37	Enclosed crusher	E.11
Photograph E.38	Active water sprays on processing facility	E.11
Photograph E.39	Stacker and stockpile	E.11
Photograph E.40	Stockpiles	E.11
Photograph E.41	Product stockpiles	E.12
Photograph E.42	Product stockpiles	E.12
Photograph E.43	Dust suppressant and associated pump	E.12
Photograph E.44	Refuelling facility	E.12
Photograph E.45	Sediment Dam E	E.12
Photograph E.46	Sediment E	E.13

Photograph E.47	Truck weight station	E.13
Photograph E.48	Internally bunded area of truck refuelling station	E.13
Photograph E.49	Road vehicle refuelling station	E.13
Photograph E.50	Quarry signage on access road	E.14
Photograph E.51	Quarry blasting signage on access road	E.14

Independent Audit Report Declaration Form

Project name	Lynwood Quarry	
Consent number	DA 128-5-2005	
Description of project	Lynwood hard rock quarry and associated infrastructure	
Project address	Unnamed Road, Marulan NSW 2579	
Proponent	Holcim (Australia) Pty Ltd	
Title of Audit	Lynwood Quarry Independent Environmental Audit 2023	
Date	26 March 24	

I declare that I have undertaken the Independent Audit and prepared the contents of the attached Independent Audit Report and to the best of my knowledge:

- i. the audit has been undertaken in accordance with relevant condition(s) of consent and the *Independent Audit Compliance Requirements* (Department 2019)
- ii. the findings of the audit are reported truthfully, accurately and completely
- iii. I have exercised due diligence and professional judgement in conducting the audit
- iv. I have acted professionally, objectively and in an unbiased manner
- v. I am not related to any proponent, owner or operator of the project neither as an employer, business partner, employee, or by sharing a common employer, having a contractual arrangement outside the audit, or by relationship as spouse, partner, sibling, parent, or child
- vi. I do not have any pecuniary interest in the audited project, including where there is a reasonable likelihood or expectation of financial gain or loss to me or spouse, partner, sibling, parent, or child
- vii. neither I nor my employer have provided consultancy services for the audited project that were subject to this audit except as otherwise declared to the Department prior to the audit
- viii. I have not accepted, nor intend to accept any inducement, commission, gift or any other benefit (apart from payment for auditing services) from any proponent, owner or operator of the project, their employees or any interested party. I have not knowingly allowed, nor intend to allow my colleagues to do so.

Note.

- Under Section 10.6 of the *Environmental Planning and Assessment Act 1979* a person must not include false or misleading information (or provide information for inclusion in) in a report of monitoring data or an audit report produced to the Minister in connection with an audit if the person knows that the information is false or misleading in a material respect. The proponent of an approved project must not fail to include information in (or provide information for inclusion in) a report of monitoring data or an audit report produced to the Minister in connection with an audit if the person knows that the information is materially relevant to the monitoring or audit. The maximum penalty is, in the case of a corporation, \$1 million and for an individual, \$250,000.
- The *Crimes Act 1900* contains other offences relating to false and misleading information: Section 307B (giving false or misleading information maximum penalty 2 years imprisonment or 200 penalty units, or both).

Name of Auditor	Thomas Frankham
Signature	
Qualification	BEnvSc, Certified Lead Environmental Auditor (Exemplar Global - Certification No. 207528)
Company	EMM Consulting
Company address	Level 3, 175 Scott Street, Newcastle NSW 2300

1 Introduction

1.1 Background


Holcim (Australia) Pty Ltd (Holcim) operates the Lynwood Quarry, located at 278 Stoney Creek Road, Marulan NSW 2579, approximately 3 kilometres (km) west of the town of Marulan, and approximately 27 km north-east of Goulburn, in the Goulburn Mulwaree local government area (LGA).

Lynwood Quarry operates under development consent DA 128-5-2005, granted by the Minister for Planning on 21 December 2005 under section 80 of the *Environmental Planning and Assessment Act 1979* (EP&A Act). The consent has been modified five times.

The approved operations at the site include the extraction and processing of hard rock of up to five million tonnes per annum (Mtpa) and transportation of quarry products by road and rail. The operational life of the quarry is forecast to be 30 years, with operations approved till 2038.

The layout of the quarry is illustrated in Figure 1.1.

Lynwood Quarry also operates pursuant to Environment Protection Licence 12939 which authorises scheduled activities being extractive activities and crushing, grinding and separating processes. The permitted scale of the activities is prescribed as >2,000,000 tonnes annual extraction and >2,000,000 tonnes annual processing.



Legend

Approved Project Area
Modification Project Area
Lynwood Infrastructure Area
Approved Disturbance Footprint
Proposed Granite Pit Disturbance Footprint
Lynwood Infrastructure Layout
Proposed Haul Road

Quarry Pit
ESS Emplacement Area

Dam
Proposed Overburden Emplacement Area
Proposed Vegetation Buffer Zone
Proposed Amenity Bund

Overview of the Modification Project

1.2 Audit team

The Independent Environmental Audit (IEA) team includes the team detailed in Table 1.1.

Table 1.1 IEA team

Name	Role	Company	Qualifications	Experience
Thomas Frankham	Lead auditor (Lead Auditor Certification No. 207528)	EMM	BEnvSc, Certified Lead Environmental Auditor (Exemplar Global - Certification No. 207528)	Associate Consultant 12 years' experience
Allan Young	Strategic advisor and project director	EMM	Master of Urban and Regional Planning Registered Environmental Assessment Practitioner Registered Planner (PIA)	Associate Director 27 years' experience

The engagement of Mr Thomas Frankham as lead auditor was endorsed by the Department of Planning, Housing and Infrastructure (DPHI, formerly the Department of Planning and Environment) on 1 December 2023. A copy of the DPHI endorsement is provided within Appendix A.

1.3 Audit objectives

The objective of the IEA is to determine the operational compliance of Lynwood Quarry against the relevant regulatory approvals applicable to the site. The Audit findings are detailed in Section 3.

1.4 Audit scope

The IEA has been completed in accordance with Schedule 5, Condition 11 of development consent DA 92/97 which states:

By 30 September 2017, and every 3 years thereafter, unless the Secretary directs otherwise, the Applicant must commission and pay the full cost of an Independent Environmental Audit of the development. This audit must:

- (a) be conducted by suitably qualified, experienced and independent team of experts whose appointment has been endorsed by the Secretary;
- (b) include consultation with the relevant agencies and the CCC;
- (c) assess the environmental performance of the development and whether it is complying with the relevant requirements in this consent and any relevant EPL and/or Water Licence (including any assessment, plan or program required under these approvals);
- (d) review the adequacy of any approved strategy, plan or program required under the these approvals;
- (e) recommend measures or actions to improve the environmental performance of the development, and/or any assessment, plan or program required under these approvals; and
- (f) be conducted and reported to the satisfaction of the Secretary.

Note: This audit team must be led by a suitably qualified auditor and include experts in any fields specified by the Secretary.

Schedule 5, Condition 12 of DA128-5-2005 also states:

Within 12 weeks of commencing this audit, or as otherwise agreed by the Secretary, the Applicant must submit a copy of the audit report to the Secretary, Council, EPA and any other NSW agency that requests it, together with its response to any recommendations contained in the audit report.

The IEA has also been prepared in accordance with Section 3.3. of the DPHI *Independent Audit – Post Approval Requirements* (May 2020).

1.5 Audit period

The audit period for this IEA covers the period between **30 September 2020 to 1 February 2024**. This represents a period commencing the day after the 2020 IEA site inspection was completed, through to the final day of the 2024 IEA site inspection.

It is noted that this period exceeds 3 years following the previous IEA. This was a result of personal circumstances of the audit team and the date on which EMM consulting was engaged to undertake the IEA. The exceedance of the 3 year period is recorded as a non-compliance within this IEA and discussed further in Section 3.

2 Audit methodology

2.1 Selection and endorsement of audit team

Holcim contacted DPHI on 1 December 2023 seeking endorsement of the proposed audit team. On 1 December 2023, DPHI responded endorsing the audit team (identified in Section 1.2).

DPHI did not identify that any further technical experts required to be engaged to inform the audit.

2.2 Audit scope development

The IEA scope was developed in accordance with the DPE *Independent Audit – Post Approval Requirements* (May 2020).

On 5 December 2023, EMM requested from DPHI confirmation of any parties or agencies that are required to be consulted with as part of the IEA, or if there were any areas of compliance or environmental management that DPHI would like EMM to focus on within the scope of the IEA.

DPHI responded on 11 December 2023, with the list of agencies to consult with and aspects to focus on. These are discussed further in Section 3.7.

2.3 Compliance evaluation

Compliance of the operations of Lynwood Quarry were assessed against the approvals and documents listed in Section 3.1.

The process of compliance evaluation involved the following steps:

- review of all approvals applicable to Lynwood Quarry operations
- development of spreadsheet of all relevant conditions
- site visit including:
 - opening meeting with applicable site personnel (Section 3.13)
 - site inspections (Section 3.11)
 - interviews of relevant site personnel (Section 3.12)
 - closing meeting (Section 3.13)
- requesting additional information from site, where required
- review of all information provided by site, site photos taken during the site inspection (Appendix E) and any notes taken during the site inspection
- further discussions with site personnel, as required.

2.4 Site interviews

Lynwood Quarry personnel interviewed as part of the IEA are noted in Table 2.1.

Table 2.1 Lynwood Quarry site personnel interviews

Name	Role
Wayne Beattie	Operations Manager
Dozie Egeonu	Environment Manager - NSW & ACT
Mohsen Vafaei Fard	Support Services Supervisor

2.5 Site inspection

The site inspection of Lynwood Quarry was completed 1 February 2024. EMM consulting observed the following locations during the site inspection:

- access road
- infrastructure area (including administration area, workshops, fuel storage, waste management area)
- processing plant
- stockpile areas
- rail and road transport load out facilities
- western and eastern excess product emplacement areas
- Lynwood and Southern overburden emplacement areas
- amenity bund
- granite quarry pit
- supply dam
- sediment dams A, E, F, G1.

2.6 Consultation

Consultation was completed with various government agencies and the community consultative committee (CCC), including:

- Department of Planning, Housing and Infrastructure (DPHI, formerly Department of Planning and Environment)
- Environment Protection Authority (EPA)
- Goulburn Mulwaree Council (Council)
- Department of Climate Change, Energy, Environment and Water (DCCEEW) Water
- Department of Primary Industries Fisheries
- all members of the CCC.

A summary of the consultation is included in Section 3.7, with evidence of consultation attached as Appendix B and Appendix C.

2.7 Compliance status descriptors

The compliance status of each compliance requirement in the audit table (Appendix D) has been determined using the relevant descriptors in Table 2.2.

 Table 2.2
 Compliance status descriptors

Status	Description
Compliant	The auditor has collected sufficient verifiable evidence to demonstrate that all elements of the requirement have been complied with within the scope of the audit.
Non-compliant	The auditor has determined that one or more specific elements of the conditions or requirements have not been complied with within the scope of the audit.
Not triggered	A requirement has an activation or timing trigger that has not been met during the temporal scope of the audit being undertaken (may be a retrospective or future requirement), therefore an assessment of compliance is not relevant.

3 Audit findings

3.1 Approval and document list

The approvals and documents audited as part of this IEA include:

- Development Consent DA 128-5-2005 and the statement of commitments
- Environment Protection Licence (EPL) 12939
- Annual Reviews for 2020, 2021, 2022
- environmental management plans (required under DA 128-5-2005)
- non-compliances of the 2020 IEA.

EMM would have also audited the Water Works Approval 10WA102709 (WWA), Water Access Licence 25575 10AL102708 (WAL) and Water Use Approval 10UA119159 (WUA), however, Holcim advised that the water licences where not relied upon during the audit period. No further information was provided in regards to these water licences, noting that water usage is reported in the Annual Reviews being sourced externally to the held licenses.

3.2 Compliance performance

Table 3.1 list the total number of compliance requirements assessed as part of this IEA including the total number of compliant, non-compliant and not triggered conditions.

Figure 3.1 shows the project performance in relation to compliance requirements assessed.

Table 3.1 Compliance performance

Aspect	Number
Compliance requirements	426
Compliant	359
Non-compliant Non-compliant	27
Not triggered	40



Figure 3.1 Compliance performance

3.3 Summary of agency notices, orders, penalty notices or prosecutions

No orders, penalty notices or prosecutions have been issued during the audit period as reported in the Annual Reviews, EPL register or as advised during site interviews.

It is noted that whilst outside the scope of the IEA, in 2021 Lynwood Quarry received two infringement notices against the operations *Environment Protection and Biodiversity Conservation Act* (EPBC Act) approval (EPBC Approval 2012/6560). The offence was identified on 30 July 2021 and infringement notices issued on 9 November 2021. The offences related to Conditions 2, 7, and 8 of the EPBC Approval 2012/6560. Holcim is working with the Commonwealth Government to address the matter.

3.4 Non compliances

A summary of the non-compliances determined as part of the 2023 IEA are provided in Table 3.2.

Table 3.2 Non-compliances

Section	Requirement	Evidence	Findings/recommendations	Unique non-compliance identification number
DA 128-5-2005				
Schedule 2, Condition 13	The Applicant must: (a) provide annual quarry production data to DRG using the standard form for that purpose; and (b) include a copy of this data in	Sighted extractive industry returns for 2019-20 and 2020-21.	It is noted that uploading of 2021-22 extractive industry return has not been possible as the portal is currently not active as advised by correspondence from Department of Regional NSW to Holcim dated 17 October 2022,. This is non-compliance as the report has not been submitted however the issue rests with Department of Regional NSW. NC1 Recommendation:	NC1
	the Annual Review.		Ensure annual quarry data is provided to DRG once portal is active.	
Schedule 3, Condition 3	The Applicant must ensure that the noise generated by the operation of the development does not exceed the criteria in Table 1 at any residence on privately-owned land.	Annual Review 2020, 2021, 2022. 2023 Quarterly Monitoring Reports.	Noise is monitored quarterly at four locations which are representative of the receivers listed in Table 1.	NC2
			2020, 21 and 22 AERs states that four quarterly monitoring events took place within each reporting period and found that review of all documents confirmed that operation noise complied with legislative noise emission requirements.	
			In Sept 2023, a negligible exceedance (1dB) was observed at N1 during the evening monitored period with an estimated quarry contribution of 36 LAeq (15min) dBA against a criteria of 35 LAeq (15min) dBA. The LA1 quarry contribution also exceeded the LA1(1min) (dBA) criteria for all locations but it was noted that LA1 was dominated by birds, road traffic and/or a passing train at each location.	
			NC2 Recommendation:	
			Review noise monitoring locations - should road and traffic noise be considered an issue an alternative location may be appropriate.	

Table 3.2 Non-compliances

Section	Requirement	Evidence	Findings/recommendations	Unique non-compliance identification number
Schedule 3, 12	The Applicant must ensure that dust generated by the development does not cause additional exceedances of the criteria listed in Tables 6-8 at any residence that exists on the date of this consent, or on more than 25 percent of any privately owned land.	Annual Review 2020, 2021, 2022. 2023 environmental monitoring database. Site observations.	It is noted during the site visit minimal dust was noted and active controls in place. It is also noted that DDG6 has been removed as per correspondence to DPE from Holcim dated June 30 2023. A number of dust exceedances were recorded during the audit period, having been reported in the 2020, 2021, 2022 Annual Reviews and evident in the 2023 monitoring database. Majority of incidents involved missed one off sampling events or likely contamination of samples. Notable exceedances are identified below: DDG6 during 2022 exceed the annual average, recording 4.74(g/m2/month). Reported to DPE, likely contamination of samples. HVAS1 missed sampling events a total of 8 times during 2022. Reported to DPE, due to inclement weather and solar power issues.	NC3
			 HVAS1 missed sampling events a total of 8 times during 2023. Reported to DPE, due to inclement weather and solar power issues. 	identification number NC3
			NC3 Recommendations:	
			 Determine root cause of the HVAS failures and appropriately action corrective measures. It is understood that a number of failed sampling events relate to power supply which Lynwood Quarry is currently in the process of improving. However, it is noted that a number of failed sampling attempts related to the run time of the HVAS or the days set. This may be improved by detailed operating procedures to reduce the risk of operator error. 	
			 Review DDG data, should a result be contaminated remove the result from the annual average data set as this appears to be artificially increasing the average values. 	

Table 3.2 Non-compliances

Section	Requirement	Evidence	Findings/recommendations	Unique non-compliance identification number
Schedule 3, 12, 15 (e)	The Applicant must implement the management plan as approved from time to time by the Secretary.	Air Quality Management Plan (August 2023). Annual Review 2020, 2021, 2022. 2023 environmental monitoring database. Site observations.	Monitoring methods described in current and revised AQMPs (both sighted). Site observations identified air quality management measures are being implemented. It is however noted that during the audit period monitoring a number of failed monitoring events and incidents occurred as noted under Schedule 3, Condition 12.	NC4
		Site observations.	NC4 Recommendation:	
			As per NC3.	
Schedule 3, 19 (a)	Ensure that the water collected in the Sediment Dams is pumped to the supply dams as soon as practicable;	Water Management Plan (November 2020). Site observations.	Water Management Plan (November 2020), Section 6.1.2 notes sediment dams (SDs) will be emptied via pump or gravity systems after rainfall events. During site inspection Sediment Dam F and Sediment Dam E were inspected and whilst not empty given recent rainfall were actively being managed. Sediment Dam G1 was also inspected and at the time of inspection was at capacity, with the water level, level with the spillway. Holcim	NC5
			Representatives D Egeonu and M Vafaei Fard, at the time advised that water discharging from Sediment Dam G1 reported internally to Sediment Dam F and did not discharge from site.	
			NC5 Recommendation:	
			It is recommended event based inspections of SDs be implemented to ensure that adequate capacity is maintained to reduce the risk of discharge events.	
Schedule 3, Condition 4 (c)	Describe in detail the measures that would be implemented over the next 5 years to rehabilitate	Rehabilitation and Landscape Management Plan (2018) - Section 3.1.	Section 3.1 of the Rehabilitation and Landscape Management Plan (2018) describes in detail rehabilitation during years 2016 - 2021. NC6 Recommendation:	NC6
	and manage the landscape on the site;		Section 3.1 of the Rehabilitation and Landscape Management Plan (2018) to be updated to account for next 5 years, i.e. 2024 to 2029.	

Table 3.2 Non-compliances

Section	Requirement	Evidence	Findings/recommendations	Unique non-compliance identification number
Schedule 3, Condition 46	Within 3 months of the Independent Environmental Audit (see Condition 11 in Schedule 5), the Applicant shall update the Rehabilitation and Landscape Management Plan to the satisfaction of the Secretary.	No evidence provided.	No evidence sighted of updates to the Rehabilitation and Landscape Management Plan following the 2020 IEA. NC7 Recommendation: Ensure management plans, following updates if required, are issued to DPHI following IEAs.	NC7
Schedule 3, Condition 48 a, b and c	Within 3 months of each Independent Environmental Audit (see Condition 11 in Schedule 5) after the lodgement of the rehabilitation bond, the Applicant must review, and if necessary revise the sum of the bond to the satisfaction of the Secretary. This review must consider: (a) the effects of inflation; (b) any changes to the total area of disturbance; and (c) the performance of the rehabilitation against the completion criteria of the Rehabilitation and Landscape Management Plan.	No evidence provided.	The auditor has not been provided any evidence of a bond review occurring following the previous audit. NC8, NC9, NC10 and NC11 Recommendations: Review and if necessary revise the bond to the satisfaction of the secretary.	NC8, NC9, NC10, NC11

Table 3.2 Non-compliances

Section	Requirement	Evidence	Findings/recommendations	Unique non-compliance identification number
Schedule 5, Condition 5	Within 3 months of the submission of an:	Annual Review 2020, 2021, 2022. Incident notifications to DPE dated	Sighted correspondence between Holcim and DPE confirm reviews of Management Plans following annual reviews.	NC12
	(a) incident report under condition 8 below;	11 December 2023, 22 May 2023, 13 January 2023.	No evidence sighted of review of plans following incidents or previous audit.	
	(b) Annual Review under condition 10 below;	Site interviews D. Egeonu.	2020 Annual Review notes an IEA Action plan is available as Appendix 3 of the document however it notes local funding initiatives not IEA actions	
	(c) audit report under condition 11		NC12 Recommendation:	
	below; and		Ensure revisions of management plans, if required, are documented and	
	(d) any modifications to this consent,		communicated to DPHI.	
	the Applicant must review, and if necessary revise, the strategies, plans, and programs required under this consent, to the			
Schedule 5, Condition 10 (i)	The Applicant must ensure that copies of the Annual Review are submitted to Council and are available to the Community Consultative Committee (see condition 7 of Schedule 5) and any interested person upon request.	Annual Review 2020, 2021, 2022.	While the AERs are publicly available on the Holcim website, there is no evidence that that the AERs in the reporting period were submitted directly to Council. NC13 Recommendation: Ensure AERs are issued to Council.	NC13
Schedule 5, Condition 11	By 30 September 2017, and every 3 years thereafter, unless the Secretary directs otherwise, the Applicant must commission and pay the full cost of an Independent Environmental Audit of the development. This audit must:	This audit.	Audit commissioned 4 December 2023, and was originally scheduled for the week the 11th of December 2023. However due to personal circumstances the auditor could not undertake the audit till 11 January 2024. NC14 Recommendation: Ensure IEA lead auditor engaged prior to the end of the audit period in future.	NC14

Table 3.2 Non-compliances

Section	Requirement	Evidence	Findings/recommendations	Unique non-compliance identification number
Schedule 5, Condition 13	 the Annual Reviews (over the last 5 years); any independent environmental audit, and the Applicant's response to the recommendations in any audit; 	Holcim Lynwood Quarry webpage (accessed 12/1/2024). https://www.holcim.com.au/about-us/community link/Lynwood/planning-approvals reporting	Only 2020, 2021 and 2022 AERs available online. 2012, 2015, 2019, and 2020 IEAs available online. No response to audits available. NC15 and NC16 Recommendation: Previous AERs made available on the Holcim website post audit. No further action necessary. Upload response to IEAs to Holcim website if available.	NC15, NC16
Appendix 7 Detailed Heritage Conditions 9 (e)	The progress on the archaeological works on site is systematically video recorded,	Previous 2020 IEA Audit.	Previous audit identified that Videos are not able to be located and it is understood that photographs were taken instead. Previous audit included action to discuss this matter with DPE. No evidence of action being addressed. NC17 Recommendation: As per previous audit Holcim to action previous recommendation outlined below: Recommendation 20: Close this issue out with DPHI to avoid ongoing on compliance issues at each audit. Ensure videos are taken during any future archaeological works on site.	NC17
Appendix 10, Condition 2	Except for wind speed at microphone height, the data to be used for determining meteorological conditions must be that recorded by the meteorological station required under condition 15A of Schedule 3.	Quarterly Noise Monitoring reports (Ramboll, MAC).	No reference in reports to reliance of meteorological station required under condition 15A of Schedule 3. NC18 Recommendation: Ensure noise consultant engaged for quarterly assessments relies on meteorological station required under condition 15A of Schedule 3.	NC18

Table 3.2 Non-compliances

Section	Requirement	Evidence	Findings/recommendations	Unique non-compliance identification number
Statement of co	ommitments			
Social impact	Monitoring • Undertake social monitoring as outlined in Table 6.14 of the EA	EA (MOD 4) - Table 6.14. CCC Minutes.	Table 6.14 states the following will be completed in regard to social monitoring: Completion of periodic community surveys to review community	NC19
	(MOD 4).		 Continued implementation of community engagement program including seeking feedback on engagement effectiveness and on the community's preferred engagement mechanisms. 	
			Continued effective operation of the CCC.	
			 Newsletter content to focus on key community issues identified as of most interest to the community. 	
			• Community survey outcomes and feedback from the CCC to be used to inform and update engagement and broader business planning.	
			No evidence sighted of periodic community surveys or newsletters during audit period.	
			It is noted CCC operated effectively.	
			NC2 Recommendation:	
			Implement periodic community engagement surveys and community newsletters.	
Rehabilitation	The key elements of the rehabilitation strategy for the Modification Project will include: • the timely and progressive rehabilitation of disturbed areas	Rehabilitation and Landscape Management Plan (2018) - Section 3.1.	Section 3.1 of the Rehabilitation and Landscape Management Plan (2018) describes in detail rehabilitation during years 2016 – 2021 only. Plan does not identify planned future rehabilitation works. NC2 Recommendation: As per NC6	NC20

Table 3.2 Non-compliances

Section	Requirement	Evidence	Findings/recommendations	Unique non-compliance identification number
EPL 12939				
P1.2	The following points referred to in the table below are identified in this licence for the purposes of monitoring and/or the setting of	Annual Review 2020, 2021, 2022. 2023 Quarterly Monitoring Reports. Site observations.	2021 All dust deposition (DD) gauges and high volume (HVAS) units were in operation. HVAS 1 failed to operate on 4 occasions during the year and HVAS 2 failed to operate on 1 occasion during the year. (Lynwood Quarry 2021 Annual Review).	NC21
	limits for the emission of pollutants to the air from the point.		2022 All dust deposition (DD) gauges and high volume (HVAS) units were in operation. HVAS 1 failed to operate on 8 occasions during the year. (Lynwood Quarry 2022 Annual Review).	NC21
			2023 - All dust deposition (DD) gauges and high volume (HVAS) units were in operation. HVAS 1 failed to operate on 8 occasions during the year and HVAS 2 failed to operate on 2 occasions during the year (Lynwood (EPL 12939) - Live Monitoring Worksheet 2023.XLS).	
			In general, all points were monitored during the three year period. Occasional failures occurred at the high volume samplers (reported as LOW NON-COMPLIANCE in 2021 and 2022 Annual Reviews). Dust deposition gauges were not collected in June 2021 due to CV19 restrictions.	
			NC21 Recommendation:	
			As per NC3.	

Table 3.2 Non-compliances

Section	Requirement	Evidence	Findings/recommendations	Unique non-compliance identification number
L3.1	Noise generated at the premises must not exceed the noise limits presented in the table below:	2021 - attended monitoring undertaken 4 times in the year at 4 representative locations (closest receivers). All compliant with agreed noise criteria. (Lynwood Quarry 2021 Annual Review / Noise Monitoring Assessment Quarterly Reports from 2021 (Muller Acoustic Consulting Pty Ltd (MAC)). 2022- attended monitoring undertaken 4 times in the year at 4 representative locations (closest receivers). All compliant with agreed noise criteria. (Lynwood Quarry 2022 Annual Review / Noise Monitoring Assessment Quarterly Reports from 2022 (Muller Acoustic Consulting Pty Ltd (MAC) / Ramboll). 2023 - attended monitoring undertaken 3 times in the year at 4 representative locations (closest receivers). All compliant with agreed noise criteria (Ramboll). (Lynwood (EPL 12939) - Live Monitoring Worksheet 2023.XLS / Noise Monitoring Assessment Quarterly Reports from 2023 (Ramboll)). Exceedance noted within spreadsheet.	4 receivers - representative as they are the closest 4 in each direction were monitored each year. No exceedances of the noise limits set were recorded due to the quarry; however, attended monitoring found occasional exceedance caused by bird noise, road traffic noise and rail (train) noise. These noise events were excluded from the results. In Sept 2023, a negligible exceedance (1dB) was observed at N1 during the evening monitored period with an estimated quarry contribution of 36 LAeq (15min) dBA against a criteria of 35 LAeq (15min) dBA. The LA1 quarry contribution also exceeded the LA1(1min) (dBA) criteria for all locations but it was noted that LA1 was dominated by birds, road traffic and/or a passing train at each location. NC2 Recommendation: As per NC2.	NC22

Table 3.2 Non-compliances

Section	Requirement	Evidence	Findings/recommendations	Unique non-compliance identification number
M2.2	Air Monitoring Requirements (Note see EPL 12939 for criteria).	Annual Review 2020, 2021, 2022. (Lynwood (EPL 12939) - Live Monitoring Worksheet 2023.XLS.	2021 All dust deposition (DD) gauges were in operation to collect PM g/sqm/month and high volume (HVAS) units were in operation to collect a HV Sample of PM10 for 24 hours every 6 days . HVAS 1 failed to operate on 4 occasions during the year and HVAS 2 failed to operate on 1 occasion during the year. (Lynwood Quarry 2021 Annual Review).	NC23
			2022 All dust deposition (DD) gauges were in operation to collect PM g/sqm/month and high volume (HVAS) units were in operation to collect a HV Sample of PM10 for 24 hours every 6 days. HVAS 1 failed to operate on 8 occasions during the year. (Lynwood Quarry 2022 Annual Review).	
			2023 - All dust deposition (DD) gauges were in operation to collect PM g/sqm/month and high volume (HVAS) units were in operation to collect a HV Sample of PM10 for 24 hours every 6 days. HVAS 1 failed to operate on 8 occasions during the year and HVAS 2 failed to operate on 2 occasions during the year (Lynwood (EPL 12939) - Live Monitoring Worksheet 2023.XLS).	
			NC23 Recommendation:	
			As per NC3.	
R2.1	Notifications must be made by telephoning the Environment Line service on 131 555.	Annual Review 2020, 2021, 2022, 2023. Site Incident management software package. Holcim website.	No evidence of incidents or exceedances reported to EPA of EPL criteria during the audit period. Notable this includes ongoing failures of air quality and noise monitoring events. It is noted that incidents recorded within the information provided are unlikely to have caused environmental harm.	NC24
			NC24 Recommendation:	
			Implement process to ensure EPA is notified of incidents in future.	

Table 3.2 Non-compliances

Section	Requirement	Evidence	Findings/recommendations	Unique non-compliance identification number
R2.2	The licensee must provide written details of the notification to the EPA within 7 days of the date on which they became aware of the incident.	Annual Review 2020, 2021, 2022, 2023. Site Incident management software package. Holcim website.	No evidence of incidents or exceedances reported to EPA of EPL criteria during the audit period. Notable this includes ongoing failures of air quality and noise monitoring events. It is noted that incidents recorded within the information provided are unlikely to have caused environmental harm.	NC25
	Note: The licensee or its employees must notify all relevant authorities of incidents causing or threatening material harm to the environment immediately after the person becomes aware of the incident in accordance with the requirements of Part 5.7 of the Act.		NC25 Recommendation: As per NC24.	
U1.2	Monitoring must be undertaken at HVAS1 and HVAS 2 as described in Condition P1.2.	Annual Review 2020, 2021, 20222023 Quarterly Monitoring ReportsSite observations.	2021 All dust deposition (DD) gauges and high volume (HVAS) units were in operation. HVAS 1 failed to operate on 4 occasions during the year and HVAS 2 failed to operate on 1 occasion during the year. (Lynwood Quarry 2021 Annual Review);	NC26
			2022 All dust deposition (DD) gauges and high volume (HVAS) units were in operation. HVAS 1 failed to operate on 8 occasions during the year. (Lynwood Quarry 2022 Annual Review); 2023 - All dust deposition (DD) gauges and high volume (HVAS) units were in operation. HVAS 1 failed to operate on 8 occasions during the year and HVAS 2 failed to operate on 2 occasions during the year (Lynwood (EPL 12939) - Live Monitoring Worksheet 2023.XLS). In general, all points were monitored during the three year period. Occasional failures occurred at the high volume samplers (reported as LOW NON-COMPLIANCE in 2021 and 2022 Annual Reviews). Dust deposition gauges were not collected in June 2021 due to CV19 restrictions. NC26 Recommendation: As per NC3.	

Table 3.2 Non-compliances

Section	Requirement	Evidence	Findings/recommendations	Unique non-compliance identification number
U1.3	Monitoring must be undertaken using the same methodology as described in Condition M2.2.	Annual Review 2020, 2021, 2022 (Lynwood (EPL 12939) - Live Monitoring Worksheet 2023.XLS.	2022 All dust deposition (DD) gauges were in operation to collect PM g/sqm/month and high volume (HVAS) units were in operation to collect a HV Sample of PM10 for 24 hours every 6 days. HVAS 1 failed to operate on 4 occasions during the year and HVAS 2 failed to operate on 1 occasion during the year. (Lynwood Quarry 2021 Annual Review). 2022 All dust deposition (DD) gauges were in operation to collect PM g/sqm/month and high volume (HVAS) units were in operation to collect a HV Sample of PM10 for 24 hours every 6 days. HVAS 1 failed to operate on 8 occasions during the year. (Lynwood Quarry 2022 Annual Review). 2023 - All dust deposition (DD) gauges were in operation to collect PM g/sqm/month and high volume (HVAS) units were in operation to collect a HV Sample of PM10 for 24 hours every 6 days. HVAS 1 failed to operate on 8 occasions during the year and HVAS 2 failed to operate on 2 occasions during the year (Lynwood (EPL 12939) - Live Monitoring Worksheet 2023.XLS). NC27 Recommendation:	NC27
			As per NC3.	

3.5 Previous audit recommendations

Table 3.3 outlines the audit recommendations that were made by Kleinflelder as part of the 2020 IEA.

Table 3.3 Previous audit recommendations

Condition reference	Aspect	Recommendation	Response	Completed?
Schedule 2, Condition 13a	Production data	Recommendation 1 Provide annual production data to DRG using the standard form for that purpose.	Not actioned, see NC1.	No

 Table 3.3
 Previous audit recommendations

Condition reference	Aspect	Recommendation	Response	Completed?
Schedule 3, Condition 48, 48 (a), 48 (b), 48 (c)	Rehabilitation and Landscaping - Rehabilitation Bond	Recommendation 9 Review and if necessary, revise the bond to the satisfaction of the Secretary.	Not actioned, see NC8, NC9, NC10, NC11.	No
Schedule 3, Condition 48A (c)	Rehabilitation and Landscaping - Retirement of Biodiversity Credits	Recommendation 10 Consult with DPIE for how to close out the issue of non-retirement of credits.	Address under Modification 5 of DA 128-5-2005. No further credits required to be secured at this time.	Yes
Schedule 5, Condition 10	Reporting - Annual Review	Recommendation 19 A list of agencies that receive the AERs is included in the AERs.	Not actioned, see NC13	No
Appendix 7, 9(e)	Appendix 7: Detailed Heritage Conditions	Recommendation 20 Close this issue out with DPIE to avoid ongoing noncompliance issues at each audit. Ensure videos are taken during any future archaeological works on site.	Not actioned, see NC17	No
Appendix 11	Project Management and Mitigation Measures – Surface Water	Recommendation 21 Review and update the Lockyersleigh Creek Riparian Area Management Plan.	Document reviewed in 2018.	Yes
EPL M4.2	Project Management and Mitigation Measures – Surface Water	Recommendation 29 For each incident recorded, include the actions taken, or if no action taken state why not.	Holcim has implemented during the audit period a new incident and complaint software package across all operations. The requirements of EPL M4.2 are addressed within.	Yes
Schedule 3, Condition 4(b)	Noise - Noise Mitigation Measures	Recommendation 2 Record the detail of the noise complaint and ensure that they are closed out.	Holcim has implemented during the audit period a new incident and complaint software package across all operations. Historic complaints are addressed and closed out within Annual Reviews and incident register.	Yes

 Table 3.3
 Previous audit recommendations

Condition reference	Aspect	Recommendation	Response	Completed?
Schedule 3, Condition 5	Noise - Operating Hours	Recommendation 3 Ensure incidents listed in InControl are closed out.	Holcim has implemented during the audit period a new incident and complaint software package across all operations.	Yes
			Lead Auditor sighted evidence of incidents raised being closed out via the system.	
Schedule 3, Condition 12	Air Quality -Impact Assessment Criteria	Recommendation 4 Close out all dust complaints in the incident register.	Holcim has implemented during the audit period a new incident and complaint software package across all operations.	Yes
			Historic complaints are addressed and closed out within Annual Reviews and incident register.	
Schedule 3, Condition	Surface and Groundwater - Sediment Dams	Recommendation 5	A review of Dams completed by GHD confirms dam sizing is consistent with DA128-5-2005. Revised naming conventions are now adopted through document.	Yes
18 (a)		Clarity should be sought around this condition if dams are now assigned different labels, or alternatively the WMP should be updated to state whether these criteria are met if still required to do so.		
Schedule 3, Condition		Recommendation 6	Dam level pegs sighted by Lead Auditor during inspection.	Yes
19 (b)	Groundwater - Operating Conditions	Suggestion to mark levels at 30 $\%$ if feasible or incorporate program for checking levels systematically.		
Schedule 3, Condition	Rehabilitation and	Recommendation 7	Not actioned, see NC6.	No
44 (c)	Landscaping – Rehabilitation and Landscape Management Plan	The Rehabilitation and Landscape Management Plan will need to be updated to manage for the next five-year period within the next 12 months.		
Schedule 3, Condition	Rehabilitation and Landscaping – Rehabilitation and Landscape Management Plan	Recommendation 8	Not actioned, see NC7.	No
46		Ensure that the Rehabilitation and Landscape Management Plan is updated to the satisfaction of the secretary within 3 months of this audit.		

 Table 3.3
 Previous audit recommendations

Condition reference	Aspect	Recommendation	Response	Completed?
Schedule 3, Condition 54	Waste Management	Recommendation 11 Edit wording of Waste Management and Minimisation Strategy to explicitly capture condition 54.	Action complete. Plan now inclusive of reference to condition.	Yes
Schedule 5, Condition 1A (b), 1A(c), 1A(d)	Evidence of Consultation	Recommendation 12 Append agency consultation to all future revisions of management plans.	Not actioned, see NC12.	No
Schedule 5, Condition 2 (a)	Management Plan Requirements	Recommendation 13 Provide previously collected detailed baseline data in any future management plan revisions.	Baseline data presented in latest revision of management plans.	Yes
Schedule 5, Condition 2 (e)	Management Plan Requirements	Recommendation 14 Provide contingency plans in any future management plan revisions if applicable to the plan.	Management plans detail management corrective actions as required should a non-compliance or event outside of a normal range is identified.	Yes
Schedule 5, Condition 2 (h)	Management Plan Requirements	Recommendation 15 Future updates to plans prepared prior to MOD4 should provide a protocol for periodic review.	Management plans identify review periods in accordance with DA128-5-2005.	Yes
Schedule 5, Condition 5	Revision of Strategies, Plans & Programs	Recommendation 16 Establish a register to ensure accurate tracking of strategy, plan and program updates against required timeframes.	Lead auditor sighted document confirming status of review of each management plan. Document is appended to correspondence to DPHI following submission of the Annual Reviews, confirm the review status.	Yes
Schedule 5, Condition 8	Reporting – Incident Reporting	Recommendation 17 PIRMP should be amended to include notification of the Secretary following an emergency incident, as per the requirements of this condition.	PIRMP includes notification procedures for incidents.	Yes
Schedule 5, Condition 10 (h)	Reporting – Annual Review	Recommendation 18 Future Annual Environmental Reviews should include information on the additional BioBanking (or equivalent) credits that will need to be purchased.	Credits retired and required to be retired consistent with the consent are detailed within the Annual Reviews.	Yes

 Table 3.3
 Previous audit recommendations

Condition reference	Aspect	Recommendation	Response	Completed?
Appendix 11, SOC	Appendix 11: Statement of Commitments – Modification Project Management and Mitigation Measures – Surface Water	Recommendation 22 The revised WMP (2020) should state if the guidelines for Water Reporting Requirements for Mines (NSW Office of Water, updated) have been used in the WMP (2020) development.	The WMP has been prepared reliant on current guidelines including the internal the Holcim Guideline Water Management. This internal document addresses the requirements of the Water Reporting Requirements for Mines (NSW Office of Water, updated) which is now a superseded guideline.	Yes
Appendix 11, SOC	Appendix 11: Statement of Commitments – Modification Project Management and Mitigation Measures – Surface Water	Recommendation 23 Close out revision to Water Management Plan and include relevant updates to surface water monitoring program.	WMP finalised in November 2020 and issued to DPHI in December 2020.	Yes
Appendix 11, SOC	Appendix 11: Statement of Commitments – Modification Project Management and Mitigation Measures – Surface Water	Recommendation 24 The website should be updated to show most recent revision of the Surface Water Monitoring Program if it was indeed approved.	Most recent version Surface Water Monitoring Program contained within the WMP finalised in November 2020.	Yes
Appendix 11, SOC	Appendix 11: Statement of Commitments – Modification Project Management and Mitigation Measures – Groundwater	Recommendation 25 Update the website to contain the revised Groundwater Management Plan (2018), or 2020 once approved.	Most recent version Groundwater Monitoring Program contained within the WMP finalised in November 2020.	Yes

 Table 3.3
 Previous audit recommendations

Condition reference	Aspect	Recommendation	Response	Completed?
Appendix 11, SOC	Appendix 11: Statement of Commitments – Modification Project Management and Mitigation Measures – Trust and Reputation	Recommendation 26 Last update to 'Information Updates' page online appears to be 2015. This page should be updated or merged with other pages that provide the more recent information such as Annual Reviews etc or with the 'Community Link' Lynwood Page which has the most recent update of December 2019.	Holcim website regularly updated within boarder company news during the audit period. CCC minutes uploaded quarterly providing an overview of operations, engagement activities and community support activities.	Yes
Appendix 11, SOC	Appendix 11: Statement of Commitments – Modification Project Management and Mitigation Measures – Visual Amenity	Recommendation 27 Close out the complaint from 20/02/2019 Recommendation: Ensure that enough detail is recorded for complaints in InControl.	Historic complaints closed out via Annual Reviews.	Yes
Appendix 11, SOC	Appendix 11: Statement of Commitments – Modification Project Management and Mitigation Measures – Gas Pipeline Hazard	Recommendation 28 Ensure pipelines are designed in accordance with relevant standards.	No gas pipeline interactions or installations during the audit period.	Yes
EPL M5.2	EPL	Recommendation 30 State clearly on the webpage that this number should be used if a community member has a complaint.	The community line is displayed on the Lynwood Quarry website: Https://www.holcim.com.au/about-us/community-link/lynwood/contact-details	Yes.

3.6 EMP, sub-plans and compliance documents

To determine the adequacy of the management plans applicable to the operation of Lynwood Quarry, the EMM audit team conducted reviews of the following plans:

- Aboriginal Heritage Management Plan, Caring for Country (2022)
- Air Quality Management Plan (August 2023)
- Blast Management Plan (February 2020)
- Box Gum Woodland Management Plan (September 2013)
- Environmental Management Strategy (February 2020)
- Noise Management Plan (February 2020)
- Pollution Incident Response Management Plan (September 2019)
- Rehabilitation and Landscape Management Plan (May 2018)
 - Riparian Area Management Plan Joarimin Creek Catchment (2021)
 - Riparian Area Management Plan Lockyersleigh Creek Catchment Revision (June 2011)
 - Riparian Area Management Plan Marulan Creek Catchment Area (2011)
- Waste Management and Minimisation Strategy (2019)
- Water Management Plan (2020)
 - Groundwater Monitoring Program (2020)
 - Surface Water Monitoring Program (2020).

The adequacy and implementation of these plans were also assessed during the site inspection. EMM determined these plans to be adequate for operation and implemented appropriately.

Opportunities for improvement are discussed in detail in Section 3.10.

3.7 Consultation outcomes

Consultation was completed with the government agencies and the community consultative committee listed in Section 2.6. A summary of the consultation is included in Table 3.4, with evidence of consultation attached as Appendix B and Appendix C.

Table 3.4 Consultation

Agency/CCC member	Date	Method	Aspects/issues raised	Response
DPHI	1 December 2023	Email	Email from Holcim seeking approval of the audit team.	Response received from DPHI on 1 December 2023 – endorsing audit team.
	5 December 2023	Email	Email from Lead Auditor to DPHI, seeking confirmation of agencies to consult and any areas of particular focus to be included within the IEA scope.	The following comments were received from DPE 11 December 2023:
				The auditor should consult with the following parties or agencies in the development of the IEA scope:
				Environment Protection Authority (EPA)
				Goulburn Mulwaree Council (Council)
				 Department of Climate Change, Energy, Environment and Water (DCCEEW) – Water
				Department of Primary Industries - Fisheries
				Community Consultative Committee.
				In addition, DPHI noted the area of environmental management that should be considered, in particular, includes management of air quality.
	6 December 2023 and 12 December 2023	Email	EMM issued letters to the below agencies and council seeking input to the IEA scope on 12 December 2023, the CCC was also contacted for input of 6 December 2023:	Individual responses are detailed below.
	12 December 2023		Environment Protection Authority (EPA)	
			Goulburn Mulwaree Council (Council)	
			 Department of Climate Change, Energy, Environment and Water (DCCEEW) – Water 	
			 Department of Primary Industries – Fisheries (DPI Fisheries) 	
			Community Consultative Committee.	
			Response received from Council, DCCEEW Water and DPI Fisheries. All responses are summarised within this table. The EPA contacted the lead auditor to organise a teleconference rather than issue correspondence. The Lead	

Table 3.4 Consultation

Agency/CCC member	Date	Method	Aspects/issues raised	Response
			Auditor coordinate the meeting for 19 December 2023, however EPA representatives did not attend.	
			Responses were not received from CCC members.	
Council	10 January 2024	Email	In response to correspondence from Lead Auditor requesting any advice regarding any areas of compliance or environmental management at Lynwood Quarry, that should be of particular focus and included within the IEA scope.	No response required, matters relating to Orica are not subject of the audit.
			Council noted that nothing has been brought to Council's attention in relation to Holcim's operations of the Lynwood Quarry. Council did note that Council has recently been made aware of potential development creep by Orica who we understand lease part of the site for the purposes of preparing explosive material. Council is in the process of preparing correspondence to Holcim in this regard.	
DCCEEW – Water	15 December 2023	Email	In response to correspondence from Lead Auditor requesting any advice regarding any areas of compliance or environmental management at Lynwood Quarry, that should be of particular focus and included within the IEA scope.	 Lynwood Quarry operates under Water Management Plan (WMP, November 2020) approved November 2020 by DPHI. The WMP includes Surface and Groundwater Monitoring Programs. An extraction plan is not required.
			DCCEEW – Water requested that the audit address compliance with the following specific elements of the consent conditions and related legislative requirements in a manner consistent with the audit scope:	 Trigger action response plans are identified within the WMP), and associated Surface and Groundwater Monitoring Programs.
				 Water supply is confirmed in Section 4 of the Water Management Plan (November 2020).
			The requirement to prepare and implement management plans that relate to water sources and their dependent ecosystems and users, and associated impact	 Water take at Lynwood Quarry is defined via the Water Balance discussed in Section 5 of the WMP. Take inconsideration of licenses held by Lynwood Quarry is summarised in Annual Reviews.
			management and mitigation. These plans may include: — Water Management Plans and related sub plans.	Water meters are installed at all water extraction points being
			Extraction Plans and related sub-plans.	Johnniefields Dam and Supply Dams 1 and 2. Recording date and time and the volume of water taken. This was confirmed via site interviews.
				 Annual reports confirm water take, use and source of water. In addition, Annual Reviews compare result to previous years and identify exceedances and proposed corrective measures as necessary.

Table 3.4 Consultation

Agency/CCC member	Date	Method	Aspects/issues raised	Response
			 The requirement to prepare and implement trigger action response plans for water source impacts which set clearly defined limits and actions. This is to be reported on within annual and exceedance-based reporting. 	
			• Water supply availability is clearly defined for the project.	
			 Water take at the site via storage, diversion, interception or extraction is clearly document and authorised by a relevant Water Access License or exemption under the Wate Management (General) Regulation 2018. 	
			 Water metering at the site is in accordance with the NSW Non-Urban Metering Framework where relevant. 	
			 Water Access Licence/s used to account for water take by the project nominates the work where the water is being taken from. 	
			 Annual reporting clearly documents; 1) water take, use and water source impacts, 2) compares results with previous years, and 3) identifies exceedances and these are managed / mitigated 	

Table 3.4 Consultation

Agency/CCC member	Date	Method	Aspects/issues raised	Response
DPI - Fisheries	13 December 2023	Email	In response to correspondence from Lead Auditor requesting any advice regarding any areas of compliance or environmental management at Lynwood Quarry, that should be of particular focus and included within the IEA scope. DPI Fisheries requested the IEA consider the following: • Audit should assess the adequacy of surface water quality treatment measures. In particular, the effectiveness of these measures to mitigate impacts to adjoining/downstream waterways. • Event based sampling should be undertaken at downstream instream monitoring points and should be based on the ANZECC Guidelines. This sampling should specifically include TSS. • DPI Fisheries recognises that Lynwood Quarry has an approval to discharge sediment basins with a limit of 50mg/L for TSS. However, it should be noted that sediment discharges of 50mg/I (well above ANZECC guidelines) result in detrimental impacts to aquatic habitat. As a matter of best practice Lynwood Quarry should be reviewing and improving their surface water management where levels are being recorded in excess of ANZECC guidelines. • The IEA should also consider whether riparian protection measures are in place.	 Surface water quality treatments, namely capture and recycling of 'dirty' water, have been reviewed and considered adequate. No discharge of waters to the receiving environment occurred during the audit period. Surface water monitoring occurs at Lynwood Quarry in accordance with the Surface Water Monitoring Program, appended to the WMP and approved November 2022. Lynwood Quarry is approved to discharge water from sediment basins with a limit of 50mg/L for TSS, as noted by DPI Fisheries. This is reflected within WMP. Holcim has advised should a discharge event occur or is predicted to occur measures to reduce sediment load would be implement to reduce TSS levels as far practicable, via measured outlined in Table 4 of the WMP. Riparian protection matters are considered adequate noting the established Marulan Creek Catchment Area, Lockyersleigh Creek Catchment and Joarimin Creek Catchment Riparian Area Management Plans.
CCC Members	6/12/2023	Email	Email from EMM to CCC Members requesting any aspects they would like addressed in the IEA.	No responses received.

3.8 Complaints

A summary of the complaints received over the IEA period are outlined in Table 3.5.

Table 3.5 Summary of complaints

Aspect	2020 (after 30 September 2020)	2021	2022	2023	2024 (up to 1 February 2024)
Lighting	0	2	0	0	0

All complaints were satisfactorily followed up in accordance with the complaints management strategy outlined in Section 6.4 of the Environmental Management Strategy (EMS).

In accordance with Schedule 5, Condition 13 of Development Consent DA 128-5-2005, a summary of all complaints are uploaded to the Holcim website.

3.9 Incidents

Table 3.6 provides a summary of the environmental incidents which occurred during the Audit period, as reported within the Annual Reviews covering the audit period.

All incidents were reported within Annual Returns in accordance with Schedule 5, 10 (c) of Development Consent DA 128-5- 2005. Regarding Condition R2.2 of EPL 12939, not all incidents were reported to the EPA within 7 days.

Table 3.6 Incidents

Date	Incident	Action – as per Annual Returns
24 March 2021	Air quality monitoring PM10 sampling event missed on 24 March 2021 due to flooding causing HVAS 1 to	Holcim notified DPE of an inability to capture Lockersleigh HVAS data due to flooding. As a result there was no data captured for 24 March 2021.
	become inaccessible.	DPE acknowledged the receipt of this notification on 7 April 2021.
March – July 2021	Air quality monitoring HVAS 1 did not sample every six days in 2021. 50 24-hour PM10 samples were taken	HVAS 1 software error impacted sampling schedule, and therefore samples were not taken by unit on the correct dates.
	in 2021 at HVAS 1.	Monitoring contractor reported issue and followed up on unit errors across March to July 2021 to resolve the issues. Resolution of unit errors and calibration were delayed due to Covid19 restrictions preventing timely attendance to site.
June 2021	Air quality monitoring Depositional Dust monitoring was missed in June 2021 due to Covid-19 restrictions preventing access to the site.	Depositional dust monitoring is a monthly requirement from the Consent. The June 2021 could not be recorded due to interruptions from Covid-19. However, depositional dust results were consistently below the Consent criteria for all other months in 2021.
Throughout	Water Quality Monitoring	Full monitoring was not undertaken at SW8 across 2021, resulting in some absent results. This
2021	$\ensuremath{pH}\xspace$, TSS, or EC were not monitored at surface monitoring location SW8 on a quarterly basis.	is a low non-compliance because the full monitoring schedule outlined in the WMP was not implemented.
Throughout	Air quality monitoring	Samples across 2022 were missed due to the sample being invalidated as unit did not run for
2022	PM10 24-hour missed samples on:	24 hours.
	• 3 May 2022	
	• 31 May 2022	
	• 4 July 2022	
	• 6 July 2022	
	• 15 July 2022	
	• 22 July 2022	
	• 28 July 2022	
	• 3 August 2022.	
Throughout	Quality Monitoring	Full monitoring was not undertaken at SW8 across 2022, due to the location being to dry.
2022	pH, TSS, EC or oil and grease were not monitored at surface monitoring location SW8 on a quarterly basis. $ \\$	This is a low noncompliance because the full monitoring schedule outlined in the WMP was not implemented.

Table 3.6 Incidents

Date	Incident	Action – as per Annual Returns
6 December	Noise Monitoring	Monitoring was not undertaken at location N3 during the night as the location was unable
2022	Night monitoring was not recorded at location N3.	to be accessed.
Throughout 2023	Air Quality Monitoring	Samples across 2023 were missed due to the sample being invalidated as unit did not run for 24 hours. This was due to power supply issues to the stations, which has since been resolved.
2023	Multiple invalidated or exceeded samples recorded during the 2023 reporting period.	Both HVAS1 and HVAS2 recorded PM10 exceedances. Holcim believes that neither
	HVAS 1 PM10 missed samples occurred on:	exceedance is due to quarry operations. All incidents were reported.
	• 25 April 2023	
	• 6 July 2023	
	• 11 August 2023	
	• 17 August 2023	
	• 23 August 2023	
	• 16 September 2023	
	• 22 September 2023	
	• 4 October 2023.	
	HVAS1 PM10 exceedance occurred on:	
	• 25 April 2023 (58.4 μg/ m3).	
	HVAS2 PM10 missed sample on:	
	• 7 May 2023.	
	HVAS 2 PM10 exceedance occurred on:	
	• 24 February 2023 (63.4 μg/ m3).	
Multiple	Surface Water Management Plan	Holcim failed to notify the DPHI or EPA during the reporting period of consecutive
dates throughout 2023	Non-Compliance for failing to notify the Department of surface water exceedances during 2023 reporting period. (pH, and Oil and Grease.)	exceedances above criteria levels Holcim will ensure that all consecutive exceedances are reported to Department and EPL in 2024
Multiple	Groundwater Monitoring Plan	Holcim failed to notify the DPHI or EPA during the reporting period of consecutive
dates throughout 2023	Non-Compliance for failing to notify the Department of ground water exceedances (pH).	exceedances above criteria levels Holcim will ensure that all consecutive exceedances are reported to DPHI and EPA in 2024.

Table 3.6 Incidents

Date	Incident	Action – as per Annual Returns
September 2023	Independent Environmental Audit Lynwood failed to undertake the 2023 IEA within the time period specified by the development consent.	Holcim acknowledges that the IEA was unable to be conducted by September 2023. On 12 January 2024, EMM undertook the IEA for Lynwood Quarry.
Multiple dates throughout 2023	Incident Notification Holcim failed to notify the department of surface and ground water exceedances during the 2023 reporting period.	Holcim will ensure that any appropriate exceedances detailed in Management Plans will be notified to the Department.

3.10 Actual verses predicted environmental impacts

The 2020, 2021, 2022 and 2023 annual reviews were reviewed in order to undertake an assessment of the compliance between actual and predicted impacts documented in relevant environmental assessments, including an assessment of the physical extent of the development in comparison with the approved boundary and any potential off-site impacts of the development required under the EP&A Act.

The annual reviews confirm the physical extent of Lynwood Quarry lies within the approved boundary.

Section 3.9 outlines environmental incidents which occurred during the audit period, as outlined in annual reviews. The air quality, water and noise incidents outlined in Section 3.9, demonstrate potential for off-site impacts in excess of predicted environmental impacts. The 2020, 2021, 2022 and 2023 confirm corrective actions taken by Lynwood Quarry to reduce the risk of reoccurrence. Recommendations are made within this audit, see Chapter 4, to address any further non-compliances identified as part of this audit.

3.11 Site inspection

Areas inspected during the site inspection are identified within Section 2.5, with evidence collected through the site inspection summarised below.

Photographs of the below noted areas inspected are available in Appendix E.

i Access road

Inspection of the access road was undertaken by the lead auditor during access to and leaving the Lynwood Quarry. The Access Road was well sign posted and fenced. Appropriate signage identifying speed limits, blasting activities and caution regarding animals was sighted.

ii Infrastructure area (including administration area, workshops, fuel storage, waste management area)

Inspection of the Infrastructure area was undertaken by the lead auditor under escort by Lynwood Quarry representatives. The inspection included the site offices, carpark, workshop, wash down bays, store, fuel bay and sumps with waste oil separators. The inspection demonstrated that the Infrastructure area was maintained generally in accordance with approved management plans, being well organised and positive segregation of waste streams. Noting, chemical storage vessels were identified outside appropriately bunded areas.

iii Processing plant and stockpile areas

Inspection of the processing plant was undertaken by the lead under escort by Lynwood Quarry representatives. The inspection included the Run of Mine (ROM) pad, ROM hopper, crusher, transfer conveyors, product stockpiles and associated laydown areas.

The inspection demonstrated that the processing plant, stockpiles and associated infrastructure was maintained generally in accordance with approved management plans, being well organised and maintained. Dust controls were in place including water cart and sprays at the time of inspection.

iv Rail and road transport load out facilities

Inspection of the processing rail and road transport load out facilities was undertaken by the lead under escort by Lynwood Quarry representatives. The inspection included both the rail load out bin, areas in which trucks are loaded via loader and associated refuelling and washdown bay for trucks.

The inspection demonstrated that the rail and road transport load out facilities was maintained generally in accordance with approved management plans, being well organised and maintained. During the audit truck loading and washdown prior to leaving site was sighted. No train loading was sighted during the inspection.

v Western and eastern excess product emplacement areas

Inspection of the western and eastern excess product emplacement areas was undertaken by the lead under escort by Lynwood Quarry representatives.

The inspection demonstrated that the excess product emplacement areas are maintained generally in accordance with approved management plans and actively relied upon by the operations. Stockpiles within the emplacement areas are managed as to reduce dust potential. The emplacement areas are largely located on hard stand and bunded, with surface runoff directed to the quarry water management system.

vi Southern overburden emplacement areas

Inspection of the southern emplacement area was undertaken by the lead under escort by Lynwood Quarry representatives.

The inspection demonstrated that the emplacement area is largely still in use and has not been subject to significant rehabilitation activities consistent with approved management plans. Weeds were sighted during the inspection of the overburden emplacement areas, as was evidence of weed management. Drainage lines within the emplacement areas were subject of erosion, however this is expected noting significant rehabilitation activities have not occurred to date. The southern overburden emplacement area was adequately bunded, catching surface water runoff, and directing to sediment structures.

vii Amenity bund

Inspection of the amenity bund was undertaken by the lead under escort by Lynwood Quarry representatives.

The inspection demonstrated that the amenity bund was maintained generally in accordance with approved management plans, with construction and revegetation occurring during the audit period. Revegetation appeared to have established well, with a diverse mix of grasses and tress species established. Minor weeds were sighted however as was management activities, via spraying.

viii Granite pit

Inspection of the granite pit was undertaken by the lead auditor and assistant auditor under escort by Lynwood Quarry representatives.

The inspection demonstrated that mining activities within the granite pit was undertaken generally in accordance with approved management plans. At the time of inspection, active mining activities were located within the granite pit, with quarry product being transported to the processing plant. Drilling was being undertaken on the bench below mining activities. Mulching and topsoil removal was not being undertaken at the time of inspection, however a previously cleared area prepared for mining activities was sighted, north-west of mining activities, site interviews confirmed this area was cleared prior to the audit period.

ix Supply dam

Inspection of the supply dam was undertaken by the lead auditor under escort Lynwood Quarry representatives.

The inspection demonstrated that the water storages were being operated in accordance with approved management plans.

x Sediment dams A, E, F and G1

Inspections of the sediment dams (SDs) A, E, F, and G1 were undertaken by the lead auditor under escort by Lynwood Quarry representatives.

The inspections demonstrated that SDs were being operated generally in accordance with approved management plans. Evidence of active management of sediment load and water levels within the SDs were sighted. SDs were also equipped with dewatering infrastructure, namely hoses with the pump itself shared between SDs. The lead auditor was provided evidence of fortnightly inspections of all SDs.

It is noted SD G1 at the time of inspection was full level with the spillway, following heavy rain in the lead up to the site inspection. Lynwood Quarry representatives, following the inspection, coordinated dewatering of the SD. The level of water within the SD G1 was raised as an internal incident and recorded within the Holcim incident management platform identifying corrective actions.

3.12 Site interviews

The audit site interviews were completed by the EMM audit team on 1 February 2024.. Interviews were conducted with Lynwood Quarry staff to verify compliance with relevant conditions. A summary of interviews conducted is outlined in Table 3.7.

Table 3.7 Site interviews summary

Name	Position	Interview matters
Wanye Beattie	Quarry Manager	Overview of activities undertaken during the audit period.
		Overview of Lynwood Quarry mining, processing and transport processes.
		• Overview of operational management systems to ensure environmental compliance.
		• Discussion on and provision of evidence to demonstrate compliance with relevant Development Consent and EPL.
		• Overview of how compliance conditions in regard to Aboriginal cultural heritage are satisfied.
		Overview of Lynwood Quarry operational water management systems.
Dozie Egeonu	Environment	Overview of operational management systems to ensure environmental compliance.
	Manager NSW & ACT	• Discussion on and provision of evidence to demonstrate compliance with relevant Development Consent and EPL.
		• Discussion on and provision of evidence to demonstrate suitable corrective actions in regard to prior audit findings.
Mohsen Vafaei	Support Services	Overview of environmental compliance data.
Fard	Supervisor	Overview of rehabilitation and biodiversity management practices.
		• Discussion on and provision of evidence in regard to preliminary non-compliances identified prior to the site visit and receipt of data.
		Overview of complaint management process and internal procedures to address.
		Overview of biodiversity management practices.
		Overview of ground disturbance procedures.
		Overview of Lynwood Quarry operational water management systems.

3.13 Opening and closing meetings

Opening and closing meetings were held at the commencement and closure of the site visit. Opening and closing meeting attendees are outlined in Table 3.8.

Table 3.8 Opening and closing meeting attendance

Name	Position
Wanye Beattie	Quarry Manager
Dozie Egeonu	Environment Manager NSW & ACT
Mohsen Vafaei Fard	Support Services Supervisor
Thomas Frankham	Lead Auditor and Associate Environmental Scientist

3.14 Improvement opportunities

Key opportunities for improvements identified during the audit are noted in the following sections.

3.14.1 Air quality

Air quality monitoring during the audit period failed to capture a significant number of sampling events as required un the DA128-5-2005 and EPL 12939. Majority of failed data capture events related to high volume air samplers (HVASs).

It is recommended that Lynwood Quarry, as outlined by the NC3 Recommendation within Table 3.2, investigate the root cause of the HVAS failures and appropriately action corrective measures. It is understood that a number of failed sampling events relate to power supply which Lynwood Quarry is currently in the process of improving. However, it is noted that historically some of the failed sampling attempts related to the run time of the HVAS or the days set. This may be improved by detailed operating procedures to reduce the risk of operator error.

3.14.2 Water management

During the site inspection it was noted that SD G1 was full to level with the spillway.

It is recommended, as outlined by the NC5 Recommendation within Table 3.2, rainfall event-based inspections of SDs be implemented to ensure that adequate capacity is maintained to reduce the risk of discharge events.

It is noted that following the audit period Holcim has revised the fortnightly inspection form to confirm capacities to be maintained.

3.14.3 Waste

A number of 1,000 L pods located around the infrastructure area and processing plant (some full, some mostly empty) were observed outside of appropriate storage areas during the site inspection. It is noted that these largely contained truck wash or dust binding agents, no fuel or oil 1,000 L pods were identified.

It is recommended to minimise potential spill incidents 1,000 L pods are appropriately stored in bunded areas.

3.15 Key strengths

Key strengths of Lynwood Quarry's environmental management and performance identified during the audit are identified in the following sections.

3.15.1 Noise, blast and vibration

The NMP is generally consistent with current best practice, concluding that Lynwood Quarry has been operated and managed in a competent manner from an acoustic perspective. This demonstrated by only one minor non-compliance of criteria under EPL 12939 and no noise complaints received during the audit period.

3.15.2 Air quality

Lynwood Quarry appears to be implementing their dust mitigation measures on-site as stated in their AQMP. Failed sampling events have occurred, however, at the time of the audit inspection minimal dust was observed. In addition it is noted that no dust complaints were received during the audit period. A significant improvement to previous audit periods.

3.15.3 Waste

Lynwood Quarry's segregation of waste streams was noted as a key strength during the site inspection. A number of waste bins of numerous types (i.e. general, steel, paper, oily rags, etc.) were inspected during the audit, with no misplaced waste identified.

4 Recommendations

4.1 Non-compliances

Details of all non-compliances associated with this 2023 IEA can be found in Section 3.4. Where a non-compliance was identified, a recommendation for improvement was made. This is detailed below in Section 4.2.

4.2 Opportunities for improvement

Table 4.1 lists the recommendations made as part of the 2023 IEA.

Table 4.1 Recommendations

Recommendation number	Recommendations
NC1 Recommendation	Ensure annual quarry data is provided to DRG once portal is active.
NC2 Recommendation (Note; this recommendation addresses NC6, NC22	 Review noise monitoring locations – should road and traffic noise be considered an issue an alternative location may be appropriate.
NC3 Recommendation (Note; this recommendation addresses NC4, NC21, NC23, NC26 and NC27)	 Determine root cause of the HVAS failures and appropriately action corrective measures. It is understood that a number of failed sampling events relate to power supply which Lynwood Quarry is currently in the process of improving. However, it is noted that a number of failed sampling attempts related to the run time of the HVAS or the days set. This may be improved by detailed operating procedures to reduce the risk of operator error. Review DDG data, should a result be contaminated remove the result from the annual average data set as this appears to be artificially increasing the average values.
NC5 Recommendation	• It is recommended event based inspections of SDs be implemented to ensure that adequate capacity is maintained to reduce the risk of discharge events.
NC6 Recommendation	 Section 3.1 of the Rehabilitation and Landscape Management Plan (2018) to be updated to account for next 5 years, i.e. 2024 to 2029.
NC7 Recommendation	Ensure management plans, following updates if required, are issued to DPHI following IEAs.
NC8 Recommendation (Note; this recommendation also addresses NC9, NC10 and NC11)	Review and if necessary revise the rehabilitation bond to the satisfaction of the Secretary.
NC12 Recommendation	Ensure revisions of management plans, if required, are documented and communicated to DPHI. It is noted this recommendation relates to revision of management plans following IEAs.
NC13 Recommendation	Ensure AERs are issued to Council.
NC14 Recommendation	Ensure IEA lead auditor engaged prior to the end of the audit period in future.

Table 4.1Recommendations

Recommendation number	Recommendations
NC15 Recommendation (Note; this recommendation also addresses NC16)	 Upload response to IEAs to Holcim website if available. It is noted previous IEAs, not available online during the audit period, have since been uploaded to the Holcim website requiring no further action.
NC17 Recommendation	• As per previous audit Holcim to action previous recommendation outlined below: Recommendation 20: Close this issue out with DPHI to avoid ongoing on compliance issues at each audit. Ensure videos are taken during any future archaeological works on site.
NC18 Recommendation	Ensure noise consultant engaged for quarterly assessments relies on meteorological station required under condition 15A of Schedule 3.
NC19 Recommendation	Implement periodic community engagement surveys and community newsletters.
NC24 Recommendation (Note; this recommendation addresses NC25)	Implement process to ensure EPA is notified of incidents in future.

5 Conclusion

An independent environmental audit of Lynwood Quarry was undertaken to meet the requirements of Schedule 5, Condition 11 of DA 128-5-2005 as modified originally approved by the Minister for Planning on 21 December 2005 and the relevant policies and guidelines.

Audit evidence was collected during a site inspection on 1 February 2024 and documents provided by Holcim before and after the inspection. The audit period was 30 September 2020 to 1 February 2024. During the audit period the quarry was in normal operational phase.

The matters raised during consultation with agencies at the start of the audit have generally been addressed.

The majority of non-compliances related to:

- documentation not meeting the requirements of DA 128-5-2005 including:
 - notification of incidents or exceedances of criteria to relevant agencies within required timeframes
 - recording/filing of all information required to demonstrate compliance
 - ensuring that all management plans are reviewed and updated within the stipulated timeframes
 - ensuring that the Holcim (Australia) website is kept up to date with all of the required information
- there were also a number of noise, air quality and water non-compliances during the audit period which have been subsequently addressed.

Overall, the quarry operation is generally being undertaken in a responsible manner and, with the exceptions noted above, in accordance with DA 128-5-2005 (including the attached Statement of Commitments) and EPL 12939.

The quarry personnel interviewed generally have a good appreciation of the quarry's DA and EPL conditions, and the quarry's EMS. The requirements of these documents are being applied in a manner that considers protection of the environment within the context of the site.

Recommendations have been provided to address all non-compliances where further actions are considered to be required. A number of recommendations have been provided based on observations that were not related to non-compliances.

Appendix A

DPHI authorisation of lead auditor



Department of Planning and Environment



Our ref: DA128-5-2005-PA-53

Mr Dozie Egeonu

Environmental Manager

Holcim (Australia) Pty Ltd

Level 7 - 799

Pacific Highway

CHATSWOOD, NSW, 2067

01/12/2023

Sent via the Major Projects Portal only

Dear Mr Egeonu

Lynwood Quarry (DA 128-5-2005)

Independent Environmental Auditor 2023

I refer to your letter of 1 December 2023 seeking approval of Mr Thomas Frankham of EMM Consulting Pty Ltd as the lead auditor for the upcoming Independent Environmental Audit of Lynwood Quarry (the development), in accordance with Schedule 5, Condition 11 of development consent DA 128-5-2005, as modified (the consent).

Having considered the qualifications and experience of Mr Frankham, the Planning Secretary endorses the appointment of Mr Frankham to undertake the audit in accordance with Schedule 5, Condition 11 of the consent. This approval is conditional on Mr Frankham being independent of the development and maintaining a relevant industry accreditation as lead auditor.

Please ensure this correspondence is appended to the Independent Audit Report.

The audit is to be conducted in accordance with AS/NZS ISO 19011 Australian/New Zealand Standard: Guidelines for quality and/or environmental management systems auditing and you may wish to consider the Audit Post Approval Requirements (Department 2020 or as updated). A copy of this guideline can be located at http://planning.nsw.gov.au/Policy-and-Legislation/Mining-and-Resources/Integrated-Mining-Policy.

Department of Planning and Environment



The audit report is to include the following:

- 1. consultation with the relevant agencies and the CCC;
- 2. a compliance table indicating the compliance status of each condition of approval and any relevant EPL;
- 3. not use the term "partial compliance";
- 4. recommend actions in response to non-compliances;
- 5. review the adequacy of plans and programs required under this consent; and
- 6. identify opportunities for improved environmental management and performance.

Within 12 weeks of undertaking the site inspection, Holcim is to submit a copy of the audit report to the Planning Secretary, Council, EPA and any other NSW agency that requests it, together with its response to any recommendations contained in the audit report and a timetable to implement the recommendations. Prior to submitting the audit report to the Planning Secretary, it is recommended that Holcim review the report to ensure it complies with the relevant consent condition.

Failure to meet these requirements will require revision and resubmission of the Audit Report.

Should you have any enquiries in relation to this matter, please contact Georgia Dragicevic, Senior Compliance Officer, on (02) 4247 1852 or by email to Georgia.Dragicevic@planning.nsw.gov.au.

Yours sincerely

Katrina O'Reilly

Team Leader - Compliance

Compliance

As nominee of the Planning Secretary

Appendix B

Consultation records – public authorities



Department of Planning and Environment



Our ref: DA128-5-2005-PA-55 Mr Wayne Beattie Quarry Manager Holcim (Australia) Pty Ltd Level 8 - 799 Pacific Highway CHATSWOOD, NSW, 2067

11/12/2023

Sent via the Major Projects Portal only Dear Mr Beattie

Lynwood Quarry (DA 128-5-2005) Independent Environmental Audit 2023

I refer to your letter of 5 December 2023 seeking confirmation of the relevant agencies required to be consulted and any areas of environmental management to be considered for the upcoming Independent Environmental Audit of Lynwood Quarry (the development), in accordance with Schedule 5, Condition 11 of development consent DA 128-5-2005, as modified (the consent).

I advise that:

- the relevant agencies to be consulted may include: Environment Protection Authority, Goulburn Mulwaree Council, Department of Primary Industries Fisheries and Water or their successors, and the Community Consultative Committee;
- the area of environmental management that should be considered, in particular, includes management of air quality.

Notwithstanding the above, it is your responsibility to ensure the Independent Environmental Audit is undertaken in accordance with Schedule 5, Condition 11 of the consent.

Should you have any enquiries in relation to this matter, please contact Georgia Dragicevic, Senior Compliance Officer, on (02) 4247 1852 or by email to Georgia. Dragicevic@planning.nsw.gov.au.

Yours sincerely

Katrina O'Reilly

Team Leader - Compliance

Compliance

As nominee of the Planning Secretary

Department of Planning and Environment







Department of Primary Industries - Fisheries Via email: information-advisory@dpi.nsw.gov.au

Re: Lynwood Quarry (DA 128-5-2005) - Independent Environment Audit

Dear Officer

EMM Consulting (EMM) has been engaged by Lynwood Quarry to undertake the 2023 Independent Environmental Audit (IEA). The IEA is required in accordance with Schedule 5, Condition 11 of development consent DA 128-5-2005, as modified.

In accordance with Section 3.2 of the Department of Planning and Environment's (the Department) *Independent Audit – Post Approval Requirements* (2020), EMM has sought advice from the Department in regard to other parties or agencies who should be consulted to assist in informing the scope of the IEA. The Department has advised that the Department of Primary Industries - Fisheries (DPI - Fisheries) be consulted and advice sort regarding any areas of compliance or environmental management at Lynwood Quarry, that should be of particular focus and included within the IEA scope.

Broadly the current IEA scope includes:

- assessing the environmental performance of Lynwood Quarry and its compliance with DA 128-5-2005,
 Environment Protection Licence (EPL 12939), Mining Leases and Water Licences;
- reviewing the adequacy of strategies and all management plans or programs required under DA 128-5-2005 including whether Lynwood Quarry has met the progressive performance and completion criteria; and
- if necessary, recommending appropriate measures or actions to improve the environmental performance.

Scope considerations received from the DPI - Fisheries will be recorded and reported in the IEA, to be submitted to the Department and made publicly available.

It would be appreciated if the DPI - Fisheries could advise EMM of any IEA scope considerations by 19 December 2023, via the contact details provided below.

Thank you for your assistance in this matter.

Yours sincerely

Thomas Frankham

Associate Environmental Scientist | Certified Lead Auditor (Exemplar Global, CN 207528) tfrankham@emmconsulting.com.au





Lynwood Quarry – NSW Environmental Protection Authority Via email: info@epa.nsw.gov.au

CC: Vanessa O'Keefe - Operations Officer

Via email - Vanessa.OKeefe@epa.nsw.gov.au

Re: Lynwood Quarry (DA 128-5-2005) - Independent Environment Audit

Dear Officer

EMM Consulting (EMM) has been engaged by Lynwood Quarry to undertake the 2023 Independent Environmental Audit (IEA). The IEA is required in accordance with Schedule 5, Condition 11 of development consent DA 128-5-2005, as modified.

In accordance with Section 3.2 of the Department of Planning and Environment's (the Department) *Independent Audit – Post Approval Requirements* (2020), EMM has sought advice from the Department in regard to other parties or agencies who should be consulted to assist in informing the scope of the IEA. The Department has advised that the NSW Environmental Protection Agency (EPA) be consulted and advice sort regarding any areas of compliance or environmental management at Lynwood Quarry, that should be of particular focus and included within the IEA scope.

Broadly the current IEA scope includes:

- assessing the environmental performance of Lynwood Quarry and its compliance with DA 128-5-2005,
 Environment Protection Licence (EPL 12939), Mining Leases and Water Licences;
- reviewing the adequacy of strategies and all management plans or programs required under DA 128-5-2005 including whether Lynwood Quarry has met the progressive performance and completion criteria; and
- if necessary, recommending appropriate measures or actions to improve the environmental performance.

Scope considerations received from the EPA will be recorded and reported in the IEA, to be submitted to the Department and made publicly available.

It would be appreciated if the EPA could advise EMM of any IEA scope considerations by 19 December 2023, via the contact details provided below.

Thank you for your assistance in this matter.

Yours sincerely

Thomas Frankham

Associate Environmental Scientist | Certified Lead Auditor (Exemplar Global, CN 207528) tfrankham@emmconsulting.com.au





Goulburn Mulwaree Council
Via email: council@goulburn.nsw.gov.au

Re: Lynwood Quarry (DA 128-5-2005) - Independent Environment Audit

Dear Officer

EMM Consulting (EMM) has been engaged by Lynwood Quarry to undertake the 2023 Independent Environmental Audit (IEA). The IEA is required in accordance with Schedule 5, Condition 11 of development consent DA 128-5-2005, as modified.

In accordance with Section 3.2 of the Department of Planning and Environment's (the Department) *Independent Audit – Post Approval Requirements* (2020), EMM has sought advice from the Department in regard to other parties or agencies who should be consulted to assist in informing the scope of the IEA. The Department has advised that the Goulburn Mulwaree Council (Council) be consulted and advice sort regarding any areas of compliance or environmental management at Lynwood Quarry, that should be of particular focus and included within the IEA scope.

Broadly the current IEA scope includes:

- assessing the environmental performance of Lynwood Quarry and its compliance with DA 128-5-2005,
 Environment Protection Licence (EPL 12939), Mining Leases and Water Licences;
- reviewing the adequacy of strategies and all management plans or programs required under DA 128-5-2005 including whether Lynwood Quarry has met the progressive performance and completion criteria; and
- if necessary, recommending appropriate measures or actions to improve the environmental performance.

Scope considerations received from the Council will be recorded and reported in the IEA, to be submitted to the Department and made publicly available.

It would be appreciated if the Council could advise EMM of any IEA scope considerations by 19 December 2023, via the contact details provided below.

Thank you for your assistance in this matter.

Yours sincerely

Thomas Frankham

Associate Environmental Scientist | Certified Lead Auditor (Exemplar Global, CN 207528) tfrankham@emmconsulting.com.au





NSW Department of Planning and Environment, Water Division via email: water.enquiries@dpie.nsw.gov.au

Re: Lynwood Quarry (DA 128-5-2005) - Independent Environment Audit

Dear Officer

EMM Consulting (EMM) has been engaged by Lynwood Quarry to undertake the 2023 Independent Environmental Audit (IEA). The IEA is required in accordance with Schedule 5, Condition 11 of development consent DA 128-5-2005, as modified.

In accordance with Section 3.2 of the Department of Planning and Environment's (the Department) *Independent Audit – Post Approval Requirements* (2020), EMM has sought advice from the Department in regard to other parties or agencies who should be consulted to assist in informing the scope of the IEA. The Department has advised that the Department of Planning and Environment – Water Division (DPE - Water) be consulted and advice sort regarding any areas of compliance or environmental management at Lynwood Quarry, that should be of particular focus and included within the IEA scope.

Broadly the current IEA scope includes:

- assessing the environmental performance of Lynwood Quarry and its compliance with DA 128-5-2005,
 Environment Protection Licence (EPL 12939), Mining Leases and Water Licences;
- reviewing the adequacy of strategies and all management plans or programs required under DA 128-5-2005 including whether Lynwood Quarry has met the progressive performance and completion criteria; and
- if necessary, recommending appropriate measures or actions to improve the environmental performance.

Scope considerations received from the DPE - Water will be recorded and reported in the IEA, to be submitted to the Department and made publicly available.

It would be appreciated if the DPE - Water could advise EMM of any IEA scope considerations by 19 December 2023, via the contact details provided below.

Thank you for your assistance in this matter.

Yours sincerely

Thomas Frankham

Associate Environmental Scientist | Certified Lead Auditor (Exemplar Global, CN 207528) tfrankham@emmconsulting.com.au

DPI Fisheries - comment on scope of Lynwood Quarry - Independent Environmental Audit

Carla Ganassin < carla.ganassin@dpi.nsw.gov.au>

Wed 12/13/2023 9:10 AM

To:Thomas Frankham <ffrankham@emmconsulting.com.au>

CAUTION: This email originated outside of the Organisation.

Dear Thomas,

DPI Fisheries has received your request for advice on the scope of the Independent Environmental Audit to be conduct at Lynwood Quarry (Marulan).

This audit should assess the adequacy of surface water quality treatment measures. In particular, the effectiveness of these measures to mitigate impacts to adjoining/downstream waterways.

Event based sampling should be undertaken at downstream instream monitoring points and should be based on the ANZECC Guidelines. This sampling should specifically include TSS.

DPI Fisheries recognises that Lynwood Quarry has an approval to discharge sediment basins with a limit of 50mg/L for TSS. However, it should be noted that sediment discharges of 50mg/l (well above ANZECC guidelines) result in detrimental impacts to aquatic habitat. As a matter of best practice Lynwood Quarry should be reviewing and improving their surface water management where levels are being recorded in excess of ANZECC guidelines.

The Independent Environmental Audit should also consider whether riparian protection measures are in place.

Regards,

Carla Ganassin

Senior Fisheries Manager, Coastal Systems
DPI Fisheries | Aboriginal Fishing & Marine & Coastal Environments
Department of Regional NSW

T 4222 8342 **M** 0447 644 357 **E** <u>carla.ganassin@dpi.nsw.gov.au</u>

regional.nsw.gov.au

Block E Level 3, 84 Crown St (PO Box 5106) Wollongong NSW 2520



Message protected by MailGuard: e-mail anti-virus, anti-spam and content filtering. https://www.mailguard.com.au/mg

Report this message as spam

RE: E231253 - Lynwood Quarry IEA - Council Consultation

Scott Martin < Scott.Martin@goulburn.nsw.gov.au>

Wed 1/10/2024 11:53 AM

To:Thomas Frankham <tfrankham@emmconsulting.com.au>

Cc:Allan Young <ayoung@emmconsulting.com.au>;Michelle Frankham <mfrankham@emmconsulting.com.au>;Sarah Ainsworth sarah.ainsworth@goulburn.nsw.gov.au>

CAUTION: This email originated outside of the Organisation.

Good Morning Tom

Thank you for your correspondence. I can confirm that during the reporting period there has been nothing brought to Council's attention in relation to Holcim's operations of the Lynwood Quarry.

I can advise however, that Council has recently been made aware of potential development creep by Orica who we understand lease part of the site for the purposes of preparing explosive material. Council is in the process of preparing correspondence to Holcim in this regard.

Please advise if you require any further information.

Kind regards



Scott Martin


Director Planning & Environment

P 02 4823 4452

E Scott.Martin@goulburn.nsw.gov.au www.goulburn.nsw.gov.au

Locked Bag 22 | Goulburn NSW 2580





Goulburn Mulwaree Council acknowledge the traditional custodians of the land where the Goulburn Mulwaree Local Government operates today and pay our respects to Elders past, present and emerging.

From: Thomas Frankham < tfrankham@emmconsulting.com.au>

Sent: Tuesday, 12 December 2023 12:47 PM **To:** Council < Council@goulburn.nsw.gov.au>

Cc: Allan Young <ayoung@emmconsulting.com.au>; Michelle Frankham <mfrankham@emmconsulting.com.au>

Subject: E231253 - Lynwood Quarry IEA - Council Consultation

Hi,

Please see attached correspondence seeking agency input to the upcoming Holcim – Lynwood Quarry independent environmental audit, in accordance with Section 3.2 of the Department of Planning and Environment's Independent Audit – Post Approval Requirements (2020).

Should you have any questions regarding this correspondence please do not hesitate to contact me via the below details.

Regards,

Tom Frankham

Associate Environmental Scientist | Sector Lead - Critical Minerals



T 02 4907 4800

M 0408 358 854

LI Connect on LinkedIn

emmconsulting.com.au

NEWCASTLE | Awabakal Country, Level 3, 175 Scott Street, Newcastle NSW 2300



Please consider the environment before printing my email.

This email and any files transmitted with it are confidential and are only to be read or used by the intended recipient as it may contain confidential information. Confidentiality or privilege is not waived or lost by erroneous transmission. If you have received this email in error, or are not the intended recipient, please notify the sender immediately and delete this email from your computer. You must not disclose, distribute, copy or use the information herein if you are not the intended recipient.

Message protected by MailGuard: e-mail anti-virus, anti-spam and content filtering. https://www.mailguard.com.au/mg

Report this message as spam

Department of Planning and Environment



Our ref: OUT23/20418

Tom Frankham

EMM Consulting

Email: tfrankham@emmconsulting.com.au

15th December 2023

Subject: Lynwood Quarry 2023 Independent Environmental Audit (DA 128-5-2005)

Dear Tom,

I refer to your request seeking advice from the Department of Planning and Environment – Water (the department) on an upcoming audit for the above matter. It is understood this consultation is in accordance with conditions of approval for the project.

The department understands that the scope of the audit as outlined under the development consent and the reference guideline, "Independent Audit Post Approval Requirements (2020)" extends to at least the following:

- Identification of compliance requirements and documentation of any noncompliances.
- Assessment of the adequacy and implementation of management plans and sub plans.
- Assessment of compliance against relevant regulatory requirements and legislation.
- Assessment of compliance between actual and predicted impacts in the environmental assessment.
- Reporting requirements for management plans.
- Identification of strengths of the project in environmental management and opportunities for improvement.

The department requests that the audit address compliance with the following specific elements of the consent conditions and related legislative requirements in a manner consistent with the above audit scope:

- The requirement to prepare and implement management plans that relate to water sources and their dependent ecosystems and users, and associated impact management and mitigation. These plans may include:
 - Water Management Plans and related sub-plans eg. Site Water Balance,
 Erosion and Sediment Control Plan, Stormwater Management Plan, Surface
 and Groundwater Management Plan.
 - Extraction Plans and related sub-plans eg. Water Management Plan,
 Subsidence Management Plan.



Department of Planning and Environment

- The requirement to prepare and implement trigger action response plans for water source impacts which set clearly defined limits and actions. This is to be reported on within annual and exceedance based reporting.
- Water supply availability is clearly defined for the project.
- Water take at the site via storage, diversion, interception or extraction is clearly documented and is authorised by a relevant Water Access Licence or exemption under the Water Management (General) Regulation 2018.
- Water metering at the site is in accordance with the NSW Non-Urban Metering Framework where relevant.
- Water Access Licence/s used to account for water take by the project nominates the work where the water is being taken from.
- Annual reporting clearly documents; 1) water take, use and water source impacts, 2) compares results with previous year's, and 3) identifies exceedances and how these are managed/mitigated.

Should you have any further queries in relation to this submission please do not hesitate to contact DPE Water Assessments at water.assessments@dpie.nsw.gov.au

Yours sincerely,

Tim Baker

Senior Project Officer

Z.33d

Water Assessments

Department of Planning and Environment — Water

Appendix C
Consultation records – community







Lynwood Quarry - Community Consultative Committee Via email

Re: Lynwood Quarry (DA128-5-2005) - Independent Environment Audit

Dear Community Consultative Committee Member

EMM Consulting (EMM) has been engaged by Lynwood Quarry to undertake the 2023 Independent Environmental Audit (IEA). The IEA is required in accordance with Schedule 5 Condition 11 of development consent DA 128-5-2005 as modified, and is required to occur every 3 years. With the purpose of the IEA being to obtain an independent and objective assessment of the environmental performance and compliance status of Lynwood Quarry.

To assist in informing the IEA scope, EMM request that Community Consultative Committee (CCC) members please advise of any areas of compliance or environmental management at Lynwood Quarry, that should be of particular focus and included within the IEA scope.

Broadly the current IEA scope includes:

- to assess the environmental performance of Lynwood Quarry and its compliance with DA 128-5-2005, Environment Protection Licence (EPL 12939), Mining Leases and Water Licences;
- review the adequacy of strategies and all management plans or programs required under DA 128-5-2005 including whether Lynwood Quarry has met the progressive performance and completion criteria; and
- if necessary, recommend appropriate measures or actions to improve the environmental performance.

The IEA is to be conducted and reported to the satisfaction of the Secretary, Department of Planning and Environment (DPE), and will be conducted in accordance with the Independent Audit Post Approval Requirements (DPE, 2020).

Comments received from the CCC will be recorded and reported in the IEA, to be submitted to DPE and made publicly available. It would be appreciated if CCC members could advise of any considerations by 19 December 2023.

Thank you for your assistance in this matter.

Yours sincerely

Thomas FrankhamAssociate Environmental Scientist | Certified Lead Auditor tfrankham@emmconsulting.com.au

Appendix D Audit compliance tables

EMM

Table A.1 - Development Consent DA 128-5-2005

Requi	irement	Evidence collected	Independent Audit Findings and Recommendations	Compliance status	Unique Identification I compliance
	NISTRATIVE CONDITIONS NIMISE HARM TO THE ENVIRONMENT				
_	pplicant must implement all practicable measures to prevent and/or minimise any harm to the environment that may result from	EMM did not note any permanent environmental harm during the site inspection.	No material and environmental harm occurred during the audit period.	Compliant	
the co	onstruction, operation, or rehabilitation of the development.	,,	Ů .	·	
F APPRO		EIC EA (MOD 4) EA (MOD 2) EA (MOD 2) EA (MOD 4) EA (MODE)	The development of the control of th	Compliant	_
	pplicant must carry out the development:	EIS, EA (MOD 1), EA (MOD 2), EA (MOD 3), EA (MOD 4), EA (MOD5)	The development was carried out in accordance with the approvals and Statement of Commitments.	Compliant	
	nerally in accordance with the EIS, EA (Mod 1), EA (Mod 2), EA (Mod 3), EA (Mod 4) and EA (Mod 5); and accordance with the Development Layout Plan, the Statement of Commitments and the conditions of this consent.	Project layout plans. Statement of Commitments.			
1, ,	:: The Development Layout Plan is included in Appendix 2	Statement of communicates.			
	tatement of Commitments is included in Appendix 11				
	re is any inconsistency between the documents identified in condition 2(a), the more recent document shall prevail to the extent of consistency. The conditions of this consent shall prevail to the extent of any inconsistency with the documents identified in	Review of approval documentation and consent.	EMM did not identify any inconsistencies with the requirements of the consent during the audit	Not triggered	
- 1	tion 2(a) or the Statement of Commitments.		period.		
	pplicant shall comply with any reasonable requirement/s of the Secretary arising from the Department's assessment of:	Holcim confirmed that no requirements have been received from the Department	Holcim confirmed that no requirements have been received from the Department during the audit	Compliant	
(a) an	y strategies, plans, programs, reviews, audits, reports or correspondence that are submitted in accordance with this consent	during the audit period.	period.		
(inclu	ding any stages of these documents);	Sighted evidence of submission of management plans to the Department annually	Sighted evidence of submission of management plans to the Department annually during the audit		
(b) an	y reviews, reports or audits commissioned by the Department regarding compliance with this consent; and	during the audit period.	period.		
(c) the	e implementation of any actions or measures contained in these documents.				
ON APPROVA	AL				
	pplicant may carry out quarrying operations as part of the development until 1 January 2038. Note:	Site observation	Audit period within approved operating years.	Compliant	
	r this consent, the Applicant is required to rehabilitate lands associated with the development and carry out additional undertakings		,		
	satisfaction of the Secretary. Consequently this consent will continue to apply in all other respects other than the right to conduct				
quarry	ying operations until the rehabilitation of lands associated with the development and those undertakings have been carried out to a				
Satisfa Delete	actory standard	Natao			
		Notes Appual Review 2020, 2021, 2022, Sighted 2023, monthly toppages report	Annual reports and 2023 monthly toppages reports confirm product transported from the site was	Compliant	-
I ne A	pplicant must not transport more than 5 million tonnes of products from the site in a year.	Annual Review 2020, 2021, 2022. Sighted 2023 monthly tonnages report.	Annual reports and 2023 monthly tonnages reports confirm product transported from the site was under 5 MT.	Compliant	
The A	pplicant must not transport more than 1.5 million tonnes of product from the site in a year by road.	Annual Review 2020, 2021, 2022. Sighted 2023 monthly tonnages report.	Annual reports and 2023 monthly tonnages reports confirm product transported from the site via	Compliant	
		, , , , , , , , , , , , , , , , , , , ,	road was under 1.5 MT.	·	
TURAL ADEQ	UACY				
	pplicant must ensure that any new buildings and structures, and any alterations or additions to existing	Annual Review 2020, 2021, 2022. Confirmed by Holcim no construction activates	1	Compliant	
- 1	ngs and structures, are constructed in accordance with the relevant requirements of the BCA.	in 2023.	confirmed this did not trigger any further approvals given the nature of the works related to the		
Notes			equipment not the structure.		
- 1	Les Deut 44 a f. No. 700 4 A at the Applicant is an arised to a haring a continuous discounting and financial and a situation and a second and a situation and a second as a situation and a second as a situation and a second as a secon		1		
• Und	ler Part 4A of the EP&A Act, the Applicant is required to obtain construction and occupation certificates for any building works.				
• Und	ler Part 4A of the EP&A Act, the Applicant is required to obtain construction and occupation certificates for any building works. 8 of the EP&A Regulation sets out the detailed requirements for the certification of development.				
• Und • Part	8 of the EP&A Regulation sets out the detailed requirements for the certification of development.				
• Und • Part DLITION The A	8 of the EP&A Regulation sets out the detailed requirements for the certification of development. pplicant must ensure that all demolition work is carried out in accordance with AS 2601-2001: The Demolition of Structures, or its	Annual Review 2020, 2021, 2022. Confirmed by Holcim no demolition activates in		Not triggered	
• Und • Part DLITION The Allatest	8 of the EP&A Regulation sets out the detailed requirements for the certification of development. pplicant must ensure that all demolition work is carried out in accordance with AS 2601-2001: The Demolition of Structures, or its version.	Annual Review 2020, 2021, 2022. Confirmed by Holcim no demolition activates in 2023.		Not triggered	
• Und • Part DLITION The Allatest	8 of the EP&A Regulation sets out the detailed requirements for the certification of development. pplicant must ensure that all demolition work is carried out in accordance with AS 2601-2001: The Demolition of Structures, or its version. BLIC INFRASTRUCTURE	2023.	N/A		
• Und • Part DLITION The Aplatest ECTION OF PUI	8 of the EP&A Regulation sets out the detailed requirements for the certification of development. pplicant must ensure that all demolition work is carried out in accordance with AS 2601-2001: The Demolition of Structures, or its version. BLIC INFRASTRUCTURE s the Applicant and the applicable authority agree otherwise, the Applicant must:	2023. Annual Review 2020, 2021, 2022 do not any damage to public infrastructure of		Not triggered Not triggered	
• Und • Part LITION The A latest CTION OF PUI Unless (a) rep	8 of the EP&A Regulation sets out the detailed requirements for the certification of development. pplicant must ensure that all demolition work is carried out in accordance with AS 2601-2001: The Demolition of Structures, or its version. BLICINFRASTRUCTURE s the Applicant and the applicable authority agree otherwise, the Applicant must: pair, or pay all reasonable costs associated with repairing any public infrastructure that is damaged by the development; and	2023.	N/A		
• Und • Part LITION The Allatest CTION OF PU Unless (a) rep (b) rel	8 of the EP&A Regulation sets out the detailed requirements for the certification of development. pplicant must ensure that all demolition work is carried out in accordance with AS 2601-2001: The Demolition of Structures, or its version. BLIC INFRASTRUCTURE s the Applicant and the applicable authority agree otherwise, the Applicant must:	2023. Annual Review 2020, 2021, 2022 do not any damage to public infrastructure of	N/A		
• Und • Part LITION The A _I latest CTION OF PUI Unless (a) rep (b) rel develo	2.8 of the EP&A Regulation sets out the detailed requirements for the certification of development. pplicant must ensure that all demolition work is carried out in accordance with AS 2601-2001: The Demolition of Structures, or its version. BLIC INFRASTRUCTURE s the Applicant and the applicable authority agree otherwise, the Applicant must: pair, or pay all reasonable costs associated with repairing any public infrastructure that is damaged by the development; and locate, or pay all reasonable costs associated with relocating any public infrastructure that needs to be relocated as a result of the opment.	2023. Annual Review 2020, 2021, 2022 do not any damage to public infrastructure of	N/A		
• Und • Part LITION The An latest CTION OF PU Unless (a) rep (b) rel develo	8 of the EP&A Regulation sets out the detailed requirements for the certification of development. pplicant must ensure that all demolition work is carried out in accordance with AS 2601-2001: The Demolition of Structures, or its version. BLIC INFRASTRUCTURE s the Applicant and the applicable authority agree otherwise, the Applicant must: pair, or pay all reasonable costs associated with repairing any public infrastructure that is damaged by the development; and locate, or pay all reasonable costs associated with relocating any public infrastructure that needs to be relocated as a result of the opment. NT AND EQUIPMENT	2023. Annual Review 2020, 2021, 2022 do not any damage to public infrastructure of requirement to pay costs. Confirmed by Holcim no demolition activates in 2023.	N/A N/A	Not triggered	
• Und • Part LITION The A _I latest CTION OF PU Unless (a) rep (b) rel develo	2.8 of the EP&A Regulation sets out the detailed requirements for the certification of development. pplicant must ensure that all demolition work is carried out in accordance with AS 2601-2001: The Demolition of Structures, or its version. BLIC INFRASTRUCTURE s the Applicant and the applicable authority agree otherwise, the Applicant must: pair, or pay all reasonable costs associated with repairing any public infrastructure that is damaged by the development; and locate, or pay all reasonable costs associated with relocating any public infrastructure that needs to be relocated as a result of the opment. NT AND EQUIPMENT pplicant must ensure that all plant and equipment at the site, or used in connection with the development are:	Annual Review 2020, 2021, 2022 do not any damage to public infrastructure of requirement to pay costs. Confirmed by Holcim no demolition activates in 2023. Plant inspection sheets and OEM reports sighted.	N/A N/A DEM and plant inspection reports confirm equipment is received by site in working order and		
• Und • Part LITION The All latest CTION OF PUI Unless (a) rep (b) rel develo THON OF PLAI The Al (a) ma	8 of the EP&A Regulation sets out the detailed requirements for the certification of development. pplicant must ensure that all demolition work is carried out in accordance with AS 2601-2001: The Demolition of Structures, or its version. BLIC INFRASTRUCTURE s the Applicant and the applicable authority agree otherwise, the Applicant must: pair, or pay all reasonable costs associated with repairing any public infrastructure that is damaged by the development; and locate, or pay all reasonable costs associated with relocating any public infrastructure that needs to be relocated as a result of the opment. NT AND EQUIPMENT pplicant must ensure that all plant and equipment at the site, or used in connection with the development are: aintained in a proper and efficient conditions; and	2023. Annual Review 2020, 2021, 2022 do not any damage to public infrastructure of requirement to pay costs. Confirmed by Holcim no demolition activates in 2023.	N/A N/A	Not triggered	
• Und • Part LITION The Al latest CTION OF PU Unless (a) rep (b) rel develo The Al (a) ma	2.8 of the EP&A Regulation sets out the detailed requirements for the certification of development. pplicant must ensure that all demolition work is carried out in accordance with AS 2601-2001: The Demolition of Structures, or its version. BLIC INFRASTRUCTURE s the Applicant and the applicable authority agree otherwise, the Applicant must: pair, or pay all reasonable costs associated with repairing any public infrastructure that is damaged by the development; and locate, or pay all reasonable costs associated with relocating any public infrastructure that needs to be relocated as a result of the opment. NT AND EQUIPMENT pplicant must ensure that all plant and equipment at the site, or used in connection with the development are:	Annual Review 2020, 2021, 2022 do not any damage to public infrastructure of requirement to pay costs. Confirmed by Holcim no demolition activates in 2023. Plant inspection sheets and OEM reports sighted.	N/A N/A DEM and plant inspection reports confirm equipment is received by site in working order and	Not triggered	
• Und • Part LITION The All latest (a) rep (b) rel develo The Al (a) ma	pplicant must ensure that all demolition work is carried out in accordance with AS 2601-2001: The Demolition of Structures, or its version. BLICINFRASTRUCTURE s the Applicant and the applicable authority agree otherwise, the Applicant must: pair, or pay all reasonable costs associated with repairing any public infrastructure that is damaged by the development; and locate, or pay all reasonable costs associated with relocating any public infrastructure that needs to be relocated as a result of the opment. NT AND EQUIPMENT pplicant must ensure that all plant and equipment at the site, or used in connection with the development are: aintained in a proper and efficient conditions; and becrated in a proper and efficient manner.	Annual Review 2020, 2021, 2022 do not any damage to public infrastructure of requirement to pay costs. Confirmed by Holcim no demolition activates in 2023. Plant inspection sheets and OEM reports sighted.	N/A N/A OEM and plant inspection reports confirm equipment is received by site in working order and maintained.	Not triggered Compliant	
• Und • Part THE AI latest CTION OF PU Unless (a) reg (b) rel develor THON OF PLAI The AI (a) ma (b) op	pplicant must ensure that all demolition work is carried out in accordance with AS 2601-2001: The Demolition of Structures, or its version. BLICINFRASTRUCTURE s the Applicant and the applicable authority agree otherwise, the Applicant must: pair, or pay all reasonable costs associated with repairing any public infrastructure that is damaged by the development; and locate, or pay all reasonable costs associated with relocating any public infrastructure that needs to be relocated as a result of the opment. NT AND EQUIPMENT pplicant must ensure that all plant and equipment at the site, or used in connection with the development are: aintained in a proper and efficient conditions; and becrated in a proper and efficient manner.	Annual Review 2020, 2021, 2022 do not any damage to public infrastructure of requirement to pay costs. Confirmed by Holcim no demolition activates in 2023. Plant inspection sheets and OEM reports sighted.	N/A N/A OEM and plant inspection reports confirm equipment is received by site in working order and maintained. It is noted that uploading of 2021-22 extractive industry return has not been possible as the portal is	Not triggered Compliant	
• Und • Part LITION The Allatest CTION OF PU Unless (a) rep (b) rel develo The All (a) ma (b) op JCTION DATA	sof the EP&A Regulation sets out the detailed requirements for the certification of development. pplicant must ensure that all demolition work is carried out in accordance with AS 2601-2001: The Demolition of Structures, or its version. BLIC INFRASTRUCTURE s the Applicant and the applicable authority agree otherwise, the Applicant must: pair, or pay all reasonable costs associated with repairing any public infrastructure that is damaged by the development; and locate, or pay all reasonable costs associated with relocating any public infrastructure that needs to be relocated as a result of the opment. NT AND EQUIPMENT pplicant must ensure that all plant and equipment at the site, or used in connection with the development are: aintained in a proper and efficient conditions; and berated in a proper and efficient manner.	Annual Review 2020, 2021, 2022 do not any damage to public infrastructure of requirement to pay costs. Confirmed by Holcim no demolition activates in 2023. Plant inspection sheets and OEM reports sighted.	N/A OEM and plant inspection reports confirm equipment is received by site in working order and maintained. It is noted that uploading of 2021-22 extractive industry return has not been possible as the portal is currently notactive as advised by correspondence from Department of Regional NSW to Holcim dated	Not triggered Compliant	
• Und • Part The All latest TION OF PUI Unless (a) rep (b) rel develor The Al (a) ma (b) op CTION DATA The Al (a) pro	s of the EP&A Regulation sets out the detailed requirements for the certification of development. pplicant must ensure that all demolition work is carried out in accordance with AS 2601-2001: The Demolition of Structures, or its version. BLIC INFRASTRUCTURE s the Applicant and the applicable authority agree otherwise, the Applicant must: pair, or pay all reasonable costs associated with repairing any public infrastructure that is damaged by the development; and locate, or pay all reasonable costs associated with relocating any public infrastructure that needs to be relocated as a result of the opment. NT AND EQUIPMENT pplicant must ensure that all plant and equipment at the site, or used in connection with the development are: aintained in a proper and efficient conditions; and berated in a proper and efficient manner.	Annual Review 2020, 2021, 2022 do not any damage to public infrastructure of requirement to pay costs. Confirmed by Holcim no demolition activates in 2023. Plant inspection sheets and OEM reports sighted. Sited maintenance activities during sight inspection.	N/A OEM and plant inspection reports confirm equipment is received by site in working order and maintained. It is noted that uploading of 2021-22 extractive industry return has not been possible as the portal is currently notactive as advised by correspondence from Department of Regional NSW to Holcim dated 17 October 2022,. This is non-complaince as the report has not been submitted however the issue	Not triggered Compliant	
• Und • Part The Allatest CTION OF PU Unless (a) reg (b) rel develor The All (a) ma (b) op CCTION DATA The All (a) pro (b) inc	sof the EP&A Regulation sets out the detailed requirements for the certification of development. pplicant must ensure that all demolition work is carried out in accordance with AS 2601-2001: The Demolition of Structures, or its version. BLIC INFRASTRUCTURE s the Applicant and the applicable authority agree otherwise, the Applicant must: pair, or pay all reasonable costs associated with repairing any public infrastructure that is damaged by the development; and locate, or pay all reasonable costs associated with relocating any public infrastructure that needs to be relocated as a result of the opment. NT AND EQUIPMENT pplicant must ensure that all plant and equipment at the site, or used in connection with the development are: aintained in a proper and efficient conditions; and perated in a proper and efficient manner. pplicant must: ovide annual quarry production data to DRG using the standard form for that purpose; and	Annual Review 2020, 2021, 2022 do not any damage to public infrastructure of requirement to pay costs. Confirmed by Holcim no demolition activates in 2023. Plant inspection sheets and OEM reports sighted.	N/A OEM and plant inspection reports confirm equipment is received by site in working order and maintained. It is noted that uploading of 2021-22 extractive industry return has not been possible as the portal is currently notactive as advised by correspondence from Department of Regional NSW to Holcim dated	Not triggered Compliant	NC1
• Und • Part LITION The Aillatest CTION OF PUI Unless (a) rep (b) rel develo The Ail (a) ma (b) op JCTION DATA The Ail (a) pro (b) inc	softhe EP&A Regulation sets out the detailed requirements for the certification of development. pplicant must ensure that all demolition work is carried out in accordance with AS 2601-2001: The Demolition of Structures, or its version. BLICINFRASTRUCTURE s the Applicant and the applicable authority agree otherwise, the Applicant must: pair, or pay all reasonable costs associated with repairing any public infrastructure that is damaged by the development; and locate, or pay all reasonable costs associated with relocating any public infrastructure that needs to be relocated as a result of the opment. NT AND EQUIPMENT pplicant must ensure that all plant and equipment at the site, or used in connection with the development are: aintained in a proper and efficient conditions; and berated in a proper and efficient manner. pplicant must: ovide annual quarry production data to DRG using the standard form for that purpose; and clude a copy of this data in the Annual Review.	Annual Review 2020, 2021, 2022 do not any damage to public infrastructure of requirement to pay costs. Confirmed by Holcim no demolition activates in 2023. Plant inspection sheets and OEM reports sighted. Sited maintenance activities during sight inspection. Sighted extractive industry returns for 2019-20 and 2020-21.	N/A OEM and plant inspection reports confirm equipment is received by site in working order and maintained. It is noted that uploading of 2021-22 extractive industry return has not been possible as the portal is currently notactive as advised by correspondence from Department of Regional NSW to Holcim dated 17 October 2022,. This is non-complaince as the report has not been submitted however the issue rests with Department of Regional NSW.	Not triggered Compliant Non-compliant	NC1
Und Part LITION The Ai latest CTION OF PU Unless (a) reg (b) rel develo CTION OF PLAI The Ai (a) pro (b) inc LIANCE The Ai Th	pplicant must ensure that all demolition work is carried out in accordance with AS 2601-2001: The Demolition of Structures, or its version. BUC INFRASTRUCTURE s the Applicant and the applicable authority agree otherwise, the Applicant must: pair, or pay all reasonable costs associated with repairing any public infrastructure that is damaged by the development; and locate, or pay all reasonable costs associated with relocating any public infrastructure that needs to be relocated as a result of the opment. NT AND EQUIPMENT pplicant must ensure that all plant and equipment at the site, or used in connection with the development are: aintained in a proper and efficient conditions; and becrated in a proper and efficient manner. pplicant must: ovide annual quarry production data to DRG using the standard form for that purpose; and clude a copy of this data in the Annual Review.	Annual Review 2020, 2021, 2022 do not any damage to public infrastructure of requirement to pay costs. Confirmed by Holcim no demolition activates in 2023. Plant inspection sheets and OEM reports sighted. Sited maintenance activities during sight inspection.	N/A DEM and plant inspection reports confirm equipment is received by site in working order and maintained. It is noted that uploading of 2021-22 extractive industry return has not been possible as the portal is currently notactive as advised by correspondence from Department of Regional NSW to Holcim dated 17 October 2022,. This is non-complaince as the report has not been submitted however the issue rests with Department of Regional NSW. Induction materials included acknowledgement of the consent and relevant environmental	Not triggered Compliant	NC1
Und Part LITION The Ai latest CTION OF PU Unless (a) reg (b) rel develo CTION OF PLAI The Ai (a) pro (b) inc LIANCE The Ai Th	softhe EP&A Regulation sets out the detailed requirements for the certification of development. pplicant must ensure that all demolition work is carried out in accordance with AS 2601-2001: The Demolition of Structures, or its version. BLICINFRASTRUCTURE s the Applicant and the applicable authority agree otherwise, the Applicant must: pair, or pay all reasonable costs associated with repairing any public infrastructure that is damaged by the development; and locate, or pay all reasonable costs associated with relocating any public infrastructure that needs to be relocated as a result of the opment. NT AND EQUIPMENT pplicant must ensure that all plant and equipment at the site, or used in connection with the development are: aintained in a proper and efficient conditions; and berated in a proper and efficient manner. pplicant must: ovide annual quarry production data to DRG using the standard form for that purpose; and clude a copy of this data in the Annual Review.	Annual Review 2020, 2021, 2022 do not any damage to public infrastructure of requirement to pay costs. Confirmed by Holcim no demolition activates in 2023. Plant inspection sheets and OEM reports sighted. Sited maintenance activities during sight inspection. Sighted extractive industry returns for 2019-20 and 2020-21.	N/A DEM and plant inspection reports confirm equipment is received by site in working order and maintained. It is noted that uploading of 2021-22 extractive industry return has not been possible as the portal is currently notactive as advised by correspondence from Department of Regional NSW to Holcim dated 17 October 2022, This is non-complaince as the report has not been submitted however the issue rests with Department of Regional NSW. Induction materials included acknowledgement of the consent and relevant environmental awareness considerations.	Not triggered Compliant Non-compliant	NC1
Undestable of the Algorithm of Plant The Algorithm of Plant Unless (a) reg (b) rel develor ATION OF PLANT The Algorithm of Plant The Algorithm of Plant Undestable of the Algorithm of Plant Th	pplicant must ensure that all demolition work is carried out in accordance with AS 2601-2001: The Demolition of Structures, or its version. BLICINFRASTRUCTURE s the Applicant and the applicable authority agree otherwise, the Applicant must: pair, or pay all reasonable costs associated with repairing any public infrastructure that is damaged by the development; and locate, or pay all reasonable costs associated with relocating any public infrastructure that needs to be relocated as a result of the opment. NT AND EQUIPMENT pplicant must ensure that all plant and equipment at the site, or used in connection with the development are: aintained in a proper and efficient conditions; and berated in a proper and efficient manner. pplicant must: ovide annual quarry production data to DRG using the standard form for that purpose; and clude a copy of this data in the Annual Review. pplicant must ensure that all employees, contractors and sub-contractors are aware of, and comply with, the conditions of this int relevant to their respective activities.	Annual Review 2020, 2021, 2022 do not any damage to public infrastructure of requirement to pay costs. Confirmed by Holcim no demolition activates in 2023. Plant inspection sheets and OEM reports sighted. Sited maintenance activities during sight inspection. Sighted extractive industry returns for 2019-20 and 2020-21.	N/A DEM and plant inspection reports confirm equipment is received by site in working order and maintained. It is noted that uploading of 2021-22 extractive industry return has not been possible as the portal is currently notactive as advised by correspondence from Department of Regional NSW to Holcim dated 17 October 2022,. This is non-complaince as the report has not been submitted however the issue rests with Department of Regional NSW. Induction materials included acknowledgement of the consent and relevant environmental	Not triggered Compliant Non-compliant	NC1
• Und • Part TITION The Ai latest TITION OF PUI Unless: (a) rep develo (b) rel develo TITION OF PLAI The Ai (a) ma (b) op TTHO ATA The Ai (a) pro (b) inc ANCE The Ai consei	applicant must ensure that all demolition work is carried out in accordance with AS 2601-2001: The Demolition of Structures, or its version. BUC INFRASTRUCTURE s the Applicant and the applicable authority agree otherwise, the Applicant must: pair, or pay all reasonable costs associated with repairing any public infrastructure that is damaged by the development; and locate, or pay all reasonable costs associated with relocating any public infrastructure that needs to be relocated as a result of the opment. NT AND EQUIPMENT pplicant must ensure that all plant and equipment at the site, or used in connection with the development are: aintained in a proper and efficient conditions; and be rated in a proper and efficient manner. pplicant must: ovide annual quarry production data to DRG using the standard form for that purpose; and clude a copy of this data in the Annual Review. pplicant must ensure that all employees, contractors and sub-contractors are aware of, and comply with, the conditions of this ent relevant to their respective activities.	Annual Review 2020, 2021, 2022 do not any damage to public infrastructure of requirement to pay costs. Confirmed by Holcim no demolition activates in 2023. Plant inspection sheets and OEM reports sighted. Sited maintenance activities during sight inspection. Sighted extractive industry returns for 2019-20 and 2020-21.	N/A DEM and plant inspection reports confirm equipment is received by site in working order and maintained. It is noted that uploading of 2021-22 extractive industry return has not been possible as the portal is currently notactive as advised by correspondence from Department of Regional NSW to Holcim dated 17 October 2022, This is non-complaince as the report has not been submitted however the issue rests with Department of Regional NSW. Induction materials included acknowledgement of the consent and relevant environmental awareness considerations.	Not triggered Compliant Non-compliant	NC1
Und Part ITION The Allatest CHON OF PU Unless (a) rep (b) rel develo The Al (a) ma (b) op CTION DATA The Al (a) pro (b) inc IANCE The Al CONSE	pplicant must ensure that all demolition work is carried out in accordance with A5 2601-2001: The Demolition of Structures, or its version. BUC INFRASTRUCTURE s the Applicant and the applicable authority agree otherwise, the Applicant must: pair, or pay all reasonable costs associated with repairing any public infrastructure that is damaged by the development; and locate, or pay all reasonable costs associated with relocating any public infrastructure that needs to be relocated as a result of the opment. NT AND EQUIPMENT pplicant must ensure that all plant and equipment at the site, or used in connection with the development are: aintained in a proper and efficient conditions; and be retated in a proper and efficient manner. pplicant must: ovide annual quarry production data to DRG using the standard form for that purpose; and clude a copy of this data in the Annual Review. pplicant must ensure that all employees, contractors and sub-contractors are aware of, and comply with, the conditions of this ent relevant to their respective activities. CIFIC ENVIRONMENTAL CONDITIONS ON AND PROCESSING PROVISIONS	Annual Review 2020, 2021, 2022 do not any damage to public infrastructure of requirement to pay costs. Confirmed by Holcim no demolition activates in 2023. Plant inspection sheets and OEM reports sighted. Sited maintenance activities during sight inspection. Sighted extractive industry returns for 2019-20 and 2020-21.	N/A DEM and plant inspection reports confirm equipment is received by site in working order and maintained. It is noted that uploading of 2021-22 extractive industry return has not been possible as the portal is currently notactive as advised by correspondence from Department of Regional NSW to Holcim dated 17 October 2022, This is non-complaince as the report has not been submitted however the issue rests with Department of Regional NSW. Induction materials included acknowledgement of the consent and relevant environmental awareness considerations.	Not triggered Compliant Non-compliant	NC1
• Und • Part THE AI latest CTION OF PU Unless (a) reg (b) rel develo THE AI (a) ma (b) op CTION DATA The AI (a) pro (b) inc IANCE THE AI consei	28 of the EP&A Regulation sets out the detailed requirements for the certification of development. pplicant must ensure that all demolition work is carried out in accordance with AS 2601-2001: The Demolition of Structures, or its version. BUIL INFRASTRUCTURE s the Applicant and the applicable authority agree otherwise, the Applicant must: pair, or pay all reasonable costs associated with repairing any public infrastructure that is damaged by the development; and locate, or pay all reasonable costs associated with relocating any public infrastructure that needs to be relocated as a result of the opment. NT AND EQUIPMENT pplicant must ensure that all plant and equipment at the site, or used in connection with the development are: aintained in a proper and efficient conditions; and be reated in a proper and efficient manner. pplicant must: ovide annual quarry production data to DRG using the standard form for that purpose; and clude a copy of this data in the Annual Review. pplicant must ensure that all employees, contractors and sub-contractors are aware of, and comply with, the conditions of this ent relevant to their respective activities. CIFIC ENVIRONMENTAL CONDITIONS ON AND PROCESSING PROVISIONS undaries	Annual Review 2020, 2021, 2022 do not any damage to public infrastructure of requirement to pay costs. Confirmed by Holcim no demolition activates in 2023. Plant inspection sheets and OEM reports sighted. Sited maintenance activities during sight inspection. Sighted extractive industry returns for 2019-20 and 2020-21. Sighted induction materials.	N/A DEM and plant inspection reports confirm equipment is received by site in working order and maintained. It is noted that uploading of 2021-22 extractive industry return has not been possible as the portal is currently notactive as advised by correspondence from Department of Regional NSW to Holcim dated 17 October 2022, This is non-complaince as the report has not been submitted however the issue rests with Department of Regional NSW. Induction materials included acknowledgement of the consent and relevant environmental awareness considerations.	Not triggered Compliant Non-compliant Compliant	NC1
• Und • Part ITION The Allatest Tion OF PU Unless (a) rep (b) rel develor The All (a) ma (b) op CTION DATA The All (a) pro (b) inc IANCE The All consei	28 of the EP&A Regulation sets out the detailed requirements for the certification of development. Poplicant must ensure that all demolition work is carried out in accordance with AS 2601-2001: The Demolition of Structures, or its version. BIBLIC INFRASTRUCTURE S the Applicant and the applicable authority agree otherwise, the Applicant must: pair, or pay all reasonable costs associated with repairing any public infrastructure that is damaged by the development; and locate, or pay all reasonable costs associated with relocating any public infrastructure that needs to be relocated as a result of the opment. NT AND EQUIPMENT pplicant must ensure that all plant and equipment at the site, or used in connection with the development are: aintained in a proper and efficient conditions; and be proper and efficient manner. pplicant must: ovide annual quarry production data to DRG using the standard form for that purpose; and clude a copy of this data in the Annual Review. pplicant must ensure that all employees, contractors and sub-contractors are aware of, and comply with, the conditions of this int relevant to their respective activities. CIFIC ENVIRONMENTAL CONDITIONS ON AND PROCESSING PROVISIONS undaries to carrying out any development, or as otherwise agreed by the Secretary, the Applicant must:	Annual Review 2020, 2021, 2022 do not any damage to public infrastructure of requirement to pay costs. Confirmed by Holcim no demolition activates in 2023. Plant inspection sheets and OEM reports sighted. Sited maintenance activities during sight inspection. Sighted extractive industry returns for 2019-20 and 2020-21. Sighted induction materials.	N/A DEM and plant inspection reports confirm equipment is received by site in working order and maintained. It is noted that uploading of 2021-22 extractive industry return has not been possible as the portal is currently notactive as advised by correspondence from Department of Regional NSW to Holcim dated 17 October 2022, This is non-complaince as the report has not been submitted however the issue rests with Department of Regional NSW. Induction materials included acknowledgement of the consent and relevant environmental awareness considerations.	Not triggered Compliant Non-compliant	NC1
ITION The Allatest. ITION OF PUA Unless: (a) reg. (b) rel develc TION OF PLAI The All (a) max (b) op CTION DATA The All (a) process The All (a) process The All (a) process The All (a) process The All Conse The All Conse Prior t (a) en (a) en (b) en (b) en (c)	28 of the EP&A Regulation sets out the detailed requirements for the certification of development. Poplicant must ensure that all demolition work is carried out in accordance with AS 2601-2001: The Demolition of Structures, or its version. BUIC INFRASTRUCTURE S the Applicant and the applicable authority agree otherwise, the Applicant must: pair, or pay all reasonable costs associated with repairing any public infrastructure that is damaged by the development; and locate, or pay all reasonable costs associated with relocating any public infrastructure that needs to be relocated as a result of the opment. NT AND EQUIPMENT pplicant must ensure that all plant and equipment at the site, or used in connection with the development are: aintained in a proper and efficient conditions; and be rated in a proper and efficient manner. Pplicant must: ovide annual quarry production data to DRG using the standard form for that purpose; and clude a copy of this data in the Annual Review. pplicant must ensure that all employees, contractors and sub-contractors are aware of, and comply with, the conditions of this ent relevant to their respective activities. CIFIC ENVIRONMENTAL CONDITIONS ON AND PROCESSING PROVISIONS undaries to carrying out any development, or as otherwise agreed by the Secretary, the Applicant must: gage an independent registered surveyor:	Annual Review 2020, 2021, 2022 do not any damage to public infrastructure of requirement to pay costs. Confirmed by Holcim no demolition activates in 2023. Plant inspection sheets and OEM reports sighted. Sited maintenance activities during sight inspection. Sighted extractive industry returns for 2019-20 and 2020-21. Sighted induction materials. While no additional surveys were identified to the auditor, it is understood that the previous audit findings indicate compliance prior to development occurring.	N/A DEM and plant inspection reports confirm equipment is received by site in working order and maintained. It is noted that uploading of 2021-22 extractive industry return has not been possible as the portal is currently notactive as advised by correspondence from Department of Regional NSW to Holcim dated 17 October 2022, This is non-complaince as the report has not been submitted however the issue rests with Department of Regional NSW. Induction materials included acknowledgement of the consent and relevant environmental awareness considerations.	Not triggered Compliant Non-compliant Compliant	NC1
• Und • Part LITION The Ai latest CTION OF PU Unless: (a) reg. (b) rel develo TION OF PLAI The Ai (a) pro. (b) inc LIANCE The Ai consei AL EXTRACTIO ication of Bou • surv	and the EP&A Regulation sets out the detailed requirements for the certification of development. By plicant must ensure that all demolition work is carried out in accordance with AS 2601-2001: The Demolition of Structures, or its version. BUCINFRASTBUCTURE Step Applicant and the applicable authority agree otherwise, the Applicant must: pair, or pay all reasonable costs associated with repairing any public infrastructure that is damaged by the development; and locate, or pay all reasonable costs associated with relocating any public infrastructure that needs to be relocated as a result of the opment. NT AND EQUIPMENT pplicant must ensure that all plant and equipment at the site, or used in connection with the development are: aintained in a proper and efficient conditions; and be reated in a proper and efficient manner. Pplicant must: worde annual quarry production data to DRG using the standard form for that purpose; and clude a copy of this data in the Annual Review. Pplicant must ensure that all employees, contractors and sub-contractors are aware of, and comply with, the conditions of this int relevant to their respective activities. CIPIC ENVIRONMENTAL CONDITIONS ON AND PROCESSING PROVISIONS undaries to carrying out any development, or as otherwise agreed by the Secretary, the Applicant must: gage an independent registered surveyor: rey the boundaries of the approved limit of extraction; and	Annual Review 2020, 2021, 2022 do not any damage to public infrastructure of requirement to pay costs. Confirmed by Holcim no demolition activates in 2023. Plant inspection sheets and OEM reports sighted. Sited maintenance activities during sight inspection. Sighted extractive industry returns for 2019-20 and 2020-21. Sighted induction materials. While no additional surveys were identified to the auditor, it is understood that the previous audit findings indicate compliance prior to development occurring. Appropriate identification of operation boundary sighted by auditor during site	N/A DEM and plant inspection reports confirm equipment is received by site in working order and maintained. It is noted that uploading of 2021-22 extractive industry return has not been possible as the portal is currently notactive as advised by correspondence from Department of Regional NSW to Holcim dated 17 October 2022, This is non-complaince as the report has not been submitted however the issue rests with Department of Regional NSW. Induction materials included acknowledgement of the consent and relevant environmental awareness considerations.	Not triggered Compliant Non-compliant Compliant	NC1
• Und • Part ITION The Allatest CTION OF PU Unless (a) reg (b) rel develor The All (a) ma (b) op CTION DATA The All (a) pro (b) inc IANCE The All consein JLE 3 - SPEC AL EXTRACTIO Cation of Bou Prior t (a) en (a) surv • subr	8 of the EP&A Regulation sets out the detailed requirements for the certification of development. pplicant must ensure that all demolition work is carried out in accordance with AS 2601-2001: The Demolition of Structures, or its version. BIBLI INFASTRUCTURE sthe Applicant and the applicable authority agree otherwise, the Applicant must: pair, or pay all reasonable costs associated with repairing any public infrastructure that is damaged by the development; and locate, or pay all reasonable costs associated with relocating any public infrastructure that needs to be relocated as a result of the opment. NT AND EQUIPMENT pplicant must ensure that all plant and equipment at the site, or used in connection with the development are: aintained in a proper and efficient conditions; and be reated in a proper and efficient manner. Applicant must: ovide annual quarry production data to DRG using the standard form for that purpose; and clude a copy of this data in the Annual Review. pplicant must ensure that all employees, contractors and sub-contractors are aware of, and comply with, the conditions of this int relevant to their respective activities. CIPIC ENVIRONMENTAL CONDITIONS ON AND PROCESSING PROVISIONS undaries to carrying out any development, or as otherwise agreed by the Secretary, the Applicant must: gage an independent registered surveyor: rey the boundaries of the approved limit of extraction; and mit a survey plan of these boundaries to the Department;	Annual Review 2020, 2021, 2022 do not any damage to public infrastructure of requirement to pay costs. Confirmed by Holcim no demolition activates in 2023. Plant inspection sheets and OEM reports sighted. Sited maintenance activities during sight inspection. Sighted extractive industry returns for 2019-20 and 2020-21. Sighted induction materials. While no additional surveys were identified to the auditor, it is understood that the previous audit findings indicate compliance prior to development occurring.	N/A DEM and plant inspection reports confirm equipment is received by site in working order and maintained. It is noted that uploading of 2021-22 extractive industry return has not been possible as the portal is currently notactive as advised by correspondence from Department of Regional NSW to Holcim dated 17 October 2022, This is non-complaince as the report has not been submitted however the issue rests with Department of Regional NSW. Induction materials included acknowledgement of the consent and relevant environmental awareness considerations.	Not triggered Compliant Non-compliant Compliant	NC1
• Und • Part ITION The Allatest CTION OF PU Unless (a) reg (b) rel develo The Al (a) ma (b) op CTION DATA The Al (a) pro (b) inc IANCE The Al conse ULE 3 - SPEC AL EXTRACTIO (cation of Bou Prior t (a) eng • surv • subr (b) ens	and the EP&A Regulation sets out the detailed requirements for the certification of development. By plicant must ensure that all demolition work is carried out in accordance with AS 2601-2001: The Demolition of Structures, or its version. BUCINFRASTBUCTURE Step Applicant and the applicable authority agree otherwise, the Applicant must: pair, or pay all reasonable costs associated with repairing any public infrastructure that is damaged by the development; and locate, or pay all reasonable costs associated with relocating any public infrastructure that needs to be relocated as a result of the opment. NT AND EQUIPMENT pplicant must ensure that all plant and equipment at the site, or used in connection with the development are: aintained in a proper and efficient conditions; and be reated in a proper and efficient manner. Pplicant must: worde annual quarry production data to DRG using the standard form for that purpose; and clude a copy of this data in the Annual Review. Pplicant must ensure that all employees, contractors and sub-contractors are aware of, and comply with, the conditions of this int relevant to their respective activities. CIPIC ENVIRONMENTAL CONDITIONS ON AND PROCESSING PROVISIONS undaries to carrying out any development, or as otherwise agreed by the Secretary, the Applicant must: gage an independent registered surveyor: rey the boundaries of the approved limit of extraction; and	Annual Review 2020, 2021, 2022 do not any damage to public infrastructure of requirement to pay costs. Confirmed by Holcim no demolition activates in 2023. Plant inspection sheets and OEM reports sighted. Sited maintenance activities during sight inspection. Sighted extractive industry returns for 2019-20 and 2020-21. Sighted induction materials. While no additional surveys were identified to the auditor, it is understood that the previous audit findings indicate compliance prior to development occurring. Appropriate identification of operation boundary sighted by auditor during site	N/A DEM and plant inspection reports confirm equipment is received by site in working order and maintained. It is noted that uploading of 2021-22 extractive industry return has not been possible as the portal is currently notactive as advised by correspondence from Department of Regional NSW to Holcim dated 17 October 2022, This is non-complaince as the report has not been submitted however the issue rests with Department of Regional NSW. Induction materials included acknowledgement of the consent and relevant environmental awareness considerations.	Not triggered Compliant Non-compliant Compliant	NC1
• Und • Part ITION The All latest CTION OF PU Unless: (a) rep (b) rel develo TION OF PLAI The Al (a) ma (b) op CTION DATA The Al (a) pro (b) inc IANCE The Al consei Prior t (a) en • surv • subr (b) eless	28 of the EP&A Regulation sets out the detailed requirements for the certification of development. Poplicant must ensure that all demolition work is carried out in accordance with AS 2601-2001: The Demolition of Structures, or its version. BIGLINFRASTRUCTURE St he Applicant and the applicable authority agree otherwise, the Applicant must: pair, or pay all reasonable costs associated with repairing any public infrastructure that is damaged by the development; and locate, or pay all reasonable costs associated with relocating any public infrastructure that needs to be relocated as a result of the opment. NT AND EQUIPMENT policant must ensure that all plant and equipment at the site, or used in connection with the development are: aintained in a proper and efficient conditions; and be reated in a proper and efficient manner. Poplicant must: poplicant must: poplicant must: poplicant must: poplicant must ensure that all employees, contractors and sub-contractors are aware of, and comply with, the conditions of this ent relevant to their respective activities. CIFIC ENVIRONMENTAL CONDITIONS ON AND PROCESSING PROVISIONS undaries to carrying out any development, or as otherwise agreed by the Secretary, the Applicant must: gage an independent registered surveyor: rey the boundaries of the approved limit of extraction; and mit a survey plan of these boundaries are clearly marked at all times in a permanent manner that allows operating staff and inspecting officers survey plan of these boundaries are clearly marked at all times in a permanent manner that allows operating staff and inspecting officers	Annual Review 2020, 2021, 2022 do not any damage to public infrastructure of requirement to pay costs. Confirmed by Holcim no demolition activates in 2023. Plant inspection sheets and OEM reports sighted. Sited maintenance activities during sight inspection. Sighted extractive industry returns for 2019-20 and 2020-21. Sighted induction materials. While no additional surveys were identified to the auditor, it is understood that the previous audit findings indicate compliance prior to development occurring. Appropriate identification of operation boundary sighted by auditor during site	N/A DEM and plant inspection reports confirm equipment is received by site in working order and maintained. It is noted that uploading of 2021-22 extractive industry return has not been possible as the portal is currently notactive as advised by correspondence from Department of Regional NSW to Holcim dated 17 October 2022. This is non-complaince as the report has not been submitted however the issue rests with Department of Regional NSW. Induction materials included acknowledgement of the consent and relevant environmental awareness considerations. Lead auditor also provided visitor induction which included acknowledgement of the Consent.	Not triggered Compliant Non-compliant Compliant	NC1
Und Part ITION The Allatest TION OF PUA Unless (a) rep (b) rel develc TION OF PLAI The Al (a) max (b) op The Al consei IANCE The Al consei IANCE The Al consei IANCE The Al consei IANCE Prior t (a) en (b) en (b) en (c)	28 of the EP&A Regulation sets out the detailed requirements for the certification of development. 29 opplicant must ensure that all demolition work is carried out in accordance with AS 2601-2001: The Demolition of Structures, or its version. 20 opplicant and the applicable authority agree otherwise, the Applicant must: 20 pair, or pay all reasonable costs associated with repairing any public infrastructure that is damaged by the development; and locate, or pay all reasonable costs associated with relocating any public infrastructure that needs to be relocated as a result of the opment. 20	Annual Review 2020, 2021, 2022 do not any damage to public infrastructure of requirement to pay costs. Confirmed by Holcim no demolition activates in 2023. Plant inspection sheets and OEM reports sighted. Sited maintenance activities during sight inspection. Sighted extractive industry returns for 2019-20 and 2020-21. Sighted induction materials. While no additional surveys were identified to the auditor, it is understood that the previous audit findings indicate compliance prior to development occurring. Appropriate identification of operation boundary sighted by auditor during site	N/A DEM and plant inspection reports confirm equipment is received by site in working order and maintained. It is noted that uploading of 2021-22 extractive industry return has not been possible as the portal is currently notactive as advised by correspondence from Department of Regional NSW to Holcim dated 17 October 2022. This is non-complaince as the report has not been submitted however the issue rests with Department of Regional NSW. Induction materials included acknowledgement of the consent and relevant environmental awareness considerations. Lead auditor also provided visitor induction which included acknowledgement of the Consent.	Not triggered Compliant Non-compliant Compliant	NC1
• Und • Part THE All latest CTION OF PU Unless (a) reg (b) rel develor The All (a) ma (b) op CTION DATA The All (a) pro (b) inc IANCE The All conseive JLE 3 - SPEC AL EXTRACTION Cation of Boul Prior t (a) en (b) en • surv • subr (b) en The All appro	pplicant must ensure that all demolition work is carried out in accordance with AS 2601-2001: The Demolition of Structures, or its version. BUCINFRASTRUCTURE S the Applicant and the applicable authority agree otherwise, the Applicant must: pair, or pay all reasonable costs associated with repairing any public infrastructure that is damaged by the development; and locate, or pay all reasonable costs associated with relocating any public infrastructure that needs to be relocated as a result of the opment. NT AND EQUIPMENT pplicant must ensure that all plant and equipment at the site, or used in connection with the development are: aintained in a proper and efficient conditions; and development and proper and efficient manner. Pplicant must: powde annual quarry production data to DRG using the standard form for that purpose; and clude a copy of this data in the Annual Review. pplicant must ensure that all employees, contractors and sub-contractors are aware of, and comply with, the conditions of this int relevant to their respective activities. CIFIC ENVIRONMENTAL CONDITIONS ON AND PROCESSING PROVISIONS undaries to carrying out any development, or as otherwise agreed by the Secretary, the Applicant must: gage an independent registered surveyor: eye; the boundaries of the approved limit of extraction; and mit a survey plan of these boundaries to the Department; sure that these boundaries are clearly marked at all times in a permanent manner that allows operating staff and inspecting officers are advised to the conditions of the popular must be carried out in accordance with an approved Riparian Area Management Plan (see	Annual Review 2020, 2021, 2022 do not any damage to public infrastructure of requirement to pay costs. Confirmed by Holcim no demolition activates in 2023. Plant inspection sheets and OEM reports sighted. Sited maintenance activities during sight inspection. Sighted extractive industry returns for 2019-20 and 2020-21. Sighted induction materials. While no additional surveys were identified to the auditor, it is understood that the previous audit findings indicate compliance prior to development occurring. Appropriate identification of operation boundary sighted by auditor during site	N/A OEM and plant inspection reports confirm equipment is received by site in working order and maintained. It is noted that uploading of 2021-22 extractive industry return has not been possible as the portal is currently notactive as advised by correspondence from Department of Regional NSW to Holcim dated 17 October 2022,. This is non-complaince as the report has not been submitted however the issue rests with Department of Regional NSW. Induction materials included acknowledgement of the consent and relevant environmental awareness considerations. Lead auditor also provided visitor induction which included acknowledgement of the Consent. Sighted previous audit findings and appropriate operational are fencing.	Not triggered Compliant Non-compliant Compliant Compliant	NC1
Und Part ITION The Ai latest ITION OF PLAI The Ai (a) pro (b) inc The Ai (a) pro (b) inc ITION OF PLAI The Ai (a) pro (b) inc ITION OF PLAI The Ai (a) pro (b) inc ITION OF PLAI The Ai (a) pro (b) inc ITION OF PLAI The Ai (a) pro (b) inc ITION OF PLAI The Ai (a) pro (b) inc ITION OF PLAI The Ai (a) pro (b) inc ITION OF PLAI The Ai (a) pro (b) inc ITION OF PLAI The Ai (a) en (b) en (c) en (c) en (d)	pplicant must ensure that all demolition work is carried out in accordance with AS 2601-2001: The Demolition of Structures, or its version. BIGLINFRASTRUCTURE s the Applicant and the applicable authority agree otherwise, the Applicant must: pair, or pay all reasonable costs associated with repairing any public infrastructure that is damaged by the development; and locate, or pay all reasonable costs associated with relocating any public infrastructure that needs to be relocated as a result of the opment. NT AND EQUIPMENT pplicant must ensure that all plant and equipment at the site, or used in connection with the development are: aintained in a proper and efficient conditions; and verated in a proper and efficient manner. Supplicant must: ovide annual quarry production data to DRG using the standard form for that purpose; and clude a copy of this data in the Annual Review. pplicant must ensure that all employees, contractors and sub-contractors are aware of, and comply with, the conditions of this ent relevant to their respective activities. CIPIC ENVIRONMENTAL CONDITIONS ON AND PROCESSING PROVISIONS undaries to carrying out any development, or as otherwise agreed by the Secretary, the Applicant must: agage an independent registered surveyor: try the boundaries of the approved limit of extraction; and mit a survey plan of these boundaries to the Department; sure that these boundaries are clearly marked at all times in a permanent manner that allows operating staff and inspecting officers activities that these boundaries are clearly marked at all times in a permanent manner that allows operating staff and inspecting officers activities that these boundaries are clearly marked at all times in a permanent manner that allows operating staff and inspecting officers activities that these boundaries are clearly marked at all times in a permanent manner that allows operating staff and inspecting officers activities.	Annual Review 2020, 2021, 2022 do not any damage to public infrastructure of requirement to pay costs. Confirmed by Holcim no demolition activates in 2023. Plant inspection sheets and OEM reports sighted. Sited maintenance activities during sight inspection. Sighted extractive industry returns for 2019-20 and 2020-21. Sighted induction materials. While no additional surveys were identified to the auditor, it is understood that the previous audit findings indicate compliance prior to development occurring. Appropriate identification of operation boundary sighted by auditor during site inspection.	N/A OEM and plant inspection reports confirm equipment is received by site in working order and maintained. It is noted that uploading of 2021-22 extractive industry return has not been possible as the portal is currently notactive as advised by correspondence from Department of Regional NSW to Holcim dated 17 October 2022, This is non-complaince as the report has not been submitted however the issue rests with Department of Regional NSW. Induction materials included acknowledgement of the consent and relevant environmental awareness considerations. Lead auditor also provided visitor induction which included acknowledgement of the Consent. Sighted previous audit findings and appropriate operational are fencing.	Not triggered Compliant Non-compliant Compliant Compliant	NC1

Assessment Location LAeq (15 minute) LAe	owned land. Evening Night I (15 minute) LAcq (15 minute) 35 35 45 35 45 35 45 35 45 37 35 46 37 35 46 38 35 55 39 37 56 42 40 53 36 47 37 36 47 37 36 47 37 36 47 37 36 47 38 37 47 35 35 47 35 35 47 35 35 47	relopment does not exceed the criteria in	Annual Review 2020, 2021, 2022. 2023 Quarterly Monitoring Reports	Noise is monitored quarterly at four locations which are representative of the receivers listed in Table 1. 2020, 21 and 22 AERs states that four quarterly monitoring events took place within each reporting period and found that review of all documents confirmed that operation noise complied with legislative noise emission requirements. In Sept 2023, a negligible exceedance (1dB) was observed at N1 during the evening monitored period with an estimated quarry contribution of 36 LAeq (15min) dBA against a criteria of 35 LAeq (15min) dBA. The LA1 quarry contribution also exceeded the LA1(1min) (dBA) criteria for all locations but it was noted that LA1 was dominated by birds, road traffic and/or a passing train at each location.		NC2
Noise genera Airblast overpressure level (dB(Lin Peak))	Allowable exceedance	levant requirements of the INP (as may be	Annual Review 2020, 2021, 2022.	Quarterly noise reports refence the INP.	Compliant	
updated fron	5% of the total number of blasts over a period of 12 months	ınder which these criteria apply and the	2023 Quarterly Monitoring Reports	No agreements established with neighbouring land holders.		
requirement: 120	0%					
However, the Table 3: Airblast overpressure impact asse	essment criteria Applicant has advised the Department in w	wner/s of the relevant residence or land to				
generate nighter noise levels, and the r	applicant has davised the Department in the	vitting of the terms of this agreement.				
gation Measures						
The Applicant must:			Note.			
(a) implement best practice management	to minimise the operational noise of the devel	opment;	Lynwood Quarry Noise Management Plan 2020 Annual Review 2020, 2021, 2022	Sighted complete noise bunds.	Compliant	
			2023 Quarterly Monitoring Reports	General compliance with noise limits outlined in Table 1, in compliance documentation		
			Site observations	Reverse squawker observed		
(b) implement all reasonable and feasible	measures to minimise road transportation noi	se associated with the development;	Lynwood Quarry Noise Management Plan 2020 - Section 7		Compliant	
(c) minimise the noise impacts of the deve	elopment during meteorological conditions wh	en the noise criteria in this consent do not apply	Lynwood Quarry Noise Management Plan 2020 - Section 7		Compliant	
(see Appendix 10);						
(d) carry out regular monitoring to determ	iine whether the development is complying wi	th the relevant conditions of this consent; and	Lynwood Quarry Noise Management Plan 2020 - Section 8 Annual Review 2020, 2021, 2022 2023 Quarterly Monitoring Reports		Compliant	
(e) regularly assess noise monitoring data	and modify and/or stop operations on site to e	ensure compliance with the relevant conditions of	Lynwood Quarry Noise Management Plan 2020		Compliant	
this consent, to the satisfaction of the Sec	retary.		Annual Review 2020, 2021, 2022 2023 Quarterly Monitoring Reports	Noise data regularly assessed as part of Annual reviews. Noise levels also reviewed on receipt of quarterly reports to ensure operations are not negatively		
			Site interview - W Beattie	trending.		
G HOURS The Applicant must comply with the opera	ating hours in Table 2:		Annual Review 2020, 2021, 2022. Sighted sample of 2023 shift reports and	Annual reviews reported compliance. Shift reports and equipment tracking confirming compliance for	Compliant	
The Applicant must comply with the opera	ating hours in Table 2:		Annual Review 2020, 2021, 2022. Sighted sample of 2023 shift reports and equipment tracking.	Annual reviews reported compliance. Shift reports and equipment tracking confirming compliance for 2023.	Compliant	
The Applicant must comply with the opera	ating hours in Table 2:				Compliant	
The Applicant must comply with the opera	ating hours in Table 2:	faction of the Secretary. In addition to the			Compliant	
The Applicant must comply with the operation of the Applicant must prepare a Noise Mana standard requirements for management p	gement Plan for the development to the satisf llans (see condition 2 of Schedule 5) this plan n	nust:	Updated April 2020 Noise management Plan has been approved by DPIE - letter sighted from 15/04/2020.	Noise Management Plan (2020) has not required review since April 2020 - as confirmed by letters to DPE in accordance with Schedule 5, Condition 5 (b).		
The Applicant must comply with the operation of the Applicant must prepare a Noise Mana standard requirements for management p (a) be submitted to the Secretary for approximately appro	gement Plan for the development to the satisf llans (see condition 2 of Schedule 5) this plan n oval by 30 November 2016, unless otherwise a	nust: greed by the Secretary;	Updated April 2020 Noise management Plan has been approved by DPIE - letter sighted from 15/04/2020. Outside of audit period, previous audits confirm compliance	Noise Management Plan (2020) has not required review since April 2020 - as confirmed by letters to DPE in accordance with Schedule 5, Condition 5 (b).	Not triggered	
The Applicant must comply with the operation of the Applicant must prepare a Noise Mana standard requirements for management p (a) be submitted to the Secretary for approx (b) describe the measures that would be in	gement Plan for the development to the satisf llans (see condition 2 of Schedule 5) this plan n oval by 30 November 2016, unless otherwise a	nust: greed by the Secretary;	Updated April 2020 Noise management Plan has been approved by DPIE - letter sighted from 15/04/2020. Outside of audit period, previous audits confirm compliance Updated April 2020 Noise management Plan has been	Noise Management Plan (2020) has not required review since April 2020 - as confirmed by letters to DPE in accordance with Schedule 5, Condition 5 (b).		
The Applicant must comply with the operation of the Applicant must prepare a Noise Mana standard requirements for management p (a) be submitted to the Secretary for approximation (b) describe the measures that would be in the noise criteria in this consent;	gement Plan for the development to the satisf lans (see condition 2 of Schedule 5) this plan n oval by 30 November 2016, unless otherwise a mplemented to ensure:	nust: greed by the Secretary;	Updated April 2020 Noise management Plan has been approved by DPIE - letter sighted from 15/04/2020. Outside of audit period, previous audits confirm compliance	Noise Management Plan (2020) has not required review since April 2020 - as confirmed by letters to DPE in accordance with Schedule 5, Condition 5 (b).	Not triggered	
The Applicant must comply with the operation of the Applicant must prepare a Noise Mana standard requirements for management pto (a) be submitted to the Secretary for approximately (b) describe the measures that would be in the noise criteria in this consent; • best practice management is being employed.	gement Plan for the development to the satisf clans (see condition 2 of Schedule 5) this plan noval by 30 November 2016, unless otherwise a mplemented to ensure:	nust: greed by the Secretary;	Updated April 2020 Noise management Plan has been approved by DPIE - letter sighted from 15/04/2020. Outside of audit period, previous audits confirm compliance Updated April 2020 Noise management Plan has been	Noise Management Plan (2020) has not required review since April 2020 - as confirmed by letters to DPE in accordance with Schedule 5, Condition 5 (b). N/A	Not triggered	
The Applicant must comply with the operation of the Applicant must prepare a Noise Manastandard requirements for management p (a) be submitted to the Secretary for approximate to the operation of the noise criteria in this consent; • best practice management is being emple the noise impacts of the development and tanaly (see Appendix 10).	gement Plan for the development to the satisf Ilans (see condition 2 of Schedule 5) this plan n oval by 30 November 2016, unless otherwise a mplemented to ensure: loyed; and re minimised during meteorological conditions	nust: greed by the Secretary; • compliance with	Updated April 2020 Noise management Plan has been approved by DPIE - letter sighted from 15/04/2020. Outside of audit period, previous audits confirm compliance Updated April 2020 Noise management Plan has been approved by DPIE - letter sighted from 15/04/2020.	Noise Management Plan (2020) has not required review since April 2020 - as confirmed by letters to DPE in accordance with Schedule 5, Condition 5 (b).	Not triggered Compliant	
The Applicant must comply with the operation agement Plan The Applicant must prepare a Noise Mana standard requirements for management p (a) be submitted to the Secretary for approximate to the submitted to the sub	gement Plan for the development to the satisf Ilans (see condition 2 of Schedule 5) this plan n oval by 30 November 2016, unless otherwise a mplemented to ensure: loyed; and re minimised during meteorological conditions	nust: greed by the Secretary; • compliance with	Updated April 2020 Noise management Plan has been approved by DPIE - letter sighted from 15/04/2020. Outside of audit period, previous audits confirm compliance Updated April 2020 Noise management Plan has been	Noise Management Plan (2020) has not required review since April 2020 - as confirmed by letters to DPE in accordance with Schedule 5, Condition 5 (b). N/A N/A	Not triggered	
The Applicant must comply with the operation agement Plan The Applicant must prepare a Noise Mana standard requirements for management p (a) be submitted to the Secretary for approximate to the submitted to the secretary for approximate the noise criteria in this consent; • best practice management is being emple the noise impacts of the development and apply (see Appendix 10): (c) describe the proposed noise management agement and apply (see Appendix 10):	gement Plan for the development to the satisf clans (see condition 2 of Schedule 5) this plan no oval by 30 November 2016, unless otherwise a mplemented to ensure: loyed; and re minimised during meteorological conditions ent system; and	nust: greed by the Secretary; • compliance with	Updated April 2020 Noise management Plan has been approved by DPIE - letter sighted from 15/04/2020. Outside of audit period, previous audits confirm compliance Updated April 2020 Noise management Plan has been approved by DPIE - letter sighted from 15/04/2020. Updated April 2020 Noise management Plan has been approved by DPIE - letter sighted from 15/04/2020.	Noise Management Plan (2020) has not required review since April 2020 - as confirmed by letters to DPE in accordance with Schedule 5, Condition 5 (b). N/A	Not triggered Compliant	
The Applicant must comply with the operation of a period of the noise impacts of the development and the noise criteria in this consent; • best practice management is being emple the noise impacts of the development and the noise criberia in this consent; • best practice management is being emple the noise impacts of the development and the noise impacts of the noise impa	gement Plan for the development to the satisfilans (see condition 2 of Schedule 5) this plan noval by 30 November 2016, unless otherwise amplemented to ensure: loyed; and re minimised during meteorological conditions ent system; and be put in place to measure noise from the developredicted noise impacts for Location 11 contails	nust: greed by the Secretary; • compliance with under which the noise criteria in this consent do	Updated April 2020 Noise management Plan has been approved by DPIE - letter sighted from 15/04/2020. Outside of audit period, previous audits confirm compliance Updated April 2020 Noise management Plan has been approved by DPIE - letter sighted from 15/04/2020. Updated April 2020 Noise management Plan has been approved by DPIE - letter sighted from 15/04/2020. Updated April 2020 Noise management Plan has been approved by DPIE - letter sighted from 15/04/2020. Updated April 2020 Noise management Plan has been approved by DPIE - letter sighted from 15/04/2020.	Noise Management Plan (2020) has not required review since April 2020 - as confirmed by letters to DPE in accordance with Schedule 5, Condition 5 (b). N/A N/A Section 7.0 of Noise Management Plan (2020)	Not triggered Compliant Compliant	
The Applicant must comply with the operation of the Applicant must prepare a Noise Manastandard requirements for management p (a) be submitted to the Secretary for approximate to the submitted to the secretary for approximate the noise criteria in this consent; • best practice management is being emple the noise impacts of the development and the noise impacts of the noise management (d) include a monitoring program that will	gement Plan for the development to the satisfilans (see condition 2 of Schedule 5) this plan noval by 30 November 2016, unless otherwise amplemented to ensure: loyed; and re minimised during meteorological conditions ent system; and be put in place to measure noise from the developredicted noise impacts for Location 11 contails	nust: greed by the Secretary; • compliance with under which the noise criteria in this consent do relopment against the noise criteria in Table 1,	Updated April 2020 Noise management Plan has been approved by DPIE - letter sighted from 15/04/2020. Outside of audit period, previous audits confirm compliance Updated April 2020 Noise management Plan has been approved by DPIE - letter sighted from 15/04/2020. Updated April 2020 Noise management Plan has been approved by DPIE - letter sighted from 15/04/2020. Updated April 2020 Noise management Plan has been approved by DPIE - letter sighted from 15/04/2020. Updated April 2020 Noise management Plan has been	Noise Management Plan (2020) has not required review since April 2020 - as confirmed by letters to DPE in accordance with Schedule 5, Condition 5 (b). N/A N/A	Not triggered Compliant Compliant	

	The Applicant must implement the management plan as approved from time to time by the Secretary.	Annual Review 2020, 2021, 2022.		Compliant
		2023 quarterly monitoring reports.	The measures listed in the Noise Management Plan (2020) appear to have been implemented.	
BLASTING A	IND VIBRATION (Incorporates OEH GTA)	Site observations.	The measures instead in the Noise Management Hair (2020) appear to have been implemented.	
	erpressure Criteria			
7	The Applicant must ensure that the airblast overpressure level from blasting at the development does not exceed the criteria in Table 3 at	Annual Review 2020, 2021, 2022.	Annual reviews reported compliance. Monitoring data demonstrates compliance for 2023.	Compliant
	any residence on privately owned land.	2023 monitoring results.		
Ground Vibra	ration Impact Assessment Criteria			
8	The Applicant must ensure that the ground vibration level from blasting at the development does not exceed the criteria in Table 4 at any	Annual Review 2020, 2021, 2022.	Annual reviews reported compliance. Monitoring data demonstrates compliance for 2023.	Compliant
	residence on privately owned land, or the criteria in Table 5 for the nominated infrastructure.	2023 monitoring results.		·
	However, if the Applicant has a written agreement with the ARTC to vary the peak particle velocity for the Main Southern Railway Line in	Advised by Holcim no agreement exists		Not triggered
	Table 5, and a copy of this agreement has been forwarded to the Department, then the Applicant may exceed the limit specified in Table 5		N/A	
Operating Co	in accordance with the written agreement.		loto	
	During the development, the Applicant must implement best blasting practice to:	T	T	Compliant
	(to the satisfaction of the Director-General.)			
		Blast Management Plan (February	The Blast management Plan has been updated and the updated plan was approved by DPE on	
		2020)	03/04/2020	
9 (a)	(a) ensure that no fly rock leaves the site;	Blast Management Plan (February	No reports of fly rock leaving site. No complaints recorded regarding fly rock.	Compliant
		2020)	Section 7 of Blast Management Plan notes that blast are designed to minimise fly rock.	
9 (b)	(b) protect the safety of people, property, and livestock;	Blast Management Plan (February	Section 7, Table 8 of the Blast Management Plan (2020) notes that Holcim will identify exclusion	Compliant
		2020)	zones for each blast to protect the safety of personnel and assets.	
9 (c)	(c) minimise the dust and fume emissions from blasting on the site, to the satisfaction of the Secretary.	2020)	The 2021 and 2022 AERs and the 2023 monitoring data report compliance with the blast	Compliant
3 (0)	ley minimise the dast distriction of the secretary.	Blast Management Plan (February	management plan.	Compilate
		2020) - specifically the Blast fume management Protocol, see Section 7.1 of BMP.	3 community complaints received within the auditor period in 2020. Incident identified as closed.	
		Community complaints register.		
		Sighted completed pre blast checklist.		
		Annual Review 2020, 2021, 2022.		
		2023 monitoring results.		
Public Notice	re			
10	During the development, the Applicant must:			
10 (a)	(a) notify the landowner/occupier of any residence within 2 kilometres of the quarry pit who registers an interest in being notified about	Blast Management Plan (February	Blast Management Plan (2020) states operational control is a blast notification Process in accordance	Compliant
	the blasting schedule on site;	2020)	with Condition 10 of Schedule 3 of the Development Consent which requires Holcim to notify residents of upcoming blasts, operate a blasting hotline and keep the community informed about this	
		Blast notification produce and sighted examples dated 12.1.24 and 3.3.23 -		
			hotline.	
		notification sent via email to neighbours, nominated persons and staff.	Sighted evidence of blast notification on 12.1.24 and 3.3.23 - notification sent via email to	
10 (b)	(b) operate a blasting hotline, or alternative system agreed to by the Secretary to enable the public to get up-to-date information on		Sighted evidence of blast notification on 12.1.24 and 3.3.23 - notification sent via email to	
10 (b)	(b) operate a blasting hotline, or alternative system agreed to by the Secretary to enable the public to get up-to-date information on blasting operations at the development; and		Sighted evidence of blast notification on 12.1.24 and 3.3.23 - notification sent via email to neighbours, nominated persons and staff. Holcim maintains a blast hotline that allows the community to contact Lynwood Quarry. This hotline also allows members of the community within a two kilometre radius to register and be	
10 (b)			Sighted evidence of blast notification on 12.1.24 and 3.3.23 - notification sent via email to neighbours, nominated persons and staff. Holcim maintains a blast hotline that allows the community to contact Lynwood Quarry. This hotline also allows members of the community within a two kilometre radius to register and be notified of blasting activities.	
10 (b)		notification sent via email to neighbours, nominated persons and staff.	Sighted evidence of blast notification on 12.1.24 and 3.3.23 - notification sent via email to neighbours, nominated persons and staff. Holcim maintains a blast hotline that allows the community to contact Lynwood Quarry. This hotline also allows members of the community within a two kilometre radius to register and be	
10 (b)		notification sent via email to neighbours, nominated persons and staff. Blast Management Plan (February 2020) Blasting hotline phone number	Sighted evidence of blast notification on 12.1.24 and 3.3.23 - notification sent via email to neighbours, nominated persons and staff. Holcim maintains a blast hotline that allows the community to contact Lynwood Quarry. This hotline also allows members of the community within a two kilometre radius to register and be notified of blasting activities.	
10 (b)		notification sent via email to neighbours, nominated persons and staff. Blast Management Plan (February 2020) Blasting hotline phone number on Holcim's website; https://www.holcim.com.au/about-	Sighted evidence of blast notification on 12.1.24 and 3.3.23 - notification sent via email to neighbours, nominated persons and staff. Holcim maintains a blast hotline that allows the community to contact Lynwood Quarry. This hotline also allows members of the community within a two kilometre radius to register and be notified of blasting activities.	Compliant
	blasting operations at the development; and	notification sent via email to neighbours, nominated persons and staff. Blast Management Plan (February 2020) Blasting hotline phone number on Holcim's website; https://www.holcim.com.au/about-	Sighted evidence of blast notification on 12.1.24 and 3.3.23 - notification sent via email to neighbours, nominated persons and staff. Holcim maintains a blast hotline that allows the community to contact Lynwood Quarry. This hotline also allows members of the community within a two kilometre radius to register and be notified of blasting activities. Hotline tested 12/1 - Answered by Quarry Manager who provided details on blasting activities	Compliant
	blasting operations at the development; and	notification sent via email to neighbours, nominated persons and staff. Blast Management Plan (February 2020) Blasting hotline phone number on Holcim's website; https://www.holcim.com.au/about-us/communitylink/lynwood/contact-details	Sighted evidence of blast notification on 12.1.24 and 3.3.23 - notification sent via email to neighbours, nominated persons and staff. Holcim maintains a blast hotline that allows the community to contact Lynwood Quarry. This hotline also allows members of the community within a two kilometre radius to register and be notified of blasting activities. Hotline tested 12/1 - Answered by Quarry Manager who provided details on blasting activities Holcim maintains a blast hotline that allows the community to contact Lynwood Quarry. This hotline	Compliant
	blasting operations at the development; and	notification sent via email to neighbours, nominated persons and staff. Blast Management Plan (February 2020) Blasting hotline phone number on Holcim's website; https://www.holcim.com.au/about-us/communitylink/lynwood/contact-details Blast Management Plan (February 2020) Blasting hotline phone number	Sighted evidence of blast notification on 12.1.24 and 3.3.23 - notification sent via email to neighbours, nominated persons and staff. Holcim maintains a blast hotline that allows the community to contact Lynwood Quarry. This hotline also allows members of the community within a two kilometre radius to register and be notified of blasting activities. Hotline tested 12/1 - Answered by Quarry Manager who provided details on blasting activities Holcim maintains a blast hotline that allows the community to contact Lynwood Quarry. This hotline also allows members of the community within a two kilometre radius to register and be	Compliant
	blasting operations at the development; and	notification sent via email to neighbours, nominated persons and staff. Blast Management Plan (February 2020) Blasting hotline phone number on Holcim's website; https://www.holcim.com.au/about-us/communitylink/lynwood/contact-details Blast Management Plan (February 2020) Blasting hotline phone number on Holcim's website; https://www.holcim.com.au/about-	Sighted evidence of blast notification on 12.1.24 and 3.3.23 - notification sent via email to neighbours, nominated persons and staff. Holcim maintains a blast hotline that allows the community to contact Lynwood Quarry. This hotline also allows members of the community within a two kilometre radius to register and be notified of blasting activities. Hotline tested 12/1 - Answered by Quarry Manager who provided details on blasting activities Holcim maintains a blast hotline that allows the community to contact Lynwood Quarry. This hotline also allows members of the community within a two kilometre radius to register and be	Compliant
	blasting operations at the development; and (c) keep the public informed about this hotline (or any alternative system).	notification sent via email to neighbours, nominated persons and staff. Blast Management Plan (February 2020) Blasting hotline phone number on Holcim's website; https://www.holcim.com.au/about-us/communitylink/lynwood/contact-details Blast Management Plan (February 2020) Blasting hotline phone number on Holcim's website; https://www.holcim.com.au/about-	Sighted evidence of blast notification on 12.1.24 and 3.3.23 - notification sent via email to neighbours, nominated persons and staff. Holcim maintains a blast hotline that allows the community to contact Lynwood Quarry. This hotline also allows members of the community within a two kilometre radius to register and be notified of blasting activities. Hotline tested 12/1 - Answered by Quarry Manager who provided details on blasting activities Holcim maintains a blast hotline that allows the community to contact Lynwood Quarry. This hotline also allows members of the community within a two kilometre radius to register and be	Compliant
	blasting operations at the development; and (c) keep the public informed about this hotline (or any alternative system).	notification sent via email to neighbours, nominated persons and staff. Blast Management Plan (February 2020) Blasting hotline phone number on Holcim's website; https://www.holcim.com.au/about-us/communitylink/lynwood/contact-details Blast Management Plan (February 2020) Blasting hotline phone number on Holcim's website; https://www.holcim.com.au/about-	Sighted evidence of blast notification on 12.1.24 and 3.3.23 - notification sent via email to neighbours, nominated persons and staff. Holcim maintains a blast hotline that allows the community to contact Lynwood Quarry. This hotline also allows members of the community within a two kilometre radius to register and be notified of blasting activities. Hotline tested 12/1 - Answered by Quarry Manager who provided details on blasting activities Holcim maintains a blast hotline that allows the community to contact Lynwood Quarry. This hotline also allows members of the community within a two kilometre radius to register and be	Compliant
10 (c)	(c) keep the public informed about this hotline (or any alternative system). to the satisfaction of the Secretary.	notification sent via email to neighbours, nominated persons and staff. Blast Management Plan (February 2020) Blasting hotline phone number on Holcim's website; https://www.holcim.com.au/about-us/communitylink/lynwood/contact-details Blast Management Plan (February 2020) Blasting hotline phone number on Holcim's website; https://www.holcim.com.au/about-	Sighted evidence of blast notification on 12.1.24 and 3.3.23 - notification sent via email to neighbours, nominated persons and staff. Holcim maintains a blast hotline that allows the community to contact Lynwood Quarry. This hotline also allows members of the community within a two kilometre radius to register and be notified of blasting activities. Hotline tested 12/1 - Answered by Quarry Manager who provided details on blasting activities Holcim maintains a blast hotline that allows the community to contact Lynwood Quarry. This hotline also allows members of the community within a two kilometre radius to register and be notified of blasting activities.	Compliant
10 (c) Blast Manag	blasting operations at the development; and (c) keep the public informed about this hotline (or any alternative system). to the satisfaction of the Secretary.	notification sent via email to neighbours, nominated persons and staff. Blast Management Plan (February 2020) Blasting hotline phone number on Holcim's website; https://www.holcim.com.au/about-us/communitylink/lynwood/contact-details Blast Management Plan (February 2020) Blasting hotline phone number on Holcim's website; https://www.holcim.com.au/about-us/communitylink/lynwood/contact-details Blast Management Plan (February 2020)	Sighted evidence of blast notification on 12.1.24 and 3.3.23 - notification sent via email to neighbours, nominated persons and staff. Holcim maintains a blast hotline that allows the community to contact Lynwood Quarry. This hotline also allows members of the community within a two kilometre radius to register and be notified of blasting activities. Hotline tested 12/1 - Answered by Quarry Manager who provided details on blasting activities Holcim maintains a blast hotline that allows the community to contact Lynwood Quarry. This hotline also allows members of the community within a two kilometre radius to register and be notified of blasting activities. The Blast management Plan has been updated and the updated plan was approved by DPE on 03/04/2020	Compliant Compliant Compliant
10 (c)	(c) keep the public informed about this hotline (or any alternative system). to the satisfaction of the Secretary. gement Plan The Applicant must prepare a Blast Management Plan for the development to the satisfaction of the Secretary. In addition to the standard	notification sent via email to neighbours, nominated persons and staff. Blast Management Plan (February 2020) Blasting hotline phone number on Holcim's website; https://www.holcim.com.au/about-us/communitylink/lynwood/contact-details Blast Management Plan (February 2020) Blasting hotline phone number on Holcim's website; https://www.holcim.com.au/about-us/communitylink/lynwood/contact-details Blast Management Plan (February 2020)	Sighted evidence of blast notification on 12.1.24 and 3.3.23 - notification sent via email to neighbours, nominated persons and staff. Holcim maintains a blast hotline that allows the community to contact Lynwood Quarry. This hotline also allows members of the community within a two kilometre radius to register and be notified of blasting activities. Hotline tested 12/1 - Answered by Quarry Manager who provided details on blasting activities Holcim maintains a blast hotline that allows the community to contact Lynwood Quarry. This hotline also allows members of the community within a two kilometre radius to register and be notified of blasting activities. The Blast management Plan has been updated and the updated plan was approved by DPE on 03/04/2020 Section 2 of BMP noted plan issued to DPE November 2016 and that further consultation has	Compliant
10 (c) Blast Manag	(c) keep the public informed about this hotline (or any alternative system). to the satisfaction of the Secretary. the Applicant must prepare a Blast Management Plan for the development to the satisfaction of the Secretary. In addition to the standard requirements for management plans (see condition 2 of Schedule 5) this plan must:	notification sent via email to neighbours, nominated persons and staff. Blast Management Plan (February 2020) Blasting hotline phone number on Holcim's website; https://www.holcim.com.au/about-us/communitylink/lynwood/contact-details Blast Management Plan (February 2020) Blasting hotline phone number on Holcim's website; https://www.holcim.com.au/about-us/communitylink/lynwood/contact-details Blast Management Plan (February 2020)	Sighted evidence of blast notification on 12.1.24 and 3.3.23 - notification sent via email to neighbours, nominated persons and staff. Holcim maintains a blast hotline that allows the community to contact Lynwood Quarry. This hotline also allows members of the community within a two kilometre radius to register and be notified of blasting activities. Hotline tested 12/1 - Answered by Quarry Manager who provided details on blasting activities Holcim maintains a blast hotline that allows the community to contact Lynwood Quarry. This hotline also allows members of the community within a two kilometre radius to register and be notified of blasting activities. The Blast management Plan has been updated and the updated plan was approved by DPE on 03/04/2020	Compliant Compliant Compliant Compliant
10 (c) Blast Manag	(c) keep the public informed about this hotline (or any alternative system). to the satisfaction of the Secretary. gement Plan The Applicant must prepare a Blast Management Plan for the development to the satisfaction of the Secretary. In addition to the standard	notification sent via email to neighbours, nominated persons and staff. Blast Management Plan (February 2020) Blasting hotline phone number on Holcim's website; https://www.holcim.com.au/about-us/communitylink/lynwood/contact-details Blast Management Plan (February 2020) Blasting hotline phone number on Holcim's website; https://www.holcim.com.au/about-us/communitylink/lynwood/contact-details Blast Management Plan (February 2020)	Sighted evidence of blast notification on 12.1.24 and 3.3.23 - notification sent via email to neighbours, nominated persons and staff. Holcim maintains a blast hotline that allows the community to contact Lynwood Quarry. This hotline also allows members of the community within a two kilometre radius to register and be notified of blasting activities. Hotline tested 12/1 - Answered by Quarry Manager who provided details on blasting activities Holcim maintains a blast hotline that allows the community to contact Lynwood Quarry. This hotline also allows members of the community within a two kilometre radius to register and be notified of blasting activities. The Blast management Plan has been updated and the updated plan was approved by DPE on 03/04/2020 Section 2 of BMP noted plan issued to DPE November 2016 and that further consultation has	Compliant Compliant Compliant
10 (c) Blast Manag	(c) keep the public informed about this hotline (or any alternative system). to the satisfaction of the Secretary. the Applicant must prepare a Blast Management Plan for the development to the satisfaction of the Secretary. In addition to the standard requirements for management plans (see condition 2 of Schedule 5) this plan must:	Blast Management Plan (February 2020) Blasting hotline phone number on Holcim's website; https://www.holcim.com.au/about-us/communitylink/lynwood/contact-details Blast Management Plan (February 2020) Blasting hotline phone number on Holcim's website; https://www.holcim.com.au/about-us/communitylink/lynwood/contact-details Blast Management Plan (February 2020) Blast Management Plan (February 2020) Blast Management Plan (February 2020) DPE approval of BMP from DPE dated 3/4/2020 (Approval letter)	Sighted evidence of blast notification on 12.1.24 and 3.3.23 - notification sent via email to neighbours, nominated persons and staff. Holcim maintains a blast hotline that allows the community to contact Lynwood Quarry. This hotline also allows members of the community within a two kilometre radius to register and be notified of blasting activities. Hotline tested 12/1 - Answered by Quarry Manager who provided details on blasting activities Holcim maintains a blast hotline that allows the community to contact Lynwood Quarry. This hotline also allows members of the community within a two kilometre radius to register and be notified of blasting activities. The Blast management Plan has been updated and the updated plan was approved by DPE on 03/04/2020 Section 2 of BMP noted plan issued to DPE November 2016 and that further consultation has occurred annual in accordance with regular reviews.	Compliant Compliant Compliant Compliant
10 (c) Blast Manag	(c) keep the public informed about this hotline (or any alternative system). to the satisfaction of the Secretary. the Applicant must prepare a Blast Management Plan for the development to the satisfaction of the Secretary. In addition to the standard requirements for management plans (see condition 2 of Schedule 5) this plan must:	notification sent via email to neighbours, nominated persons and staff. Blast Management Plan (February 2020) Blasting hotline phone number on Holcim's website; https://www.holcim.com.au/about-us/communitylink/lynwood/contact-details Blast Management Plan (February 2020) Blasting hotline phone number on Holcim's website; https://www.holcim.com.au/about-us/communitylink/lynwood/contact-details Blast Management Plan (February 2020)	Sighted evidence of blast notification on 12.1.24 and 3.3.23 - notification sent via email to neighbours, nominated persons and staff. Holcim maintains a blast hotline that allows the community to contact Lynwood Quarry. This hotline also allows members of the community within a two kilometre radius to register and be notified of blasting activities. Hotline tested 12/1 - Answered by Quarry Manager who provided details on blasting activities Holcim maintains a blast hotline that allows the community to contact Lynwood Quarry. This hotline also allows members of the community within a two kilometre radius to register and be notified of blasting activities. The Blast management Plan has been updated and the updated plan was approved by DPE on 03/04/2020 Section 2 of BMP noted plan issued to DPE November 2016 and that further consultation has	Compliant Compliant Compliant Compliant
10 (c) Blast Manag 11 11 (a)	(c) keep the public informed about this hotline (or any alternative system). to the satisfaction of the Secretary. The Applicant must prepare a Blast Management Plan for the development to the satisfaction of the Secretary. In addition to the standard requirements for management plans (see condition 2 of Schedule 5) this plan must: (a) be submitted to the Secretary for approval by 30 November 2016, unless otherwise agreed by the Secretary; (b) describe the measures that would be implemented to ensure compliance with the blast criteria and operating conditions of this consent;	Blast Management Plan (February 2020) Blasting hotline phone number on Holcim's website; https://www.holcim.com.au/about-us/communitylink/lynwood/contact-details Blast Management Plan (February 2020) Blasting hotline phone number on Holcim's website; https://www.holcim.com.au/about-us/communitylink/lynwood/contact-details Blast Management Plan (February 2020) Blast Management Plan (February 2020) Blast Management Plan (February 2020) DPE approval of BMP from DPE dated 3/4/2020 (Approval letter)	Sighted evidence of blast notification on 12.1.24 and 3.3.23 - notification sent via email to neighbours, nominated persons and staff. Holcim maintains a blast hotline that allows the community to contact Lynwood Quarry. This hotline also allows members of the community within a two kilometre radius to register and be notified of blasting activities. Hotline tested 12/1 - Answered by Quarry Manager who provided details on blasting activities Holcim maintains a blast hotline that allows the community to contact Lynwood Quarry. This hotline also allows members of the community within a two kilometre radius to register and be notified of blasting activities. The Blast management Plan has been updated and the updated plan was approved by DPE on 03/04/2020 Section 2 of BMP noted plan issued to DPE November 2016 and that further consultation has occurred annual in accordance with regular reviews.	Compliant Compliant Compliant Compliant Compliant
10 (c) Blast Manag 11 11 (a)	(c) keep the public informed about this hotline (or any alternative system). to the satisfaction of the Secretary. to the satisfaction of the Secretary. The Applicant must prepare a Blast Management Plan for the development to the satisfaction of the Secretary. In addition to the standard requirements for management plans (see condition 2 of Schedule 5) this plan must: (a) be submitted to the Secretary for approval by 30 November 2016, unless otherwise agreed by the Secretary; (b) describe the measures that would be implemented to ensure compliance with the blast criteria and operating conditions of this	Blast Management Plan (February 2020) Blasting hotline phone number on Holcim's website; https://www.holcim.com.au/about-us/communitylink/lynwood/contact-details Blast Management Plan (February 2020) Blasting hotline phone number on Holcim's website; https://www.holcim.com.au/about-us/communitylink/lynwood/contact-details Blast Management Plan (February 2020) Blast Management Plan (February 2020)	Sighted evidence of blast notification on 12.1.24 and 3.3.23 - notification sent via email to neighbours, nominated persons and staff. Holcim maintains a blast hotline that allows the community to contact Lynwood Quarry. This hotline also allows members of the community within a two kilometre radius to register and be notified of blasting activities. Hotline tested 12/1 - Answered by Quarry Manager who provided details on blasting activities Holcim maintains a blast hotline that allows the community to contact Lynwood Quarry. This hotline also allows members of the community within a two kilometre radius to register and be notified of blasting activities. The Blast management Plan has been updated and the updated plan was approved by DPE on 03/04/2020 Section 2 of BMP noted plan issued to DPE November 2016 and that further consultation has occurred annual in accordance with regular reviews. Section 2 of BMP noted plan issued to DPE November 2016 - original approval sits outside audit term. Section 8, BMP addresses Condition 11 (b)	Compliant Compliant Compliant Compliant Compliant
10 (c) Blast Manag 11 11 (a) 11 (b)	(c) keep the public informed about this hotline (or any alternative system). to the satisfaction of the Secretary. The Applicant must prepare a Blast Management Plan for the development to the satisfaction of the Secretary. In addition to the standard requirements for management plans (see condition 2 of Schedule 5) this plan must: (a) be submitted to the Secretary for approval by 30 November 2016, unless otherwise agreed by the Secretary; (b) describe the measures that would be implemented to ensure compliance with the blast criteria and operating conditions of this consent;	Blast Management Plan (February 2020) Blasting hotline phone number on Holcim's website; https://www.holcim.com.au/about-us/communitylink/lynwood/contact-details Blast Management Plan (February 2020) Blasting hotline phone number on Holcim's website; https://www.holcim.com.au/about-us/communitylink/lynwood/contact-details Blast Management Plan (February 2020)	Sighted evidence of blast notification on 12.1.24 and 3.3.23 - notification sent via email to neighbours, nominated persons and staff. Holcim maintains a blast hotline that allows the community to contact Lynwood Quarry. This hotline also allows members of the community within a two kilometre radius to register and be notified of blasting activities. Hotline tested 12/1 - Answered by Quarry Manager who provided details on blasting activities Holcim maintains a blast hotline that allows the community to contact Lynwood Quarry. This hotline also allows members of the community within a two kilometre radius to register and be notified of blasting activities. The Blast management Plan has been updated and the updated plan was approved by DPE on 03/04/2020 Section 2 of BMP noted plan issued to DPE November 2016 and that further consultation has occurred annual in accordance with regular reviews. Section 2 of BMP noted plan issued to DPE November 2016 - original approval sits outside audit term.	Compliant Compliant Compliant Compliant Compliant Compliant

	The Applicant must implement the management plan as approved from time to time by the Secretary.	I		Compliant	
	The Applicant must implement the management plan as approved from time to time by the Secretary.			Compilant	
			Blast occurred on site during audit - blasting appeared to occur in accordance with BMP.		
NB OHAHI	Y (Incorporates OEH GTA)	Blast Management Plan (February 2020)	Lack of blast related complaints suggested compliance.		
	essment Criteria				
12	The Applicant must encountry that distributed in Tables	Annual Review 2020, 2021, 2022.	It is noted during the site visit minimal dust was noted and active controls in place. It is also noted	Non-compliant	
	6-8 at any residence th Peak particle velocity (mm/s) Allowable exceedance owned land.	2023 environmental monitoring database.	that DDG6 has been removed as per correspondence to DPE from Holcim dated June 30 2023.		
	5 5% of the total number of blasts over a period of 12 months	Site observations.	A number of dust exceedances were recorded during the audit period, having being report in the		
	10 0%		2020, 2021, 2022 Annual Reviews and evident in the 2023 monitoring database. Majority of incidents		
	Construction wol Table 4: Ground vibration impact assessment criteria for residences on privately-owned land		involved missed one off sampling events or likely contamination of samples. Notable exceedances are identified below:		
	Topsoil/ overburd Peak particle velocity Infrastructure (mm/s)		- DDG6 during 2022 exceed the annual average, recording 4.74(g/m2/month). Reported to DPE, likely		
	Table Blasting 25 Main Southern Railway Line Reservoir		contamination of samples.		
	Pipeline		- HVAS1 missed sampling events a total of 8 times during 2022. Reported to DPE, due to inclement		
	Pollutant Averaging period Criterion		weather and solar power issues. -HVAS1 missed sampling events a total of 8 times during 2023. Reported to DPE, due to inclement		
	Total suspended particulate (TSP) matter		weather and solar power issues.		
			·		
	Table 6: Long term impact assessment criteria for particulate matter Notes: Table 2 only relates to construction works that are audible at any residential receivers on privately owned				
	Table • Table 2 only relates to construction works that are audible at any residential receivers on privately owned land. Construction works that are inaudible at any residential receiver may be carried out at any time. • Construction works within the Hume Hinbway reserve may be undertaken outside the hours specified in				
	Pollutant Averaging period Criterion				
	Particulate matter < 10 µm (PM ₁₀) 24 hour 50 µg/m ³				
	Table 7: Short term impact assessment criteria for particulate matter				
	Table 8: Long term impact assessment criteria for deposited dust				
	Pollutant Averaging period Maximum increase in deposited dust level deposited dust level				
	Deposited dust Annual 2 g/m²/month 4 g/m²/month				
	Table 8: Long term impact assessment criteria for deposited dust				
	Note: Deposited dust is assessed as insoluble solids as defined by Standards Australia, 1991, AS 3580.10.1-1991: Methods for				
Operating (Conditions (Incorporates OEH GTA)				NC3
13	The Applicant must:				
13 (a)	(a) implement best practice management to minimise the dust emissions of the development;	Air Quality Management Plan (August 2023).	Site inspection identified use of water carts and	Compliant	
		Annual Review 2020, 2021, 2022.	various dust control measures such as dust		
		2023 environmental monitoring database. Site observations.	suppressant application to stockpiles, dust		
			sprinklers and restricting traffic to defined routes		
13 (b)	(b) carry out periodic air quality monitoring to determine whether the development is complying with the relevant conditions of this	Air Quality Management Plan (August 2023). Annual Review 2020, 2021, 2022.	Ongoing monitoring is in place.	Compliant	
	consent;	2023 environmental monitoring database.			
		Site observations.			
			Annual Review 2020, 2021 and 2022 include review od air quality and meteorological monitoring		
13 (c)	(c) regularly assess meteorological and air quality monitoring data and relocate, modify and/or stop operations on site to ensure compliance with the air quality criteria in this consent;	Air Quality Management Plan (August 2023).	data.	Compliant	
	compliance with the an quality circula in this consent,	Annual Review 2020, 2021, 2022.	Evidence of review of 2023 data within monitoring database.		
		Site interviews.	Observed review of data during site visit. Sighted Ramboll 2023 report assessing relocation options for HVAS2. Noting this was in appreciation		
		Proposed relocation options for HVAS2 at Lynwood Quarry (Ramboll 2023)	of EPL condition U2.2		
13 (d)	(d) minimise the air quality impacts of the development during adverse meteorological conditions and extraordinary events; and		Pallution reduction plan is currently with EDA for accomment	Compliant	
			Pollution reduction plan is currently with EPA for assessment. The Air Quality Management Plan has been revised, submitted and pending approval at the		
			time of audit.		
		Air Quality Management Plan (August 2023).	Dust suppressant is applied to stockpiles via an automated system when certain wind criteria are met.		
		Annual Review 2020, 2021, 2022. 2023 environmental monitoring database.	The auditor observed the application of spray to the stockpiles.		
		Site observations.	Water carts were in use on the day of the audit.		
			No significant dust was observed on site.		
13 (e)	(e) minimise the area of surface disturbance and maximise progressive rehabilitation of the site, to the satisfaction of the Secretary.			Compliant	
			Sighted outcomes of rehabilitation works on the visual bund.		
			Sighted tree planting in previously disturbed areas.		
			Disturbance activities in active mining areas appear to be minimised as far as practicable. Overburden emplacement are stabilised.		
			The Air Quality Management Plan has been revised, submitted and pending approval at the		
		Site Observations, site interviews	time of audit.		
Quarry-ow		Cita integrious	Not triggered confirmed by Heleine	Not triggored	
14	The Applicant must ensure that all reasonable and feasible avoidance and mitigation measures are employed so that particulate matter emissions generated by the development do not cause exceedances of the criteria in Tables 6-8 at any occupied residence on quarry-	Site interviews	Not triggered confirmed by Holcim	Not triggered	
	owned land unless:				
14 (a)	(a) the tenant has been notified of any health risks associated with such exceedances in accordance with the notification requirements under Schedule 4 of this consent; and	Site interviews	Not triggered confirmed by Holcim	Not triggered	
14 (b)		Site interviews	Not triggered confirmed by Holcim	Not triggered	
	reasonable notice, to the satisfaction of the Secretary.				
Air Quality 15	Management Plan The Applicant must prepare an Air Quality Management Plan for the development to the satisfaction of the Secretary. In addition to the		The Air Quality Management Plan was revised in August 2023, with the 2022 AER stating	Compliant	
IJ	standard requirements for management plans (see condition 2 of Schedule 5) this plan must:		approval was received by DPIE on 11/03/2020. However, the most recent revision is pending		
		Air Quality Management Plan (August 2023).	approval at the time of the audit.		
15 (a)	(a) be submitted to the Secretary for approval by 30 November 2016, unless otherwise agreed by the Secretary;	Also Coults Advanced Blood Associations		Compliant	
		Air Quality Management Plan (August 2023).	Original approval outside of audit period, however is noted in the Air Quality Management Plan		

15 (b)	(b) be prepared in consultation with the EPA;	1	Section 2 of the revised Air Quality Management Plan states it was prepared in consultation	Compliant	
13 (0)	(b) be prepared in consultation with the LFA,	Air Quality Management Plan (August 2023).	with the EPA.	Compilant	
15 (c)	(c) describe the measures that would be implemented to ensure:	All Quality Wallagement Flam (August 2023).	With the LFA.	Compliant	
25 (0)	compliance with the relevant conditions of this consent;			Compilant	
	best practice management is being employed; and				
	• the air quality impacts of the development are minimised during adverse meteorological conditions and extraordinary events;	Air Quality Management Plan (August 2023).	Section 3 and 6 of the revised Air Quality Management Plan		
15 (d)	(d) describe the proposed air quality management system; and	Air Quality Management Plan (August 2023). Air Quality Management Plan (August 2023).	Section 6 of the revised Air Quality Management Plan	Compliant	
15 (e)	(e) include an air quality monitoring program that:	All Quality Management Fian (August 2023).	Section 6 of the revised Air Quality Management Flam	Compliant	
15 (0)	• is capable of evaluating the performance of the development;			Compilant	
	includes a protocol for determining any exceedances of the relevant conditions of consent;				
	effectively supports the air quality management system; and	Air Quality Management Plan (August 2023).	Section 7 and 8 of the revised Air Quality Management Plan		
	evaluates and renorts on the adequacy of the air quality management system The Applicant must implement the management plan as approved from time to time by the Secretary.	Air Quality Management Plan (August 2023).	Section 7 and 6 of the revised All Quality Management half	Non-compliant	
		Annual Review 2020, 2021, 2022.	Monitoring methods described in current and revised AQMPs (both sighted). Site observations	·	
		2023 environmental monitoring database.	identified air quality management measures are being implemented.		
		Site observations.	It is however noted that during the audit period monitoring a number of failed monitoring events and incidents occurred as noted under Schedule 3, Condition 12.		NC4
METEORO	OGICAL MONITORING (Incorporates OEH GTA)		induction occurred as noted under somedificial political state.		HCT
15A	For the life of the development, the Applicant must ensure that there is a suitable meteorological station operating in the vicinity of the		A meteorological station is installed at Lynwood Quarry in accordance with the requirements of	Compliant	
	site that complies with the requirements in the Approved Methods for Sampling of Air Pollutants in New South Wales guideline.	Air Quality Management Plan (August 2023).	this condition. The data is used to assess dust related compliance or complaints, and to assist		
		Annual Review 2020, 2021, 2022. 2023 environmental monitoring database.	proactive air quality/dust controls.		
		Site observations.	The station uses telemetry to provide real time site weather data.		
Greenhous	e Gas Emissions				
15B	The Applicant must implement all reasonable and feasible measures to minimise the release of greenhouse gas emissions from the site.		Inere are a number of energy-saving programs on site including automatic lights. Holcim reports to the Department of the Environment and Energy - National Pollution Inventory (NPI)	Compliant	
			with a list of all emissions leaving the		
			site.		
			Management of greenhouse gas emissions is not mentioned in Holcim's Lynwood Quarry Air Quality		
		Site interviews.	Management Plan (August 2023), or the 2020, 2021, 2022 Annual Reviews.		
SURFACE A	IND GROUND WATER (Incorporates NOW and OEH GTAs)		Groundwater is not extracted at the site.		
	Note: Under the Water Act 1912 and/or the Water Management Act 2000, the Applicant is required to obtain the necessary water licences for the development.	Site interviews.	Water is not extracted at the site.	Not triggered	
Pollution o	f Waters	Site interviews.	water is not extracted from water courses.		
16	Except as may be expressly provided by a License, the Applicant must comply with section 120 of the Protection of the Environment	Annual Review 2020, 2021, 2022.	No discharge events were reported in the 2020, 2021, 2022 Annual Reviews, nor reported to DPE	Compliant	
	Operations Act 1997 during the carrying out of the development.	2023 environmental monitoring database.	during the audit period.	·	
Water Disc	harge Limits				
17	Except as may be expressly provided by a License, the Applicant must ensure that any controlled discharge from the controlled discharge	T The state of the	No discharge events were reported in the 2020, 2021, 2022 Annual Reviews, nor reported to DPE	Compliant	Ι
1	points at Sediment Dams A to F comply with the limits in Table 10.		during the audit period.	Compilant	
	Pollutant Unit of measure 100 Percentile concentration limit Total suspended solids mg/L 50				
	PH pH 6.5-8.5	Annual Review 2020, 2021, 2022.			
	Oil and grease mg/L 10 or none visible	2023 environmental monitoring database.			
	Table 10: Surface Water Discharge Limits				
	Note: For more information on the location of Sediment Dams A to F see Appendix 4.				
Sediment I					
18	The Applicant must ensure that:				
18 (a)	(a) Sediment Dams A, B and F are capable of treating the 90th percentile 5 day rainfall event; and	Previous 2019 IEA Audit	,	Compliant	
		Water Management Plan (November 2020)	Water Management Plan (November 2020) notes sizing of dams, see Table 5, however is		
		Site observations	incomplete. Dam A design criteria is not identified and Dam B, not yet constructed is not		
			acknowledged.		
					REC1
18 (b)	(b) Sediment Dams C, D and E are capable of treating the 1:20 year ARI Critical Duration Storm Event.	Previous 2019 IEA Audit	Previous 2019 IEA identified compliance via letter from GHD to Holcim dated 21 May 2012.	Compliant	ILC1
-5 (5)	To the state of th	Water Management Plan (November 2020)	Water Management Plan (November 2020) notes sizing of dams against individual criteria.		
		Site observations	Dams C, D, and E are all listed as having Minimum Design Criteria that meet critical storm		
			duration.		
				0 11	
	Notes:	Previous 2019 IEA Audit		Compliant	
	 Locations of the Sediment Dams referred to in this condition are shown on the plans in Appendix 4; Dams must be designed to be in accordance with 'Managing Urban Stormwater: Soils and Construction (the Blue Book)', including 	Water Management Plan (November 2020)			
L	- Sams mass se designed to be in accordance with intunuging orban stormwater, sons and construction (the blue book), including	Site observations			
	Volume 1 (Landcom, 2004) and Volume 2 (OEH, 2008).				
Operating	Volume 1 (Landcom, 2004) and Volume 2 (OFH, 2008). Conditions				
Operating 19			Walet Waliapellell Fial INIVENIES 2000		
	Conditions		water wanagement Fran (November 2020), Section 0.1.2 notes sediment dams will be emptied via pump or gravity systems after rainfall events.	Non-compliant	
	Conditions		water wanagement Fran (November 2020), Section 0.1.2 notes sediment dams will be emptied via pump or gravity systems after rainfall events. During site inspection Sediment Dam F and Sediment Dam E were inspected and whilst not empty	Non-compliant	
	Conditions		pump or gravity systems after rainfall events. During site inspection Sediment Dam F and Sediment Dam E were inspected and whilst not empty given recent rainfall were actively being managed.	Non-compliant	
	Conditions		pump or gravity systems after rainfall events. During site inspection Sediment Dam F and Sediment Dam E were inspected and whilst not empty given recent rainfall were actively being managed. Sediment Dam G1 was also inspected and at the time of inspection was at capacity, with the water	Non-compliant	
	Conditions	Water Management Plan (November 2020)	pump or gravity systems after rainfall events. During site inspection Sediment Dam F and Sediment Dam E were inspected and whilst not empty given recent rainfall were actively being managed. Sediment Dam G1 was also inspected and at the time of inspection was at capacity, with the water level, level with the spillway. Holcim Representatives D Egoneo and M Vafaei Fard, at the time		
	Conditions	Water Management Plan (November 2020) Site observations	pump or gravity systems after rainfall events. During site inspection Sediment Dam F and Sediment Dam E were inspected and whilst not empty given recent rainfall were actively being managed. Sediment Dam G1 was also inspected and at the time of inspection was at capacity, with the water		NC5

			WMP (2020) states All sediment dams will be managed to ensure that accumulated sediment is kept	Compliant
		Water Management Plan (November 2020)	below 30% of the dam design capacity	
		,	Sighted multiple dam inspection forms following rainfall event triggers. Form includes consideration	
		Site observations	of sediment build up.	
19 (b)	(b) ensure that the accumulated sediment in all the Sediment Dams is kept below 30% of their design capacity;	Dam inspection forms	Sighted evidence of dredging at Dam E.	
			<u>.</u>	Compliant
	(c) construct impervious bunds around all fuel, oil, chemical storage areas that are large enough to contain 110% of the volume held in the		Site observations demonstrated appropriate storage of chemicals. Bunded containers are in use. Spill	
19 (c)	largest container in accordance with the requirements in the OEH Bunding and Spill Management manual; and	Site Observations, site interviews	response kits were sighted.	
		Water Management Plan (November 2020)		Compliant
		Annual Review 2020, 2021, 2022.	WMP (2020) states: Any proposed flocculent system will be discussed with the EPA prior to use.	
		2023 environmental monitoring database.	No reported discharges within the audit period or use within sediment dams within the audit period	
19 (d)	(d) not use any flocculants on site for water pollution control treatment without the written approval of OEH.	Site interviews	as reported by Holcim.	
	Note: The EIS indicated that flocculants maybe used for the treatment of collected stormwater. While the specific flocculent was not			
	specified, some types of flocculants have the potential to cause ecotoxicological impacts on receiving waters.	Note only	C. 1. 5.2 (1) (1) (1) (1) (1) (1) (1) (1) (1) (1)	
			Section 5.3 of the WMP (2020) describes the site water balance and Section 5.4 describes the process	Compliant
			for external water licencing.	
	The Applicant must ensure it has sufficient water for all stages of the development, and if necessary, adjust the scale of operations to		Site interviews confirmed during audit period suitable water has been available to the operation, not	
19A	match the licensed water entitlements, to the satisfaction of the Secretary.	Water Management Plan (November 2020)	exceeding predictions.	
Managemer	t and Monitoring		<u> </u>	
20	The Applicant must prepare a Water Management Plan for the development to the satisfaction of the Secretary. In addition to the			Compliant
	standard requirements for management plans (see condition 2 of Schedule 5) this plan must:	Water Management Plan (November 2020)		
20 (a)	(a) be prepared in consultation with the EPA, WaterNSW, DPI Water and DPI Fisheries;		Holcim has consulted with all relevant agencies in preparing the 2020 Water Management	Compliant
			Plan. Comments received on the draft plan were addressed and the final plan submitted to	
		Water Management Plan (November 2020) - Appendix 4	DPE in 2020.	
20 (b)	(b) be submitted to the Secretary for approval by 30 November 2016, unless otherwise agreed by the Secretary;	1 1 2 2 2 2 2 3 1 1 1 1 1 1 1 1 1 1 1 1	Original approval of the WMP sits outside of the audit term. It is understood the 2018	Compliant
	,		version of the plan was the last version of the plan to be formally endorsed by DPE. The	
			WMP was updated in 2020 and issued to DPE for approval following receipt of comments	
			from stakeholders.	
			The most recent revision is from 2020 which is currently pending approval following	
		Water Management Plan (November 2020) - Appendix 4	inclusion of agency feedback. This is consistent with the previous audit findings.	
20 (c)	(c) include a Water Balance;	Water Management Plan (November 2020) - Section 5.3	Sighted.	Compliant
20 (d)	(d) include an Erosion and Sediment Control Plan;	Water Management Plan (November 2020) - Section 6	Sighted.	Compliant
20 (e)	(e) include a Surface Water Monitoring Program;	Water Management Plan (November 2020) - Appendix 2	Sighted.	Compliant
				-
20 (f)	(f) include a Ground Water Monitoring Program; and	Water Management Plan (November 2020) - Appendix 3	Sighted.	Compliant
20 (g)	(g) include a Surface and Ground Water Response Plan to address any potential adverse impacts associated with the development.	Water Management Blag (Newspher 2020), Casting C	Ciaband	Compliant
		Water Management Plan (November 2020) - Section 8	Sighted.	
	The Applicant must implement the management plan as approved from time to time by the Secretary.	Noted		
21	The Water Balance must:	Noted		
21 (a)	(a) include details of all water extracted (including water make), dewatered, transferred, used and/or discharged by quarry; and	Water Management Plan (November 2020) - Section 5	Sighted.	Compliant
21 (b)	(b) describe measures to minimise water use by the development.	Water Management Plan (November 2020) - Section 5.5	Sighted.	Compliant
22	The Erosion and Sediment Control Plan must:	Noted	U-g-riccus	
		Noted		Compliant
22 (a)	(a) be consistent with the requirements of the Landcom's Managing Urban Stormwater: Soils and Construction manual;			Compilant
			Water Management Plan (2020) states works are consistent with Managing Urban	
		Water Management Plan (November 2020)	Stormwater – Soils and Construction, Volume 1 (the Blue Book) (Landcom 2004)	
22 (b)	(b) identify activities that could cause soil erosion and generate sediment;		Stormwater – Soils and Construction, Volume 1 (the Blue Book) (Landcom 2004) Sighted.	Compliant
22 (b) 22 (c)	(b) identify activities that could cause soil erosion and generate sediment; (c) describe measures to minimise soil erosion and the potential for the transport of sediment to downstream waters;	Water Management Plan (November 2020) Water Management Plan (November 2020) - Section 6 Water Management Plan (November 2020) - Section 6		Compliant Compliant
22 (c)	(c) describe measures to minimise soil erosion and the potential for the transport of sediment to downstream waters;	Water Management Plan (November 2020) - Section 6 Water Management Plan (November 2020) - Section 6	Sighted. Sighted.	Compliant
22 (c) 22 (d)	(c) describe measures to minimise soil erosion and the potential for the transport of sediment to downstream waters; (d) describe the location, function, and capacity of erosion and sediment control structures; and	Water Management Plan (November 2020) - Section 6 Water Management Plan (November 2020) - Section 6 Water Management Plan (November 2020) - Section 6	Sighted. Sighted. Sighted.	Compliant Compliant
22 (c) 22 (d) 22 (e)	(c) describe measures to minimise soil erosion and the potential for the transport of sediment to downstream waters; (d) describe the location, function, and capacity of erosion and sediment control structures; and (e) describe what measures would be implemented to maintain (and if necessary decommission) the structures over time.	Water Management Plan (November 2020) - Section 6 Water Management Plan (November 2020) - Section 6 Water Management Plan (November 2020) - Section 6 Water Management Plan (November 2020) - Section 9	Sighted. Sighted.	Compliant
22 (c) 22 (d) 22 (e) 23	(c) describe measures to minimise soil erosion and the potential for the transport of sediment to downstream waters; (d) describe the location, function, and capacity of erosion and sediment control structures; and (e) describe what measures would be implemented to maintain (and if necessary decommission) the structures over time. The Surface Water Monitoring Program must include:	Water Management Plan (November 2020) - Section 6 Water Management Plan (November 2020) - Section 6 Water Management Plan (November 2020) - Section 6	Sighted. Sighted. Sighted.	Compliant Compliant Compliant
22 (c) 22 (d) 22 (e)	(c) describe measures to minimise soil erosion and the potential for the transport of sediment to downstream waters; (d) describe the location, function, and capacity of erosion and sediment control structures; and (e) describe what measures would be implemented to maintain (and if necessary decommission) the structures over time.	Water Management Plan (November 2020) - Section 6 Water Management Plan (November 2020) - Section 6 Water Management Plan (November 2020) - Section 6 Water Management Plan (November 2020) - Section 9 Noted	Sighted. Sighted. Sighted. Sighted.	Compliant Compliant
22 (c) 22 (d) 22 (e) 23 23 (a)	(c) describe measures to minimise soil erosion and the potential for the transport of sediment to downstream waters; (d) describe the location, function, and capacity of erosion and sediment control structures; and (e) describe what measures would be implemented to maintain (and if necessary decommission) the structures over time. The Surface Water Monitoring Program must include: (a) detailed baseline data on surface water flows and quality in Joarimin Creek, Lockyersleigh Creek, and Marulan Creek;	Water Management Plan (November 2020) - Section 6 Water Management Plan (November 2020) - Section 6 Water Management Plan (November 2020) - Section 6 Water Management Plan (November 2020) - Section 9 Noted Water Management Plan (November 2020) - Appendix 2, Section 2.	Sighted. Sighted. Sighted. Sighted. Sighted.	Compliant Compliant Compliant Compliant
22 (c) 22 (d) 22 (e) 23 23 (a) 23 (b)	(c) describe measures to minimise soil erosion and the potential for the transport of sediment to downstream waters; (d) describe the location, function, and capacity of erosion and sediment control structures; and (e) describe what measures would be implemented to maintain (and if necessary decommission) the structures over time. The Surface Water Monitoring Program must include: (a) detailed baseline data on surface water flows and quality in Joarimin Creek, Lockyersleigh Creek, and Marulan Creek; (b) surface water impact assessment criteria;	Water Management Plan (November 2020) - Section 6 Water Management Plan (November 2020) - Section 6 Water Management Plan (November 2020) - Section 6 Water Management Plan (November 2020) - Section 9 Noted Water Management Plan (November 2020) - Appendix 2, Section 2. Water Management Plan (November 2020) - Appendix 2	Sighted. Sighted. Sighted. Sighted. Sighted. Sighted. Sighted.	Compliant Compliant Compliant Compliant Compliant
22 (c) 22 (d) 22 (e) 23 23 (a)	(c) describe measures to minimise soil erosion and the potential for the transport of sediment to downstream waters; (d) describe the location, function, and capacity of erosion and sediment control structures; and (e) describe what measures would be implemented to maintain (and if necessary decommission) the structures over time. The Surface Water Monitoring Program must include: (a) detailed baseline data on surface water flows and quality in Joarimin Creek, Lockyersleigh Creek, and Marulan Creek;	Water Management Plan (November 2020) - Section 6 Water Management Plan (November 2020) - Section 6 Water Management Plan (November 2020) - Section 6 Water Management Plan (November 2020) - Section 9 Noted Water Management Plan (November 2020) - Appendix 2, Section 2.	Sighted. Sighted. Sighted. Sighted. Sighted.	Compliant Compliant Compliant Compliant
22 (c) 22 (d) 22 (e) 23 23 (a) 23 (b)	(c) describe measures to minimise soil erosion and the potential for the transport of sediment to downstream waters; (d) describe the location, function, and capacity of erosion and sediment control structures; and (e) describe what measures would be implemented to maintain (and if necessary decommission) the structures over time. The Surface Water Monitoring Program must include: (a) detailed baseline data on surface water flows and quality in Joarimin Creek, Lockyersleigh Creek, and Marulan Creek; (b) surface water impact assessment criteria;	Water Management Plan (November 2020) - Section 6 Water Management Plan (November 2020) - Section 6 Water Management Plan (November 2020) - Section 6 Water Management Plan (November 2020) - Section 9 Noted Water Management Plan (November 2020) - Appendix 2, Section 2. Water Management Plan (November 2020) - Appendix 2	Sighted. Sighted. Sighted. Sighted. Sighted. Sighted. Sighted.	Compliant Compliant Compliant Compliant Compliant
22 (c) 22 (d) 22 (e) 23 23 (a) 23 (b) 23 (c)	(c) describe measures to minimise soil erosion and the potential for the transport of sediment to downstream waters; (d) describe the location, function, and capacity of erosion and sediment control structures; and (e) describe what measures would be implemented to maintain (and if necessary decommission) the structures over time. The Surface Water Monitoring Program must include: (a) detailed baseline data on surface water flows and quality in Joarimin Creek, Lockyersleigh Creek, and Marulan Creek; (b) surface water impact assessment criteria; (c) a program to monitor surface water flows and quality;	Water Management Plan (November 2020) - Section 6 Water Management Plan (November 2020) - Section 6 Water Management Plan (November 2020) - Section 6 Water Management Plan (November 2020) - Section 9 Noted Water Management Plan (November 2020) - Appendix 2, Section 2. Water Management Plan (November 2020) - Appendix 2	Sighted.	Compliant Compliant Compliant Compliant Compliant Compliant Compliant
22 (c) 22 (d) 22 (e) 23 23 (a) 23 (b) 23 (c) 23 (d)	(c) describe measures to minimise soil erosion and the potential for the transport of sediment to downstream waters; (d) describe the location, function, and capacity of erosion and sediment control structures; and (e) describe what measures would be implemented to maintain (and if necessary decommission) the structures over time. The Surface Water Monitoring Program must include: (a) detailed baseline data on surface water flows and quality in Joarimin Creek, Lockyersleigh Creek, and Marulan Creek; (b) surface water impact assessment criteria; (c) a program to monitor surface water flows and quality; (d) a protocol for the investigation of identified exceedances of the surface water impact assessment criteria; and (e) a program to monitor the effectiveness of the Erosion and Sediment Control Plan.	Water Management Plan (November 2020) - Section 6 Water Management Plan (November 2020) - Section 6 Water Management Plan (November 2020) - Section 6 Water Management Plan (November 2020) - Section 9 Noted Water Management Plan (November 2020) - Appendix 2, Section 2. Water Management Plan (November 2020) - Appendix 2 Water Management Plan (November 2020) - Appendix 2 Water Management Plan (November 2020) - Appendix 2 Water Management Plan (November 2020) - Section 10	Sighted. Sighted. Sighted. Sighted. Sighted. Sighted. Sighted. Sighted. Sighted.	Compliant Compliant Compliant Compliant Compliant Compliant Compliant Compliant Compliant
22 (c) 22 (d) 22 (e) 23 23 (a) 23 (b) 23 (c) 23 (d) 23 (e)	(c) describe measures to minimise soil erosion and the potential for the transport of sediment to downstream waters; (d) describe the location, function, and capacity of erosion and sediment control structures; and (e) describe what measures would be implemented to maintain (and if necessary decommission) the structures over time. The Surface Water Monitoring Program must include: (a) detailed baseline data on surface water flows and quality in Joarimin Creek, Lockyersleigh Creek, and Marulan Creek; (b) surface water impact assessment criteria; (c) a program to monitor surface water flows and quality; (d) a protocol for the investigation of identified exceedances of the surface water impact assessment criteria; and (e) a program to monitor the effectiveness of the Erosion and Sediment Control Plan. Note: Monitoring of surface flows to be completed by visual assessment.	Water Management Plan (November 2020) - Section 6 Water Management Plan (November 2020) - Section 6 Water Management Plan (November 2020) - Section 6 Water Management Plan (November 2020) - Section 9 Noted Water Management Plan (November 2020) - Appendix 2, Section 2. Water Management Plan (November 2020) - Appendix 2 Water Management Plan (November 2020) - Section 10 Noted	Sighted.	Compliant
22 (c) 22 (d) 22 (e) 23 23 (a) 23 (b) 23 (c) 23 (d) 23 (e)	(c) describe measures to minimise soil erosion and the potential for the transport of sediment to downstream waters; (d) describe the location, function, and capacity of erosion and sediment control structures; and (e) describe what measures would be implemented to maintain (and if necessary decommission) the structures over time. The Surface Water Monitoring Program must include: (a) detailed baseline data on surface water flows and quality in Joarimin Creek, Lockyersleigh Creek, and Marulan Creek; (b) surface water impact assessment criteria; (c) a program to monitor surface water flows and quality; (d) a protocol for the investigation of identified exceedances of the surface water impact assessment criteria; and (e) a program to monitor the effectiveness of the Erosion and Sediment Control Plan. Note: Monitoring of surface flows to be completed by visual assessment. The Ground Water Monitoring Program must include:	Water Management Plan (November 2020) - Section 6 Water Management Plan (November 2020) - Section 6 Water Management Plan (November 2020) - Section 6 Water Management Plan (November 2020) - Section 9 Noted Water Management Plan (November 2020) - Appendix 2, Section 2. Water Management Plan (November 2020) - Appendix 2 Water Management Plan (November 2020) - Appendix 2 Water Management Plan (November 2020) - Appendix 2 Water Management Plan (November 2020) - Section 10 Noted Water Management Plan (November 2020) - Appendix 3	Sighted.	Compliant
22 (c) 22 (d) 22 (e) 23 23 (a) 23 (b) 23 (c) 23 (d) 23 (e) 24 24 (a)	(c) describe measures to minimise soil erosion and the potential for the transport of sediment to downstream waters; (d) describe the location, function, and capacity of erosion and sediment control structures; and (e) describe what measures would be implemented to maintain (and if necessary decommission) the structures over time. The Surface Water Monitoring Program must include: (a) detailed baseline data on surface water flows and quality in Joarimin Creek, Lockyersleigh Creek, and Marulan Creek; (b) surface water impact assessment criteria; (c) a program to monitor surface water flows and quality; (d) a protocol for the investigation of identified exceedances of the surface water impact assessment criteria; and (e) a program to monitor the effectiveness of the Erosion and Sediment Control Plan. Note: Monitoring of surface flows to be completed by visual assessment. The Ground Water Monitoring Program must include: (a) detailed baseline data on ground water levels, flows, and quality, based on statistical analysis;	Water Management Plan (November 2020) - Section 6 Water Management Plan (November 2020) - Section 6 Water Management Plan (November 2020) - Section 6 Water Management Plan (November 2020) - Section 9 Noted Water Management Plan (November 2020) - Appendix 2, Section 2. Water Management Plan (November 2020) - Appendix 2 Water Management Plan (November 2020) - Appendix 2 Water Management Plan (November 2020) - Appendix 2 Water Management Plan (November 2020) - Section 10 Noted Water Management Plan (November 2020) - Appendix 3 Water Management Plan (November 2020) - Appendix 3 Water Management Plan (November 2020) - Appendix 3	Sighted.	Compliant
22 (c) 22 (d) 22 (e) 23 23 (a) 23 (b) 23 (c) 23 (d) 23 (e)	(c) describe measures to minimise soil erosion and the potential for the transport of sediment to downstream waters; (d) describe the location, function, and capacity of erosion and sediment control structures; and (e) describe what measures would be implemented to maintain (and if necessary decommission) the structures over time. The Surface Water Monitoring Program must include: (a) detailed baseline data on surface water flows and quality in Joarimin Creek, Lockyersleigh Creek, and Marulan Creek; (b) surface water impact assessment criteria; (c) a program to monitor surface water flows and quality; (d) a protocol for the investigation of identified exceedances of the surface water impact assessment criteria; and (e) a program to monitor the effectiveness of the Erosion and Sediment Control Plan. Note: Monitoring of surface flows to be completed by visual assessment. The Ground Water Monitoring Program must include: (a) detailed baseline data on ground water levels, flows, and quality, based on statistical analysis; (b) groundwater impact assessment criteria for monitoring bores;	Water Management Plan (November 2020) - Section 6 Water Management Plan (November 2020) - Section 6 Water Management Plan (November 2020) - Section 6 Water Management Plan (November 2020) - Section 9 Noted Water Management Plan (November 2020) - Appendix 2, Section 2. Water Management Plan (November 2020) - Appendix 2 Water Management Plan (November 2020) - Appendix 2 Water Management Plan (November 2020) - Appendix 2 Water Management Plan (November 2020) - Section 10 Noted Water Management Plan (November 2020) - Appendix 3	Sighted.	Compliant
22 (c) 22 (d) 22 (e) 23 23 (a) 23 (b) 23 (c) 23 (d) 23 (e) 24 24 (a)	(c) describe measures to minimise soil erosion and the potential for the transport of sediment to downstream waters; (d) describe the location, function, and capacity of erosion and sediment control structures; and (e) describe what measures would be implemented to maintain (and if necessary decommission) the structures over time. The Surface Water Monitoring Program must include: (a) detailed baseline data on surface water flows and quality in Joarimin Creek, Lockyersleigh Creek, and Marulan Creek; (b) surface water impact assessment criteria; (c) a program to monitor surface water flows and quality; (d) a protocol for the investigation of identified exceedances of the surface water impact assessment criteria; and (e) a program to monitor the effectiveness of the Erosion and Sediment Control Plan. Note: Monitoring of surface flows to be completed by visual assessment. The Ground Water Monitoring Program must include: (a) detailed baseline data on ground water levels, flows, and quality, based on statistical analysis;	Water Management Plan (November 2020) - Section 6 Water Management Plan (November 2020) - Section 6 Water Management Plan (November 2020) - Section 6 Water Management Plan (November 2020) - Section 9 Noted Water Management Plan (November 2020) - Appendix 2, Section 2. Water Management Plan (November 2020) - Appendix 2 Water Management Plan (November 2020) - Appendix 2 Water Management Plan (November 2020) - Appendix 2 Water Management Plan (November 2020) - Section 10 Noted Water Management Plan (November 2020) - Appendix 3 Water Management Plan (November 2020) - Appendix 3 Water Management Plan (November 2020) - Appendix 3	Sighted.	Compliant
22 (c) 22 (d) 22 (e) 23 23 (a) 23 (b) 23 (c) 23 (d) 23 (e) 24 24 (a) 24 (b)	(c) describe measures to minimise soil erosion and the potential for the transport of sediment to downstream waters; (d) describe the location, function, and capacity of erosion and sediment control structures; and (e) describe what measures would be implemented to maintain (and if necessary decommission) the structures over time. The Surface Water Monitoring Program must include: (a) detailed baseline data on surface water flows and quality in Joarimin Creek, Lockyersleigh Creek, and Marulan Creek; (b) surface water impact assessment criteria; (c) a program to monitor surface water flows and quality; (d) a protocol for the investigation of identified exceedances of the surface water impact assessment criteria; and (e) a program to monitor the effectiveness of the Erosion and Sediment Control Plan. Note: Monitoring of surface flows to be completed by visual assessment. The Ground Water Monitoring Program must include: (a) detailed baseline data on ground water levels, flows, and quality, based on statistical analysis; (b) groundwater impact assessment criteria for monitoring bores;	Water Management Plan (November 2020) - Section 6 Water Management Plan (November 2020) - Section 6 Water Management Plan (November 2020) - Section 6 Water Management Plan (November 2020) - Section 9 Noted Water Management Plan (November 2020) - Appendix 2, Section 2. Water Management Plan (November 2020) - Appendix 2 Water Management Plan (November 2020) - Appendix 2 Water Management Plan (November 2020) - Appendix 2 Water Management Plan (November 2020) - Section 10 Noted Water Management Plan (November 2020) - Appendix 3	Sighted.	Compliant
22 (c) 22 (d) 22 (e) 23 23 (a) 23 (b) 23 (c) 23 (d) 23 (e) 24 24 (a) 24 (b) 24 (c)	(c) describe measures to minimise soil erosion and the potential for the transport of sediment to downstream waters; (d) describe the location, function, and capacity of erosion and sediment control structures; and (e) describe what measures would be implemented to maintain (and if necessary decommission) the structures over time. The Surface Water Monitoring Program must include: (a) detailed baseline data on surface water flows and quality in Joarimin Creek, Lockyersleigh Creek, and Marulan Creek; (b) surface water impact assessment criteria; (c) a program to monitor surface water flows and quality; (d) a protocol for the investigation of identified exceedances of the surface water impact assessment criteria; and (e) a program to monitor the effectiveness of the Erosion and Sediment Control Plan. Note: Monitoring of surface flows to be completed by visual assessment. The Ground Water Monitoring Program must include: (a) detailed baseline data on ground water levels, flows, and quality, based on statistical analysis; (b) groundwater impact assessment criteria for monitoring bores; (c) a program to monitor regional ground water levels and quality; and	Water Management Plan (November 2020) - Section 6 Water Management Plan (November 2020) - Section 6 Water Management Plan (November 2020) - Section 6 Water Management Plan (November 2020) - Section 9 Noted Water Management Plan (November 2020) - Appendix 2, Section 2. Water Management Plan (November 2020) - Appendix 2 Water Management Plan (November 2020) - Appendix 2 Water Management Plan (November 2020) - Appendix 2 Water Management Plan (November 2020) - Section 10 Noted Water Management Plan (November 2020) - Appendix 3	Sighted.	Compliant
22 (c) 22 (d) 22 (e) 23 23 (a) 23 (b) 23 (c) 23 (d) 23 (e) 24 24 (a) 24 (b) 24 (c)	(c) describe measures to minimise soil erosion and the potential for the transport of sediment to downstream waters; (d) describe the location, function, and capacity of erosion and sediment control structures; and (e) describe what measures would be implemented to maintain (and if necessary decommission) the structures over time. The Surface Water Monitoring Program must include: (a) detailed baseline data on surface water flows and quality in Joarimin Creek, Lockyersleigh Creek, and Marulan Creek; (b) surface water impact assessment criteria; (c) a program to monitor surface water flows and quality; (d) a protocol for the investigation of identified exceedances of the surface water impact assessment criteria; and (e) a program to monitor the effectiveness of the Erosion and Sediment Control Plan. Note: Monitoring of surface flows to be completed by visual assessment. The Ground Water Monitoring Program must include: (a) detailed baseline data on ground water levels, flows, and quality, based on statistical analysis; (b) groundwater impact assessment criteria for monitoring bores; (c) a program to monitor regional ground water levels and quality; and (d) a protocol for the investigation of identified exceedances of the groundwater impact assessment criteria. Note: The surface and ground water monitoring programs must be consistent with the current version of Approved Methods for the	Water Management Plan (November 2020) - Section 6 Water Management Plan (November 2020) - Section 6 Water Management Plan (November 2020) - Section 6 Water Management Plan (November 2020) - Section 9 Noted Water Management Plan (November 2020) - Appendix 2, Section 2. Water Management Plan (November 2020) - Appendix 2 Water Management Plan (November 2020) - Appendix 2 Water Management Plan (November 2020) - Appendix 2 Water Management Plan (November 2020) - Section 10 Noted Water Management Plan (November 2020) - Appendix 3	Sighted.	Compliant
22 (c) 22 (d) 22 (e) 23 23 (a) 23 (b) 23 (c) 23 (d) 23 (e) 24 24 (a) 24 (b) 24 (c)	(c) describe measures to minimise soil erosion and the potential for the transport of sediment to downstream waters; (d) describe the location, function, and capacity of erosion and sediment control structures; and (e) describe what measures would be implemented to maintain (and if necessary decommission) the structures over time. The Surface Water Monitoring Program must include: (a) detailed baseline data on surface water flows and quality in Joarimin Creek, Lockyersleigh Creek, and Marulan Creek; (b) surface water impact assessment criteria; (c) a program to monitor surface water flows and quality; (d) a protocol for the investigation of identified exceedances of the surface water impact assessment criteria; and (e) a program to monitor the effectiveness of the Erosion and Sediment Control Plan. Note: Monitoring of surface flows to be completed by visual assessment. The Ground Water Monitoring Program must include: (a) detailed baseline data on ground water levels, flows, and quality, based on statistical analysis; (b) groundwater impact assessment criteria for monitoring bores; (c) a program to monitor regional ground water levels and quality; and (d) a protocol for the investigation of identified exceedances of the groundwater impact assessment criteria.	Water Management Plan (November 2020) - Section 6 Water Management Plan (November 2020) - Section 6 Water Management Plan (November 2020) - Section 6 Water Management Plan (November 2020) - Section 9 Noted Water Management Plan (November 2020) - Appendix 2, Section 2. Water Management Plan (November 2020) - Appendix 2 Water Management Plan (November 2020) - Appendix 2 Water Management Plan (November 2020) - Appendix 2 Water Management Plan (November 2020) - Section 10 Noted Water Management Plan (November 2020) - Appendix 3	Sighted. Water Management Plan (2020) Appendix 2 and Appendix 3 state the programs must be consistent wit the current version Approved Methods for the Sampling and Analysis of	Compliant
22 (c) 22 (d) 22 (e) 23 23 (a) 23 (b) 23 (c) 23 (d) 23 (e) 24 24 (a) 24 (b) 24 (c) 24 (d)	(c) describe measures to minimise soil erosion and the potential for the transport of sediment to downstream waters; (d) describe the location, function, and capacity of erosion and sediment control structures; and (e) describe what measures would be implemented to maintain (and if necessary decommission) the structures over time. The Surface Water Monitoring Program must include: (a) detailed baseline data on surface water flows and quality in Joarimin Creek, Lockyersleigh Creek, and Marulan Creek; (b) surface water impact assessment criteria; (c) a program to monitor surface water flows and quality; (d) a protocol for the investigation of identified exceedances of the surface water impact assessment criteria; and (e) a program to monitor the effectiveness of the Erosion and Sediment Control Plan. Note: Monitoring of surface flows to be completed by visual assessment. The Ground Water Monitoring Program must include: (a) detailed baseline data on ground water levels, flows, and quality, based on statistical analysis; (b) groundwater impact assessment criteria for monitoring bores; (c) a program to monitor regional ground water levels and quality; and (d) a protocol for the investigation of identified exceedances of the groundwater impact assessment criteria. Note: The surface and ground water monitoring programs must be consistent with the current version of Approved Methods for the Sampling and Analysis of Water Pollutants in New South Wales (OEH).	Water Management Plan (November 2020) - Section 6 Water Management Plan (November 2020) - Section 6 Water Management Plan (November 2020) - Section 6 Water Management Plan (November 2020) - Section 9 Noted Water Management Plan (November 2020) - Appendix 2, Section 2. Water Management Plan (November 2020) - Appendix 2 Water Management Plan (November 2020) - Appendix 2 Water Management Plan (November 2020) - Appendix 2 Water Management Plan (November 2020) - Section 10 Noted Water Management Plan (November 2020) - Appendix 3	Sighted.	Compliant
22 (c) 22 (d) 22 (e) 23 23 (a) 23 (b) 23 (c) 23 (d) 23 (e) 24 24 (a) 24 (b) 24 (c) 24 (d)	(c) describe measures to minimise soil erosion and the potential for the transport of sediment to downstream waters; (d) describe the location, function, and capacity of erosion and sediment control structures; and (e) describe what measures would be implemented to maintain (and if necessary decommission) the structures over time. The Surface Water Monitoring Program must include: (a) detailed baseline data on surface water flows and quality in Joarimin Creek, Lockyersleigh Creek, and Marulan Creek; (b) surface water impact assessment criteria; (c) a program to monitor surface water flows and quality; (d) a protocol for the investigation of identified exceedances of the surface water impact assessment criteria; and (e) a program to monitor the effectiveness of the Erosion and Sediment Control Plan. Note: Monitoring of surface flows to be completed by visual assessment. The Ground Water Monitoring Program must include: (a) detailed baseline data on ground water levels, flows, and quality, based on statistical analysis; (b) groundwater impact assessment criteria for monitoring bores; (c) a program to monitor regional ground water levels and quality; and (d) a protocol for the investigation of identified exceedances of the groundwater impact assessment criteria. Note: The surface and ground water monitoring programs must be consistent with the current version of Approved Methods for the Sampling and Analysis of Water Pollutants in New South Wales (OEH).	Water Management Plan (November 2020) - Section 6 Water Management Plan (November 2020) - Section 6 Water Management Plan (November 2020) - Section 6 Water Management Plan (November 2020) - Section 9 Noted Water Management Plan (November 2020) - Appendix 2, Section 2. Water Management Plan (November 2020) - Appendix 2 Water Management Plan (November 2020) - Appendix 2 Water Management Plan (November 2020) - Appendix 2 Water Management Plan (November 2020) - Section 10 Noted Water Management Plan (November 2020) - Appendix 3	Sighted. Water Management Plan (2020) Appendix 2 and Appendix 3 state the programs must be consistent wit the current version Approved Methods for the Sampling and Analysis of Water Pollutants in New South Wales.	Compliant
22 (c) 22 (d) 22 (e) 23 23 (a) 23 (b) 23 (c) 23 (d) 23 (e) 24 24 (a) 24 (b) 24 (c) 24 (d)	(c) describe measures to minimise soil erosion and the potential for the transport of sediment to downstream waters; (d) describe the location, function, and capacity of erosion and sediment control structures; and (e) describe what measures would be implemented to maintain (and if necessary decommission) the structures over time. The Surface Water Monitoring Program must include: (a) detailed baseline data on surface water flows and quality in Joarimin Creek, Lockyersleigh Creek, and Marulan Creek; (b) surface water impact assessment criteria; (c) a program to monitor surface water flows and quality; (d) a protocol for the investigation of identified exceedances of the surface water impact assessment criteria; and (e) a program to monitor the effectiveness of the Erosion and Sediment Control Plan. Note: Monitoring of surface flows to be completed by visual assessment. The Ground Water Monitoring Program must include: (a) detailed baseline data on ground water levels, flows, and quality, based on statistical analysis; (b) groundwater impact assessment criteria for monitoring bores; (c) a program to monitor regional ground water levels and quality; and (d) a protocol for the investigation of identified exceedances of the groundwater impact assessment criteria. Note: The surface and ground water monitoring programs must be consistent with the current version of Approved Methods for the Sampling and Analysis of Water Pollutants in New South Wales (OEH).	Water Management Plan (November 2020) - Section 6 Water Management Plan (November 2020) - Section 6 Water Management Plan (November 2020) - Section 6 Water Management Plan (November 2020) - Section 9 Noted Water Management Plan (November 2020) - Appendix 2, Section 2. Water Management Plan (November 2020) - Appendix 2 Water Management Plan (November 2020) - Appendix 2 Water Management Plan (November 2020) - Appendix 2 Water Management Plan (November 2020) - Section 10 Noted Water Management Plan (November 2020) - Appendix 3	Sighted. Water Management Plan (2020) Appendix 2 and Appendix 3 state the programs must be consistent wit the current version Approved Methods for the Sampling and Analysis of	Compliant
22 (c) 22 (d) 22 (e) 23 23 (a) 23 (b) 23 (c) 23 (d) 23 (e) 24 24 (a) 24 (b) 24 (c) 24 (d)	(c) describe measures to minimise soil erosion and the potential for the transport of sediment to downstream waters; (d) describe the location, function, and capacity of erosion and sediment control structures; and (e) describe what measures would be implemented to maintain (and if necessary decommission) the structures over time. The Surface Water Monitoring Program must include: (a) detailed baseline data on surface water flows and quality in Joarimin Creek, Lockyersleigh Creek, and Marulan Creek; (b) surface water impact assessment criteria; (c) a program to monitor surface water flows and quality; (d) a protocol for the investigation of identified exceedances of the surface water impact assessment criteria; and (e) a program to monitor the effectiveness of the Erosion and Sediment Control Plan. Note: Monitoring of surface flows to be completed by visual assessment. The Ground Water Monitoring Program must include: (a) detailed baseline data on ground water levels, flows, and quality, based on statistical analysis; (b) groundwater impact assessment criteria for monitoring bores; (c) a program to monitor regional ground water levels and quality; and (d) a protocol for the investigation of identified exceedances of the groundwater impact assessment criteria. Note: The surface and ground water monitoring programs must be consistent with the current version of Approved Methods for the Sampling and Analysis of Water Pollutants in New South Wales (OEH). **Ossings** The vehicular crossing of Lockyersleigh Creek as detailed in EA (Mod 4) must be designed and constructed in accordance with the Policy and Guidelines for Fish Friendly Water Crossings (DPI Fisheries, 2004) and Why Do Fish Need to Cross the Road? Fish Passage	Water Management Plan (November 2020) - Section 6 Water Management Plan (November 2020) - Section 6 Water Management Plan (November 2020) - Section 6 Water Management Plan (November 2020) - Section 9 Noted Water Management Plan (November 2020) - Appendix 2, Section 2. Water Management Plan (November 2020) - Appendix 2 Water Management Plan (November 2020) - Appendix 2 Water Management Plan (November 2020) - Appendix 2 Water Management Plan (November 2020) - Section 10 Noted Water Management Plan (November 2020) - Appendix 3	Sighted. Water Management Plan (2020) Appendix 2 and Appendix 3 state the programs must be consistent wit the current version Approved Methods for the Sampling and Analysis of Water Pollutants in New South Wales.	Compliant
22 (c) 22 (d) 22 (e) 23 23 (a) 23 (b) 23 (c) 23 (d) 23 (e) 24 24 (a) 24 (b) 24 (c) 24 (d)	(c) describe measures to minimise soil erosion and the potential for the transport of sediment to downstream waters; (d) describe the location, function, and capacity of erosion and sediment control structures; and (e) describe what measures would be implemented to maintain (and if necessary decommission) the structures over time. The Surface Water Monitoring Program must include: (a) detailed baseline data on surface water flows and quality in Joarimin Creek, Lockyersleigh Creek, and Marulan Creek; (b) surface water impact assessment criteria; (c) a program to monitor surface water flows and quality; (d) a protocol for the investigation of identified exceedances of the surface water impact assessment criteria; and (e) a program to monitor the effectiveness of the Erosion and Sediment Control Plan. Note: Monitoring of surface flows to be completed by visual assessment. The Ground Water Monitoring Program must include: (a) detailed baseline data on ground water levels, flows, and quality, based on statistical analysis; (b) groundwater impact assessment criteria for monitoring bores; (c) a program to monitor regional ground water levels and quality; and (d) a protocol for the investigation of identified exceedances of the groundwater impact assessment criteria. Note: The surface and ground water monitoring programs must be consistent with the current version of Approved Methods for the Sampling and Analysis of Water Pollutants in New South Wales (OEH).	Water Management Plan (November 2020) - Section 6 Water Management Plan (November 2020) - Section 6 Water Management Plan (November 2020) - Section 6 Water Management Plan (November 2020) - Section 9 Noted Water Management Plan (November 2020) - Appendix 2, Section 2. Water Management Plan (November 2020) - Appendix 2 Water Management Plan (November 2020) - Appendix 2 Water Management Plan (November 2020) - Appendix 2 Water Management Plan (November 2020) - Section 10 Noted Water Management Plan (November 2020) - Appendix 3	Sighted. Construction of the crossing was outside of the audit period. However, the 2019 IEA	Compliant
22 (c) 22 (d) 22 (e) 23 23 (a) 23 (b) 23 (c) 23 (d) 23 (e) 24 24 (a) 24 (b) 24 (c) 24 (d) Waterway C	(c) describe measures to minimise soil erosion and the potential for the transport of sediment to downstream waters; (d) describe the location, function, and capacity of erosion and sediment control structures; and (e) describe what measures would be implemented to maintain (and if necessary decommission) the structures over time. The Surface Water Monitoring Program must include: (a) detailed baseline data on surface water flows and quality in Joarimin Creek, Lockyersleigh Creek, and Marulan Creek; (b) surface water impact assessment criteria; (c) a program to monitor surface water flows and quality; (d) a protocol for the investigation of identified exceedances of the surface water impact assessment criteria; and (e) a program to monitor the effectiveness of the Erosion and Sediment Control Plan. Note: Monitoring of surface flows to be completed by visual assessment. The Ground Water Monitoring Program must include: (a) detailed baseline data on ground water levels, flows, and quality, based on statistical analysis; (b) groundwater impact assessment criteria for monitoring bores; (c) a program to monitor regional ground water levels and quality; and (d) a protocol for the investigation of identified exceedances of the groundwater impact assessment criteria. Note: The surface and ground water monitoring programs must be consistent with the current version of Approved Methods for the Sampling and Analysis of Water Pollutants in New South Wales (OEH). **Cossings** The vehicular crossing of Lockyersleigh Creek as detailed in EA (Mod 4) must be designed and constructed in accordance with the Policy and Guidelines for Fish Friendly Water Crossings (DPI Fisheries, 2004) and Why Do Fish Need to Cross the Road? Fish Passage Requirements for Waterway Crossings (2004) to the satisfaction of DPI Fisheries. Design plans should be submitted to DPI Fisheries for approval Drior to the construction.	Water Management Plan (November 2020) - Section 6 Water Management Plan (November 2020) - Section 6 Water Management Plan (November 2020) - Section 6 Water Management Plan (November 2020) - Section 9 Noted Water Management Plan (November 2020) - Appendix 2, Section 2. Water Management Plan (November 2020) - Appendix 2 Water Management Plan (November 2020) - Appendix 2 Water Management Plan (November 2020) - Appendix 2 Water Management Plan (November 2020) - Section 10 Noted Water Management Plan (November 2020) - Appendix 3	Sighted. Construction of the crossing was outside of the audit period. However, the 2019 IEA	Compliant
22 (c) 22 (d) 22 (e) 23 23 (a) 23 (b) 23 (c) 23 (d) 23 (e) 24 24 (a) 24 (b) 24 (c) 24 (d) Waterway C 25	(c) describe measures to minimise soil erosion and the potential for the transport of sediment to downstream waters; (d) describe the location, function, and capacity of erosion and sediment control structures; and (e) describe what measures would be implemented to maintain (and if necessary decommission) the structures over time. The Surface Water Monitoring Program must include: (a) detailed baseline data on surface water flows and quality in Joarimin Creek, Lockyersleigh Creek, and Marulan Creek; (b) surface water impact assessment criteria; (c) a program to monitor surface water flows and quality; (d) a protocol for the investigation of identified exceedances of the surface water impact assessment criteria; and (e) a program to monitor the effectiveness of the Erosion and Sediment Control Plan. Note: Monitoring of surface flows to be completed by visual assessment. The Ground Water Monitoring Program must include: (a) detailed baseline data on ground water levels, flows, and quality, based on statistical analysis; (b) groundwater impact assessment criteria for monitoring bores; (c) a program to monitor regional ground water levels and quality; and (d) a protocol for the investigation of identified exceedances of the groundwater impact assessment criteria. Note: The surface and ground water monitoring programs must be consistent with the current version of Approved Methods for the Sampling and Analysis of Water Pollutants in New South Wales (OEH). Tossings The vehicular crossing of Lockyersleigh Creek as detailed in EA (Mod 4) must be designed and constructed in accordance with the Policy and Guidelines for Fish Friendly Water Crossings (DPI Fisheries, 2004) and Why Do Fish Need to Cross the Road? Fish Passage Requirements for Waterway Crossings (2004) to the satisfaction of DPI Fisheries. Design plans should be submitted to DPI Fisheries for Approval DPI Fisheries For Approval DPI Fisheries.	Water Management Plan (November 2020) - Section 6 Water Management Plan (November 2020) - Section 6 Water Management Plan (November 2020) - Section 6 Water Management Plan (November 2020) - Section 9 Noted Water Management Plan (November 2020) - Appendix 2, Section 2. Water Management Plan (November 2020) - Appendix 2 Water Management Plan (November 2020) - Appendix 2 Water Management Plan (November 2020) - Appendix 2 Water Management Plan (November 2020) - Section 10 Noted Water Management Plan (November 2020) - Appendix 3	Sighted. Construction of the crossing was outside of the audit period. However, the 2019 IEA	Compliant
22 (c) 22 (d) 22 (e) 23 23 (a) 23 (b) 23 (c) 23 (d) 23 (e) 24 24 (a) 24 (b) 24 (c) 24 (d) Waterway C	(c) describe measures to minimise soil erosion and the potential for the transport of sediment to downstream waters; (d) describe the location, function, and capacity of erosion and sediment control structures; and (e) describe what measures would be implemented to maintain (and if necessary decommission) the structures over time. The Surface Water Monitoring Program must include: (a) detailed baseline data on surface water flows and quality in Joarimin Creek, Lockyersleigh Creek, and Marulan Creek; (b) surface water impact assessment criteria; (c) a program to monitor surface water flows and quality; (d) a protocol for the investigation of identified exceedances of the surface water impact assessment criteria; and (e) a program to monitor the effectiveness of the Erosion and Sediment Control Plan. Note: Monitoring of surface flows to be completed by visual assessment. The Ground Water Monitoring Program must include: (a) detailed baseline data on ground water levels, flows, and quality, based on statistical analysis; (b) groundwater impact assessment criteria for monitoring bores; (c) a program to monitor regional ground water levels and quality; and (d) a protocol for the investigation of identified exceedances of the groundwater impact assessment criteria. Note: The surface and ground water monitoring programs must be consistent with the current version of Approved Methods for the Sampling and Analysis of Water Pollutants in New South Wales (OEH). Tossings The vehicular crossing of Lockyersleigh Creek as detailed in EA (Mod 4) must be designed and constructed in accordance with the Policy and Guidelines for Fish Friendly Water Crossings (DPI Fisheries, 2004) and Why Do Fish Need to Cross the Road? Fish Passage Requirements for Waterway Crossings (2004) to the satisfaction of DPI Fisheries. Design plans should be submitted to DPI Fisheries for approval notion to the construction. TRANSPORT (Incorporates RTA, Council and Department of Lands GTAs)	Water Management Plan (November 2020) - Section 6 Water Management Plan (November 2020) - Section 6 Water Management Plan (November 2020) - Section 6 Water Management Plan (November 2020) - Section 9 Noted Water Management Plan (November 2020) - Appendix 2, Section 2. Water Management Plan (November 2020) - Appendix 2 Water Management Plan (November 2020) - Appendix 2 Water Management Plan (November 2020) - Appendix 2 Water Management Plan (November 2020) - Section 10 Noted Water Management Plan (November 2020) - Appendix 3	Sighted. Construction of the crossing was outside of the audit period. However, the 2019 IEA	Compliant
22 (c) 22 (d) 22 (e) 23 23 (a) 23 (b) 23 (c) 23 (d) 23 (e) 24 24 (a) 24 (b) 24 (c) 24 (d) Waterway C 25	(c) describe measures to minimise soil erosion and the potential for the transport of sediment to downstream waters; (d) describe the location, function, and capacity of erosion and sediment control structures; and (e) describe what measures would be implemented to maintain (and if necessary decommission) the structures over time. The Surface Water Monitoring Program must include: (a) detailed baseline data on surface water flows and quality in Joarimin Creek, Lockyersleigh Creek, and Marulan Creek; (b) surface water impact assessment criteria; (c) a program to monitor surface water flows and quality; (d) a protocol for the investigation of identified exceedances of the surface water impact assessment criteria; and (e) a program to monitor the effectiveness of the Erosion and Sediment Control Plan. Note: Monitoring of surface flows to be completed by visual assessment. The Ground Water Monitoring Program must include: (a) detailed baseline data on ground water levels, flows, and quality, based on statistical analysis; (b) groundwater impact assessment criteria for monitoring bores; (c) a program to monitor regional ground water levels and quality; and (d) a protocol for the investigation of identified exceedances of the groundwater impact assessment criteria. Note: The surface and ground water monitoring programs must be consistent with the current version of Approved Methods for the Sampling and Analysis of Water Pollutants in New South Wales (OEH). Tossings The vehicular crossing of Lockyersleigh Creek as detailed in EA (Mod 4) must be designed and constructed in accordance with the Policy and Guidelines for Fish Friendly Water Crossings (DPI Fisheries, 2004) and Why Do Fish Need to Cross the Road? Fish Passage Requirements for Waterway Crossings (2004) to the satisfaction of DPI Fisheries. Design plans should be submitted to DPI Fisheries for Approval DPI Fisheries For Approval DPI Fisheries.	Water Management Plan (November 2020) - Section 6 Water Management Plan (November 2020) - Section 6 Water Management Plan (November 2020) - Section 6 Water Management Plan (November 2020) - Section 9 Noted Water Management Plan (November 2020) - Appendix 2, Section 2. Water Management Plan (November 2020) - Appendix 2 Water Management Plan (November 2020) - Appendix 2 Water Management Plan (November 2020) - Appendix 2 Water Management Plan (November 2020) - Section 10 Noted Water Management Plan (November 2020) - Appendix 3	Sighted. Construction of the crossing was outside of the audit period. However, the 2019 IEA	Compliant
22 (c) 22 (d) 22 (e) 23 23 (a) 23 (b) 23 (c) 23 (d) 23 (e) 24 24 (a) 24 (b) 24 (c) 24 (d) Waterway C 25	(c) describe measures to minimise soil erosion and the potential for the transport of sediment to downstream waters; (d) describe the location, function, and capacity of erosion and sediment control structures; and (e) describe what measures would be implemented to maintain (and if necessary decommission) the structures over time. The Surface Water Monitoring Program must include: (a) detailed baseline data on surface water flows and quality in Joarimin Creek, Lockyersleigh Creek, and Marulan Creek; (b) surface water impact assessment criteria; (c) a program to monitor surface water flows and quality; (d) a protocol for the investigation of identified exceedances of the surface water impact assessment criteria; and (e) a program to monitor the effectiveness of the Erosion and Sediment Control Plan. Note: Monitoring of surface flows to be completed by visual assessment. The Ground Water Monitoring Program must include: (a) detailed baseline data on ground water levels, flows, and quality, based on statistical analysis; (b) groundwater impact assessment criteria for monitoring bores; (c) a program to monitor regional ground water levels and quality; and (d) a protocol for the investigation of identified exceedances of the groundwater impact assessment criteria. Note: The surface and ground water monitoring programs must be consistent with the current version of Approved Methods for the Sampling and Analysis of Water Pollutants in New South Wales (OEH). Tossings The vehicular crossing of Lockyersleigh Creek as detailed in EA (Mod 4) must be designed and constructed in accordance with the Policy and Guidelines for Fish Friendly Water Crossings (DPI Fisheries, 2004) and Why Do Fish Need to Cross the Road? Fish Passage Requirements for Waterway Crossings (2004) to the satisfaction of DPI Fisheries. Design plans should be submitted to DPI Fisheries for approval notion to the construction. TRANSPORT (Incorporates RTA, Council and Department of Lands GTAs)	Water Management Plan (November 2020) - Section 6 Water Management Plan (November 2020) - Section 6 Water Management Plan (November 2020) - Section 6 Water Management Plan (November 2020) - Section 9 Noted Water Management Plan (November 2020) - Appendix 2, Section 2. Water Management Plan (November 2020) - Appendix 2 Water Management Plan (November 2020) - Appendix 2 Water Management Plan (November 2020) - Appendix 2 Water Management Plan (November 2020) - Section 10 Noted Water Management Plan (November 2020) - Appendix 3 Water Management Plan (November 2020) - Appendix 2 and 3 Site interview Previous 2019 IEA Audit	Sighted. Construction of the crossing was outside of the audit period. However, the 2019 IEA	Compliant
22 (c) 22 (d) 22 (e) 23 23 (a) 23 (b) 23 (c) 23 (d) 23 (e) 24 24 (a) 24 (b) 24 (c) 24 (d) Waterway C 25 TRAFFIC ANT Construction 26	(c) describe measures to minimise soil erosion and the potential for the transport of sediment to downstream waters; (d) describe the location, function, and capacity of erosion and sediment control structures; and (e) describe what measures would be implemented to maintain (and if necessary decommission) the structures over time. The Surface Water Monitoring Program must include: (a) detailed baseline data on surface water flows and quality in Joarimin Creek, Lockyersleigh Creek, and Marulan Creek; (b) surface water impact assessment criteria; (c) a program to monitor surface water flows and quality; (d) a protocol for the investigation of identified exceedances of the surface water impact assessment criteria; and (e) a program to monitor surface water flows and quality; (d) a protocol for the investigation of identified exceedances of the surface water impact assessment criteria; and (e) a program to monitor ing of surface flows to be completed by visual assessment. The Ground Water Monitoring Program must include: (a) detailed baseline data on ground water levels, flows, and quality, based on statistical analysis; (b) groundwater impact assessment criteria for monitoring bores; (c) a program to monitor regional ground water levels and quality; and (d) a protocol for the investigation of identified exceedances of the groundwater impact assessment criteria. Note: The surface and ground water monitoring programs must be consistent with the current version of Approved Methods for the Sampling and Analysis of Water Pollutants in New South Wales (OEH). Tossings The vehicular crossing of Lockyersleigh Creek as detailed in EA (Mod 4) must be designed and constructed in accordance with the Policy and Guidelines for Fish Friendly Water Crossings (DPI Fisheries, 2004) and Why Do Fish Need to Cross the Road? Fish Passage Requirements for Waterway Crossings (2004) to the satisfaction of DPI Fisheries. Design plans should be submitted to DPI Fisheries for approval prior to the construction. The Applicant must ensure	Water Management Plan (November 2020) - Section 6 Water Management Plan (November 2020) - Section 6 Water Management Plan (November 2020) - Section 6 Water Management Plan (November 2020) - Section 9 Noted Water Management Plan (November 2020) - Appendix 2, Section 2. Water Management Plan (November 2020) - Appendix 2 Water Management Plan (November 2020) - Appendix 2 Water Management Plan (November 2020) - Appendix 2 Water Management Plan (November 2020) - Section 10 Noted Water Management Plan (November 2020) - Appendix 3 Water Management Plan (November 2020) - Appendix 2 and 3 Site interview Previous 2019 IEA Audit	Sighted. Construction of the crossing was outside of the audit period. However, the 2019 IEA determined compliance.	Compliant
22 (c) 22 (d) 22 (e) 23 23 (a) 23 (b) 23 (c) 23 (d) 23 (e) 24 24 (a) 24 (b) 24 (c) 24 (d) Waterway C 25 TRAFFIC ANT Construction 26	(c) describe measures to minimise soil erosion and the potential for the transport of sediment to downstream waters; (d) describe the location, function, and capacity of erosion and sediment control structures; and (e) describe what measures would be implemented to maintain (and if necessary decommission) the structures over time. The Surface Water Monitoring Program must include: (a) detailed baseline data on surface water flows and quality in Joarimin Creek, Lockyersleigh Creek, and Marulan Creek; (b) surface water impact assessment criteria; (c) a program to monitor surface water flows and quality; (d) a protocol for the investigation of identified exceedances of the surface water impact assessment criteria; and (e) a program to monitor surface water flows and quality; (d) a protocol for the investigation of identified exceedances of the surface water impact assessment criteria; and (e) a program to monitor ing of surface flows to be completed by visual assessment. The Ground Water Monitoring Program must include: (a) detailed baseline data on ground water levels, flows, and quality, based on statistical analysis; (b) groundwater impact assessment criteria for monitoring bores; (c) a program to monitor regional ground water levels and quality; and (d) a protocol for the investigation of identified exceedances of the groundwater impact assessment criteria. Note: The surface and ground water monitoring programs must be consistent with the current version of Approved Methods for the Sampling and Analysis of Water Pollutants in New South Wales (OEH). Tossings The vehicular crossing of Lockyersleigh Creek as detailed in EA (Mod 4) must be designed and constructed in accordance with the Policy and Guidelines for Fish Friendly Water Crossings (DPI Fisheries, 2004) and Why Do Fish Need to Cross the Road? Fish Passage Requirements for Waterway Crossings (2004) to the satisfaction of DPI Fisheries. Design plans should be submitted to DPI Fisheries for approval prior to the construction. The Applicant must ensure	Water Management Plan (November 2020) - Section 6 Water Management Plan (November 2020) - Section 6 Water Management Plan (November 2020) - Section 6 Water Management Plan (November 2020) - Section 9 Noted Water Management Plan (November 2020) - Appendix 2, Section 2. Water Management Plan (November 2020) - Appendix 2 Water Management Plan (November 2020) - Appendix 2 Water Management Plan (November 2020) - Appendix 2 Water Management Plan (November 2020) - Section 10 Noted Water Management Plan (November 2020) - Appendix 3 Water Management Plan (November 2020) - Appendix 3 Water Management Plan (November 2020) - Appendix 3 Water Management Plan (November 2020) - Appendix 2 and 3 Site interview Previous 2019 IEA Audit	Sighted. Construction of the crossing was outside of the audit period. However, the 2019 IEA determined compliance.	Compliant
22 (c) 22 (d) 22 (e) 23 23 (a) 23 (b) 23 (c) 23 (d) 23 (e) 24 24 (a) 24 (b) 24 (c) 24 (d) Waterway C 25 TRAFFIC ANI Construction 26 26 (a) 26 (b)	(c) describe measures to minimise soil erosion and the potential for the transport of sediment to downstream waters; (d) describe the location, function, and capacity of erosion and sediment control structures; and (e) describe what measures would be implemented to maintain (and if necessary decommission) the structures over time. The Surface Water Monitoring Program must include: (a) detailed baseline data on surface water flows and quality in Joarimin Creek, Lockyersleigh Creek, and Marulan Creek; (b) surface water impact assessment criteria; (c) a program to monitor surface water flows and quality; (d) a protocol for the investigation of identified exceedances of the surface water impact assessment criteria; and (e) a program to monitor the effectiveness of the Erosion and Sediment Control Plan. Note: Monitoring of surface flows to be completed by visual assessment. The Ground Water Monitoring Program must include: (a) detailed baseline data on ground water levels, flows, and quality, based on statistical analysis; (b) groundwater impact assessment criteria for monitoring bores; (c) a program to monitor regional ground water levels and quality; and (d) a protocol for the investigation of identified exceedances of the groundwater impact assessment criteria. Note: The surface and ground water monitoring programs must be consistent with the current version of Approved Methods for the Sampling and Analysis of Water Pollutants in New South Wales (OEH). Ossings The vehicular crossing of Lockyersleigh Creek as detailed in EA (Mod 4) must be designed and constructed in accordance with the Policy and Guidelines for Fish Friendly Water Crossings (DPI Fisheries, 2004) and Why Do Fish Need to Cross the Road? Fish Passage Requirements for Waterway Crossings (2004) to the satisfaction of DPI Fisheries. Design plans should be submitted to DPI Fisheries for approach and to to the construction. DRANSPORT (Incorporates RTA, Council and Department of Lands GTAs) Traffic The Applicant must ensure that: (a) constructio	Water Management Plan (November 2020) - Section 6 Water Management Plan (November 2020) - Section 6 Water Management Plan (November 2020) - Section 6 Water Management Plan (November 2020) - Section 9 Noted Water Management Plan (November 2020) - Appendix 2, Section 2. Water Management Plan (November 2020) - Appendix 2 Water Management Plan (November 2020) - Appendix 2 Water Management Plan (November 2020) - Appendix 2 Water Management Plan (November 2020) - Section 10 Noted Water Management Plan (November 2020) - Appendix 3 Water Management Plan (November 2020) - Appendix 2 and 3 Site interview Previous 2019 IEA Audit	Sighted. Construction of the current version Approved Methods for the Sampling and Analysis of Water Pollutants in New South Wales. Construction of the crossing was outside of the audit period. However, the 2019 IEA determined compliance. Construction/commissioning phase completed on 5 October 2015 outside of the audit period. Construction/commissioning phase completed on 5 October 2015 outside of the audit period.	Compliant
22 (c) 22 (d) 22 (e) 23 23 (a) 23 (b) 23 (c) 23 (d) 23 (e) 24 24 (a) 24 (b) 24 (c) 24 (d) Waterway C 25 TRAFFIC ANT Construction 26 26 (a)	(c) describe measures to minimise soil erosion and the potential for the transport of sediment to downstream waters; (d) describe the location, function, and capacity of erosion and sediment control structures; and (e) describe what measures would be implemented to maintain (and if necessary decommission) the structures over time. The Surface Water Monitoring Program must include: (a) detailed baseline data on surface water flows and quality in Joarimin Creek, Lockyersleigh Creek, and Marulan Creek; (b) surface water impact assessment criteria; (c) a program to monitor surface water flows and quality; (d) a protocol for the investigation of identified exceedances of the surface water impact assessment criteria; and (e) a program to monitor the effectiveness of the Erosion and Sediment Control Plan. Note: Monitoring of surface flows to be completed by visual assessment. The Ground Water Monitoring Program must include: (a) detailed baseline data on ground water levels, flows, and quality, based on statistical analysis; (b) groundwater impact assessment criteria for monitoring bores; (c) a program to monitor regional ground water levels and quality; and (d) a protocol for the investigation of identified exceedances of the groundwater impact assessment criteria. Note: The surface and ground water monitoring programs must be consistent with the current version of Approved Methods for the Sampling and Analysis of Water Pollutants in New South Wales (OEH). **Ossings** The vehicular crossing of Lockyersleigh Creek as detailed in EA (Mod 4) must be designed and constructed in accordance with the Policy and Guidelines for Fish Friendly Water Crossings (DPI Fisheries, 2004) and Why Do Fish Need to Cross the Road? Fish Passage Requirements for Waterway Crossings (DPI Fisheries, 2004) and Why Do Fish Need to Cross the Road? Fish Passage Requirements for Waterway Crossings (DOE) to the satisfaction of DPI Fisheries. Design plans should be submitted to DPI Fisheries for approval arior to the construction. TRANSPORT (Inc	Water Management Plan (November 2020) - Section 6 Water Management Plan (November 2020) - Section 6 Water Management Plan (November 2020) - Section 6 Water Management Plan (November 2020) - Section 9 Noted Water Management Plan (November 2020) - Appendix 2, Section 2. Water Management Plan (November 2020) - Appendix 2 Water Management Plan (November 2020) - Appendix 2 Water Management Plan (November 2020) - Appendix 2 Water Management Plan (November 2020) - Section 10 Noted Water Management Plan (November 2020) - Appendix 3 Water Management Plan (November 2020) - Appendix 2 and 3 Site interview Previous 2019 IEA Audit	Sighted. Construction of the crossing was outside of the audit period. However, the 2019 IEA determined compliance. Construction/commissioning phase completed on 5 October 2015 outside of the audit period.	Compliant
22 (c) 22 (d) 22 (e) 23 23 (a) 23 (b) 23 (c) 23 (d) 23 (e) 24 24 (a) 24 (b) 24 (c) 24 (d) Waterway C 25 TRAFFIC ANT Construction 26 26 (a) 26 (b) 26 (c)	(c) describe measures to minimise soil erosion and the potential for the transport of sediment to downstream waters; (d) describe the location, function, and capacity of erosion and sediment control structures; and (e) describe what measures would be implemented to maintain (and if necessary decommission) the structures over time. The Surface Water Monitoring Program must include: (a) detailed baseline data on surface water flows and quality in Joarimin Creek, Lockyersleigh Creek, and Marulan Creek; (b) surface water impact assessment criteria; (c) a program to monitor surface water flows and quality; (d) a protocol for the investigation of identified exceedances of the surface water impact assessment criteria; and (e) a program to monitor the effectiveness of the Erosion and Sediment Control Plan. Note: Monitoring of surface flows to be completed by visual assessment. The Ground Water Monitoring Program must include: (a) detailed baseline data on ground water levels, flows, and quality, based on statistical analysis; (b) groundwater impact assessment criteria for monitoring bores; (c) a program to monitor regional ground water levels and quality; and (d) a protocol for the investigation of identified exceedances of the groundwater impact assessment criteria. Note: The surface and ground water monitoring programs must be consistent with the current version of Approved Methods for the Sampling and Analysis of Water Pollutants in New South Wales (OEH). Tosings The vehicular crossing of Lockyersleigh Creek as detailed in EA (Mod 4) must be designed and constructed in accordance with the Policy and Guidelines for Fish Friendly Water Crossings (DPI Fisheries, 2004) and Why Do Fish Need to Cross the Road? Fish Passage Requirements for Waterway Crossings (2004) to the satisfaction of DPI Fisheries. Design plans should be submitted to DPI Fisheries for annoval prior to the construction. TRANSPORT (Incorporates RTA, Council and Department of Lands GTAS) Troffic The Applicant must ensure that: (a) construction	Water Management Plan (November 2020) - Section 6 Water Management Plan (November 2020) - Section 6 Water Management Plan (November 2020) - Section 6 Water Management Plan (November 2020) - Section 9 Noted Water Management Plan (November 2020) - Appendix 2, Section 2. Water Management Plan (November 2020) - Appendix 2 Water Management Plan (November 2020) - Appendix 2 Water Management Plan (November 2020) - Appendix 2 Water Management Plan (November 2020) - Section 10 Noted Water Management Plan (November 2020) - Appendix 3 Water Management Plan (November 2020) - Appendix 3 Water Management Plan (November 2020) - Appendix 3 Water Management Plan (November 2020) - Appendix 2 and 3 Site interviews Site Observations Site interviews Site Observations Site interviews Site Observations Site interviews Site Observations Site interviews	Sighted. Construction of the current version Approved Methods for the Sampling and Analysis of Water Pollutants in New South Wales. Construction of the crossing was outside of the audit period. However, the 2019 IEA determined compliance. Construction/commissioning phase completed on 5 October 2015 outside of the audit period. Access road used as other access option, Stoney Creek Rd, is now locked.	Compliant
22 (c) 22 (d) 22 (e) 23 23 (a) 23 (b) 23 (c) 23 (d) 23 (e) 24 24 (a) 24 (b) 24 (c) 24 (d) Waterway C 25 TRAFFIC ANI Construction 26 26 (a) 26 (b)	(c) describe measures to minimise soil erosion and the potential for the transport of sediment to downstream waters; (d) describe the location, function, and capacity of erosion and sediment control structures; and (e) describe what measures would be implemented to maintain (and if necessary decommission) the structures over time. The Surface Water Monitoring Program must include: (a) detailed baseline data on surface water flows and quality in Joarimin Creek, Lockyersleigh Creek, and Marulan Creek; (b) surface water impact assessment criteria; (c) a program to monitor surface water flows and quality; (d) a protocol for the investigation of identified exceedances of the surface water impact assessment criteria; and (e) a program to monitor the effectiveness of the Erosion and Sediment Control Plan. Note: Monitoring of surface flows to be completed by visual assessment. The Ground Water Monitoring Program must include: (a) detailed baseline data on ground water levels, flows, and quality, based on statistical analysis; (b) groundwater impact assessment criteria for monitoring bores; (c) a program to monitor regional ground water levels and quality, and (d) a protocol for the investigation of identified exceedances of the groundwater impact assessment criteria. Note: The surface and ground water monitoring programs must be consistent with the current version of Approved Methods for the Sampling and Analysis of Water Pollutants in New South Wales (OEH). **OSTITUTE** The Vehicular crossing of Lockyersleigh Creek as detailed in EA (Mod 4) must be designed and constructed in accordance with the Policy and Guidelines for Fish Friendly Water Crossings (DPI Fisheries, 2004) and Why Do Fish Need to Cross the Road? Fish Passage Requirements for Waterway Crossings (2004) to the satisfaction of DPI Fisheries. Design plans should be submitted to DPI Fisheries for annormal prior to the construction. The Applicant must ensure that: (a) construction traffic on the temporary construction access is kept to a minimum; (b)	Water Management Plan (November 2020) - Section 6 Water Management Plan (November 2020) - Section 6 Water Management Plan (November 2020) - Section 6 Water Management Plan (November 2020) - Section 9 Noted Water Management Plan (November 2020) - Appendix 2, Section 2. Water Management Plan (November 2020) - Appendix 2 Water Management Plan (November 2020) - Appendix 2 Water Management Plan (November 2020) - Appendix 2 Water Management Plan (November 2020) - Section 10 Noted Water Management Plan (November 2020) - Appendix 3 Water Management Plan (November 2020) - Appendix 3 Water Management Plan (November 2020) - Appendix 3 Water Management Plan (November 2020) - Appendix 3 Water Management Plan (November 2020) - Appendix 3 Site interview Previous 2019 IEA Audit	Sighted. Construction of the current version Approved Methods for the Sampling and Analysis of Water Pollutants in New South Wales. Construction of the crossing was outside of the audit period. However, the 2019 IEA determined compliance. Construction/commissioning phase completed on 5 October 2015 outside of the audit period. Construction/commissioning phase completed on 5 October 2015 outside of the audit period.	Compliant
22 (c) 22 (d) 22 (e) 23 23 (a) 23 (b) 23 (c) 23 (d) 23 (e) 24 24 (a) 24 (b) 24 (c) 24 (d) Waterway C 25 TRAFFIC ANT Construction 26 26 (a) 26 (b) 26 (c)	(c) describe measures to minimise soil erosion and the potential for the transport of sediment to downstream waters; (d) describe the location, function, and capacity of erosion and sediment control structures; and (e) describe what measures would be implemented to maintain (and if necessary decommission) the structures over time. The Surface Water Monitoring Program must include: (a) detailed baseline data on surface water flows and quality in Joarimin Creek, Lockyersleigh Creek, and Marulan Creek; (b) surface water impact assessment criteria; (c) a program to monitor surface water flows and quality; (d) a protocol for the investigation of identified exceedances of the surface water impact assessment criteria; and (e) a program to monitor the effectiveness of the Erosion and Sediment Control Plan. Note: Monitoring of surface flows to be completed by visual assessment. The Ground Water Monitoring Program must include: (a) detailed baseline data on ground water levels, flows, and quality, based on statistical analysis; (b) groundwater impact assessment criteria for monitoring bores; (c) a program to monitor regional ground water levels and quality; and (d) a protocol for the investigation of identified exceedances of the groundwater impact assessment criteria. Note: The surface and ground water monitoring programs must be consistent with the current version of Approved Methods for the Sampling and Analysis of Water Pollutants in New South Wales (OEH). Tosings The vehicular crossing of Lockyersleigh Creek as detailed in EA (Mod 4) must be designed and constructed in accordance with the Policy and Guidelines for Fish Friendly Water Crossings (DPI Fisheries, 2004) and Why Do Fish Need to Cross the Road? Fish Passage Requirements for Waterway Crossings (2004) to the satisfaction of DPI Fisheries. Design plans should be submitted to DPI Fisheries for annoval prior to the construction. TRANSPORT (Incorporates RTA, Council and Department of Lands GTAS) Troffic The Applicant must ensure that: (a) construction	Water Management Plan (November 2020) - Section 6 Water Management Plan (November 2020) - Section 6 Water Management Plan (November 2020) - Section 6 Water Management Plan (November 2020) - Section 9 Noted Water Management Plan (November 2020) - Appendix 2, Section 2. Water Management Plan (November 2020) - Appendix 2 Water Management Plan (November 2020) - Appendix 2 Water Management Plan (November 2020) - Appendix 2 Water Management Plan (November 2020) - Section 10 Noted Water Management Plan (November 2020) - Appendix 3 Water Management Plan (November 2020) - Appendix 3 Water Management Plan (November 2020) - Appendix 3 Water Management Plan (November 2020) - Appendix 2 and 3 Site interviews Site Observations Site interviews Site Observations Site interviews Site Observations Site interviews Site Observations Site interviews	Sighted. Construction of the current version Approved Methods for the Sampling and Analysis of Water Pollutants in New South Wales. Construction of the crossing was outside of the audit period. However, the 2019 IEA determined compliance. Construction/commissioning phase completed on 5 October 2015 outside of the audit period. Access road used as other access option, Stoney Creek Rd, is now locked.	Compliant

	To a second seco	I		
26 (e)	(e) heavy vehicle construction traffic using George Street does not exceed 40kph; and	Site Observations Site interviews	Construction/commissioning phase completed on 5 October 2015 outside of the audit perior	Compliant
26 (f)	(f) no traffic uses the construction site access once the proposed Hume Highway Interchange has been commissioned.	Site Observations	The Hume Highway Interchange is used exclusively to access the site.	Compliant
	Note: The terrangery construction process and are shown in Amendia (T. The requirements of this condition was to be reflected in the	Site interviews		
	Note: The temporary construction access routes are shown in Appendix 5. The requirements of this condition are to be reflected in the Construction Traffic Management Plan required under Condition 28 below.	Noted		
27	Prior to the commissioning of the proposed Hume Highway Interchange, the Applicant shall maintain the public roads on the construction	Site Observations	Construction/commissioning phase completed on 5 October 2015 outside of the audit	Compliant
		Site interviews	period. The Hume Highway Interchange is now used exclusively to access the site.	
	access, to the satisfaction of Council and/or the Department of Lands.			
28	Prior to carrying out any development, the Applicant must prepare (and following approval implement) a Construction Traffic	Site Observations	Construction/commissioning phase completed on 5 October 2015 outside of the audit period	Compliant
	Management Plan for the development, in consultation with the RMS, Council and the Department of Lands, and to the satisfaction of the Secretary. This plan must:	Site interviews		
	(a) include a Road Dilapidation Report of the public roads on the construction access routes; and			
	(b) describe what measures would be implemented to:			
	maintain the public roads;			
	minimise the potential noise and safety impacts associated with the construction traffic; and least the community informed of any traffic discreptions that would be caused by the development.			
Hume Highv	vay Interchange			
29	The Applicant must:	Noted		
29 (a)	(a) design and construct the proposed grade separated intersection at the existing junction of the Hume Highway (SH2) and Marulan South Road/Jerrara Road; and following the satisfactory completion of this development,	Site Observations Site interviews	Construction/commissioning phase completed on 5 October 2015, outside of the audit	Compliant
	South Road/Jerrara Road, and following the Satisfactory completion of this development,	Site interviews	period. The Hume Highway Interchange is now used exclusively to access the site.	
29 (b)	(b) close the existing median and proclaimed access point on the Hume Highway,	Site Observations	Construction/commissioning phase completed on 5 October 2015, outside of the audit	Compliant
23 (0)	Notes:	Size Sasti Futions	construction/commissioning phase completed on 5 october 2015, outside of the addit	- Companie
	The design of these works must be in accordance with relevant RMS standards and specifications: • The design of these works must be in accordance with relevant RMS standards and specifications:			
	- geometric road design in accordance with RMS Road Design Guide;			
	- pavement design in accordance with the AUSTROADS Pavement Design Guide;			
	- bridge design in accordance with Australian Standard AS5100; and - grade senarated interchange in accordance with NAASRA (AUSTROADS) Grade Senarated Interchanges – A Design Guide	Noted		
	• The Applicant will be required to meet all the costs associated with this development, including design, land acquisitions, gazettal of new	Need		
	boundaries and access point, construction and project management. • If other quarries or developments are approved that use this intersection, the applicants for such developments may be required to	Noted		
	• If other quarries or developments are approved that use this intersection, the applicants for such developments may be required to contribute to the cost of constructing the intersection, pro-rata on maximum usage rates. The Applicant must keep detailed records of the			
	intersection design and construction costs and provide this information to the Secretary if requested to assist in levying costs on any such			
20	develonments.	Noted	Controlled to the state of the	Consider
30	Prior to carrying out any development in the Hume Highway road reserve, the Applicant must prepare a Traffic Management Plan for the proposed development in the road reserve to the satisfaction of the RMS.	Site Observations Site interviews	Construction/commissioning phase completed on 5 October 2015, outside of the audit	Compliant
	proposed development in the road reserve to the satisfaction of the tivis.	Site interviews	period. The Hume Highway Interchange is now used exclusively to access the site.	
Crown Road	l s/Land			
31	The Applicant must not carry out any development on Crown roads or land without the written approval of the Department of Lands.			Compliant
		Site interviews	No further works undertaken during audit period requiring approval.	
Road Haulag				
	The Applicant court on one that all leaded out take a contact or a leader of the area accounted at all there a			Committee
32	The Applicant must ensure that all loaded vehicles entering or leaving the site are covered at all times. The Applicant must ensure that all loaded vehicles leaving the site are cleaned of materials that may fall on the road before they are	Site Observations Site Observations	Sighted truck leaving sighted with load covered No debris was observed on roads leading to the site. Wheel wash was observed in operation	Compliant
32	The Applicant must ensure that all loaded vehicles entering or leaving the site are covered at all times. The Applicant must ensure that all loaded vehicles leaving the site are cleaned of materials that may fall on the road before they are allowed to leave the site.	Site Observations Site Observations Site interviews	Sighted truck leaving sighted with load covered No debris was observed on roads leading to the site. Wheel wash was observed in operation on	Compliant Compliant
33	The Applicant must ensure that all loaded vehicles leaving the site are cleaned of materials that may fall on the road before they are	Site Observations	Sighted truck leaving sighted with load covered No debris was observed on roads leading to the site. Wheel wash was observed in operation on	Compliant Compliant
33 Monitoring	The Applicant must ensure that all loaded vehicles leaving the site are cleaned of materials that may fall on the road before they are allowed to leave the site. of Quarry Product Transport The Applicant must keep accurate records of all laden truck movements from the site (weekly, monthly and annually) and publish a	Site Observations Site interviews	Sighted truck leaving sighted with load covered No debris was observed on roads leading to the site. Wheel wash was observed in operation on Hard copies of documents are archived at the weighbridge. Laden truck movements for	Compliant Compliant Compliant
33 Monitoring	The Applicant must ensure that all loaded vehicles leaving the site are cleaned of materials that may fall on the road before they are allowed to leave the site. of Quarry Product Transport	Site Observations Site interviews Annual Review 2020, 2021, 2022.	No debris was observed on roads leading to the site. Wheel wash was observed in operation on Hard copies of documents are archived at the weighbridge. Laden truck movements for each	Compliant
33 Monitoring	The Applicant must ensure that all loaded vehicles leaving the site are cleaned of materials that may fall on the road before they are allowed to leave the site. of Quarry Product Transport The Applicant must keep accurate records of all laden truck movements from the site (weekly, monthly and annually) and publish a	Site Observations Site interviews Annual Review 2020, 2021, 2022. Site Observations - Sighted hard copy transport records and digital	No debris was observed on roads leading to the site. Wheel wash was observed in operation on Hard copies of documents are archived at the weighbridge. Laden truck movements for each month are provided in the 2020, 2021, 2022 Annual Reviews.	Compliant
33 Monitoring (33A	The Applicant must ensure that all loaded vehicles leaving the site are cleaned of materials that may fall on the road before they are allowed to leave the site. of Quarry Product Transport The Applicant must keep accurate records of all laden truck movements from the site (weekly, monthly and annually) and publish a	Site Observations Site interviews Annual Review 2020, 2021, 2022.	No debris was observed on roads leading to the site. Wheel wash was observed in operation on Hard copies of documents are archived at the weighbridge. Laden truck movements for each	Compliant
33 Monitoring of 33A Protection of	The Applicant must ensure that all loaded vehicles leaving the site are cleaned of materials that may fall on the road before they are allowed to leave the site. of Quarry Product Transport The Applicant must keep accurate records of all laden truck movements from the site (weekly, monthly and annually) and publish a summary of records in its Annual Review. f Aboriginal Sites	Site Observations Site interviews Annual Review 2020, 2021, 2022. Site Observations - Sighted hard copy transport records and digital tracking platform.	No debris was observed on roads leading to the site. Wheel wash was observed in operation on Hard copies of documents are archived at the weighbridge. Laden truck movements for each month are provided in the 2020, 2021, 2022 Annual Reviews. Digital tracking platform updated daily.	Compliant
33 Monitoring (33A	The Applicant must ensure that all loaded vehicles leaving the site are cleaned of materials that may fall on the road before they are allowed to leave the site. of Quarry Product Transport The Applicant must keep accurate records of all laden truck movements from the site (weekly, monthly and annually) and publish a summary of records in its Annual Review. f Aboriginal Sites The Applicant must ensure that the development does not cause any direct or indirect impact on identified Aboriginal sites located	Site Observations Site interviews Annual Review 2020, 2021, 2022. Site Observations - Sighted hard copy transport records and digital tracking platform. Lynwood Quarry Aboriginal Heritage Management Plan, Caring for County	No debris was observed on roads leading to the site. Wheel wash was observed in operation on Hard copies of documents are archived at the weighbridge. Laden truck movements for each month are provided in the 2020, 2021, 2022 Annual Reviews. Digital tracking platform updated daily. Exclusion fencing was observed throughout the site and is clearly signed as areas of cultural	Compliant
33 Monitoring of 33A Protection of	The Applicant must ensure that all loaded vehicles leaving the site are cleaned of materials that may fall on the road before they are allowed to leave the site. If Quarry Product Transport The Applicant must keep accurate records of all laden truck movements from the site (weekly, monthly and annually) and publish a summary of records in its Annual Review. If Aboriginal Sites The Applicant must ensure that the development does not cause any direct or indirect impact on identified Aboriginal sites located outside the approved disturbance area of the development. Only those Aboriginal sites identified within the approved Aboriginal Cultural Heritage Management Plan (see condition 35) or any approved Aboriginal Heritage Impact Permit may be impacted within the approved	Site Observations Site interviews Annual Review 2020, 2021, 2022. Site Observations - Sighted hard copy transport records and digital tracking platform. Lynwood Quarry Aboriginal Heritage Management Plan, Caring for County	No debris was observed on roads leading to the site. Wheel wash was observed in operation on Hard copies of documents are archived at the weighbridge. Laden truck movements for each month are provided in the 2020, 2021, 2022 Annual Reviews. Digital tracking platform updated daily.	Compliant
33 Monitoring of 33A Protection of	The Applicant must ensure that all loaded vehicles leaving the site are cleaned of materials that may fall on the road before they are allowed to leave the site. If Quarry Product Transport The Applicant must keep accurate records of all laden truck movements from the site (weekly, monthly and annually) and publish a summary of records in its Annual Review. If Aboriginal Sites The Applicant must ensure that the development does not cause any direct or indirect impact on identified Aboriginal sites located outside the approved disturbance area of the development. Only those Aboriginal sites identified within the approved Aboriginal Cultural	Site Observations Site interviews Annual Review 2020, 2021, 2022. Site Observations - Sighted hard copy transport records and digital tracking platform. Lynwood Quarry Aboriginal Heritage Management Plan, Caring for County (Umwelt 2022)	No debris was observed on roads leading to the site. Wheel wash was observed in operation on Hard copies of documents are archived at the weighbridge. Laden truck movements for each month are provided in the 2020, 2021, 2022 Annual Reviews. Digital tracking platform updated daily. Exclusion fencing was observed throughout the site and is clearly signed as areas of cultural	Compliant
33 Monitoring 33A Protection o 34	The Applicant must ensure that all loaded vehicles leaving the site are cleaned of materials that may fall on the road before they are allowed to leave the site. If Quarry Product Transport The Applicant must keep accurate records of all laden truck movements from the site (weekly, monthly and annually) and publish a summary of records in its Annual Review. If Aboriginal Sites The Applicant must ensure that the development does not cause any direct or indirect impact on identified Aboriginal sites located outside the approved disturbance area of the development. Only those Aboriginal sites identified within the approved Aboriginal Cultural Heritage Management Plan (see condition 35) or any approved Aboriginal Heritage Impact Permit may be impacted within the approved disturbance area of the development.	Site Observations Site interviews Annual Review 2020, 2021, 2022. Site Observations - Sighted hard copy transport records and digital tracking platform. Lynwood Quarry Aboriginal Heritage Management Plan, Caring for County (Umwelt 2022) Site Observations Site interviews	No debris was observed on roads leading to the site. Wheel wash was observed in operation on Hard copies of documents are archived at the weighbridge. Laden truck movements for each month are provided in the 2020, 2021, 2022 Annual Reviews. Digital tracking platform updated daily. Exclusion fencing was observed throughout the site and is clearly signed as areas of cultural significance.	Compliant Compliant Compliant
33 Monitoring 33A Protection o 34	The Applicant must ensure that all loaded vehicles leaving the site are cleaned of materials that may fall on the road before they are allowed to leave the site. If Quarry Product Transport The Applicant must keep accurate records of all laden truck movements from the site (weekly, monthly and annually) and publish a summary of records in its Annual Review. If Aboriginal Sites The Applicant must ensure that the development does not cause any direct or indirect impact on identified Aboriginal sites located outside the approved disturbance area of the development. Only those Aboriginal sites identified within the approved Aboriginal Heritage Management Plan (see condition 35) or any approved Aboriginal Heritage Impact Permit may be impacted within the approved disturbance area of the development. Ultural Heritage Management Plan The Applicant must prepare an Aboriginal Cultural Heritage Management Plan for the development to the satisfaction of the Secretary.	Site Observations Site interviews Annual Review 2020, 2021, 2022. Site Observations - Sighted hard copy transport records and digital tracking platform. Lynwood Quarry Aboriginal Heritage Management Plan, Caring for County (Umwelt 2022) Site Observations Site interviews Lynwood Quarry Aboriginal Heritage Management Plan, Caring for County	No debris was observed on roads leading to the site. Wheel wash was observed in operation on Hard copies of documents are archived at the weighbridge. Laden truck movements for each month are provided in the 2020, 2021, 2022 Annual Reviews. Digital tracking platform updated daily. Exclusion fencing was observed throughout the site and is clearly signed as areas of cultural significance.	Compliant
33 Monitoring of 33A Protection of 34 Aboriginal C	The Applicant must ensure that all loaded vehicles leaving the site are cleaned of materials that may fall on the road before they are allowed to leave the site. If Quarry Product Transport The Applicant must keep accurate records of all laden truck movements from the site (weekly, monthly and annually) and publish a summary of records in its Annual Review. If Aboriginal Sites The Applicant must ensure that the development does not cause any direct or indirect impact on identified Aboriginal sites located outside the approved disturbance area of the development. Only those Aboriginal sites identified within the approved Aboriginal Cultural Heritage Management Plan (see condition 35) or any approved Aboriginal Heritage Impact Permit may be impacted within the approved disturbance area of the development.	Site Observations Site interviews Annual Review 2020, 2021, 2022. Site Observations - Sighted hard copy transport records and digital tracking platform. Lynwood Quarry Aboriginal Heritage Management Plan, Caring for County (Umwelt 2022) Site Observations Site interviews Lynwood Quarry Aboriginal Heritage Management Plan, Caring for County (Umwelt 2022)	No debris was observed on roads leading to the site. Wheel wash was observed in operation on Hard copies of documents are archived at the weighbridge. Laden truck movements for each month are provided in the 2020, 2021, 2022 Annual Reviews. Digital tracking platform updated daily. Exclusion fencing was observed throughout the site and is clearly signed as areas of cultural significance. Sighted current Aboriginal Heritage Management Plan, Caring for County (Umwelt 2022)	Compliant Compliant Compliant
33 Monitoring of 33A Protection of 34 Aboriginal C	The Applicant must ensure that all loaded vehicles leaving the site are cleaned of materials that may fall on the road before they are allowed to leave the site. If Quarry Product Transport The Applicant must keep accurate records of all laden truck movements from the site (weekly, monthly and annually) and publish a summary of records in its Annual Review. If Aboriginal Sites The Applicant must ensure that the development does not cause any direct or indirect impact on identified Aboriginal sites located outside the approved disturbance area of the development. Only those Aboriginal sites identified within the approved Aboriginal Heritage Management Plan (see condition 35) or any approved Aboriginal Heritage Impact Permit may be impacted within the approved disturbance area of the development. Ultural Heritage Management Plan The Applicant must prepare an Aboriginal Cultural Heritage Management Plan for the development to the satisfaction of the Secretary.	Site Observations Site interviews Annual Review 2020, 2021, 2022. Site Observations - Sighted hard copy transport records and digital tracking platform. Lynwood Quarry Aboriginal Heritage Management Plan, Caring for County (Umwelt 2022) Site Observations Site interviews Lynwood Quarry Aboriginal Heritage Management Plan, Caring for County (Umwelt 2022) Correspondence Holcim to DPE dated 30 June 2023, regarding	No debris was observed on roads leading to the site. Wheel wash was observed in operation on Hard copies of documents are archived at the weighbridge. Laden truck movements for each month are provided in the 2020, 2021, 2022 Annual Reviews. Digital tracking platform updated daily. Exclusion fencing was observed throughout the site and is clearly signed as areas of cultural significance. Sighted current Aboriginal Heritage Management Plan, Caring for County (Umwelt 2022) and correspondence to DPE confirm no revision to the plan following the 2022 Annual	Compliant Compliant Compliant
33 Monitoring 33A Protection o 34 Aboriginal C 35	The Applicant must ensure that all loaded vehicles leaving the site are cleaned of materials that may fall on the road before they are allowed to leave the site. If Quarry Product Transport The Applicant must keep accurate records of all laden truck movements from the site (weekly, monthly and annually) and publish a summary of records in its Annual Review. If Aboriginal Sites The Applicant must ensure that the development does not cause any direct or indirect impact on identified Aboriginal sites located outside the approved disturbance area of the development. Only those Aboriginal sites identified within the approved Aboriginal Cultural Heritage Management Plan (see condition 35) or any approved Aboriginal Heritage Impact Permit may be impacted within the approved disturbance area of the development. Ultural Heritage Management Plan The Applicant must prepare an Aboriginal Cultural Heritage Management Plan for the development to the satisfaction of the Secretary. The plan must:	Site Observations Site interviews Annual Review 2020, 2021, 2022. Site Observations - Sighted hard copy transport records and digital tracking platform. Lynwood Quarry Aboriginal Heritage Management Plan, Caring for County (Umwelt 2022) Site Observations Site interviews Lynwood Quarry Aboriginal Heritage Management Plan, Caring for County (Umwelt 2022)	No debris was observed on roads leading to the site. Wheel wash was observed in operation on Hard copies of documents are archived at the weighbridge. Laden truck movements for each month are provided in the 2020, 2021, 2022 Annual Reviews. Digital tracking platform updated daily. Exclusion fencing was observed throughout the site and is clearly signed as areas of cultural significance. Sighted current Aboriginal Heritage Management Plan, Caring for County (Umwelt 2022) and correspondence to DPE confirm no revision to the plan following the 2022 Annual Review.	Compliant Compliant Compliant Compliant
33 Monitoring 33A Protection o 34 Aboriginal C	The Applicant must ensure that all loaded vehicles leaving the site are cleaned of materials that may fall on the road before they are allowed to leave the site. If Quarry Product Transport The Applicant must keep accurate records of all laden truck movements from the site (weekly, monthly and annually) and publish a summary of records in its Annual Review. If Aboriginal Sites The Applicant must ensure that the development does not cause any direct or indirect impact on identified Aboriginal sites located outside the approved disturbance area of the development. Only those Aboriginal sites identified within the approved Aboriginal Heritage Management Plan (see condition 35) or any approved Aboriginal Heritage Impact Permit may be impacted within the approved disturbance area of the development. Ultural Heritage Management Plan The Applicant must prepare an Aboriginal Cultural Heritage Management Plan for the development to the satisfaction of the Secretary.	Site Observations Site interviews Annual Review 2020, 2021, 2022. Site Observations - Sighted hard copy transport records and digital tracking platform. Lynwood Quarry Aboriginal Heritage Management Plan, Caring for County (Umwelt 2022) Site Observations Site interviews Lynwood Quarry Aboriginal Heritage Management Plan, Caring for County (Umwelt 2022) Correspondence Holcim to DPE dated 30 June 2023, regarding	No debris was observed on roads leading to the site. Wheel wash was observed in operation on Hard copies of documents are archived at the weighbridge. Laden truck movements for each month are provided in the 2020, 2021, 2022 Annual Reviews. Digital tracking platform updated daily. Exclusion fencing was observed throughout the site and is clearly signed as areas of cultural significance. Sighted current Aboriginal Heritage Management Plan, Caring for County (Umwelt 2022) and correspondence to DPE confirm no revision to the plan following the 2022 Annual	Compliant Compliant Compliant
33 Monitoring 33A Protection o 34 Aboriginal C 35	The Applicant must ensure that all loaded vehicles leaving the site are cleaned of materials that may fall on the road before they are allowed to leave the site. If Quarry Product Transport The Applicant must keep accurate records of all laden truck movements from the site (weekly, monthly and annually) and publish a summary of records in its Annual Review. If Aboriginal Sites The Applicant must ensure that the development does not cause any direct or indirect impact on identified Aboriginal sites located outside the approved disturbance area of the development. Only those Aboriginal sites identified within the approved Aboriginal Cultural Heritage Management Plan (see condition 35) or any approved Aboriginal Heritage Impact Permit may be impacted within the approved disturbance area of the development. Ultural Heritage Management Plan The Applicant must prepare an Aboriginal Cultural Heritage Management Plan for the development to the satisfaction of the Secretary. The plan must:	Site Observations Site interviews Annual Review 2020, 2021, 2022. Site Observations - Sighted hard copy transport records and digital tracking platform. Lynwood Quarry Aboriginal Heritage Management Plan, Caring for County (Umwelt 2022) Site Observations Site interviews Lynwood Quarry Aboriginal Heritage Management Plan, Caring for County (Umwelt 2022) Correspondence Holcim to DPE dated 30 June 2023, regarding management plan reviews.	No debris was observed on roads leading to the site. Wheel wash was observed in operation on Hard copies of documents are archived at the weighbridge. Laden truck movements for each month are provided in the 2020, 2021, 2022 Annual Reviews. Digital tracking platform updated daily. Exclusion fencing was observed throughout the site and is clearly signed as areas of cultural significance. Sighted current Aboriginal Heritage Management Plan, Caring for County (Umwelt 2022) and correspondence to DPE confirm no revision to the plan following the 2022 Annual Review. Previous audit sighted DPE's letter of 5 December 2016 endorses the appointment of Jan	Compliant Compliant Compliant Compliant
33 Monitoring 33A Protection o 34 Aboriginal C 35	The Applicant must ensure that all loaded vehicles leaving the site are cleaned of materials that may fall on the road before they are allowed to leave the site. of Quarry Product Transport The Applicant must keep accurate records of all laden truck movements from the site (weekly, monthly and annually) and publish a summary of records in its Annual Review. f Aboriginal Sites The Applicant must ensure that the development does not cause any direct or indirect impact on identified Aboriginal sites located outside the approved disturbance area of the development. Only those Aboriginal sites identified within the approved Aboriginal Cultural Heritage Management Plan (see condition 35) or any approved Aboriginal Heritage Impact Permit may be impacted within the approved disturbance area of the development. ultural Heritage Management Plan The Applicant must prepare an Aboriginal Cultural Heritage Management Plan for the development to the satisfaction of the Secretary. The plan must: (a) be prepared by suitably qualified and experienced person/s whose appointment has been endorsed by the Secretary;	Site Observations Site interviews Annual Review 2020, 2021, 2022. Site Observations - Sighted hard copy transport records and digital tracking platform. Lynwood Quarry Aboriginal Heritage Management Plan, Caring for County (Umwelt 2022) Site Observations Site interviews Lynwood Quarry Aboriginal Heritage Management Plan, Caring for County (Umwelt 2022) Correspondence Holcim to DPE dated 30 June 2023, regarding management plan reviews.	No debris was observed on roads leading to the site. Wheel wash was observed in operation on Hard copies of documents are archived at the weighbridge. Laden truck movements for each month are provided in the 2020, 2021, 2022 Annual Reviews. Digital tracking platform updated daily. Exclusion fencing was observed throughout the site and is clearly signed as areas of cultural significance. Sighted current Aboriginal Heritage Management Plan, Caring for County (Umwelt 2022) and correspondence to DPE confirm no revision to the plan following the 2022 Annual Review. Previous audit sighted DPE's letter of 5 December 2016 endorses the appointment of Jan Wilson, Principal Archaeologist Umwelt to prepare the	Compliant Compliant Compliant Compliant Compliant Compliant
33 Monitoring 33A Protection o 34 Aboriginal C 35	The Applicant must ensure that all loaded vehicles leaving the site are cleaned of materials that may fall on the road before they are allowed to leave the site. of Quarry Product Transport The Applicant must keep accurate records of all laden truck movements from the site (weekly, monthly and annually) and publish a summary of records in its Annual Review. f Aboriginal Sites The Applicant must ensure that the development does not cause any direct or indirect impact on identified Aboriginal sites located outside the approved disturbance area of the development. Only those Aboriginal sites identified within the approved Aboriginal Cultural Heritage Management Plan (see condition 35) or any approved Aboriginal Heritage Impact Permit may be impacted within the approved disturbance area of the development. ultural Heritage Management Plan The Applicant must prepare an Aboriginal Cultural Heritage Management Plan for the development to the satisfaction of the Secretary. The plan must: (a) be prepared by suitably qualified and experienced person/s whose appointment has been endorsed by the Secretary;	Site Observations Site interviews Annual Review 2020, 2021, 2022. Site Observations - Sighted hard copy transport records and digital tracking platform. Lynwood Quarry Aboriginal Heritage Management Plan, Caring for County (Umwelt 2022) Site Observations Site interviews Lynwood Quarry Aboriginal Heritage Management Plan, Caring for County (Umwelt 2022) Correspondence Holcim to DPE dated 30 June 2023, regarding management plan reviews. DPE Letter of 5 December 2016 Lynwood Quarry Aboriginal Heritage Management Plan, Caring for County	No debris was observed on roads leading to the site. Wheel wash was observed in operation on Hard copies of documents are archived at the weighbridge. Laden truck movements for each month are provided in the 2020, 2021, 2022 Annual Reviews. Digital tracking platform updated daily. Exclusion fencing was observed throughout the site and is clearly signed as areas of cultural significance. Sighted current Aboriginal Heritage Management Plan, Caring for County (Umwelt 2022) and correspondence to DPE confirm no revision to the plan following the 2022 Annual Review. Previous audit sighted DPE's letter of 5 December 2016 endorses the appointment of Jan Wilson, Principal Archaeologist Umwelt to prepare the Section 1.3 of the approved Lynwood Quarry Aboriginal Heritage Management Plan (2022) confirms consultation with Register Aboriginal Parties. Section 1.4 of the approved Lynwood Quarry Aboriginal Heritage Management Plan (2022)	Compliant Compliant Compliant Compliant Compliant Compliant
33 Monitoring 33A Protection of 34 Aboriginal C 35 35 (a) 35 (b)	The Applicant must ensure that all loaded vehicles leaving the site are cleaned of materials that may fall on the road before they are allowed to leave the site. If Quarry Product Transport The Applicant must keep accurate records of all laden truck movements from the site (weekly, monthly and annually) and publish a summary of records in its Annual Review. If Aboriginal Sites The Applicant must ensure that the development does not cause any direct or indirect impact on identified Aboriginal sites located outside the approved disturbance area of the development. Only those Aboriginal sites identified within the approved Aboriginal Cultural Heritage Management Plan (see condition 35) or any approved Aboriginal Heritage Impact Permit may be impacted within the approved disturbance area of the development. Ultural Heritage Management Plan The Applicant must prepare an Aboriginal Cultural Heritage Management Plan for the development to the satisfaction of the Secretary. The plan must: (a) be prepared by suitably qualified and experienced person/s whose appointment has been endorsed by the Secretary; (b) be prepared in consultation with OEH and local Aboriginal stakeholders;	Site Observations Site interviews Annual Review 2020, 2021, 2022. Site Observations - Sighted hard copy transport records and digital tracking platform. Lynwood Quarry Aboriginal Heritage Management Plan, Caring for County (Umwelt 2022) Site Observations Site interviews Lynwood Quarry Aboriginal Heritage Management Plan, Caring for County (Umwelt 2022) Correspondence Holcim to DPE dated 30 June 2023, regarding management plan reviews. DPE Letter of 5 December 2016 Lynwood Quarry Aboriginal Heritage Management Plan, Caring for County (Umwelt 2022)	No debris was observed on roads leading to the site. Wheel wash was observed in operation on Hard copies of documents are archived at the weighbridge. Laden truck movements for each month are provided in the 2020, 2021, 2022 Annual Reviews. Digital tracking platform updated daily. Exclusion fencing was observed throughout the site and is clearly signed as areas of cultural significance. Sighted current Aboriginal Heritage Management Plan, Caring for County (Umwelt 2022) and correspondence to DPE confirm no revision to the plan following the 2022 Annual Review. Previous audit sighted DPE's letter of 5 December 2016 endorses the appointment of Jan Wilson, Principal Archaeologist Umwelt to prepare the Section 1.3 of the approved Lynwood Quarry Aboriginal Heritage Management Plan (2022) confirms consultation with Register Aboriginal Parties. Section 1.4 of the approved Lynwood Quarry Aboriginal Heritage Management Plan (2022) confirms consultation with government agencies.	Compliant Compliant Compliant Compliant Compliant Compliant Compliant
33 Monitoring 33A Protection o 34 Aboriginal C 35 35 (a) 35 (b)	The Applicant must ensure that all loaded vehicles leaving the site are cleaned of materials that may fall on the road before they are allowed to leave the site. If Quarry Product Transport The Applicant must keep accurate records of all laden truck movements from the site (weekly, monthly and annually) and publish a summary of records in its Annual Review. If Aboriginal Sites The Applicant must ensure that the development does not cause any direct or indirect impact on identified Aboriginal sites located outside the approved disturbance area of the development. Only those Aboriginal sites identified within the approved Aboriginal Cultural Heritage Management Plan (see condition 35) or any approved Aboriginal Heritage Impact Permit may be impacted within the approved disturbance area of the development. Ultural Heritage Management Plan The Applicant must prepare an Aboriginal Cultural Heritage Management Plan for the development to the satisfaction of the Secretary. The plan must: (a) be prepared by suitably qualified and experienced person/s whose appointment has been endorsed by the Secretary; (b) be prepared in consultation with OEH and local Aboriginal stakeholders;	Site Observations Site interviews Annual Review 2020, 2021, 2022. Site Observations - Sighted hard copy transport records and digital tracking platform. Lynwood Quarry Aboriginal Heritage Management Plan, Caring for County (Umwelt 2022) Site Observations Site interviews Lynwood Quarry Aboriginal Heritage Management Plan, Caring for County (Umwelt 2022) Correspondence Holcim to DPE dated 30 June 2023, regarding management plan reviews. DPE Letter of 5 December 2016 Lynwood Quarry Aboriginal Heritage Management Plan, Caring for County	No debris was observed on roads leading to the site. Wheel wash was observed in operation on Hard copies of documents are archived at the weighbridge. Laden truck movements for each month are provided in the 2020, 2021, 2022 Annual Reviews. Digital tracking platform updated daily. Exclusion fencing was observed throughout the site and is clearly signed as areas of cultural significance. Sighted current Aboriginal Heritage Management Plan, Caring for County (Umwelt 2022) and correspondence to DPE confirm no revision to the plan following the 2022 Annual Review. Previous audit sighted DPE's letter of 5 December 2016 endorses the appointment of Jan Wilson, Principal Archaeologist Umwelt to prepare the Section 1.3 of the approved Lynwood Quarry Aboriginal Heritage Management Plan (2022) confirms consultation with Register Aboriginal Parties. Section 1.4 of the approved Lynwood Quarry Aboriginal Heritage Management Plan (2022)	Compliant Compliant Compliant Compliant Compliant Compliant Compliant Compliant
33 Monitoring 33A Protection o 34 Aboriginal C 35 35 (a) 35 (b)	The Applicant must ensure that all loaded vehicles leaving the site are cleaned of materials that may fall on the road before they are allowed to leave the site. Figuarry Product Transport The Applicant must keep accurate records of all laden truck movements from the site (weekly, monthly and annually) and publish a summary of records in its Annual Review. FAboriginal Sites The Applicant must ensure that the development does not cause any direct or indirect impact on identified Aboriginal sites located outside the approved disturbance area of the development. Only those Aboriginal sites identified within the approved Aboriginal Cultural Heritage Management Plan (see condition 35) or any approved Aboriginal Heritage Impact Permit may be impacted within the approved disturbance area of the development. **Ultural Heritage Management Plan** The Applicant must prepare an Aboriginal Cultural Heritage Management Plan for the development to the satisfaction of the Secretary. The plan must: (a) be prepared by suitably qualified and experienced person/s whose appointment has been endorsed by the Secretary; (b) be prepared in consultation with OEH and local Aboriginal stakeholders; (c) be submitted to the Secretary for approval by 30 November 2016, unless the Secretary agrees otherwise; (d) include the following;	Site Observations Site interviews Annual Review 2020, 2021, 2022. Site Observations - Sighted hard copy transport records and digital tracking platform. Lynwood Quarry Aboriginal Heritage Management Plan, Caring for County (Umwelt 2022) Site Observations Site interviews Lynwood Quarry Aboriginal Heritage Management Plan, Caring for County (Umwelt 2022) Correspondence Holcim to DPE dated 30 June 2023, regarding management plan reviews. DPE Letter of 5 December 2016 Lynwood Quarry Aboriginal Heritage Management Plan, Caring for County (Umwelt 2022) Previous 2020 IEA Audit	No debris was observed on roads leading to the site. Wheel wash was observed in operation on Hard copies of documents are archived at the weighbridge. Laden truck movements for each month are provided in the 2020, 2021, 2022 Annual Reviews. Digital tracking platform updated daily. Exclusion fencing was observed throughout the site and is clearly signed as areas of cultural significance. Sighted current Aboriginal Heritage Management Plan, Caring for County (Umwelt 2022) and correspondence to DPE confirm no revision to the plan following the 2022 Annual Review. Previous audit sighted DPE's letter of 5 December 2016 endorses the appointment of Jan Wilson, Principal Archaeologist Umwelt to prepare the Section 1.3 of the approved Lynwood Quarry Aboriginal Heritage Management Plan (2022) confirms consultation with Register Aboriginal Parties. Section 1.4 of the approved Lynwood Quarry Aboriginal Heritage Management Plan (2022) confirms consultation with government agencies.	Compliant Compliant Compliant Compliant Compliant Compliant Compliant
33 Monitoring 33A Protection o 34 Aboriginal C 35 35 (a) 35 (b)	The Applicant must ensure that all loaded vehicles leaving the site are cleaned of materials that may fall on the road before they are allowed to leave the site. If Quarry Product Transport The Applicant must keep accurate records of all laden truck movements from the site (weekly, monthly and annually) and publish a summary of records in its Annual Review. If Aboriginal Sites The Applicant must ensure that the development does not cause any direct or indirect impact on identified Aboriginal sites located outside the approved disturbance area of the development. Only those Aboriginal sites identified within the approved Aboriginal Cultural Heritage Management Plan (see condition 35) or any approved Aboriginal Heritage Impact Permit may be impacted within the approved disturbance area of the development. Ultural Heritage Management Plan The Applicant must prepare an Aboriginal Cultural Heritage Management Plan for the development to the satisfaction of the Secretary. The plan must: (a) be prepared by suitably qualified and experienced person/s whose appointment has been endorsed by the Secretary; (b) be prepared in consultation with OEH and local Aboriginal stakeholders;	Site Observations Site interviews Annual Review 2020, 2021, 2022. Site Observations - Sighted hard copy transport records and digital tracking platform. Lynwood Quarry Aboriginal Heritage Management Plan, Caring for County (Umwelt 2022) Site Observations Site interviews Lynwood Quarry Aboriginal Heritage Management Plan, Caring for County (Umwelt 2022) Correspondence Holcim to DPE dated 30 June 2023, regarding management plan reviews. DPE Letter of 5 December 2016 Lynwood Quarry Aboriginal Heritage Management Plan, Caring for County (Umwelt 2022) Previous 2020 IEA Audit	No debris was observed on roads leading to the site. Wheel wash was observed in operation on Hard copies of documents are archived at the weighbridge. Laden truck movements for each month are provided in the 2020, 2021, 2022 Annual Reviews. Digital tracking platform updated daily. Exclusion fencing was observed throughout the site and is clearly signed as areas of cultural significance. Sighted current Aboriginal Heritage Management Plan, Caring for County (Umwelt 2022) and correspondence to DPE confirm no revision to the plan following the 2022 Annual Review. Previous audit sighted DPE's letter of 5 December 2016 endorses the appointment of Jan Wilson, Principal Archaeologist Umwelt to prepare the Section 1.3 of the approved Lynwood Quarry Aboriginal Heritage Management Plan (2022) confirms consultation with Register Aboriginal Parties. Section 1.4 of the approved Lynwood Quarry Aboriginal Heritage Management Plan (2022) confirms consultation with government agencies. Outside of audit period, previous 2019 IEA Audit confirms compliance.	Compliant Compliant Compliant Compliant Compliant Compliant Compliant Compliant
33 Monitoring 33A Protection of 34 Aboriginal C 35 35 (a) 35 (b)	The Applicant must ensure that all loaded vehicles leaving the site are cleaned of materials that may fall on the road before they are allowed to leave the site. I Quarry Product Transport The Applicant must keep accurate records of all laden truck movements from the site (weekly, monthly and annually) and publish a summary of records in its Annual Review. Faboriginal Sites The Applicant must ensure that the development does not cause any direct or indirect impact on identified Aboriginal sites located outside the approved disturbance area of the development. Only those Aboriginal sites identified within the approved Aboriginal Cultural Heritage Management Plan (see condition 35) or any approved Aboriginal Heritage Impact Permit may be impacted within the approved disturbance area of the development. Ultural Heritage Management Plan The Applicant must prepare an Aboriginal Cultural Heritage Management Plan for the development to the satisfaction of the Secretary. The plan must: (a) be prepared by suitably qualified and experienced person/s whose appointment has been endorsed by the Secretary; (b) be prepared in consultation with OEH and local Aboriginal stakeholders; (c) be submitted to the Secretary for approval by 30 November 2016, unless the Secretary agrees otherwise; (d) include the following; • a Conservation Management Plan that details how the Cultural Heritage Management Zones (shown conceptually on the plan in	Site Observations Site interviews Annual Review 2020, 2021, 2022. Site Observations - Sighted hard copy transport records and digital tracking platform. Lynwood Quarry Aboriginal Heritage Management Plan, Caring for County (Umwelt 2022) Site Observations Site interviews Lynwood Quarry Aboriginal Heritage Management Plan, Caring for County (Umwelt 2022) Correspondence Holcim to DPE dated 30 June 2023, regarding management plan reviews. DPE Letter of 5 December 2016 Lynwood Quarry Aboriginal Heritage Management Plan, Caring for County (Umwelt 2022) Previous 2020 IEA Audit Lynwood Quarry Aboriginal Heritage Management Plan, Caring for County (Umwelt 2022) Lynwood Quarry Aboriginal Heritage Management Plan, Caring for County (Umwelt 2022) Lynwood Quarry Aboriginal Heritage Management Plan, Caring for County (Umwelt 2022)	No debris was observed on roads leading to the site. Wheel wash was observed in operation on Hard copies of documents are archived at the weighbridge. Laden truck movements for each month are provided in the 2020, 2021, 2022 Annual Reviews. Digital tracking platform updated daily. Exclusion fencing was observed throughout the site and is clearly signed as areas of cultural significance. Sighted current Aboriginal Heritage Management Plan, Caring for County (Umwelt 2022) and correspondence to DPE confirm no revision to the plan following the 2022 Annual Review. Previous audit sighted DPE's letter of 5 December 2016 endorses the appointment of Jan Wilson, Principal Archaeologist Umwelt to prepare the Section 1.3 of the approved Lynwood Quarry Aboriginal Heritage Management Plan (2022) confirms consultation with Register Aboriginal Parties. Section 1.4 of the approved Lynwood Quarry Aboriginal Heritage Management Plan (2022) confirms consultation with government agencies. Outside of audit period, previous 2019 IEA Audit confirms compliance. Site observations sighted sign-posted and cordoned-off cultural heritage management zones. Section 3.1 of the Lynwood Quarry Aboriginal Heritage Management Plan, Caring for County	Compliant Compliant Compliant Compliant Compliant Compliant Compliant Compliant Compliant
33 Monitoring 33A Protection of 34 Aboriginal C 35 35 (a) 35 (b)	The Applicant must ensure that all loaded vehicles leaving the site are cleaned of materials that may fall on the road before they are allowed to leave the site. f Quarry Product Transport The Applicant must keep accurate records of all laden truck movements from the site (weekly, monthly and annually) and publish a summary of records in its Annual Review. f Aboriginal Sites The Applicant must ensure that the development does not cause any direct or indirect impact on identified Aboriginal Sites located outside the approved disturbance area of the development. Only those Aboriginal sites identified within the approved Aboriginal Cultural Heritage Management Plan (see condition 35) or any approved Aboriginal Heritage Impact Permit may be impacted within the approved disturbance area of the development. Ditural Heritage Management Plan The Applicant must prepare an Aboriginal Cultural Heritage Management Plan for the development to the satisfaction of the Secretary. The plan must: (a) be prepared by suitably qualified and experienced person/s whose appointment has been endorsed by the Secretary; (b) be prepared in consultation with OEH and local Aboriginal stakeholders; (c) be submitted to the Secretary for approval by 30 November 2016, unless the Secretary agrees otherwise; (d) include the following; * a Conservation Management Plan that details how the Cultural Heritage Management Zones (shown conceptually on the plan in Appendix 6) are managed: * a detailled archaeological salvage program for Aboriginal sites/objects will be managed and protected; and	Site Observations Site interviews Annual Review 2020, 2021, 2022. Site Observations - Sighted hard copy transport records and digital tracking platform. Lynwood Quarry Aboriginal Heritage Management Plan, Caring for County (Umwelt 2022) Site Observations Site interviews Lynwood Quarry Aboriginal Heritage Management Plan, Caring for County (Umwelt 2022) Correspondence Holcim to DPE dated 30 June 2023, regarding management plan reviews. DPE Letter of 5 December 2016 Lynwood Quarry Aboriginal Heritage Management Plan, Caring for County (Umwelt 2022) Previous 2020 IEA Audit Lynwood Quarry Aboriginal Heritage Management Plan, Caring for County (Umwelt 2022) Lynwood Quarry Aboriginal Heritage Management Plan, Caring for County (Umwelt 2022) Lynwood Quarry Aboriginal Heritage Management Plan, Caring for County (Umwelt 2022)	No debris was observed on roads leading to the site. Wheel wash was observed in operation on Hard copies of documents are archived at the weighbridge. Laden truck movements for each month are provided in the 2020, 2021, 2022 Annual Reviews. Digital tracking platform updated daily. Exclusion fencing was observed throughout the site and is clearly signed as areas of cultural significance. Sighted current Aboriginal Heritage Management Plan, Caring for County (Umwelt 2022) and correspondence to DPE confirm no revision to the plan following the 2022 Annual Review. Previous audit sighted DPE's letter of 5 December 2016 endorses the appointment of Jan Wilson, Principal Archaeologist Umwelt to prepare the Section 1.3 of the approved Lynwood Quarry Aboriginal Heritage Management Plan (2022) confirms consultation with Register Aboriginal Parties. Section 1.4 of the approved Lynwood Quarry Aboriginal Heritage Management Plan (2022) confirms consultation with government agencies. Outside of audit period, previous 2019 IEA Audit confirms compliance. Site observations sighted sign-posted and cordoned-off cultural heritage management zones.	Compliant
33 Monitoring 33A Protection o 34 Aboriginal C 35 35 (a) 35 (b)	The Applicant must ensure that all loaded vehicles leaving the site are cleaned of materials that may fall on the road before they are allowed to leave the site. 7 (Quarry Product Transport The Applicant must keep accurate records of all laden truck movements from the site (weekly, monthly and annually) and publish a summary of records in its Annual Review. Aboriginal Sites The Applicant must ensure that the development does not cause any direct or indirect impact on identified Aboriginal sites located outside the approved disturbance area of the development. Only those Aboriginal sites identified within the approved Aboriginal Cultural Heritage Management Plan (see condition 35) or any approved Aboriginal Heritage Impact Permit may be impacted within the approved disturbance area of the development. Autural Heritage Management Plan The Applicant must prepare an Aboriginal Cultural Heritage Management Plan for the development to the satisfaction of the Secretary. The plan must: (a) be prepared by suitably qualified and experienced person/s whose appointment has been endorsed by the Secretary; (b) be prepared in consultation with OEH and local Aboriginal stakeholders; (c) be submitted to the Secretary for approval by 30 November 2016, unless the Secretary agrees otherwise; (d) include the following; • a Conservation Management Plan that details how the Cultural Heritage Management Zones (shown conceptually on the plan in Appendix 6) are managed: • a detailed archaeological salvage program for Aboriginal sites/objects will be managed and protected; and	Site Observations Site interviews Annual Review 2020, 2021, 2022. Site Observations - Sighted hard copy transport records and digital tracking platform. Lynwood Quarry Aboriginal Heritage Management Plan, Caring for County (Umwelt 2022) Site Observations Site interviews Lynwood Quarry Aboriginal Heritage Management Plan, Caring for County (Umwelt 2022) Correspondence Holcim to DPE dated 30 June 2023, regarding management plan reviews. DPE Letter of 5 December 2016 Lynwood Quarry Aboriginal Heritage Management Plan, Caring for County (Umwelt 2022) Previous 2020 IEA Audit Lynwood Quarry Aboriginal Heritage Management Plan, Caring for County (Umwelt 2022) Lynwood Quarry Aboriginal Heritage Management Plan, Caring for County (Umwelt 2022) Lynwood Quarry Aboriginal Heritage Management Plan, Caring for County (Umwelt 2022) Noted.	No debris was observed on roads leading to the site. Wheel wash was observed in operation on Hard copies of documents are archived at the weighbridge. Laden truck movements for each month are provided in the 2020, 2021, 2022 Annual Reviews. Digital tracking platform updated daily. Exclusion fencing was observed throughout the site and is clearly signed as areas of cultural significance. Sighted current Aboriginal Heritage Management Plan, Caring for County (Umwelt 2022) and correspondence to DPE confirm no revision to the plan following the 2022 Annual Review. Previous audit sighted DPE's letter of 5 December 2016 endorses the appointment of Jan Wilson, Principal Archaeologist Umwelt to prepare the Section 1.3 of the approved Lynwood Quarry Aboriginal Heritage Management Plan (2022) confirms consultation with Register Aboriginal Parties. Section 1.4 of the approved Lynwood Quarry Aboriginal Heritage Management Plan (2022) confirms consultation with government agencies. Outside of audit period, previous 2019 IEA Audit confirms compliance. Site observations sighted sign-posted and cordoned-off cultural heritage management zones. Section 3.1 of the Lynwood Quarry Aboriginal Heritage Management Plan, Caring for County	Compliant
33 Monitoring 33A Protection o 34 Aboriginal C 35 35 (a) 35 (b)	The Applicant must ensure that all loaded vehicles leaving the site are cleaned of materials that may fall on the road before they are allowed to leave the site. f Quarry Product Transport The Applicant must keep accurate records of all laden truck movements from the site (weekly, monthly and annually) and publish a summary of records in its Annual Review. f Aboriginal Sites The Applicant must ensure that the development does not cause any direct or indirect impact on identified Aboriginal Sites located outside the approved disturbance area of the development. Only those Aboriginal sites identified within the approved Aboriginal Cultural Heritage Management Plan (see condition 35) or any approved Aboriginal Heritage Impact Permit may be impacted within the approved disturbance area of the development. Ditural Heritage Management Plan The Applicant must prepare an Aboriginal Cultural Heritage Management Plan for the development to the satisfaction of the Secretary. The plan must: (a) be prepared by suitably qualified and experienced person/s whose appointment has been endorsed by the Secretary; (b) be prepared in consultation with OEH and local Aboriginal stakeholders; (c) be submitted to the Secretary for approval by 30 November 2016, unless the Secretary agrees otherwise; (d) include the following; * a Conservation Management Plan that details how the Cultural Heritage Management Zones (shown conceptually on the plan in Appendix 6) are managed: * a detailled archaeological salvage program for Aboriginal sites/objects will be managed and protected; and	Site Observations Site interviews Annual Review 2020, 2021, 2022. Site Observations - Sighted hard copy transport records and digital tracking platform. Lynwood Quarry Aboriginal Heritage Management Plan, Caring for County (Umwelt 2022) Site Observations Site interviews Lynwood Quarry Aboriginal Heritage Management Plan, Caring for County (Umwelt 2022) Correspondence Holcim to DPE dated 30 June 2023, regarding management plan reviews. DPE Letter of 5 December 2016 Lynwood Quarry Aboriginal Heritage Management Plan, Caring for County (Umwelt 2022) Previous 2020 IEA Audit Lynwood Quarry Aboriginal Heritage Management Plan, Caring for County (Umwelt 2022) Lynwood Quarry Aboriginal Heritage Management Plan, Caring for County (Umwelt 2022) Lynwood Quarry Aboriginal Heritage Management Plan, Caring for County (Umwelt 2022) Noted. Lynwood Quarry Aboriginal Heritage Management Plan, Caring for County (Umwelt 2022)	No debris was observed on roads leading to the site. Wheel wash was observed in operation on Hard copies of documents are archived at the weighbridge. Laden truck movements for each month are provided in the 2020, 2021, 2022 Annual Reviews. Digital tracking platform updated daily. Exclusion fencing was observed throughout the site and is clearly signed as areas of cultural significance. Sighted current Aboriginal Heritage Management Plan, Caring for County (Umwelt 2022) and correspondence to DPE confirm no revision to the plan following the 2022 Annual Review. Previous audit sighted DPE's letter of 5 December 2016 endorses the appointment of Jan Wilson, Principal Archaeologist Umwelt to prepare the Section 1.3 of the approved Lynwood Quarry Aboriginal Heritage Management Plan (2022) confirms consultation with Register Aboriginal Parties. Section 1.4 of the approved Lynwood Quarry Aboriginal Heritage Management Plan (2022) confirms consultation with government agencies. Outside of audit period, previous 2019 IEA Audit confirms compliance. Site observations sighted sign-posted and cordoned-off cultural heritage management zones. Section 3.1 of the Lynwood Quarry Aboriginal Heritage Management Plan, Caring for County	Compliant
33 Monitoring 33A Protection o 34 Aboriginal C 35 35 (a) 35 (b)	The Applicant must ensure that all loaded vehicles leaving the site are cleaned of materials that may fall on the road before they are allowed to leave the site. 7 (Quarry Product Transport) The Applicant must keep accurate records of all laden truck movements from the site (weekly, monthly and annually) and publish a summary of records in its Annual Review. Faboriginal Sites The Applicant must ensure that the development does not cause any direct or indirect impact on identified Aboriginal sites located outside the approved disturbance area of the development. Only those Aboriginal sites identified within the approved Aboriginal Cultural Heritage Management Plan (see condition 35) or any approved Aboriginal Heritage Impact Permit may be impacted within the approved disturbance area of the development. **Outural Heritage Management Plan** The Applicant must prepare an Aboriginal Cultural Heritage Management Plan for the development to the satisfaction of the Secretary. The plan must: (a) be prepared by suitably qualified and experienced person/s whose appointment has been endorsed by the Secretary; (b) be prepared in consultation with OEH and local Aboriginal stakeholders; (c) be submitted to the Secretary for approval by 30 November 2016, unless the Secretary agrees otherwise; (d) include the following; * a Conservation Management Plan that details how the Cultural Heritage Management Zones (shown conceptually on the plan in Appendix 6) are managed: * a detailed archaeological salvage program for Aboriginal sites/objects will be managed and protected; and * a description of the measures that would be implemented for: protecting, monitoring and managing Aboriginal sites outside the approved disturbance area;	Site Observations Site interviews Annual Review 2020, 2021, 2022. Site Observations - Sighted hard copy transport records and digital tracking platform. Lynwood Quarry Aboriginal Heritage Management Plan, Caring for County (Umwelt 2022) Site Observations Site interviews Lynwood Quarry Aboriginal Heritage Management Plan, Caring for County (Umwelt 2022) Correspondence Holcim to DPE dated 30 June 2023, regarding management plan reviews. DPE Letter of 5 December 2016 Lynwood Quarry Aboriginal Heritage Management Plan, Caring for County (Umwelt 2022) Previous 2020 IEA Audit Lynwood Quarry Aboriginal Heritage Management Plan, Caring for County (Umwelt 2022) Lynwood Quarry Aboriginal Heritage Management Plan, Caring for County (Umwelt 2022) Noted. Lynwood Quarry Aboriginal Heritage Management Plan, Caring for County (Umwelt 2022) Noted. Lynwood Quarry Aboriginal Heritage Management Plan, Caring for County (Umwelt 2022)	No debris was observed on roads leading to the site. Wheel wash was observed in operation on Hard copies of documents are archived at the weighbridge. Laden truck movements for each month are provided in the 2020, 2021, 2022 Annual Reviews. Digital tracking platform updated daily. Exclusion fencing was observed throughout the site and is clearly signed as areas of cultural significance. Sighted current Aboriginal Heritage Management Plan, Caring for County (Umwelt 2022) and correspondence to DPE confirm no revision to the plan following the 2022 Annual Review. Previous audit sighted DPE's letter of 5 December 2016 endorses the appointment of Jan Wilson, Principal Archaeologist Umwelt to prepare the Section 1.3 of the approved Lynwood Quarry Aboriginal Heritage Management Plan (2022) confirms consultation with Register Aboriginal Parties. Section 1.4 of the approved Lynwood Quarry Aboriginal Heritage Management Plan (2022) confirms consultation with government agencies. Outside of audit period, previous 2019 IEA Audit confirms compliance. Site observations sighted sign-posted and cordoned-off cultural heritage management zones. Section 3.1 of the Lynwood Quarry Aboriginal Heritage Management Plan, Caring for County (Umwelt 2022)	Compliant
33 Monitoring 33A Protection of 34 Aboriginal C 35 35 (a) 35 (b)	The Applicant must ensure that all loaded vehicles leaving the site are cleaned of materials that may fall on the road before they are allowed to leave the site. 7 (Quarry Product Transport The Applicant must keep accurate records of all laden truck movements from the site (weekly, monthly and annually) and publish a summary of records in its Annual Review. Aboriginal Sites The Applicant must ensure that the development does not cause any direct or indirect impact on identified Aboriginal sites located outside the approved disturbance area of the development. Only those Aboriginal sites identified within the approved Aboriginal Cultural Heritage Management Plan (see condition 35) or any approved Aboriginal Heritage Impact Permit may be impacted within the approved disturbance area of the development. Autural Heritage Management Plan The Applicant must prepare an Aboriginal Cultural Heritage Management Plan for the development to the satisfaction of the Secretary. The plan must: (a) be prepared by suitably qualified and experienced person/s whose appointment has been endorsed by the Secretary; (b) be prepared in consultation with OEH and local Aboriginal stakeholders; (c) be submitted to the Secretary for approval by 30 November 2016, unless the Secretary agrees otherwise; (d) include the following; • a Conservation Management Plan that details how the Cultural Heritage Management Zones (shown conceptually on the plan in Appendix 6) are managed: • a detailed archaeological salvage program for Aboriginal sites/objects will be managed and protected; and	Site Observations Site interviews Annual Review 2020, 2021, 2022. Site Observations - Sighted hard copy transport records and digital tracking platform. Lynwood Quarry Aboriginal Heritage Management Plan, Caring for County (Umwelt 2022) Site Observations Site interviews Lynwood Quarry Aboriginal Heritage Management Plan, Caring for County (Umwelt 2022) Correspondence Holcim to DPE dated 30 June 2023, regarding management plan reviews. DPE Letter of 5 December 2016 Lynwood Quarry Aboriginal Heritage Management Plan, Caring for County (Umwelt 2022) Previous 2020 IEA Audit Lynwood Quarry Aboriginal Heritage Management Plan, Caring for County (Umwelt 2022) Lynwood Quarry Aboriginal Heritage Management Plan, Caring for County (Umwelt 2022) Noted. Lynwood Quarry Aboriginal Heritage Management Plan, Caring for County (Umwelt 2022) Noted. Lynwood Quarry Aboriginal Heritage Management Plan, Caring for County (Umwelt 2022) Lynwood Quarry Aboriginal Heritage Management Plan, Caring for County (Umwelt 2022) Lynwood Quarry Aboriginal Heritage Management Plan, Caring for County (Umwelt 2022) Lynwood Quarry Aboriginal Heritage Management Plan, Caring for County (Umwelt 2022)	No debris was observed on roads leading to the site. Wheel wash was observed in operation on Hard copies of documents are archived at the weighbridge. Laden truck movements for each month are provided in the 2020, 2021, 2022 Annual Reviews. Digital tracking platform updated daily. Exclusion fencing was observed throughout the site and is clearly signed as areas of cultural significance. Sighted current Aboriginal Heritage Management Plan, Caring for County (Umwelt 2022) and correspondence to DPE confirm no revision to the plan following the 2022 Annual Review. Previous audit sighted DPE's letter of 5 December 2016 endorses the appointment of Jan Wilson, Principal Archaeologist Umwelt to prepare the Section 1.3 of the approved Lynwood Quarry Aboriginal Heritage Management Plan (2022) confirms consultation with Register Aboriginal Parties. Section 1.4 of the approved Lynwood Quarry Aboriginal Heritage Management Plan (2022) confirms consultation with government agencies. Outside of audit period, previous 2019 IEA Audit confirms compliance. Site observations sighted sign-posted and cordoned-off cultural heritage management zones. Section 3.1 of the Lynwood Quarry Aboriginal Heritage Management Plan, Caring for County (Umwelt 2022)	Compliant
33 Monitoring 33A Protection o 34 Aboriginal C 35 35 (a) 35 (b)	The Applicant must ensure that all loaded vehicles leaving the site are cleaned of materials that may fall on the road before they are allowed to leave the site. 7 (Quarry Product Transport) The Applicant must keep accurate records of all laden truck movements from the site (weekly, monthly and annually) and publish a summary of records in its Annual Review. Faboriginal Sites The Applicant must ensure that the development does not cause any direct or indirect impact on identified Aboriginal sites located outside the approved disturbance area of the development. Only those Aboriginal sites identified within the approved Aboriginal Cultural Heritage Management Plan (see condition 35) or any approved Aboriginal Heritage Impact Permit may be impacted within the approved disturbance area of the development. **Outural Heritage Management Plan** The Applicant must prepare an Aboriginal Cultural Heritage Management Plan for the development to the satisfaction of the Secretary. The plan must: (a) be prepared by suitably qualified and experienced person/s whose appointment has been endorsed by the Secretary; (b) be prepared in consultation with OEH and local Aboriginal stakeholders; (c) be submitted to the Secretary for approval by 30 November 2016, unless the Secretary agrees otherwise; (d) include the following; * a Conservation Management Plan that details how the Cultural Heritage Management Zones (shown conceptually on the plan in Appendix 6) are managed: * a detailed archaeological salvage program for Aboriginal sites/objects will be managed and protected; and * a description of the measures that would be implemented for: protecting, monitoring and managing Aboriginal sites outside the approved disturbance area;	Site Observations Site interviews Annual Review 2020, 2021, 2022. Site Observations - Sighted hard copy transport records and digital tracking platform. Lynwood Quarry Aboriginal Heritage Management Plan, Caring for County (Umwelt 2022) Site Observations Site interviews Lynwood Quarry Aboriginal Heritage Management Plan, Caring for County (Umwelt 2022) Correspondence Holcim to DPE dated 30 June 2023, regarding management plan reviews. DPE Letter of 5 December 2016 Lynwood Quarry Aboriginal Heritage Management Plan, Caring for County (Umwelt 2022) Previous 2020 IEA Audit Lynwood Quarry Aboriginal Heritage Management Plan, Caring for County (Umwelt 2022) Lynwood Quarry Aboriginal Heritage Management Plan, Caring for County (Umwelt 2022) Noted. Lynwood Quarry Aboriginal Heritage Management Plan, Caring for County (Umwelt 2022) Lynwood Quarry Aboriginal Heritage Management Plan, Caring for County (Umwelt 2022) Lynwood Quarry Aboriginal Heritage Management Plan, Caring for County (Umwelt 2022) Lynwood Quarry Aboriginal Heritage Management Plan, Caring for County (Umwelt 2022)	No debris was observed on roads leading to the site. Wheel wash was observed in operation on Hard copies of documents are archived at the weighbridge. Laden truck movements for each month are provided in the 2020, 2021, 2022 Annual Reviews. Digital tracking platform updated daily. Exclusion fencing was observed throughout the site and is clearly signed as areas of cultural significance. Sighted current Aboriginal Heritage Management Plan, Caring for County (Umwelt 2022) and correspondence to DPE confirm no revision to the plan following the 2022 Annual Review. Previous audit sighted DPE's letter of 5 December 2016 endorses the appointment of Jan Wilson, Principal Archaeologist Umwelt to prepare the Section 1.3 of the approved Lynwood Quarry Aboriginal Heritage Management Plan (2022) confirms consultation with Register Aboriginal Parties. Section 1.4 of the approved Lynwood Quarry Aboriginal Heritage Management Plan (2022) confirms consultation with government agencies. Outside of audit period, previous 2019 IEA Audit confirms compliance. Site observations sighted sign-posted and cordoned-off cultural heritage management zones. Section 3.1 of the Lynwood Quarry Aboriginal Heritage Management Plan, Caring for County (Umwelt 2022)	Compliant
33 Monitoring 33A Protection of 34 Aboriginal C 35 35 (a) 35 (b)	The Applicant must ensure that all loaded vehicles leaving the site are cleaned of materials that may fall on the road before they are allowed to leave the site. 17 doarny Product Transport The Applicant must keep accurate records of all laden truck movements from the site (weekly, monthly and annually) and publish a summary of records in its Annual Review. 18 Aboriginal Sites 19 The Applicant must ensure that the development does not cause any direct or indirect impact on identified Aboriginal sites located outside the approved disturbance area of the development. Only those Aboriginal sites identified within the approved Aboriginal Cultural Heritage Management Plan (see condition 35) or any approved Aboriginal Heritage Impact Permit may be impacted within the approved disturbance area of the development. 10 The Applicant must prepare an Aboriginal Cultural Heritage Management Plan for the development to the satisfaction of the Secretary. The plan must: 10 The Applicant must prepare an Aboriginal Cultural Heritage Management Plan for the development to the satisfaction of the Secretary. The plan must: 10 be prepared by suitably qualified and experienced person/s whose appointment has been endorsed by the Secretary; 10 be prepared in consultation with OEH and local Aboriginal stakeholders; 10 be prepared in consultation with OEH and local Aboriginal stakeholders; 11 c) be submitted to the Secretary for approval by 30 November 2016, unless the Secretary agrees otherwise; 12 c) be submitted to the Secretary for approval by 30 November 2016, unless the Secretary agrees otherwise; 13 c) and a management Plan that details how the Cultural Heritage Management Zones (shown conceptually on the plan in Annual Ann	Site Observations Site interviews Annual Review 2020, 2021, 2022. Site Observations - Sighted hard copy transport records and digital tracking platform. Lynwood Quarry Aboriginal Heritage Management Plan, Caring for County (Umwelt 2022) Site Observations Site interviews Lynwood Quarry Aboriginal Heritage Management Plan, Caring for County (Umwelt 2022) Correspondence Holcim to DPE dated 30 June 2023, regarding management plan reviews. DPE Letter of 5 December 2016 Lynwood Quarry Aboriginal Heritage Management Plan, Caring for County (Umwelt 2022) Previous 2020 IEA Audit Lynwood Quarry Aboriginal Heritage Management Plan, Caring for County (Umwelt 2022) Lynwood Quarry Aboriginal Heritage Management Plan, Caring for County (Umwelt 2022) Noted. Lynwood Quarry Aboriginal Heritage Management Plan, Caring for County (Umwelt 2022) Noted. Lynwood Quarry Aboriginal Heritage Management Plan, Caring for County (Umwelt 2022) Lynwood Quarry Aboriginal Heritage Management Plan, Caring for County (Umwelt 2022) Lynwood Quarry Aboriginal Heritage Management Plan, Caring for County (Umwelt 2022) Lynwood Quarry Aboriginal Heritage Management Plan, Caring for County (Umwelt 2022)	No debris was observed on roads leading to the site. Wheel wash was observed in operation on Hard copies of documents are archived at the weighbridge. Laden truck movements for each month are provided in the 2020, 2021, 2022 Annual Reviews. Digital tracking platform updated daily. Exclusion fencing was observed throughout the site and is clearly signed as areas of cultural significance. Sighted current Aboriginal Heritage Management Plan, Caring for County (Umwelt 2022) and correspondence to DPE confirm no revision to the plan following the 2022 Annual Review. Previous audit sighted DPE's letter of 5 December 2016 endorses the appointment of Jan Wilson, Principal Archaeologist Umwelt to prepare the Section 1.3 of the approved Lynwood Quarry Aboriginal Heritage Management Plan (2022) confirms consultation with Register Aboriginal Parties. Section 1.4 of the approved Lynwood Quarry Aboriginal Heritage Management Plan (2022) confirms consultation with government agencies. Outside of audit period, previous 2019 IEA Audit confirms compliance. Site observations sighted sign-posted and cordoned-off cultural heritage management zones. Section 3.1 of the Lynwood Quarry Aboriginal Heritage Management Plan, Caring for County (Umwelt 2022)	Compliant
33 Monitoring 33A Protection of 34 Aboriginal C 35 35 (a) 35 (b)	The Applicant must ensure that all loaded vehicles leaving the site are cleaned of materials that may fall on the road before they are allowed to leave the site. Goarny Product Transport	Site Observations Site interviews Annual Review 2020, 2021, 2022. Site Observations - Sighted hard copy transport records and digital tracking platform. Lynwood Quarry Aboriginal Heritage Management Plan, Caring for County (Umwelt 2022) Site Observations Site interviews Lynwood Quarry Aboriginal Heritage Management Plan, Caring for County (Umwelt 2022) Correspondence Holcim to DPE dated 30 June 2023, regarding management plan reviews. DPE Letter of 5 December 2016 Lynwood Quarry Aboriginal Heritage Management Plan, Caring for County (Umwelt 2022) Previous 2020 IEA Audit Lynwood Quarry Aboriginal Heritage Management Plan, Caring for County (Umwelt 2022) Lynwood Quarry Aboriginal Heritage Management Plan, Caring for County (Umwelt 2022) Noted. Lynwood Quarry Aboriginal Heritage Management Plan, Caring for County (Umwelt 2022) Lynwood Quarry Aboriginal Heritage Management Plan, Caring for County (Umwelt 2022) Lynwood Quarry Aboriginal Heritage Management Plan, Caring for County (Umwelt 2022) Lynwood Quarry Aboriginal Heritage Management Plan, Caring for County (Umwelt 2022) Lynwood Quarry Aboriginal Heritage Management Plan, Caring for County (Umwelt 2022) Lynwood Quarry Aboriginal Heritage Management Plan, Caring for County (Umwelt 2022)	No debris was observed on roads leading to the site. Wheel wash was observed in operation on Hard copies of documents are archived at the weighbridge. Laden truck movements for each month are provided in the 2020, 2021, 2022 Annual Reviews. Digital tracking platform updated daily. Exclusion fencing was observed throughout the site and is clearly signed as areas of cultural significance. Sighted current Aboriginal Heritage Management Plan, Caring for County (Umwelt 2022) and correspondence to DPE confirm no revision to the plan following the 2022 Annual Review. Previous audit sighted DPE's letter of 5 December 2016 endorses the appointment of Jan Wilson, Principal Archaeologist Umwelt to prepare the Section 1.3 of the approved Lynwood Quarry Aboriginal Heritage Management Plan (2022) confirms consultation with Register Aboriginal Parties. Section 1.4 of the approved Lynwood Quarry Aboriginal Heritage Management Plan (2022) confirms consultation with government agencies. Outside of audit period, previous 2019 IEA Audit confirms compliance. Site observations sighted sign-posted and cordoned-off cultural heritage management zones. Section 3.1 of the Lynwood Quarry Aboriginal Heritage Management Plan, Caring for County (Umwelt 2022)	Compliant
33 Monitoring 33A 33A Protection of 34 Aboriginal C 35 (a) 35 (b) 35 (c)	The Applicant must ensure that all loaded vehicles leaving the site are cleaned of materials that may fall on the road before they are allowed to leave the site. To Clourny Product Transport The Applicant must keep accurate records of all laden truck movements from the site (weekly, monthly and annually) and publish a summary of records in its Annual Review. Aboriginal Sites The Applicant must ensure that the development does not cause any direct or indirect impact on identified Aboriginal sites located outside the approved disturbance area of the development. Only those Aboriginal sites identified within the approved Aboriginal Cultural Heritage Management Plan (see condition 35) or any approved Aboriginal Heritage Impact Permit may be impacted within the approved disturbance area of the development. **ultural Heritage Management Plan The Applicant must prepare an Aboriginal Cultural Heritage Management Plan for the development to the satisfaction of the Secretary. The plan must: (a) be prepared by suitably qualified and experienced person/s whose appointment has been endorsed by the Secretary; (b) be prepared in consultation with OEH and local Aboriginal stakeholders; (c) be submitted to the Secretary for approval by 30 November 2016, unless the Secretary agrees otherwise; (d) include the following; • a Conservation Management Plan that details how the Cultural Heritage Management Zones (shown conceptually on the plan in Appendix G) are managed: • a detailed archaeological salvage program for Aboriginal sites/objects will be managed and protected; and • a description of the measures that would be implemented for: protecting, monitoring and managing Aboriginal sites outside the approved disturbance area; maintaining and managing reasonable access for Aboriginal stakeholders to cultural heritage items on site; managing the discovery of any human remains or previously unidentified Aboriginal objects on site, including (in the case of human remains) stop work provisions and notification protocols;	Site Observations Site interviews Annual Review 2020, 2021, 2022. Site Observations - Sighted hard copy transport records and digital tracking platform. Lynwood Quarry Aboriginal Heritage Management Plan, Caring for County (Umwelt 2022) Site Observations Site interviews Lynwood Quarry Aboriginal Heritage Management Plan, Caring for County (Umwelt 2022) Correspondence Holcim to DPE dated 30 June 2023, regarding management plan reviews. DPE Letter of 5 December 2016 Lynwood Quarry Aboriginal Heritage Management Plan, Caring for County (Umwelt 2022) Previous 2020 IEA Audit Lynwood Quarry Aboriginal Heritage Management Plan, Caring for County (Umwelt 2022) Lynwood Quarry Aboriginal Heritage Management Plan, Caring for County (Umwelt 2022) Noted. Lynwood Quarry Aboriginal Heritage Management Plan, Caring for County (Umwelt 2022) Lynwood Quarry Aboriginal Heritage Management Plan, Caring for County (Umwelt 2022) Lynwood Quarry Aboriginal Heritage Management Plan, Caring for County (Umwelt 2022) Lynwood Quarry Aboriginal Heritage Management Plan, Caring for County (Umwelt 2022) Lynwood Quarry Aboriginal Heritage Management Plan, Caring for County (Umwelt 2022) Lynwood Quarry Aboriginal Heritage Management Plan, Caring for County (Umwelt 2022)	No debris was observed on roads leading to the site. Wheel wash was observed in operation on Hard copies of documents are archived at the weighbridge. Laden truck movements for each month are provided in the 2020, 2021, 2022 Annual Reviews. Digital tracking platform updated daily. Exclusion fencing was observed throughout the site and is clearly signed as areas of cultural significance. Sighted current Aboriginal Heritage Management Plan, Caring for County (Umwelt 2022) and correspondence to DPE confirm no revision to the plan following the 2022 Annual Review. Previous audit sighted DPE's letter of 5 December 2016 endorses the appointment of Jan Wilson, Principal Archaeologist Umwelt to prepare the Section 1.3 of the approved Lynwood Quarry Aboriginal Heritage Management Plan (2022) confirms consultation with Register Aboriginal Parties. Section 1.4 of the approved Lynwood Quarry Aboriginal Heritage Management Plan (2022) confirms consultation with government agencies. Outside of audit period, previous 2019 IEA Audit confirms compliance. Site observations sighted sign-posted and cordoned-off cultural heritage management zones. Section 3.1 of the Lynwood Quarry Aboriginal Heritage Management Plan, Caring for County (Umwelt 2022)	Compliant Compliant

ensuring any workers on site receive suitable heritage inductions prior to carrying out any activities which may disturb Aboriginal sites,	Lynwood Quarry Aboriginal Heritage Management Plan, Caring for County		Compliant
and that suitable records are kept of these inductions.	(Umwelt 2022)	Induction provided to auditor prior to inspecting site, induction inclusive of heritage	
	Site induction	considerations	
The Applicant must implement the management plan as approved from time to time by the Secretary.	Site Observations		Compliant
	Site interviews		
36 deleted			
37 Unless the OEH approves otherwise, the Applicant must ensure that all ground disturbing works on the site are monitored at all times by		No topsoil stripping occurred during the audit period.	Compliant
suitably qualified and experienced archaeologist and representatives of all the relevant Aboriginal community groups. If this monitoring	Lynwood Quarry Aboriginal Heritage Management Plan, Caring for County		
detects any previously unrecorded Aboriginal objects not listed in Table 10, then the Applicant must immediately cease work in the area and notify the OEH.	(Umwelt 2022)	does not reference Condition 37.	
Notes:	Site Observations		
This monitoring only relates to topsoil stripping, not quarrying operations.	Site interviews - W Beattie		
• For safety reasons, tonsoil stripping may be undertaken before the commencement of development			
Old Marulan Township			
The Applicant may carry out the development in the area identified in the State Heritage Register as the Old Marulan Township (SHR No.	Previous 2020 IEA Audit	Previous audit stated:" Original letter from NSW Heritage Council not sighted but ongoing	Compliant
00127) with the written approval of the NSW Heritage Council.		correspondence from the council indicates that it approved development in Old Marulan	
		Township (e.g. application to vary S 65A no 2007/S65/11. Confirmed by Heritage Branch	
20 Disease assistantia assessad the Applicant pour adoption of detailed investigation of the application of	Desire A distribute Old Marcha Const. And In Assessment desire	22/10/09)"	Consider
39 Prior to seeking this approval, the Applicant must undertake a detailed investigation of the archaeological potential of the proposed development area in the Old Marulan Township, including archaeological testing, to the satisfaction of the NSW Heritage Council. This	Previous Audit evidence: Old Marulan County Argyle: A research design	Considered complete as per previous audit	Compliant
archaeological investigation must clarify the nature, extent, and significance of the relics in the proposed development area.	and archaeological compliance program for work by Readymix (Gojak)		
defined against the sugardant material and a sugardant control of the fellowing the proposed defendment area.	2006		
Note: The Applicant will be required to submit an application to the NSW Heritage Council under Section 60 of the Heritage Act 1977 for	Note		
this archaeological investigation.			
In seeking this approval, the Applicant must submit the following information to the NSW Heritage Council:	Note	Constitution and the constitut	Consultant
40 (a) (a) the final design of the proposed Hume Highway interchange, incorporating the results of the archaeological investigations (see	Previous 2020 IEA Audit	Considered complete as per previous audit	Compliant
condition 39), and including information on landscaping, lighting, and stormwater management; 40 (b) (b) an Archaeological Assessment of the area to be impacted by the proposed interchange, that includes the:	Note		
nomination of an Excavation Director and archaeology team which will be approved by the Director of the NSW Heritage Office;	Previous Audit evidence: Old Marulan County Argyle: A research design	Considered complete as per previous audit	Compliant
and the state of t	and archaeological compliance program for work by Readymix (Gojak)	Solision of complete as per previous dudit	
	2006		
assessment of the significance of the archaeological remains to be impacted within the development area,	Previous Audit Evidence: Nonindigenous archaeology assessment, Old	Considered complete as per previous audit	Compliant
assessment of the symmetric or the distinction of the second of the seco	Marulan County Argyle: A research design and archaeological compliance	considered complete as per previous addit	Compilant
	program for work by Readymix (Gojak) 2006		
	program for work by Readymix (dojak) 2000		
 plans and details of the location and depth of excavation works and assessment of the exact impact on potential archaeological remains 	· Previous Audit evidence: Old Marulan County Argyle: A research design	Considered complete as per previous audit	Compliant
part of a certain of the certain of	and archaeological compliance program for work by Readymix (Gojak)	considered complete as per previous addit	- Compilation
	2006		
identification of research themes and identification of both site specific and general research questions,	Previous Audit Evidence: Nonindigenous archaeology assessment, Old	Considered complete as per previous audit	Compliant
termination of research status and termination of outside specific and general section (4economy)	Marulan County Argyle: A research design and archaeological compliance	considered complete as per previous addit	
	program for work by Readymix (Gojak) 2006		
	program for work by Readymix (dojak) 2000		
details of the proposed on-site excavation methodology including details on	Previous Audit evidence: Old Marulan County Argyle: A research design	Considered complete as per previous audit	Compliant
philosophical approach to on-site work and the process and procedures proposed for recovery and recording of archaeological data, and	and archaeological compliance program for work by Readymix (Gojak)	Considered complete as per previous addit	Compliant
details on how the archaeological research is proposed to be satisfactorily completed,	2006		
details of the proposed post-excavation methodology; and	Previous Audit Evidence: Nonindigenous archaeology assessment, Old	Considered complete as per previous audit	Compliant
	Marulan County Argyle: A research design and archaeological compliance	Considered complete as per previous addit	
	program for work by Readymix (Gojak) 2006		
	program for mork by reductions (column 2000		
details of the Interpretation Plan for the entire Old Marulan Township precinct.	Previous Audit evidence: Old Marulan County Argyle: A research design	Considered complete as per previous audit	Compliant
	and archaeological compliance program for work by Readymix (Gojak)		
	2006		
40A The Applicant must prepare a structural integrity report for the Lockyersleigh Homestead Property and Garden, subject to receiving the	Previous audit evidence: A & R Engineering Design Pty Ltd condition	Considered complete as per previous audit	Compliant
landowner's agreement, by 30 June 2016.	report (structural integrity report) dated 22 June 2016.		
Operating Conditions			
41 The Applicant must ensure that:	Note.		
41 (a) (a) the development does not have any impact on:			Compliant
• the archaeological remains within the former Lot 1, DP210885;		The AERs report on European Heritage. The 2020, 21 and 22 AERs report no additional	
	Annual Review 2020, 2021, 2022.	European Heritage management actions were undertaken during the report periods	
• heritage items MRNH1, MRNH2, and MRNH3;	Site interviews	No activities undertaken within the area during the audit period.	Compliant
	Previous Audit Evidence: Sighted letter from Heritage	Considered complete as per previous audit.	
	Branch_SheepDipMRNH1_ArtefactPolicy_20090907a_ltrLTR_CWC_Cess		
	Pit_OldMarulan_August 2011		
• the section of the State Heritage Register curtilage located at the eastern side of the Hume Highway, other than the impact upon the		There sites are adjusted the Heavy Order of Consequence of	Compliant
timber lined cistern/well (MRNH8) except where undertaken in accordance with the written approval of the NSW Heritage Council;	Previous audit evidence and no further development in this area during	These sites are adjacent to the Hume Highway intersection. There was no construction in	
41/h) /h) as much fahric of the timber liped cictory (well (MDNIHO) and the evaluation remains unaccount through the evaluation of the timber liped cictory (well (MDNIHO) and the evaluation remains unaccount through the evaluation of the timber liped cictory (well (MDNIHO)) and the evaluation remains unaccount through the evaluation of the timber liped cictory (well (MDNIHO)) and the evaluation of the tim	the audit period.	this area in the audit period.	Compliant
41 (b) (b) as much fabric of the timber-lined cistern/well (MRNH8) and the archaeological remains uncovered through the archaeological excavation as possible is salvaged and incorporated as a key element in the interpretation of the site as part of the new development; and	Danida and and a state of the s	These sites are adjacent to the Hume Highway intersection. There was no construction in	Compliant
executation as possible is salvaged and incorporated as a key element in the interpretation of the site as part of the new development; and		this area in the audit period.	
	MRNH8_InterpPlan_20090305 which details approved specification, Old		
41 (c) (c) the mayament of machines across archaeologically concitive areas is kept to a minimum	Marulan Archaeological_Letter to DECC 27 Oct 2010	Extraction and evaluation areas are well signed	Compliant
41 (c) (c) the movement of machines across archaeologically sensitive areas is kept to a minimum.		Extraction and exclusion areas are well signed.	Compilant
	Site Observations	Exclusion fencing was observed throughout the site and is clearly signed as areas of	
	Site Observations Site interviews	archaeological significance. Movements outside of disturbance areas are confined to formed	
Archaeological Field Work/Excavations	Site interviews	roadways.	
42 The Applicant must comply with the detailed requirements in Appendix 7 to the satisfaction of the NSW Heritage Office.			Compliant
12 The Applicant most comply with the detailed requirements in Appendix 7 to the Satisfaction of the NSVV mentage office.		See Appendix 7 conditions detailed later in this table	Compilation
		pee appearant / containons actuated later in this table	
REHABILITATION AND LANDSCAPING			

The second secon	43	The Applicant must rehabilitate the site in a manner that is generally consistent with the conceptual final landform in Appendix 8, to the	Site Observations]	Not triggered	
See the control of th		,	Site interviews	Significant rehabilitation has not yet commenced.		
Registros Association (security control and province and information (security design and province) and information (security design and province) and province and information (security design and province) and province and information (security design and province) and province and provinc			Dravious audit avidance:	The approved Rehabilitation and Landscape Management Plan (2019) is the current plan	Compliant	
Residence of the control of the cont	''			The approved renabilitation and Landscape Management Flam (2010) is the current plan	Compilation	
Part		This plan must:	(RLMP).			
Manual Proposition (Annual Proposition (Annu						
Michael Parlament of Michael Parlament (Michael Parlament) (Michae			DPE letter to Holcim dated 11 July 2018 confirming approval of the RLMP.			
Meleonard plane pl	44 (a)	(a) describe in general the short, medium, and long-term measures that would be implemented to:	Noted.			
Part		• rehabilitate the site;			Compliant	
Methods (Section (Control (Con		s implement the Habitat Management Area (shows concentrally in Annordiy O) unless this area is incorporated into a concentrally	Rehabilitation and Landscape Management Plan (2018) - Section 3		Compliant	
Marie Mari		· · · · · · · · · · · · · · · · · · ·		The Habitat Management Area shown in Figure 3.5 of the Rehabilitation and Landscape	Compilant	
Section for interesting of the protection of t			Rehabilitation and Landscape Management Plan (2018)			
Marke of the control						
The standard contribution of the contribution		nollows to be cleared;		· ·		DEC.3
Michael Product for parties of surface of the foliage of the product of the pro		manage the remnant vegetation and habitat on the site; and	Ecological Monitoring of Nest Boxes Whiter 2023 (SER 2023)	infolitored during the addit period, in excess of the hollow-bearing tress cleared.	Compliant	NECZ
Mathematical Activation (Assembly Continued			Rehabilitation and Landscape Management Plan (2018) - Section 3			
Column Process Proce		landscape the site to mitigate any visual impacts of the development;	Debet (1914) and the decrease Management Plan (2010). See the 2.5		Compliant	
Management of the control of the con	44 (b)	include Riparian Area Management Plan/s (see condition 45) for those riparian areas to be disturbed in the next 5 years, excluding areas	Renabilitation and Landscape Management Plan (2018) - Section 3.5		Compliant	
Model Security Model M			Rehabilitation and Landscape Management Plan (2018) - Section 3.6			
Control Cont	44 (c)	describe in detail the measures that would be implemented over the next 5 years to rehabilitate and manage the landscape on the site;	Rehabilitation and Landscape Management Plan (2018) - Section 3.1		Non-compliant	
Recolations and Encounter Menagement Plans [2013]—Section 4 Regulation and Supposed Plans Promited For Annalization of Management Plans [2013]—Section 5 Regulation and Supposed Plans Promited For Annalization of Management Plans [2013]—Section 6 Regulation and Supposed Plans Promited For Annalization of Management Plans [2013]—Section 6 Regulation Annalization of Management Plans [2013]—Section	44 (d)	describe how the performance of these measures would be monitored over time: and		rehabilitation during years 2016 - 2021.	Compliant	NCb
Mathematical participation of the proposed stay and playing staying quinter fragment from the programment of the proposed of	(۵)	account the performance of these measures mount see inclinity and	Rehabilitation and Landscape Management Plan (2018) - Section 4		Compilation	
Part	44 (e)	set completion criteria for the rehabilitation of the site.			Compliant	
Property of the service of the measures that would be impressed to the end of the original property and service of the measures that would be impressed to the end of the original property and service of the measures that would be impressed to the end of the original property and the end of the	45	The Rinarian Area Management Plan/s must be prepared by a suitably qualified hydrologist; whose appointment has been approved by			Compliant	
Part	45				Compilant	
Part						
Registrate Management Plan, Mariatan Creak Catchment Area, Rev 2, Morgania Management Plan, Mariatan Creak Catchment Area, R						
May 2015. May 1970 May 1970 May 2016 May 2016 May 1970						
Marine survey of treats, providing ensing bed, but and vergetion official mide including segmentation to the designment including segmentation and implacement man. Plans, Lockyrasisigh Creek Catchment Area, Rev 2, May and Antagement Plans, Lockyrasisigh Creek Catchment Area, Rev 2, May and Antagement Plans, Lockyrasisigh Creek Catchment Area, Rev 2, May and Antagement Plans, Lockyrasisigh Creek Catchment Area, Rev 2, May and Antagement Plans, Lockyrasisigh Creek Catchment Area, Rev 2, May and Antagement Plans, Lockyrasisigh Creek Catchment Area, Rev 2, May and Antagement Plans, Lockyrasisigh Creek Catchment Area, Rev 2, May and Antagement Plans, Lockyrasisigh Creek Catchment Area, Rev 2, May and Antagement Plans, Lockyrasisigh Creek Catchment Area, Rev 2, May and Antagement Plans, Lockyrasisigh Creek Catchment Area, Rev 2, May and Antagement Plans, Lockyrasisigh Creek Catchment Area, Rev 2, May and Antagement Plans, Lockyrasisigh Creek Catchment Area, Rev 2, May and Antagement Plans, Lockyrasisigh Creek Catchment Area, Rev 2, May and Antagement Plans, Lockyrasisigh Creek Catchment Area, Rev 2, May and Antagement Plans, Lockyrasisigh Creek Catchment Area, Rev 2, May and Antagement Plans, Lockyrasisigh Creek Catchment Area, Rev 2, May and Antagement Plans, Lockyrasisigh Creek Catchment Area, Rev 2, May and Antagement Plans, Lockyrasisigh Creek Catchment Area, Rev 2, May and Antagement Plans, Lockyrasisigh Creek Catchment Area, Rev 2, May and Antagement Plans, Lockyrasisigh Creek Catchment Area, Rev 2, May and Antagement Plans, Lockyrasisigh Creek Catchment Area, Rev 2, May and Antagement Plans, Lockyrasisigh Creek Catchment Area, Rev 2, May and Antagement Plans, Lockyrasisigh Creek Catchment Area, Rev 2, May and Antagement Plans, Lockyrasisigh Creek Catchment Area, Rev 2, May and Antagement Plans, Lockyrasisigh Creek Catchment Area, Rev 2, May and Antagement Plans, Lockyrasisigh Creek Catchment Area, Rev 2, May and Antagement Plans, Lockyrasisigh Creek Catchment Area, Rev 2, May and Antagement Plans, Lockyrasis						
45.6.1 As whether survey of creeks, providing entitive [sect. list and vergetation information for full time presentative cross and programs Management Flan, Lockyranigh Creek Catchment Area, Rev 2, May 2018. Apparation Management Flan, Incompressing Creek Catchment Area, Rev 2, May 2018. Apparation Management Flan, Marulan Creek Catchment Area, Rev 2, May 2018. Apparation Management Flan, Marulan Creek Catchment Area, Rev 2, May 2018. Apparation Management Flan, Marulan Creek Catchment Area, Rev 2, May 2018. Apparation Management Flan, Marulan Creek Catchment Area, Rev 2, May 2018. Apparation Management Flan, Marulan Creek Catchment Area, Rev 2, May 2018. Apparation Management Flan, Marulan Creek Catchment Area, Rev 2, May 2018. Apparation Management Flan, Marulan Creek Catchment Area, Rev 2, May 2018. Apparation Management Flan, Marulan Creek Catchment Area, Rev 2, May 2018. Apparation Management Flan, Marulan Creek Catchment Area, Rev 2, May 2018. Apparation Management Flan, Marulan Creek Catchment Area, Rev 2, May 2018. Apparation Management Flan, Marulan Creek Catchment Area, Rev 2, May 2018. Apparation Management Flan, Marulan Creek Catchment Area, Rev 2, May 2018. Apparation Management Flan, Marulan Creek Catchment Area, Rev 2, May 2018. Apparation Management Flan, Marulan Creek Catchment Area, Rev 2, May 2018. Apparation Management Flan, Marulan Creek Catchment Area, Rev 2, May 2018. Apparation Management Flan, Marulan Creek Catchment Area, Rev 2, May 2018. Apparation Management Flan, Marulan Creek Catchment Area, Rev 2, May 2018. Apparation Management Flan, Marulan Creek Catchment Area, Rev 2, May 2018. Apparation Management Flan, Marulan Creek Catchment Area, Rev 2, May 2018. Apparation Management Flan, Marulan Creek Catchment Area, Rev 2, May 2018. Apparation Management Flan, Marulan Creek Catchment Area, Rev 2, May 2018. Apparation Management Flan, Marulan Creek Catchment Area, Rev 2, May 2018. Apparation Management Flan, Marulan Creek Catchment Area, Rev 2, May 2018. Appara						
Statistics In the arosation which the developments is include, variating five quarry pits and enginements Plass, Lockyerside(in) Creek Catchment Area, Rev 2, June 2015. Application Management Plan, Marulan Creek Catchment Area, Rev 2, June 2015. Application Management Plan, Lockyerside(in) Creek Catchment Area, Rev 2, June 2015. Application Management Plan, Lockyerside(in) Creek Catchment Area, Rev 2, June 2015. Application Management Plan, Lockyerside(in) Creek Catchment Area, Rev 2, June 2015. Application Management Plan, Lockyerside(in) Creek Catchment Area, Rev 2, June 2015. Application Management Plan, Lockyerside(in) Creek Catchment Area, Rev 2, June 2015. Application Management Plan, Lockyerside(in) Creek Catchment Area, Rev 2, June 2015. Application Management Plan, Lockyerside(in) Creek Catchment Area, Rev 2, June 2015. Application Management Plan, Lockyerside(in) Creek Catchment Area, Rev 2, June 2015. Application Management Plan, Lockyerside(in) Creek Catchment Area, Rev 2, June 2015. Application Management Plan, Lockyerside(in) Creek Catchment Area, Rev 2, June 2015. Application Management Plan, Lockyerside(in) Creek Catchment Area, Rev 2, June 2015. Application Management Plan, Lockyerside(in) Creek Catchment Area, Rev 2, June 2015. Application Management Plan, Lockyerside(in) Creek Catchment Area, Rev 2, June 2015. Application Management Plan, Lockyerside(in) Creek Catchment Area, Rev 2, June 2015. Application Management Plan, Lockyerside(in) Creek Catchment Area, Rev 2, June 2015. Application Management Plan, Lockyerside(in) Creek Catchment Area, Rev 2, June 2015. Application Management Plan, Lockyerside(in) Creek Catchment Area, Rev 2, June 2015. Application Management Plan, Lockyerside(in) Creek Catchment Area, Rev 2, June 2015. Application Management Plan, Lockyerside(in) Creek Catchment Area, Rev 2, June 2015. Application Management Plan, Lockyerside(in) Creek Catchment Area, Rev 2, June 2015. Application Management Plan, Lockyerside(in) Creek C	45 (a)	haseline surveys of creeks, providing existing hed, hank and vegetation information (including representative cross and longitudinal		Current version of plans updated by approved person Susan Shields.	Compliant	
May 2018. Rigarian Management Plan, Murulan Creek Catchment Area, Rev 2, June 2019. 40 Ibility of the proposed works, including any processed stabilization, scour protection, and/or enhancement works including Avg 2018. Rigarian Management Plan, Lockyersleigh Creek Catchment Area, Rev 2, May 2018. Rigarian Management Plan, Marulan Creek Catchment Area, Rev 2, May 2018. Rigarian Management Plan, Marulan Creek Catchment Area, Rev 2, May 2018. Rigarian Management Plan, Marulan Creek Catchment Area, Rev 2, May 2018. Rigarian Management Plan, Dosiriumi Creek Catchment Area, Rev 2, May 2018. Rigarian Management Plan, Marulan Creek Catchment Area, Rev 2, May 2018. Rigarian Management Plan, Marulan Creek Catchment Area, Rev 2, May 2018. Rigarian Management Plan, Management Plan, Marulan Creek Catchment Area, Rev 2, May 2018. Rigarian Management Plan, Dosiriumi Creek Catchment Area, Rev 2, May 2018. Rigarian Management Plan, Dosiriumi Creek Catchment Area, Rev 2, May 2018. Rigarian Management Plan, Dosiriumi Creek Catchment Area, Rev 2, May 2018. Rigarian Management Plan, Manulan Creek Catchment Area, Rev 2, May 2018. Rigarian Management Plan, Manulan Creek Catchment Area, Rev 2, May 2018. Rigarian Management Plan, Manulan Creek Catchment Area, Rev 2, May 2018. Rigarian Management Plan, Manulan Creek Catchment Area, Rev 2, May 2018. Rigarian Management Plan, Manulan Creek Catchment Area, Rev 2, May 2018. Rigarian Management Plan, Manulan Creek Catchment Area, Rev 2, May 2018. Rigarian Management Plan, Manulan Creek Catchment Area, Rev 2, May 2018. Rigarian Management Plan, Manulan Creek Catchment Area, Rev 2, May 2018. Rigarian Management Plan, Manulan Creek Catchment Area, Rev 2, May 2018. Rigarian Management Plan, Manulan Creek Catchment Area, Rev 2, May 2018. Rigarian Management Plan, Manulan Creek Catchment Area, Rev 2, May 2018. Rigarian Management Plan, Manulan Creek Catchment Area, Rev 2, May 2018. Rigarian Management Plan, Manulan Creek Catchment Area, Rev 2, May 2018. Rigarian Management Plan, Manulan Creek Cat	45 (u)				Compilant	
Repair A Management Plan, Marulan Creek Catchment Area, Rev 2, Inversion of the proposet works, including any proposed stabilization, scour protection, end/or enhancement works including any proposed stabilization, scour protection, end/or enhancement works including any proposed stabilization, scour protection, end/or enhancement works including extension of the research shut would be implemented in the event of flooding during construction/enhabilitation. 45 (c) 4 description of the measures that would be implemented in the event of flooding during construction/enhabilitation. 45 (c) 4 part of Management Plan, Lockypriseligh Creek Catchment Area, Rev 2, May 2018. Repairan Management Plan, Lockypriseligh Creek Catchment Area, Rev 2, May 2018. Repairan Management Plan, Lockypriseligh Creek Catchment Area, Rev 2, May 2018. Repairan Management Plan, Lockypriseligh Creek Catchment Area, Rev 2, May 2018. Repairan Management Plan, Lockypriseligh Creek Catchment Area, Rev 2, May 2018. Repairan Management Plan, Lockypriseligh Creek Catchment Area, Rev 2, May 2018. Repairan Management Plan, Lockypriseligh Creek Catchment Area, Rev 2, May 2018. Repairan Management Plan, Lockypriseligh Creek Catchment Area, Rev 2, May 2018. Repairan Management Plan, Lockypriseligh Creek Catchment Area, Rev 2, May 2018. Repairan Management Plan, Lockypriseligh Creek Catchment Area, Rev 2, May 2018. Repairan Management Plan, Lockypriseligh Creek Catchment Area, Rev 2, May 2018. Repairan Management Plan, Lockypriseligh Creek Catchment Area, Rev 2, May 2018. Repairan Management Plan, Lockypriseligh Creek Catchment Area, Rev 2, May 2018. Repairan Management Plan, Lockypriseligh Creek Catchment Area, Rev 2, May 2018. Repairan Management Plan, Lockypriseligh Creek Catchment Area, Rev 2, May 2018. Repairan Management Plan, Lockypriseligh Creek Catchment Area, Rev 2, May 2018. Repairan Management Plan, Lockypriseligh Creek Catchment Area, Rev 2, May 2018. Repairan Management Plan, Lockypriseligh Creek Catchment Area, Rev 2, May 2018. Repairan						
State Stat			'			
eppersentative cross and longitudinal sections). 2018 Siparain Management Plan, Lockyersleigh Creek Catchment Area, Rev 2, June 2018 Alay 2018. Reparain Management Plan, Marulain Creek Catchment Area, Rev 2, June 2019 Alay 2018 Alay 20						
Has a description of the measures that would be implemented in the event of flooding during construction/rehabilitation. 45 (1) a description of the measures that would be implemented in the event of flooding during construction/rehabilitation. 81 payrain Management Plan, Joantimin Creek Catchment Area, Rev 2, May 2018. 81 payrain Management Plan, Lockyersleigh Creek Catchment Area, Rev 2, June 2019. 84 payrain Management Plan, Lockyersleigh Creek Catchment Area, Rev 2, June 2019. 85 (0) details of proposed staging of the works; 85 payrain Management Plan, Joantimin Creek Catchment Area, Rev 2, June 2019. 85 (1) payrain Management Plan, Doartimin Creek Catchment Area, Rev 2, June 2019. 85 (1) payrain Management Plan, Doartimin Creek Catchment Area, Rev 2, June 2019. 85 (1) payrain Management Plan, Joantimin Creek Catchment Area, Rev 2, June 2019. 85 (1) payrain Management Plan, Joantimin Creek Catchment Area, Rev 2, June 2019. 85 (1) payrain Management Plan, Joantimin Creek Catchment Area, Rev 2, May 2018. 85 (1) payrain Management Plan, Joantimin Creek Catchment Area, Rev 2, May 2018. 85 (1) payrain Management Plan, Joantimin Creek Catchment Area, Rev 2, May 2018. 85 (1) payrain Management Plan, Joantimin Creek Catchment Area, Rev 2, May 2018. 85 (1) payrain Management Plan, Joantimin Creek Catchment Area, Rev 2, May 2018. 85 (1) payrain Management Plan, Joantimin Creek Catchment Area, Rev 2, May 2018. 85 (1) payrain Management Plan, Joantimin Creek Catchment Area, Rev 2, May 2018. 85 (1) payrain Management Plan, Joantimin Creek Catchment Area, Rev 2, May 2018. 85 (1) payrain Management Plan, Joantimin Creek Catchment Area, Rev 2, May 2018. 85 (1) payrain Management Plan, Joantimin Creek Catchment Area, Rev 2, May 2018. 85 (1) payrain Management Plan, Joantimin Creek Catchment Area, Rev 2, June 2019. 85 (1) payrain Management Plan, Joantimin Creek Catchment Area, Rev 2, June 2019. 85 (1) payrain Management Plan, Joantimin Creek Catchment Area, Rev 2, June 2019. 85 (1) payrain Management Plan, Joantimin Cree	45 (b)				Compliant	
Ag 2018. Sparan Management Plan, Marulan Creek Catchment Area, Rev 2, June 2011. Sparan Management Plan, Datamin Creek Catchment Area, Rev 2, May 2018. Sparan Management Plan, Lockyersleigh Creek Catchment Area, Rev 2, May 2018. Sparan Management Plan, Datamin Creek Catchment Area, Rev 2, May 2018. Sparan Management Plan, Marulan Creek Catchment Area, Rev 2, May 2018. Sparan Management Plan, Datamin Creek Catchment Area, Rev 2, May 2018. Sparan Management Plan, Datamin Creek Catchment Area, Rev 2, May 2018. Sparan Management Plan, Datamin Creek Catchment Area, Rev 2, May 2018. Sparan Management Plan, Datamin Creek Catchment Area, Rev 2, May 2018. Sparan Management Plan, Datamin Creek Catchment Area, Rev 2, May 2018. Sparan Management Plan, Datamin Creek Catchment Area, Rev 2, May 2018. Sparan Management Plan, Datamin Creek Catchment Area, Rev 2, May 2018. Sparan Management Plan, Datamin Creek Catchment Area, Rev 2, May 2018. Sparan Management Plan, Datamin Creek Catchment Area, Rev 2, May 2018. Sparan Management Plan, Datamin Creek Catchment Area, Rev 2, May 2018. Sparan Management Plan, Datamin Creek Catchment Area, Rev 2, May 2018. Sparan Management Plan, Datamin Creek Catchment Area, Rev 2, May 2018. Sparan Management Plan, Datamin Creek Catchment Area, Rev 2, May 2018. Sparan Management Plan, Datamin Creek Catchment Area, Rev 2, May 2018. Sparan Management Plan, Datamin Creek Catchment Area, Rev 2, May 2018. Sparan Management Plan, Datamin Creek Catchment Area, Rev 2, May 2018. Sparan Management Plan, Datamin Creek Catchment Area, Rev 2, May 2018. Sparan Management Plan, Datamin Creek Catchment Area, Rev 2, May 2018. Sparan Management Plan, Datamin Creek Catchment Area, Rev 2, May 2018. Sparan Management Plan, Datamin Creek Catchment Area, Rev 2, May 2018. Sparan Management Plan, Datamin Creek Catchment Area, Rev 2, May 2018. Sparan Management Plan, Datamin Creek Catchment Area, Rev 2, May 2018. Sparan Management Plan, Marulan Creek Catchment Area, R		representative cross and longitudinal sections);				
Sparian Management Plan, Marulan Creek Catchment Area, Rev 2, May 2018. Sparian Management Plan, Inarimin Creek Catchment Area, Rev 2, May 2018. Sparian Management Plan, Inarimin Creek Catchment Area, Rev 2, May 2018. Sparian Management Plan, Inarimin Creek Catchment Area, Rev 2, May 2018. Sparian Management Plan, Marulan Creek Catchment Area, Rev 2, May 2018. Sparian Management Plan, Marulan Creek Catchment Area, Rev 2, May 2018. Sparian Management Plan, Inarimin Creek Catchment Area, Rev 2, May 2018. Sparian Management Plan, Inarimin Creek Catchment Area, Rev 2, May 2018. Sparian Management Plan, Inarimin Creek Catchment Area, Rev 2, May 2018. Sparian Management Plan, Inarimin Creek Catchment Area, Rev 2, May 2018. Sparian Management Plan, Marulan Creek Catchment Area, Rev 2, May 2018. Sparian Management Plan, Marulan Creek Catchment Area, Rev 2, May 2018. Sparian Management Plan, Marulan Creek Catchment Area, Rev 2, May 2018. Sparian Management Plan, Marulan Creek Catchment Area, Rev 2, May 2018. Sparian Management Plan, Marulan Creek Catchment Area, Rev 2, May 2018. Sparian Management Plan, Marulan Creek Catchment Area, Rev 2, June 2011. Sparian Management Plan, Marulan Creek Catchment Area, Rev 2, June 2018. Sparian Management Plan, Marulan Creek Catchment Area, Rev 2, June 2018. Sparian Management Plan, Marulan Creek Catchment Area, Rev 2, June 2018. Sparian Management Plan, Marulan Creek Catchment Area, Rev 2, May 2018. Sparian Management Plan, Marulan Creek Catchment Area, Rev 2, May 2018. Sparian Management Plan, Marulan Creek Catchment Area, Rev 2, May 2018. Sparian Management Plan, Marulan Creek Catchment Area, Rev 2, May 2018. Sparian Management Plan, Marulan Creek Catchment Area, Rev 2, May 2018. Sparian Management Plan, Marulan Creek Catchment Area, Rev 2, May 2018. Sparian Management Plan, Marulan Creek Catchment Area, Rev 2, May 2018. Sparian Management Plan, Marulan Creek Catchment Area, Rev 2, May 2018. Sparian Management Plan, Marulan Cr						
45 (c) a description of the measures that would be implemented in the event of flooding during construction/rehabilitation. Siparian Management Plan, Lockyersleigh Creek Catchment Area, Rev 2, May 2018. Riparian Management Plan, Lockyersleigh Creek Catchment Area, Rev 2, June 2011. 45 (d) details of proposed staging of the works; 45 (e) details of proposed staging of the works; 45 (e) completion criteria for the rehabilitation of the riparian area; 45 (e) a protocol for monitoring the performance of the rehabilitation over time. 45 (f) a protocol for monitoring the performance of the rehabilitation over time. 45 (f) a protocol for monitoring the performance of the rehabilitation over time. 45 (f) A protocol for monitoring the performance of the rehabilitation over time. 45 (f) Biparian Management Plan, Marulan Creek Catchment Area, Rev 2, May 2018. Riparian Management Plan, Marulan Creek Catchment Area, Rev 2, May 2018. Riparian Management Plan, Marulan Creek Catchment Area, Rev 2, May 2018. Riparian Management Plan, Marulan Creek Catchment Area, Rev 2, May 2018. Riparian Management Plan, Marulan Creek Catchment Area, Rev 2, June 2011. 45 (f) a protocol for monitoring the performance of the rehabilitation over time. 45 (f) a protocol for monitoring the performance of the rehabilitation over time. 45 (f) Algorithm Area, Rev 2, May 2018. Riparian Management Plan, Marulan Creek Catchment Area, Rev 2, May 2018. Riparian Management Plan, Marulan Creek Catchment Area, Rev 2, May 2018. Riparian Management Plan, Marulan Creek Catchment Area, Rev 2, May 2018. Riparian Management Plan, Marulan Creek Catchment Area, Rev 2, May 2018. Riparian Management Plan, Marulan Creek Catchment Area, Rev 2, May 2018. Riparian Management Plan, Marulan Creek Catchment Area, Rev 2, May 2018. Riparian Management Plan, Marulan Creek Catchment Area, Rev 2, May 2018. Riparian Management Plan, Marulan Creek Catchment Area, Rev 2, May 2018. Riparian Management Plan, Marulan Creek Catchment Area, Rev 2, May 2018. Riparian Management			I -			
2018. Raparian Management Plan, Lockyersleigh Creek Catchment Area, Rev 2, Mey 2018. Raparian Management Plan, Marulan Creek Catchment Area, Rev 2, Mey 2019. 45 (d) details of proposed staging of the works: 46 (d) details of proposed staging of the works: 47 (d) details of proposed staging of the works: 48 (d) details of proposed staging of the works: 48 (d) details of proposed staging of the works: 48 (d) details of proposed staging of the works: 48 (d) details of proposed staging of the works: 48 (d) details of proposed staging of	4E (c)	a description of the measures that would be implemented in the event of flooding during construction (subshillitation			Compliant	
Bigarian Management Plan, Lockyersleigh Creek Catchment Area, Rev 2, May 2018. Riparian Management Plan, Marulan Creek Catchment Area, Rev 2, June 2019. Riparian Management Plan, Joarimin Creek Catchment Area, Rev 2, May 2018. Riparian Management Plan, Lockyersleigh Creek Catchment Area, Rev 2, May 2018. Riparian Management Plan, Marulan Creek Catchment Area, Rev 2, June 2011.	43 (0)	a description of the measures that would be implemented in the event of hooding during construction/rendomation.			Compilant	
A5 (d) details of proposed staging of the works; Riparian Management Plan, Marulan Creek Catchment Area, Rev 2, May 2018. Riparian Management Plan, Lockyersleigh Creek Catchment Area, Rev 2, May 2018. Riparian Management Plan, Lockyersleigh Creek Catchment Area, Rev 2, May 2018. 45 (e) completion criteria for the rehabilitation of the riparian area; Riparian Management Plan, Lockyersleigh Creek Catchment Area, Rev 2, May 2018. Riparian Management Plan, Lockyersleigh Creek Catchment Area, Rev 2, May 2018. Riparian Management Plan, Lockyersleigh Creek Catchment Area, Rev 2, June 2011. 45 (f) a protocol for monitoring the performance of the rehabilitation over time. 45 (f) a protocol for monitoring the performance of the rehabilitation over time. 46 (f) Riparian Management Plan, Lockyersleigh Creek Catchment Area, Rev 2, May 2018. Riparian Management Plan, Lockyersleigh Creek Catchment Area, Rev 2, May 2018. Riparian Management Plan, Lockyersleigh Creek Catchment Area, Rev 2, May 2018. Riparian Management Plan, Lockyersleigh Creek Catchment Area, Rev 2, May 2018. Riparian Management Plan, Lockyersleigh Creek Catchment Area, Rev 2, May 2018. Riparian Management Plan, Marulan Creek Catchment Area, Rev 2, May 2018. Riparian Management Plan, Marulan Creek Catchment Area, Rev 2, May 2018. Riparian Management Plan, Marulan Creek Catchment Area, Rev 2, May 2018. Riparian Management Plan, Marulan Creek Catchment Area, Rev 2, May 2018. Riparian Management Plan, Marulan Creek Catchment Area, Rev 2, May 2018. Riparian Management Plan, Marulan Creek Catchment Area, Rev 2, May 2018. Riparian Management Plan, Marulan Creek Catchment Area, Rev 2, May 2018. Riparian Management Plan, Marulan Creek Catchment Area, Rev 2, May 2018. Riparian Management Plan, Marulan Creek Catchment Area, Rev 2, May 2018. Riparian Management Plan, Marulan Creek Catchment Area, Rev 2, May 2018. Riparian Management Plan, Marulan Creek Catchment Area, Rev 2, May 2018. Riparian Management Plan, Marulan Creek Catchment Area, Rev 2, May 2018. Riparian M						
A5 (d) details of proposed staging of the works; Riparian Management Plan, Joarimin Creek Catchment Area, Rev 2, May 2018. Riparian Management Plan, Marulan Creek Catchment Area, Rev 2, June 2011.			ļ '			
45 (d) details of proposed staging of the works; Riparian Management Plan, Joarnimin Creek Catchment Area, Rev 2, May 2018. Riparian Management Plan, Lockyersleigh Creek Catchment Area, Rev 2, June 2011. 45 (e) completion criteria for the rehabilitation of the riparian area; Riparian Management Plan, Narulan Creek Catchment Area, Rev 2, May 2018. Riparian Management Plan, Joarnimin Creek Catchment Area, Rev 2, May 2018. Riparian Management Plan, Lockyersleigh Creek Catchment Area, Rev 2, May 2018. Riparian Management Plan, Marulan Creek Catchment Area, Rev 2, June 2011. 45 (f) a protocol for monitoring the performance of the rehabilitation over time. Riparian Management Plan, Joarnimin Creek Catchment Area, Rev 2, May 2018. Riparian Management Plan, Joarnimin Creek Catchment Area, Rev 2, May 2018. Riparian Management Plan, Lockyersleigh Creek Catchment Area, Rev 2, May 2018. Riparian Management Plan, Lockyersleigh Creek Catchment Area, Rev 2, May 2018. Riparian Management Plan, Lockyersleigh Creek Catchment Area, Rev 2, May 2018. Riparian Management Plan, Marulan Creek Catchment Area, Rev 2, May 2018. Riparian Management Plan, Marulan Creek Catchment Area, Rev 2, June 2018. Riparian Management Plan, Marulan Creek Catchment Area, Rev 2, June 2018. Riparian Management Plan, Marulan Creek Catchment Area, Rev 2, June 2018.						
Riparian Management Plan, Lockyersleigh Creek Catchment Area, Rev 2, May 2018. Riparian Management Plan, Marulan Creek Catchment Area, Rev 2, June 2011. 45 (e) completion criteria for the rehabilitation of the riparian area; Riparian Management Plan, Joarimin Creek Catchment Area, Rev 2, May 2018. Riparian Management Plan, Lockyersleigh Creek Catchment Area, Rev 2, June 2011. 45 (f) a protocol for monitoring the performance of the rehabilitation over time. Riparian Management Plan, Joarimin Creek Catchment Area, Rev 2, May 2018. Riparian Management Plan, Joarimin Creek Catchment Area, Rev 2, May 2018. Riparian Management Plan, Lockyersleigh Creek Catchment Area, Rev 2, June 2011. Riparian Management Plan, Lockyersleigh Creek Catchment Area, Rev 2, May 2018. Riparian Management Plan, Marulan Creek Catchment Area, Rev 2, June	45 (d)	details of proposed staging of the works;			Compliant	
May 2018. Riparian Management Plan, Marulan Creek Catchment Area, Rev 2, June 2011. 45 (e) completion criteria for the rehabilitation of the riparian area; Riparian Management Plan, Joarimin Creek Catchment Area, Rev 2, May 2018. Riparian Management Plan, Lockyersleigh Creek Catchment Area, Rev 2, May 2018. Riparian Management Plan, Marulan Creek Catchment Area, Rev 2, June 2011. 45 (f) a protocol for monitoring the performance of the rehabilitation over time. Riparian Management Plan, Joarimin Creek Catchment Area, Rev 2, May 2018. Riparian Management Plan, Joarimin Creek Catchment Area, Rev 2, May 2018. Riparian Management Plan, Lockyersleigh Creek Catchment Area, Rev 2, May 2018. Riparian Management Plan, Marulan Creek Catchment Area, Rev 2, June						
Riparian Management Plan, Marulan Creek Catchment Area, Rev 2, June 2011. 45 (e) completion criteria for the rehabilitation of the riparian area; Riparian Management Plan, Joarimin Creek Catchment Area, Rev 2, May 2018. Riparian Management Plan, Lockyersleigh Creek Catchment Area, Rev 2, May 2018. Riparian Management Plan, Marulan Creek Catchment Area, Rev 2, June 2011. 45 (f) a protocol for monitoring the performance of the rehabilitation over time. Riparian Management Plan, Joarimin Creek Catchment Area, Rev 2, May 2018. Riparian Management Plan, Lockyersleigh Creek Catchment Area, Rev 2, May 2018. Riparian Management Plan, Lockyersleigh Creek Catchment Area, Rev 2, May 2018. Riparian Management Plan, Management Plan, Management Plan, Lockyersleigh Creek Catchment Area, Rev 2, May 2018. Riparian Management Plan, Management Plan, Marulan Creek Catchment Area, Rev 2, June						
A5 (e) completion criteria for the rehabilitation of the riparian area; Riparian Management Plan, Joarimin Creek Catchment Area, Rev 2, May 2018. Riparian Management Plan, Lockyersleigh Creek Catchment Area, Rev 2, May 2018. Riparian Management Plan, Marulan Creek Catchment Area, Rev 2, June 2011. A5 (f) a protocol for monitoring the performance of the rehabilitation over time. Riparian Management Plan, Joarimin Creek Catchment Area, Rev 2, May 2018. Riparian Management Plan, Lockyersleigh Creek Catchment Area, Rev 2, May 2018. Riparian Management Plan, Lockyersleigh Creek Catchment Area, Rev 2, June Riparian Management Plan, Lockyersleigh Creek Catchment Area, Rev 2, May 2018. Riparian Management Plan, Marulan Creek Catchment Area, Rev 2, June			'			
2018. Riparian Management Plan, Lockyersleigh Creek Catchment Area, Rev 2, May 2018. Riparian Management Plan, Marulan Creek Catchment Area, Rev 2, June 2011. 45 (f) a protocol for monitoring the performance of the rehabilitation over time. Riparian Management Plan, Joarimin Creek Catchment Area, Rev 2, May 2018. Riparian Management Plan, Lockyersleigh Creek Catchment Area, Rev 2, May 2018. Riparian Management Plan, Marulan Creek Catchment Area, Rev 2, May 2018. Riparian Management Plan, Marulan Creek Catchment Area, Rev 2, June	45 ()	and the same of th			Compliant	
Riparian Management Plan, Lockyersleigh Creek Catchment Area, Rev 2, May 2018. Riparian Management Plan, Marulan Creek Catchment Area, Rev 2, June 2011. 45 (f) a protocol for monitoring the performance of the rehabilitation over time. Riparian Management Plan, Joarimin Creek Catchment Area, Rev 2, May 2018. Riparian Management Plan, Lockyersleigh Creek Catchment Area, Rev 2, May 2018. Riparian Management Plan, Marulan Creek Catchment Area, Rev 2, June Riparian Management Plan, Marulan Creek Catchment Area, Rev 2, June	45 (e)	completion criteria for the renabilitation of the riparian area;			Compliant	
Riparian Management Plan, Marulan Creek Catchment Area, Rev 2, June 2011. 45 (f) a protocol for monitoring the performance of the rehabilitation over time. Riparian Management Plan, Joarimin Creek Catchment Area, Rev 2, May 2018. Riparian Management Plan, Lockyersleigh Creek Catchment Area, Rev 2, May 2018. Riparian Management Plan, Marulan Creek Catchment Area, Rev 2, June						
2011. 45 (f) a protocol for monitoring the performance of the rehabilitation over time. Riparian Management Plan, Lockyersleigh Creek Catchment Area, Rev 2, May 2018. Riparian Management Plan, Lockyersleigh Creek Catchment Area, Rev 2, May 2018. Riparian Management Plan, Marulan Creek Catchment Area, Rev 2, June			I '			
45 (f) a protocol for monitoring the performance of the rehabilitation over time. Riparian Management Plan, Joarimin Creek Catchment Area, Rev 2, May 2018. Riparian Management Plan, Lockyersleigh Creek Catchment Area, Rev 2, May 2018. Riparian Management Plan, Marulan Creek Catchment Area, Rev 2, June Riparian Management Plan, Marulan Creek Catchment Area, Rev 2, June						
Riparian Management Plan, Lockyersleigh Creek Catchment Area, Rev 2, May 2018. Riparian Management Plan, Marulan Creek Catchment Area, Rev 2, June	45 (f)	a protocol for monitoring the performance of the rehabilitation over time.			Compliant	
May 2018. Riparian Management Plan, Marulan Creek Catchment Area, Rev 2, June						
Riparian Management Plan, Marulan Creek Catchment Area, Rev 2, June						
			'			

	Within 3 months of the Independent Environmental Audit (see Condition 11 in Schedule 5), the Applicant shall update the Rehabilitation and Landscape Management Plan to the satisfaction of the Secretary.		No evidence sighted of updates to the Rehabilitation and Landscape Management Plan following the 2020 IEA.	Non-compliant	NC7
bilitation				Compliant	
	Within 3 months of the first Independent Environmental Audit (see Condition 11 in Schedule 5), the Applicant must lodge a rehabilitation bond for the development with the Secretary. The sum of the bond must be calculated at \$2.50/m ² for the total area to be disturbed in each 5 year period, or as otherwise directed by the Secretary. Notes:	Previous audit evidence: Letter to Director-General DP&I lodging rehabilitation bond to value of \$1,844,272 (11/02/13)		Compliant	
	• If the rehabilitation is completed to the satisfaction of the Secretary, the Secretary will release the rehabilitation bond. • If the rehabilitation is not completed to the satisfaction of the Secretary, the Secretary will call in all or part of the rehabilitation bond, and arrange for the satisfactory completion of the relevant works.	Noted.			
	within 3 months of each Independent Environmental Audit (see Condition 11 in Schedule 5) after the lodgement of the rehabilitation bond, the Applicant must review, and if necessary revise the sum of the bond to the satisfaction of the Secretary. This review must		The auditor has not been provided any evidence of a bond review occurring following the	Non-compliant	
	consider: (a) the effects of inflation;	No evidence provided.	previous audit. The auditor has not been provided any evidence of a bond review occurring following the	Non-compliant	NC8
B (b)	(b) any changes to the total area of disturbance; and	No evidence provided.	previous audit. The auditor has not been provided any evidence of a bond review occurring following the	Non-compliant	NC9
		No evidence provided.	previous audit.	·	NC10
8 (c)	(c) the performance of the rehabilitation against the completion criteria of the Rehabilitation and Landscape Management Plan.		The auditor has not been provided any evidence of a bond review occurring following the previous audit.	Non-compliant	NC11
	f Biodiversity Credits				
	Table 11. Biodiversity Credits to be retired				
	The Applicant must retire the biodiversity credits specified in Table 11 to the satisfaction of the Secretary and OEH. The retirement of credits must be undertaken in accordance with the Framework for Biodiversity Assessment - NSW Biodiversity Offsets Policy for Major Projects by:		The latest correspondence regarding the retirement of credits is as per the previous audit from July 2018. 2022 AER confirms no credits have been retired since this time.	Compliant	
8A (a)	(a) acquiring or retiring credits under the Biobanking Scheme in the TSC Act;	Note.			
	(b) making payments into an offset fund that has been developed by the NSW Government; or	Note.			
	(c) providing supplementary measures.	Note.			
	Credits may be retired progressively as the vegetation to be offset by the credits is cleared. By 31 May 2017, unless otherwise agreed by the Secretary, the Applicant must retire the credits associated with the projected vegetation clearing for the following five years. Credits must continue to be obtained and retired in five-yearly increments prior to clearance of the area of vegetation expected to be cleared in the forthcoming five years. Each Annual Review required under condition 10 of Schedule 5 must record the number of credits retired in the reporting year (or previously) and the area of vegetation expected to be cleared in the forthcoming five years).			Compliant	
		Annual Review 2020, 2021, 2022.	AERs provide comment on number of credits retired in the reporting year.	Compliant	
	Credit type: Ecosystem credits: HN614 Yellow Box – Blakely's Red Gum grassy woodland on the tablelands, South Eastern Highlands Bioregion Credits to be retired: 2124 Credit type: Ecosystem credits: HN570 Red Stringybark – Brittle Gum – Inland Scribbly Gum dry open forest of the tablelands, South	Annual Review 2020, 2021, 2022.	AERs confirm offsets are secured in relation to level of clearing undertaken. Consistent with I	Compliant	
	Eastern Highlands Bioregion Credits to be retired: 881	Annual Review 2020, 2021, 2022.	Total number of credits retired in 2018.	· ·	
	Credit type: Ecosystem credits: HN515 Broad-leaved Peppermint – Ribbon Gum grassy open forest in the north-east of the South Eastern Highlands Bioregion Credits to be Retired 33	Annual Review 2020, 2021, 2022.	AERs confirm offsets are secured in relation to level of clearing undertaken. Consistent with I	Compliant	
	Credit type: Ecosystem credits: Total: 3038 (2124 + 881 + 33)	·	AERs confirm offsets are secured in relation to level of clearing undertaken. Consistent with I	Compliant	
	Credit type: Species Credits: Squirrel Glider (Petaurus norfolcensis) Credits to be retired: 1725		Total number of credits retired in 2018.	Compliant	
	Credit type: Species Credits: Total: 1725	Annual Review 2020, 2021, 2022.	Total number of credits retired in 2018.	Compliant	
	Note: The management actions used to generate credits will need to avoid impacting on Aboriginal cultural heritage unless these impacts are identified within an approved Aboriginal Cultural Heritage Management Plan (see condition 35) or an approved Aboriginal Heritage	Note.			
JAL IMPA					
	The Applicant must minimise the visual impacts of the development to the satisfaction of the Director-General.			Compliant	
		Site observations	Sighted earthen visual bund and sail bund approximate to the administration area.		
		Site interviews	Lighting equipment installed as to avoid light spill.		
ting Emiss	sions				
50	The Applicant must take all practicable measures to prevent and/or minimise any off-site lighting impacts from the development.			Compliant	
50	The Applicant must take all practicable measures to prevent and/or minimise any off-site lighting impacts from the development.	Site observations	Sighted earthen visual bund and sail visual bund approximate to the administration area.	Compliant	
		Site interviews	Sighted earthen visual bund and sail visual bund approximate to the administration area. Lighting equipment installed as to avoid light spill.		
51	All external lighting associated with the development must comply with Australian Standard AS4282 (INT) 1995 – Control of Obtrusive	Site interviews Previous audit evidence: GHD Lynwood Hard Rock Quarry Detailed Design		Compliant	
51		Site interviews Previous audit evidence: GHD Lynwood Hard Rock Quarry Detailed Design and Documentation Design Certificate for Process Area External Lighting			
51	All external lighting associated with the development must comply with Australian Standard AS4282 (INT) 1995 – Control of Obtrusive	Site interviews Previous audit evidence: GHD Lynwood Hard Rock Quarry Detailed Design			
51 ertising	All external lighting associated with the development must comply with Australian Standard AS4282 (INT) 1995 – Control of Obtrusive Effects of Outdoor Lighting. The Applicant must not erect or display any advertising structure(s) or advertisements on the site without the written approval of the	Site interviews Previous audit evidence: GHD Lynwood Hard Rock Quarry Detailed Design and Documentation Design Certificate for Process Area External Lighting (31/01/14)	Lighting equipment installed as to avoid light spill.		
51 ertising 52	All external lighting associated with the development must comply with Australian Standard AS4282 (INT) 1995 – Control of Obtrusive Effects of Outdoor Lighting. The Applicant must not erect or display any advertising structure(s) or advertisements on the site without the written approval of the Secretary.	Site interviews Previous audit evidence: GHD Lynwood Hard Rock Quarry Detailed Design and Documentation Design Certificate for Process Area External Lighting		Compliant	
51 ertising 52 STE MANA	All external lighting associated with the development must comply with Australian Standard AS4282 (INT) 1995 – Control of Obtrusive Effects of Outdoor Lighting. The Applicant must not erect or display any advertising structure(s) or advertisements on the site without the written approval of the Secretary. AGEMENT	Site interviews Previous audit evidence: GHD Lynwood Hard Rock Quarry Detailed Design and Documentation Design Certificate for Process Area External Lighting (31/01/14)	Lighting equipment installed as to avoid light spill.	Compliant	
51 ertising 52 STE MANA 53	All external lighting associated with the development must comply with Australian Standard AS4282 (INT) 1995 – Control of Obtrusive Effects of Outdoor Lighting. The Applicant must not erect or display any advertising structure(s) or advertisements on the site without the written approval of the Secretary.	Site interviews Previous audit evidence: GHD Lynwood Hard Rock Quarry Detailed Design and Documentation Design Certificate for Process Area External Lighting (31/01/14)	Lighting equipment installed as to avoid light spill.	Compliant	
51 ertising 52 STE MANA 53	All external lighting associated with the development must comply with Australian Standard AS4282 (INT) 1995 – Control of Obtrusive Effects of Outdoor Lighting. The Applicant must not erect or display any advertising structure(s) or advertisements on the site without the written approval of the Secretary. AGEMENT The Applicant must:	Site interviews Previous audit evidence: GHD Lynwood Hard Rock Quarry Detailed Design and Documentation Design Certificate for Process Area External Lighting (31/01/14) Site observations	Lighting equipment installed as to avoid light spill.	Compliant	
51 ertising 52 55 55 53 3 (a)	All external lighting associated with the development must comply with Australian Standard AS4282 (INT) 1995 – Control of Obtrusive Effects of Outdoor Lighting. The Applicant must not erect or display any advertising structure(s) or advertisements on the site without the written approval of the Secretary. AGEMENT The Applicant must:	Site interviews Previous audit evidence: GHD Lynwood Hard Rock Quarry Detailed Design and Documentation Design Certificate for Process Area External Lighting (31/01/14) Site observations Annual Review 2020, 2021, 2022.	Lighting equipment installed as to avoid light spill. Nil sighted during site inspection	Compliant	
51 51 52 52 5TE MANA 53 (a) 3 (b) 3 (c)	All external lighting associated with the development must comply with Australian Standard AS4282 (INT) 1995 – Control of Obtrusive Effects of Outdoor Lighting. The Applicant must not erect or display any advertising structure(s) or advertisements on the site without the written approval of the Secretary. AGEMENT The Applicant must: (a) monitor the amount of waste generated by the development; (b) investigate ways to minimise waste generated by the development; (c) implement reasonable and feasible measures to minimise waste generated by the development; and	Site interviews Previous audit evidence: GHD Lynwood Hard Rock Quarry Detailed Design and Documentation Design Certificate for Process Area External Lighting (31/01/14) Site observations Annual Review 2020, 2021, 2022. Waste tracking records and invoices	Lighting equipment installed as to avoid light spill. Nil sighted during site inspection	Compliant Compliant Compliant	
51 ste MANA 53 3 (a) 3 (b) 33 (c) 3 (d)	All external lighting associated with the development must comply with Australian Standard AS4282 (INT) 1995 – Control of Obtrusive Effects of Outdoor Lighting. The Applicant must not erect or display any advertising structure(s) or advertisements on the site without the written approval of the Secretary. AGEMENT The Applicant must: (a) monitor the amount of waste generated by the development; (b) investigate ways to minimise waste generated by the development; (c) implement reasonable and feasible measures to minimise waste generated by the development; and (d) report on waste management and minimisation in the Annual Review.	Site interviews Previous audit evidence: GHD Lynwood Hard Rock Quarry Detailed Design and Documentation Design Certificate for Process Area External Lighting (31/01/14) Site observations Annual Review 2020, 2021, 2022. Waste tracking records and invoices Waste Management and Minimisation Strategy 2019 Waste Management and Minimisation Strategy 2019 Annual Review 2020, 2021, 2022.	Lighting equipment installed as to avoid light spill. Nil sighted during site inspection	Compliant Compliant Compliant Compliant	
51 52 53 3 (a) 3 (b) 3 (c) 3 (d)	All external lighting associated with the development must comply with Australian Standard AS4282 (INT) 1995 – Control of Obtrusive Effects of Outdoor Lighting. The Applicant must not erect or display any advertising structure(s) or advertisements on the site without the written approval of the Secretary. AGEMENT The Applicant must: (a) monitor the amount of waste generated by the development; (b) investigate ways to minimise waste generated by the development; (c) implement reasonable and feasible measures to minimise waste generated by the development; and (d) report on waste management and minimisation in the Annual Review. to the satisfaction of the Secretary.	Site interviews Previous audit evidence: GHD Lynwood Hard Rock Quarry Detailed Design and Documentation Design Certificate for Process Area External Lighting (31/01/14) Site observations Annual Review 2020, 2021, 2022. Waste tracking records and invoices Waste Management and Minimisation Strategy 2019 Waste Management and Minimisation Strategy 2019	Lighting equipment installed as to avoid light spill. Nil sighted during site inspection	Compliant Compliant Compliant Compliant Compliant Compliant	
51 51 52 52 55 53 3 (a) 3 (b) 3 (c) 3 (d) 54	All external lighting associated with the development must comply with Australian Standard AS4282 (INT) 1995 – Control of Obtrusive Effects of Outdoor Lighting. The Applicant must not erect or display any advertising structure(s) or advertisements on the site without the written approval of the Secretary. AGEMENT The Applicant must: (a) monitor the amount of waste generated by the development; (b) investigate ways to minimise waste generated by the development; (c) implement reasonable and feasible measures to minimise waste generated by the development; and (d) report on waste management and minimisation in the Annual Review. to the satisfaction of the Secretary. The Applicant must ensure that all wastes generated or stored at the site are assessed, classified and managed in accordance with the Assessment, Classification and Management of Liquid and Non-liquid Waste (OEH) guideline, or its successor (incorporates OEH GTA).	Site interviews Previous audit evidence: GHD Lynwood Hard Rock Quarry Detailed Design and Documentation Design Certificate for Process Area External Lighting (31/01/14) Site observations Annual Review 2020, 2021, 2022. Waste tracking records and invoices Waste Management and Minimisation Strategy 2019 Waste Management and Minimisation Strategy 2019 Annual Review 2020, 2021, 2022.	Lighting equipment installed as to avoid light spill. Nil sighted during site inspection	Compliant Compliant Compliant Compliant Compliant	
51 52 52 53 53 (a) 53 (b) 53 (c) 53 (d) 54 54 54	All external lighting associated with the development must comply with Australian Standard AS4282 (INT) 1995 – Control of Obtrusive Effects of Outdoor Lighting. The Applicant must not erect or display any advertising structure(s) or advertisements on the site without the written approval of the Secretary. AGEMENT The Applicant must: (a) monitor the amount of waste generated by the development; (b) investigate ways to minimise waste generated by the development; (c) implement reasonable and feasible measures to minimise waste generated by the development; and (d) report on waste management and minimisation in the Annual Review. to the satisfaction of the Secretary. The Applicant must ensure that all wastes generated or stored at the site are assessed, classified and managed in accordance with the Assessment, Classification and Management of Liquid and Non-liquid Waste (OEH) guideline, or its successor (incorporates OEH GTA). AND HAZARDS MANAGEMENT	Site interviews Previous audit evidence: GHD Lynwood Hard Rock Quarry Detailed Design and Documentation Design Certificate for Process Area External Lighting (31/01/14) Site observations Annual Review 2020, 2021, 2022. Waste tracking records and invoices Waste Management and Minimisation Strategy 2019 Waste Management and Minimisation Strategy 2019 Annual Review 2020, 2021, 2022. Noted Site observations	Lighting equipment installed as to avoid light spill. Nil sighted during site inspection The AERs report on the volumes of waste generated. Waste removed from site by licensed contractor.	Compliant Compliant Compliant Compliant Compliant Compliant	
51	All external lighting associated with the development must comply with Australian Standard AS4282 (INT) 1995 – Control of Obtrusive Effects of Outdoor Lighting. The Applicant must not erect or display any advertising structure(s) or advertisements on the site without the written approval of the Secretary. AGEMENT The Applicant must: (a) monitor the amount of waste generated by the development; (b) investigate ways to minimise waste generated by the development; (c) implement reasonable and feasible measures to minimise waste generated by the development; and (d) report on waste management and minimisation in the Annual Review. to the satisfaction of the Secretary. The Applicant must ensure that all wastes generated or stored at the site are assessed, classified and managed in accordance with the Assessment, Classification and Management of Liquid and Non-liquid Waste (OEH) guideline, or its successor (incorporates OEH GTA). AND HAZARDS MANAGEMENT	Site interviews Previous audit evidence: GHD Lynwood Hard Rock Quarry Detailed Design and Documentation Design Certificate for Process Area External Lighting (31/01/14) Site observations Annual Review 2020, 2021, 2022. Waste tracking records and invoices Waste Management and Minimisation Strategy 2019 Waste Management and Minimisation Strategy 2019 Annual Review 2020, 2021, 2022. Noted Site observations	Lighting equipment installed as to avoid light spill. Nil sighted during site inspection The AERs report on the volumes of waste generated. Waste removed from site by licensed contractor.	Compliant Compliant Compliant Compliant Compliant Compliant Compliant	
51 ertising 52 ste MANA 53 33 (a) 53 (b) 53 (c) 53 (d) 54 errgency / gerous GC 55	All external lighting associated with the development must comply with Australian Standard AS4282 (INT) 1995 – Control of Obtrusive Effects of Outdoor Lighting. The Applicant must not erect or display any advertising structure(s) or advertisements on the site without the written approval of the Secretary. AGEMENT The Applicant must: (a) monitor the amount of waste generated by the development; (b) investigate ways to minimise waste generated by the development; (c) implement reasonable and feasible measures to minimise waste generated by the development; and (d) report on waste management and minimisation in the Annual Review. to the satisfaction of the Secretary. The Applicant must ensure that all wastes generated or stored at the site are assessed, classified and managed in accordance with the Assessment, Classification and Management of Liquid and Non-liquid Waste (OEH) guideline, or its successor (incorporates OEH GTA). AND HAZARDS MANAGEMENT	Site interviews Previous audit evidence: GHD Lynwood Hard Rock Quarry Detailed Design and Documentation Design Certificate for Process Area External Lighting (31/01/14) Site observations Annual Review 2020, 2021, 2022. Waste tracking records and invoices Waste Management and Minimisation Strategy 2019 Waste Management and Minimisation Strategy 2019 Annual Review 2020, 2021, 2022. Noted Site observations Site interviews	Nil sighted during site inspection The AERs report on the volumes of waste generated. Waste removed from site by licensed contractor. Sighted evidence of appropriate waste segregation.	Compliant Compliant Compliant Compliant Compliant Compliant	
51 52 55 53 3 (a) 3 (b) 3 (c) 3 (d) 54	All external lighting associated with the development must comply with Australian Standard AS4282 (INT) 1995 – Control of Obtrusive Effects of Outdoor Lighting. The Applicant must not erect or display any advertising structure(s) or advertisements on the site without the written approval of the Secretary. AGEMIENT The Applicant must: (a) monitor the amount of waste generated by the development; (b) investigate ways to minimise waste generated by the development; (c) implement reasonable and feasible measures to minimise waste generated by the development; and (d) report on waste management and minimisation in the Annual Review. to the satisfaction of the Secretary. The Applicant must ensure that all wastes generated or stored at the site are assessed, classified and managed in accordance with the Assessment, Classification and Management of Liquid and Non-liquid Waste (OEH) guideline, or its successor (incorporates OEH GTA). AND HAZARDS MANAGEMENT Boods The Applicant must ensure that the storage, handling, and transport of dangerous goods are conducted in accordance with the relevant	Site interviews Previous audit evidence: GHD Lynwood Hard Rock Quarry Detailed Design and Documentation Design Certificate for Process Area External Lighting (31/01/14) Site observations Annual Review 2020, 2021, 2022. Waste tracking records and invoices Waste Management and Minimisation Strategy 2019 Waste Management and Minimisation Strategy 2019 Annual Review 2020, 2021, 2022. Noted Site observations Site interviews	Lighting equipment installed as to avoid light spill. Nil sighted during site inspection The AERs report on the volumes of waste generated. Waste removed from site by licensed contractor.	Compliant Compliant Compliant Compliant Compliant Compliant Compliant	
51 51 52 53 3 (a) 3 (b) 3 (c) 3 (d) 54 RGENCY 6 55 55 55	All external lighting associated with the development must comply with Australian Standard AS4282 (INT) 1995 – Control of Obtrusive Effects of Outdoor Lighting. The Applicant must not erect or display any advertising structure(s) or advertisements on the site without the written approval of the Secretary. AGEMENT The Applicant must: (a) monitor the amount of waste generated by the development; (b) investigate ways to minimise waste generated by the development; (c) implement reasonable and feasible measures to minimise waste generated by the development; and (d) report on waste management and minimisation in the Annual Review. to the satisfaction of the Secretary. The Applicant must ensure that all wastes generated or stored at the site are assessed, classified and managed in accordance with the Assessment, Classification and Management of Liquid and Non-liquid Waste (OEH) guideline, or its successor (incorporates OEH GTA). AND HAZARDS MANAGEMENT Boods The Applicant must ensure that the storage, handling, and transport of dangerous goods are conducted in accordance with the relevant Australian Standards , particularly AS1940 and AS1596, and the Dangerous Goods Code.	Site interviews Previous audit evidence: GHD Lynwood Hard Rock Quarry Detailed Design and Documentation Design Certificate for Process Area External Lighting (31/01/14) Site observations Annual Review 2020, 2021, 2022. Waste tracking records and invoices Waste Management and Minimisation Strategy 2019 Waste Management and Minimisation Strategy 2019 Annual Review 2020, 2021, 2022. Noted Site observations Site interviews Site Observations Sighted Dangerous Goods Register - only diesel volume is the trigger	Lighting equipment installed as to avoid light spill. Nil sighted during site inspection The AERs report on the volumes of waste generated. Waste removed from site by licensed contractor. Sighted evidence of appropriate waste segregation. Site observations indicated that materials are securely stored in specified locations.	Compliant Compliant Compliant Compliant Compliant Compliant Compliant Compliant	
51 51 52 53 3 (a) 3 (b) 3 (c) 3 (d) 54 RGENCY 6 55 55 55	All external lighting associated with the development must comply with Australian Standard AS4282 (INT) 1995 – Control of Obtrusive Effects of Outdoor Lighting. The Applicant must not erect or display any advertising structure(s) or advertisements on the site without the written approval of the Secretary. AGEMIENT The Applicant must: (a) monitor the amount of waste generated by the development; (b) investigate ways to minimise waste generated by the development; (c) implement reasonable and feasible measures to minimise waste generated by the development; and (d) report on waste management and minimisation in the Annual Review. to the satisfaction of the Secretary. The Applicant must ensure that all wastes generated or stored at the site are assessed, classified and managed in accordance with the Assessment, Classification and Management of Liquid and Non-liquid Waste (OEH) guideline, or its successor (incorporates OEH GTA). AND HAZARDS MANAGEMENT Boods The Applicant must ensure that the storage, handling, and transport of dangerous goods are conducted in accordance with the relevant	Site interviews Previous audit evidence: GHD Lynwood Hard Rock Quarry Detailed Design and Documentation Design Certificate for Process Area External Lighting (31/01/14) Site observations Annual Review 2020, 2021, 2022. Waste tracking records and invoices Waste Management and Minimisation Strategy 2019 Waste Management and Minimisation Strategy 2019 Annual Review 2020, 2021, 2022. Noted Site observations Site interviews Site Observations Sighted Dangerous Goods Register - only diesel volume is the trigger	Nil sighted during site inspection The AERs report on the volumes of waste generated. Waste removed from site by licensed contractor. Sighted evidence of appropriate waste segregation.	Compliant Compliant Compliant Compliant Compliant Compliant Compliant	

57	The Applicant must:	Note.	T	
57(a)	ensure that the development is suitably equipped to respond to any fires on-site; and	Note.	Fire fighting equipment was observed on site. The site contains extensive water	Compliant
37 (u)	and the delengment states, equipped to expense to any mass on site, and		management infrastructure, including dams and water carts that could be used to source	Compilation
		Site Observations	and move fire fighting water	
57(b)	assist the rural fire service and emergency services as much as possible if there is a fire on-site.		Waste removed from site by licensed contractor.	Compliant
			Sighted evidence of appropriate waste segregation.	
		Site interviews		
58	deleted	Note.		
QUARRY EXI	TSTRATEGY			
59	At least 5 years prior to the cessation of quarry operations, the Applicant must prepare a Quarry Exit Strategy for the development, in			Not triggered
	consultation with the DPI Water and Council, and to the satisfaction of the Secretary. This plan must:	Site observations	Quarry approved to operate till 1 January 2038, as such condition not triggered during audit	
59 (a)	define the objectives and criteria for quarry closure;	DA128-5-2005	period.	Not triggered
55 (4)	active disjectives and arteria to quarry assure;	Site observations	Quarry approved to operate till 1 January 2038, as such condition not triggered during audit	The triggered
		DA128-5-2005	period.	
59 (b)	investigate options for the future use of the site, including any final void/s;		Quarry approved to operate till 1 January 2038, as such condition not triggered during audit	Not triggered
59 (c)	describe the measures that would be implemented to minimise or manage the ongoing environmental effects of the development; and	DA128-5-2005 Site observations	period. Quarry approved to operate till 1 January 2038, as such condition not triggered during audit	Not triggored
33 (c)	describe the measures that would be implemented to minimise of manage the origining environmental effects of the development, and	DA128-5-2005	period.	Not triggered
59 (d)	describe how the performance of these measures would be monitored over time.		Quarry approved to operate till 1 January 2038, as such condition not triggered during audit	Not triggered
		DA128-5-2005	period.	
	ADDITIONAL PROCEDURES			
	ON OF LANDOWNERS			
	As soon as practicable after obtaining monitoring results shown:	A I D		Net trippered
1 (a)	(a) an exceedance of any relevant criteria in Schedule 3, the Applicant must notify the affected landowners in writing of the exceedance, and provide regular monitoring results to each affected landowner until the development is again complying with the relevant criteria;	Annual Review 2020, 2021, 2022.	Evenodances reported in AERs and those reported to DRF did not result in inspect.	Not triggered
	and	Incident notifications to DPE dated 11 December 2023, 22 May 2023, 13 January 2023	Exceedances reported in AERs, and those reported to DPE did not result in impacts to neighbouring landholders.	
1 (b)	(b) an exceedance of any relevant air quality criteria in Schedule 3, the Applicant must send a copy of the NSW Health fact sheet entitled	Annual Review 2020, 2021, 2022.	non-processing terretrotters.	Not triggered
,	"Mine Dust and You" (as may be updated from time to time) to the affected landowners and current tenants of the land (including the	Incident notifications to DPE dated 11 December 2023, 22 May 2023, 13	Exceedances reported in AERs, and those reported to DPE did not result in impacts to	
	tenants of land which is not privately owned).	January 2023	neighbouring landholders. Incidents either a result of contamination or failed sample runs.	
NDEPEND	ENT REVIEW			
2	If an owner of privately-owned land considers the development to be exceeding the relevant criteria in Schedule 3, then he/she may ask			Not triggered
	the Secretary in writing for an independent review of the impacts of the development on his/her land.	Annual Review 2020, 2021, 2022.		
		Site interview - W Beattie	No such request made during the audit period as reported in AERs and confirmed via site int	
3	If the Secretary is satisfied that an independent review is warranted, then within 2 months of the Secretary's decision the Applicant must:	Annual Review 2020, 2021, 2022. Site interview - W Beattie	No such assurationed administration and the socied as assurated in AFRs and as affirmed tip site into	Not triggered
3 (a)	(a) commission a suitably qualified, experienced and independent person, whose appointment has been approved by the Secretary, to:	Site lifterview - W beattle	No such request made during the audit period as reported in AERs and confirmed via site int	Not triggered
- (-)	• consult with the landowner to determine his/her concerns;			
	• conduct monitoring to determine whether the development is complying with the relevant criteria in Schedule 3; and			
	• if the development is not complying with these criteria then identify measures that could be implemented to ensure compliance with the relevant criteria; and	Annual Review 2020, 2021, 2022.		
	the relevant criteria, and	Site interview - W Beattie	No such request made during the audit period as reported in AERs and confirmed via site int	
3 (b)	(b) give the Secretary and landowner a copy of the independent review.	Annual Review 2020, 2021, 2022.		Not triggered
CHEDINE	ENVIRONMENTAL MANAGEMENT, MONITORING, AUDITING AND REPORTING	Site interview - W Beattie	No such request made during the audit period as reported in AERs and confirmed via site int	
	ENVIRONMENTAL MANAGEMENT, MONITORING, ADDITING AND REPORTING ENTAL MANAGEMENT STRATEGY (Incorporates OEH GTA)			
1	If the Secretary requires, the Applicant must prepare an Environmental Management Strategy for the development to the satisfaction of		Previous IEA confirm Secretary approval of the document.	Compliant
	the Secretary. This strategy must:		Sighted correspondence to DPE dated 30 June 2023 issuing confirm no updates to the plan	
		Lynwood Quarry Environmental Management Strategy (Feb 2020)	following submission of the 2022 Annual Review.	
1 (a)	(a) be submitted to the Secretary for approval within 6 months of the Secretary requiring preparation of the strategy by notice to the	Previous IEA 2020	Original approval outside of audit period, considered compliant on basis of findings of previo	Compliant
1 (b)	Applicant; (b) provide the strategic framework for the environmental management of the development;	Lynwood Quarry Environmental Management Strategy (Feb 2020) -	Tonginal approval outside of addit period, considered compilant on pass of infulligs of previo	Compliant
v - /		Section 4		
1 (c)	(c) identify the statutory approvals that apply to the development;	Lynwood Quarry Environmental Management Strategy (Feb 2020) -		Compliant
		Section 3		
1 (d)	(d) describe the role, responsibility, authority and accountability of all key personnel involved in the environmental management of the	Lynwood Quarry Environmental Management Strategy (Feb 2020) -		Compliant
4/3	development;	Section 6.1		Constitute
1 (e)	(e) describe the procedures that would be implemented to:	Ivaviand Outray Environmental Management Strategy (Feb 2020)		Compliant
	keep the local community and relevant agencies informed about the operation and environmental performance of the development;	Lynwood Quarry Environmental Management Strategy (Feb 2020) Lynwood Quarry Environmental Management Strategy (Feb 2020) -		Compliant
	and the development,	Section 6		
	receive, handle, respond to, and record complaints;	Lynwood Quarry Environmental Management Strategy (Feb 2020) -		Compliant
		Section 6.4		
	• resolve any disputes that may arise during the course of the development;	Lynwood Quarry Environmental Management Strategy (Feb 2020) -		Compliant
		Section 6.4.2		
	• respond to any non-compliance; and	Lynwood Quarry Environmental Management Strategy (Feb 2020) -		Compliant
	A recoord to emergencies; and	Section 6 and 7		Compliant
	• respond to emergencies; and	Lynwood Quarry Environmental Management Strategy (Feb 2020) -		Compliant
	(f) include:	Section 6.7		Compliant
1 (f)		Lynwood Quarry Environmental Management Strategy (Feb 2020) -		
1 (f)	copies of any strategies, plans and programs approved under the conditions of this development consent; and			
1 (f)	copies of any strategies, plans and programs approved under the conditions of this development consent; and a clear plan depicting all the monitoring required to be carried out under the conditions of this consent.	Section 5.2		Consilient
	 copies of any strategies, plans and programs approved under the conditions of this development consent; and a clear plan depicting all the monitoring required to be carried out under the conditions of this consent. The Applicant must implement any Environmental Management Strategy as approved from time to time by the Secretary. 		EMS appears implemented as appropriate	Compliant
	copies of any strategies, plans and programs approved under the conditions of this development consent; and a clear plan depicting all the monitoring required to be carried out under the conditions of this consent.	Section 5.2	EMS appears implemented as appropriate	Compliant

1A (a)	(a) consult with the relevant public authority prior to submitting the required document to the Secretary for approval;	Air Quality Management Plan (Aug 2023) Aboriginal Heritage Management Plan (November 2022)	Revisions of management plans during the audit period describe the consultation undertaken during their preparation. Sighted numerous letters/emails involving consultation with government agencies regarding conditions relevant to their jurisdiction, plans /programs/ strategies relevant to their scope.	Compliant
1A (b)	(b) submit evidence of this consultation as part of the relevant document;	Air Quality Management Plan (Aug 2023) Aboriginal Heritage Management Plan (November 2022) Site interviews - D. Egeonu	Air Quality Management Plan (Aug 2023) - consultation with agencies outlined in Section 2 Aboriginal Heritage Management Plan (November 2022) - consultation with agencies outlined in Section 1.4 Neither management plan identifies feedback from consulted agencies nor was the auditor made aware during site interviews that feedback had been received.	Compliant
1A (c)	(c) describe how matters raised by the authority have been addressed and any matters not resolved; and	Air Quality Management Plan (Aug 2023) Aboriginal Heritage Management Plan (November 2022) Site interviews - D. Egeonu	Air Quality Management Plan (Aug 2023) - consultation with agencies outlined in Section 2.3 outlies matters raised by EPA during reporting period and notes comments have been addressed in the revised document. Aboriginal Heritage Management Plan (November 2022) - consultation with agencies outlined in Section 1.4 - No feedback from agencies identified nor was the auditor made aware during site interviews that feedback had been received.	
	(d) include details of any outstanding issues raised by the authority and an explanation of disagreement between any public authority and the Applicant.	Air Quality Management Plan (Aug 2023) Aboriginal Heritage Management Plan (Nov 2022) Site interviews - D. Egeonu	No outstanding matters identified in management plans updated during the audit period or identified via site interviews.	Compliant
MANAGEMI 2	The Applicant must ensure that the Management Plans required under this consent are prepared in accordance with any relevant			
2 (a)	guidelines, and include: (a) detailed baseline data;	Note. Air Quality Management Plan (Aug 2023) Aboriginal Heritage Management Plan (Nov2022) Lynwood Quarry Environmental Management Strategy (Feb 2020) Rehabilitation and Landscape Management Plan (2018) (RLMP). Noise Management Plan (Feb 2023) Blast Management Plan (Feb 2020) Water Management Plan (November 2020)		Compliant
2 (b)	(b) a description of: • the relevant statutory requirements (including any relevant approval, licence or lease conditions); • any relevant limits or performance measures/criteria; and • the specific performance indicators that are proposed to be used to judge the performance of, or guide the implementation of, the development or any management measures;	Air Quality Management Plan (Aug 2023) Aboriginal Heritage Management Plan (Nov2022) Lynwood Quarry Environmental Management Strategy (Feb 2020) Rehabilitation and Landscape Management Plan (2018) (RLMP). Noise Management Plan (Feb 2023) Blast Management Plan (Feb 2020) Water Management Plan (November 2020)		Compliant
2 (c)		Air Quality Management Plan (Aug 2023) Aboriginal Heritage Management Plan (Nov2022) Lynwood Quarry Environmental Management Strategy (Feb 2020) Rehabilitation and Landscape Management Plan (2018) (RLMP). Noise Management Plan (Feb 2023) Blast Management Plan (Feb 2020) Water Management Plan (November 2020)		Compliant
2 (d)	(d) a program to monitor and report on the: • impacts and environmental performance of the development; and • effectiveness of any management measures (see (c) above)	Air Quality Management Plan (Aug 2023) Aboriginal Heritage Management Plan (Nov2022) Lynwood Quarry Environmental Management Strategy (Feb 2020) Rehabilitation and Landscape Management Plan (2018) (RLMP). Noise Management Plan (Feb 2023) Blast Management Plan (Feb 2020) Water Management Plan (November 2020)		Compliant
2 (e)		Air Quality Management Plan (Aug 2023) Aboriginal Heritage Management Plan (Nov2022) Lynwood Quarry Environmental Management Strategy (Feb 2020) Rehabilitation and Landscape Management Plan (2018) (RLMP). Noise Management Plan (Feb 2023) Blast Management Plan (Feb 2020) Water Management Plan (November 2020)		Compliant

2 (f)	(f) a program to investigate and implement ways to improve the environmental performance of the development over time;	Air Quality Management Plan (Aug 2023)		Compliant	
. ,	,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,	Aboriginal Heritage Management Plan (Nov2022)			
		Lynwood Quarry Environmental Management Strategy (Feb 2020)			
		Rehabilitation and Landscape Management Plan (2018) (RLMP).			
		Noise Management Plan (Feb 2023)			
		Blast Management Plan (Feb 2020)			
		Water Management Plan (November 2020)			
2 ()				0 1: .	
2 (g)	(g) a protocol for managing and reporting any:	Air Quality Management Plan (Aug 2023)		Compliant	
	• incidents;	Aboriginal Heritage Management Plan (Nov2022)			
	• complaints;	Lynwood Quarry Environmental Management Strategy (Feb 2020)			
	non-compliances with statutory requirements; and	Rehabilitation and Landscape Management Plan (2018) (RLMP).			
	exceedances of the impact assessment criteria and/or performance criteria; and				
		Noise Management Plan (Feb 2023)			
		Blast Management Plan (Feb 2020)			
		Water Management Plan (November 2020)			
				- "	
2 (h)	(h) a protocol for periodic review of the plan.	Air Quality Management Plan (Aug 2023)		Compliant	
		Aboriginal Heritage Management Plan (Nov2022)			
		Lynwood Quarry Environmental Management Strategy (Feb 2020)			
		, , ,			
1		Rehabilitation and Landscape Management Plan (2018) (RLMP).			1
		Noise Management Plan (Feb 2023)			
1		Blast Management Plan (Feb 2020)			1
		Water Management Plan (November 2020)			
1		ייימנכי ייומוומקכוווכוונ רומוו (ייטייבוווטכו בטבט)			1
1					1
	Note: The Secretary may waive some of these requirements if they are unnecessary or unwarranted for particular management plans.				
L		Note.		<u> </u>	<u> </u>
3	Prior to approval of management plans required under Schedule 3, all existing management plans, monitoring programs, strategies,				
_	programs, protocols, etc approved as at the date of approval of Modification 4 must continue to have full force and effect, and may be				
1	revised under the requirements of condition 5 below as if subject to the conditions of this consent that applied prior to the approval of				
	Modification 4, or otherwise with the approval of the Secretary.				
		Note.			
UPDATING 8	s STAGING SUBMISSION OF STRATEGIES, PLANS OR PROGRAMS				
4	To ensure the strategies, plans or programs under this consent are updated on a regular basis, and that they incorporate any appropriate				
· .	mitigation measures to improve the environmental performance of the development, the Applicant may at any time submit revised				
1	strategies, plans or programs to the Secretary for approval. With the agreement of the Secretary, the Applicant may also submit newseu				
		Note.			
	trategy plan or program required by this consent on a staged basis	note.		-	
	With the agreement of the Secretary, the Applicant may revise any strategy, plan or program approved under this consent without	Note			
	consulting with all the parties nominated under the applicable conditions of consent.	Note.			
	consulting with all the parties nominated under the applicable conditions of consent. Notes: • While any strategy, plan or program may be submitted on a progressive basis, the Applicant will need to ensure that the existing	Note.			
	consulting with all the parties nominated under the applicable conditions of consent. Notes: • While any strategy, plan or program may be submitted on a progressive basis, the Applicant will need to ensure that the existing operations on site are covered by suitable strategies, plans or programs at all times.	Note.			
	consulting with all the parties nominated under the applicable conditions of consent. Notes: • While any strategy, plan or program may be submitted on a progressive basis, the Applicant will need to ensure that the existing	Note.			
	consulting with all the parties nominated under the applicable conditions of consent. Notes: • While any strategy, plan or program may be submitted on a progressive basis, the Applicant will need to ensure that the existing operations on site are covered by suitable strategies, plans or programs at all times.				
	consulting with all the parties nominated under the applicable conditions of consent. Notes: • While any strategy, plan or program may be submitted on a progressive basis, the Applicant will need to ensure that the existing operations on site are covered by suitable strategies, plans or programs at all times. • If the submission of any strategy, plan or program is to be staged, then the relevant strategy, plan or program must clearly describe the specific stage to which the strategy, plan or program applies, the relationship of this stage to any future stages, and the trigger for undation the strategy, plan or program.	Note.			
	consulting with all the parties nominated under the applicable conditions of consent. Notes: • While any strategy, plan or program may be submitted on a progressive basis, the Applicant will need to ensure that the existing operations on site are covered by suitable strategies, plans or programs at all times. • If the submission of any strategy, plan or program is to be staged, then the relevant strategy, plan or program must clearly describe the specific stage to which the strategy, plan or program applies, the relationship of this stage to any future stages, and the trigger for undation the strategy, plan or program. STRATEGIES, PLANS & PROGRAMS				
	consulting with all the parties nominated under the applicable conditions of consent. Notes: • While any strategy, plan or program may be submitted on a progressive basis, the Applicant will need to ensure that the existing operations on site are covered by suitable strategies, plans or programs at all times. • If the submission of any strategy, plan or program is to be staged, then the relevant strategy, plan or program must clearly describe the specific stage to which the strategy, plan or program applies, the relationship of this stage to any future stages, and the trigger for undation the strategy, plan or program.			Non-compliant	
	consulting with all the parties nominated under the applicable conditions of consent. Notes: • While any strategy, plan or program may be submitted on a progressive basis, the Applicant will need to ensure that the existing operations on site are covered by suitable strategies, plans or programs at all times. • If the submission of any strategy, plan or program is to be staged, then the relevant strategy, plan or program must clearly describe the specific stage to which the strategy, plan or program applies, the relationship of this stage to any future stages, and the trigger for undation the strategy, plan or program. STRATEGIES, PLANS & PROGRAMS		Sighted correspondence between Holcim and DPE confirm reviews of Management Plans	Non-compliant	
	consulting with all the parties nominated under the applicable conditions of consent. Notes: • While any strategy, plan or program may be submitted on a progressive basis, the Applicant will need to ensure that the existing operations on site are covered by suitable strategies, plans or programs at all times. • If the submission of any strategy, plan or program is to be staged, then the relevant strategy, plan or program must clearly describe the specific stage to which the strategy, plan or program applies, the relationship of this stage to any future stages, and the trigger for undation the strategy, plan or program. STRATEGIES, PLANS & PROGRAMS Within 3 months of the submission of an:	Note.		Non-compliant	
	consulting with all the parties nominated under the applicable conditions of consent. Notes: • While any strategy, plan or program may be submitted on a progressive basis, the Applicant will need to ensure that the existing operations on site are covered by suitable strategies, plans or programs at all times. • If the submission of any strategy, plan or program is to be staged, then the relevant strategy, plan or program must clearly describe the specific stage to which the strategy, plan or program applies, the relationship of this stage to any future stages, and the trigger for undation the strategy, plan or program. STRATEGIES, PLANS & PROGRAMS Within 3 months of the submission of an: (a) incident report under condition 8 below;	Note. Annual Review 2020, 2021, 2022.	following annual reviews.	Non-compliant	
	consulting with all the parties nominated under the applicable conditions of consent. Notes: • While any strategy, plan or program may be submitted on a progressive basis, the Applicant will need to ensure that the existing operations on site are covered by suitable strategies, plans or programs at all times. If the submission of any strategy, plan or program is to be staged, then the relevant strategy, plan or program must clearly describe the specific stage to which the strategy, plan or program applies, the relationship of this stage to any future stages, and the trigger for undation the strategy plan or program. STRATEGIES, PLANS & PROGRAMS Within 3 months of the submission of an: (a) incident report under condition 8 below; (b) Annual Review under condition 10 below; (c) audit report under condition 11 below; and	Annual Review 2020, 2021, 2022. Incident notifications to DPE dated 11 December 2023, 22 May 2023, 13	following annual reviews. No evidence sighted of review of plans following incidents or previous audit.	Non-compliant	
	consulting with all the parties nominated under the applicable conditions of consent. Notes: • While any strategy, plan or program may be submitted on a progressive basis, the Applicant will need to ensure that the existing operations on site are covered by suitable strategies, plans or programs at all times. • If the submission of any strategy, plan or program is to be staged, then the relevant strategy, plan or program must clearly describe the specific stage to which the strategy, plan or program applies, the relationship of this stage to any future stages, and the trigger for undation the strategy, plan or program. • STRATEGIES, PLANS & PROGRAMS Within 3 months of the submission of an: (a) incident report under condition 8 below; (b) Annual Review under condition 10 below; (c) audit report under condition 11 below; and (d) any modifications to this consent,	Note. Annual Review 2020, 2021, 2022.	following annual reviews. No evidence sighted of review of plans following incidents or previous audit. 2020 Annual Review notes an IEA Action plan is available as Appendix 3 of the document	Non-compliant	
	consulting with all the parties nominated under the applicable conditions of consent. Notes: • While any strategy, plan or program may be submitted on a progressive basis, the Applicant will need to ensure that the existing operations on site are covered by suitable strategies, plans or programs at all times. If the submission of any strategy, plan or program is to be staged, then the relevant strategy, plan or program must clearly describe the specific stage to which the strategy, plan or program applies, the relationship of this stage to any future stages, and the trigger for undation the strategy plan or program. STRATEGIES, PLANS & PROGRAMS Within 3 months of the submission of an: (a) incident report under condition 8 below; (b) Annual Review under condition 10 below; (c) audit report under condition 11 below; and	Annual Review 2020, 2021, 2022. Incident notifications to DPE dated 11 December 2023, 22 May 2023, 13	following annual reviews. No evidence sighted of review of plans following incidents or previous audit.	Non-compliant	NC12
	consulting with all the parties nominated under the applicable conditions of consent. Notes: • While any strategy, plan or program may be submitted on a progressive basis, the Applicant will need to ensure that the existing operations on site are covered by suitable strategies, plans or programs at all times. • If the submission of any strategy, plan or program is to be staged, then the relevant strategy, plan or program must clearly describe the specific stage to which the strategy, plan or program applies, the relationship of this stage to any future stages, and the trigger for undation the strategy, plan or program. • STRATEGIES, PLANS & PROGRAMS Within 3 months of the submission of an: (a) incident report under condition 8 below; (b) Annual Review under condition 10 below; (c) audit report under condition 11 below; and (d) any modifications to this consent,	Annual Review 2020, 2021, 2022. Incident notifications to DPE dated 11 December 2023, 22 May 2023, 13 January 2023	following annual reviews. No evidence sighted of review of plans following incidents or previous audit. 2020 Annual Review notes an IEA Action plan is available as Appendix 3 of the document	Non-compliant	NC12
	consulting with all the parties nominated under the applicable conditions of consent. Notes: • While any strategy, plan or program may be submitted on a progressive basis, the Applicant will need to ensure that the existing operations on site are covered by suitable strategies, plans or programs at all times. • If the submission of any strategy, plan or program is to be staged, then the relevant strategy, plan or program must clearly describe the specific stage to which the strategy, plan or program applies, the relationship of this stage to any future stages, and the trigger for undation the strategy, plan or program. STRATEGIES, PLANS & PROGRAMS Within 3 months of the submission of an: (a) incident report under condition 8 below; (b) Annual Review under condition 10 below; (c) audit report under condition 11 below; and (d) any modifications to this consent, the Applicant must review, and if necessary revise, the strategies, plans, and programs required under this consent, to the satisfaction of the Secretary.	Annual Review 2020, 2021, 2022. Incident notifications to DPE dated 11 December 2023, 22 May 2023, 13 January 2023	following annual reviews. No evidence sighted of review of plans following incidents or previous audit. 2020 Annual Review notes an IEA Action plan is available as Appendix 3 of the document	Non-compliant	NC12
5	consulting with all the parties nominated under the applicable conditions of consent. Notes: • While any strategy, plan or program may be submitted on a progressive basis, the Applicant will need to ensure that the existing operations on site are covered by suitable strategies, plans or programs at all times. If the submission of any strategy, plan or program is to be staged, then the relevant strategy, plan or program must clearly describe the specific stage to which the strategy, plan or program applies, the relationship of this stage to any future stages, and the trigger for undation the strategy plan or program. STRATEGIES, PLANS & PROGRAMS Within 3 months of the submission of an: (a) incident report under condition 8 below; (b) Annual Review under condition 10 below; (c) audit report under condition 11 below; and (d) any modifications to this consent, the Applicant must review, and if necessary revise, the strategies, plans, and programs required under this consent, to the satisfaction of the Secretary. Note: This is to ensure the strategies, plans and programs are updated on a regular basis, and incorporate any recommended measures to	Annual Review 2020, 2021, 2022. Incident notifications to DPE dated 11 December 2023, 22 May 2023, 13 January 2023 Site interviews D. Egeonu	following annual reviews. No evidence sighted of review of plans following incidents or previous audit. 2020 Annual Review notes an IEA Action plan is available as Appendix 3 of the document	Non-compliant	NC12
5	consulting with all the parties nominated under the applicable conditions of consent. Notes: • While any strategy, plan or program may be submitted on a progressive basis, the Applicant will need to ensure that the existing operations on site are covered by suitable strategies, plans or programs at all times. • If the submission of any strategy, plan or program is to be staged, then the relevant strategy, plan or program must clearly describe the specific stage to which the strategy, plan or program applies, the relationship of this stage to any future stages, and the trigger for undation the strategy, plan or program. *STRATEGIES, PLANS & PROGRAMS Within 3 months of the submission of an: (a) incident report under condition 8 below; (b) Annual Review under condition 10 below; (c) audit report under condition 11 below; and (d) any modifications to this consent, the Applicant must review, and if necessary revise, the strategies, plans, and programs required under this consent, to the satisfaction of the Applicant must review, and if necessary revise, the strategies, plans, and programs required any recommended measures to improve the environmental performance of the development.	Annual Review 2020, 2021, 2022. Incident notifications to DPE dated 11 December 2023, 22 May 2023, 13 January 2023 Site interviews D. Egeonu	following annual reviews. No evidence sighted of review of plans following incidents or previous audit. 2020 Annual Review notes an IEA Action plan is available as Appendix 3 of the document	Non-compliant	NC12
5	consulting with all the parties nominated under the applicable conditions of consent. Notes: • While any strategy, plan or program may be submitted on a progressive basis, the Applicant will need to ensure that the existing operations on site are covered by suitable strategies, plans or programs at all times. • If the submission of any strategy, plan or program is to be staged, then the relevant strategy, plan or program must clearly describe the specific stage to which the strategy, plan or program applies, the relationship of this stage to any future stages, and the trigger for undation the strategy alan or program. • TRATEGIES, PLANS & PROGRAMS Within 3 months of the submission of an: (a) incident report under condition 8 below; (b) Annual Review under condition 10 below; (c) audit report under condition 11 below; and (d) any modifications to this consent, the Applicant must review, and if necessary revise, the strategies, plans, and programs required under this consent, to the satisfaction of the Applicant must review, and if necessary revise, the strategies, plans, and programs required under this consent, to the satisfaction of the Applicant must review, and if necessary revise, the strategies, plans, and incorporate any recommended measures to improve the environmental performance of the development. **ANAGEMENT** The Applicant must assess and manage development-related risks to ensure that there are no exceedances of the criteria and/or	Annual Review 2020, 2021, 2022. Incident notifications to DPE dated 11 December 2023, 22 May 2023, 13 January 2023 Site interviews D. Egeonu Note.	following annual reviews. No evidence sighted of review of plans following incidents or previous audit. 2020 Annual Review notes an IEA Action plan is available as Appendix 3 of the document	Non-compliant	NC12
5	consulting with all the parties nominated under the applicable conditions of consent. Notes: • While any strategy, plan or program may be submitted on a progressive basis, the Applicant will need to ensure that the existing operations on site are covered by suitable strategies, plans or programs at all times. • If the submission of any strategy, plan or program is to be staged, then the relevant strategy, plan or program must clearly describe the specific stage to which the strategy, plan or program applies, the relationship of this stage to any future stages, and the trigger for undation the strategy plan or program applies, the relationship of this stage to any future stages, and the trigger for undation the strategy plan or program applies, the relationship of this stage to any future stages, and the trigger for undation the strategy plan or program applies, the relationship of this stage to any future stages, and the trigger for undation the strategies, plans of this stage to any future stages, and the trigger for undation the strategies, plans of this stage to any future stages, and the trigger for undation the strategies, plans and treview under condition 10 below; (b) Annual Review under condition 10 below; (c) audit report under condition 10 below; and (d) any modifications to this consent, the Applicant must review, and if necessary revise, the strategies, plans, and programs required under this consent, to the satisfaction of the Correction. Note: This is to ensure the strategies, plans and programs are updated on a regular basis, and incorporate any recommended measures to improve the environmental performance of the development. ANAGEMENT The Applicant must assess and manage development-related risks to ensure that there are no exceedances of the criteria and/or performance measures in Schedule 3. Any exceedance of these criteria and/or performance measures constitutes a breach of this consent	Annual Review 2020, 2021, 2022. Incident notifications to DPE dated 11 December 2023, 22 May 2023, 13 January 2023 Site interviews D. Egeonu Note.	following annual reviews. No evidence sighted of review of plans following incidents or previous audit. 2020 Annual Review notes an IEA Action plan is available as Appendix 3 of the document	Non-compliant	NC12
5	consulting with all the parties nominated under the applicable conditions of consent. Notes: • While any strategy, plan or program may be submitted on a progressive basis, the Applicant will need to ensure that the existing operations on site are covered by suitable strategies, plans or programs at all times. If the submission of any strategy, plan or program is to be staged, then the relevant strategy, plan or program must clearly describe the specific stage to which the strategy, plan or program applies, the relationship of this stage to any future stages, and the trigger for undation the strategy plan or program. STRATEGIES, PLANS & PROGRAMS Within 3 months of the submission of an: (a) incident report under condition 8 below; (b) Annual Review under condition 10 below; (c) audit report under condition 11 below; and (d) any modifications to this consent, the Applicant must review, and if necessary revise, the strategies, plans, and programs required under this consent, to the satisfaction of the Coercian. Note: This is to ensure the strategies, plans and programs are updated on a regular basis, and incorporate any recommended measures to improve the environmental performance of the development. ANAGEMENT The Applicant must assess and manage development-related risks to ensure that there are no exceedances of the criteria and/or performance measures in Schedule 3. Any exceedance of these criteria and/or performance measures constitutes a breach of this consent and may be subject to penalty or offence provisions under the EP&A Act or EP&A Regulation.	Annual Review 2020, 2021, 2022. Incident notifications to DPE dated 11 December 2023, 22 May 2023, 13 January 2023 Site interviews D. Egeonu Note.	following annual reviews. No evidence sighted of review of plans following incidents or previous audit. 2020 Annual Review notes an IEA Action plan is available as Appendix 3 of the document	Non-compliant	NC12
5	consulting with all the parties nominated under the applicable conditions of consent. Notes: • While any strategy, plan or program may be submitted on a progressive basis, the Applicant will need to ensure that the existing operations on site are covered by suitable strategies, plans or programs at all times. • If the submission of any strategy, plan or program is to be staged, then the relevant strategy, plan or program must clearly describe the specific stage to which the strategy, plan or program applies, the relationship of this stage to any future stages, and the trigger for undation the strategy plan or program applies, the relationship of this stage to any future stages, and the trigger for undation the strategy plan or program applies, the relationship of this stage to any future stages, and the trigger for undation the strategy plan or program applies, the relationship of this stage to any future stages, and the trigger for undation the strategies, plans of this stage to any future stages, and the trigger for undation the strategies, plans of this stage to any future stages, and the trigger for undation the strategies, plans and treview under condition 10 below; (b) Annual Review under condition 10 below; (c) audit report under condition 10 below; and (d) any modifications to this consent, the Applicant must review, and if necessary revise, the strategies, plans, and programs required under this consent, to the satisfaction of the Correction. Note: This is to ensure the strategies, plans and programs are updated on a regular basis, and incorporate any recommended measures to improve the environmental performance of the development. ANAGEMENT The Applicant must assess and manage development-related risks to ensure that there are no exceedances of the criteria and/or performance measures in Schedule 3. Any exceedance of these criteria and/or performance measures constitutes a breach of this consent	Annual Review 2020, 2021, 2022. Incident notifications to DPE dated 11 December 2023, 22 May 2023, 13 January 2023 Site interviews D. Egeonu Note.	following annual reviews. No evidence sighted of review of plans following incidents or previous audit. 2020 Annual Review notes an IEA Action plan is available as Appendix 3 of the document	Non-compliant	NC12
ADAPTIVE N	consulting with all the parties nominated under the applicable conditions of consent. Notes: • While any strategy, plan or program may be submitted on a progressive basis, the Applicant will need to ensure that the existing operations on site are covered by suitable strategies, plans or programs at all times. • If the submission of any strategy, plan or program is to be staged, then the relevant strategy, plan or program must clearly describe the specific stage to which the strategy, plan or program applies, the relationship of this stage to any future stages, and the trigger for undation the strategy plan or program. • If the submission of any strategy, plan or program applies, the relationship of this stage to any future stages, and the trigger for undation the strategy. • If the submission of any strategy, plan or program applies, the relationship of this stage to any future stages, and the trigger for undation the strategy. • If the submission of any strategy, plan or program applies, the relationship of this stage to any future stages, and the trigger for undation the strategy. • If the submission of any strategy, plans or program applies, the relationship of this stage to any future stages, and the trigger for undation the strategy. • If the submission of any strategy, plans or program applies, the relationship of this stage to any future stages, and the trigger for undation the strategies, plans of this stage to any future stages, and the trigger for undation the strategies of the submission of any stages to any future stages, and the trigger for undation the strategies, plans and programs are updated on a regular basis, and incorporate any recommended measures to improve the environmental performance of the development. • If the submission of any strategy, plans and programs are updated on a regular basis, and incorporate any recommended measures to improve the environmental performance of the development. • If the submission of any strategy, plans and programs are updated on a regular basis, a	Annual Review 2020, 2021, 2022. Incident notifications to DPE dated 11 December 2023, 22 May 2023, 13 January 2023 Site interviews D. Egeonu Note. Note.	following annual reviews. No evidence sighted of review of plans following incidents or previous audit. 2020 Annual Review notes an IEA Action plan is available as Appendix 3 of the document however is notes local funding initiatives not IEA actions		NC12
5	consulting with all the parties nominated under the applicable conditions of consent. Notes: • While any strategy, plan or program may be submitted on a progressive basis, the Applicant will need to ensure that the existing operations on site are covered by suitable strategies, plans or programs at all times. If the submission of any strategy, plan or program is to be staged, then the relevant strategy, plan or program must clearly describe the specific stage to which the strategy, plan or program applies, the relationship of this stage to any future stages, and the trigger for undation the strategy plan or program. STRATEGIES, PLANS & PROGRAMS Within 3 months of the submission of an: (a) incident report under condition 8 below; (b) Annual Review under condition 10 below; (c) audit report under condition 11 below; and (d) any modifications to this consent, the Applicant must review, and if necessary revise, the strategies, plans, and programs required under this consent, to the satisfaction of the Coercian. Note: This is to ensure the strategies, plans and programs are updated on a regular basis, and incorporate any recommended measures to improve the environmental performance of the development. ANAGEMENT The Applicant must assess and manage development-related risks to ensure that there are no exceedances of the criteria and/or performance measures in Schedule 3. Any exceedance of these criteria and/or performance measures constitutes a breach of this consent and may be subject to penalty or offence provisions under the EP&A Act or EP&A Regulation.	Annual Review 2020, 2021, 2022. Incident notifications to DPE dated 11 December 2023, 22 May 2023, 13 January 2023 Site interviews D. Egeonu Note. Note. Note. Annual Review 2020, 2021, 2022.	following annual reviews. No evidence sighted of review of plans following incidents or previous audit. 2020 Annual Review notes an IEA Action plan is available as Appendix 3 of the document however is notes local funding initiatives not IEA actions Sighted AERs and DPE incident notification letters for the audit period, each of which shows		NC12
ADAPTIVE N	consulting with all the parties nominated under the applicable conditions of consent. Notes: • While any strategy, plan or program may be submitted on a progressive basis, the Applicant will need to ensure that the existing operations on site are covered by suitable strategies, plans or programs at all times. • If the submission of any strategy, plan or program is to be staged, then the relevant strategy, plan or program must clearly describe the specific stage to which the strategy, plan or program applies, the relationship of this stage to any future stages, and the trigger for undation the strategy plan or program. • If the submission of any strategy, plan or program applies, the relationship of this stage to any future stages, and the trigger for undation the strategy. • If the submission of any strategy, plan or program applies, the relationship of this stage to any future stages, and the trigger for undation the strategy. • If the submission of any strategy, plan or program applies, the relationship of this stage to any future stages, and the trigger for undation the strategy. • If the submission of any strategy, plans or program applies, the relationship of this stage to any future stages, and the trigger for undation the strategy. • If the submission of any strategy, plans or program applies, the relationship of this stage to any future stages, and the trigger for undation the strategies, plans of this stage to any future stages, and the trigger for undation the strategies of the submission of any stages to any future stages, and the trigger for undation the strategies, plans and programs are updated on a regular basis, and incorporate any recommended measures to improve the environmental performance of the development. • If the submission of any strategy, plans and programs are updated on a regular basis, and incorporate any recommended measures to improve the environmental performance of the development. • If the submission of any strategy, plans and programs are updated on a regular basis, a	Annual Review 2020, 2021, 2022. Incident notifications to DPE dated 11 December 2023, 22 May 2023, 13 January 2023 Site interviews D. Egeonu Note. Note. Note. Annual Review 2020, 2021, 2022. Incident notifications to DPE dated 11 December 2023, 22 May 2023, 13	following annual reviews. No evidence sighted of review of plans following incidents or previous audit. 2020 Annual Review notes an IEA Action plan is available as Appendix 3 of the document however is notes local funding initiatives not IEA actions Sighted AERs and DPE incident notification letters for the audit period, each of which shows actions taken to minimise/control/report on exceedances. Proportionate to the exceedance		NC12
6 (a)	consulting with all the parties nominated under the applicable conditions of consent. Notes: • While any strategy, plan or program may be submitted on a progressive basis, the Applicant will need to ensure that the existing operations on site are covered by suitable strategies, plans or programs at all times. • If the submission of any strategy, plan or program is to be staged, then the relevant strategy, plan or program must clearly describe the specific stage to which the strategy, plan or program applies, the relationship of this stage to any future stages, and the trigger for undation the strategy, plan or program **STRATEGIES, PLANS & PROGRAMS** Within 3 months of the submission of an: (a) incident report under condition 8 below; (b) Annual Review under condition 10 below; (c) audit report under condition 11 below; and (d) any modifications to this consent, the Applicant must review, and if necessary revise, the strategies, plans, and programs required under this consent, to the satisfaction of the Consentant. **Note: This is to ensure the strategies, plans and programs are updated on a regular basis, and incorporate any recommended measures to improve the environmental performance of the development. **NANGEMENT** The Applicant must assess and manage development-related risks to ensure that there are no exceedances of the criteria and/or performance measures in Schedule 3. Any exceedance of these criteria and/or performance measures in Schedule 3. Any exceedance of these criteria and/or performance measures constitutes a breach of this consent and may be subject to penalty or offence provisions under the EP&A Act or EP&A Regulation. Where any exceedance of these criteria and/or performance measures has occurred, the Applicant must, at the earliest opportunity: take all reasonable and feasible measures to ensure that the exceedance ceases and does not recur;	Annual Review 2020, 2021, 2022. Incident notifications to DPE dated 11 December 2023, 22 May 2023, 13 January 2023 Site interviews D. Egeonu Note. Note. Note. Annual Review 2020, 2021, 2022.	following annual reviews. No evidence sighted of review of plans following incidents or previous audit. 2020 Annual Review notes an IEA Action plan is available as Appendix 3 of the document however is notes local funding initiatives not IEA actions Sighted AERs and DPE incident notification letters for the audit period, each of which shows actions taken to minimise/control/report on exceedances. Proportionate to the exceedance identified.	Compliant	NC12
6 (a)	consulting with all the parties nominated under the applicable conditions of consent. Notes: • While any strategy, plan or program may be submitted on a progressive basis, the Applicant will need to ensure that the existing operations on site are covered by suitable strategies, plans or programs at all times. • If the submission of any strategy, plan or program is to be staged, then the relevant strategy, plan or program must clearly describe the specific stage to which the strategy, plan or program applies, the relationship of this stage to any future stages, and the trigger for undation the strategy, plan or program applies, the relationship of this stage to any future stages, and the trigger for undational the strategy plan or program. **STRATEGIES, PLANS & PROGRAMS** Within 3 months of the submission of an: (a) incident report under condition 10 below; (b) Annual Review under condition 11 below; and (d) any modifications to this consent, the Applicant must review, and if necessary revise, the strategies, plans, and programs required under this consent, to the satisfaction of the Applicant must review, and if necessary revise, the strategies, plans, and programs required under this consent, to the satisfaction of the Applicant must assess and manage development. **NAGEMENT** The Applicant must assess and manage development-related risks to ensure that there are no exceedances of the criteria and/or performance measures in Schedule 3. Any exceedance of these criteria and/or performance measures constitutes a breach of this consent and may be subject to penalty or offence provisions under the FP&A Act or EP&A Regulation. Where any exceedance of these criteria and/or performance measures and does not recur; consider all reasonable and feasible options for remediation (where relevant) and submit a report to the Department describing those	Annual Review 2020, 2021, 2022. Incident notifications to DPE dated 11 December 2023, 22 May 2023, 13 January 2023 Site interviews D. Egeonu Note. Note. Note. Annual Review 2020, 2021, 2022. Incident notifications to DPE dated 11 December 2023, 22 May 2023, 13	following annual reviews. No evidence sighted of review of plans following incidents or previous audit. 2020 Annual Review notes an IEA Action plan is available as Appendix 3 of the document however is notes local funding initiatives not IEA actions Sighted AERs and DPE incident notification letters for the audit period, each of which shows actions taken to minimise/control/report on exceedances. Proportionate to the exceedance	Compliant	NC12
6 (a)	consulting with all the parties nominated under the applicable conditions of consent. Notes: • While any strategy, plan or program may be submitted on a progressive basis, the Applicant will need to ensure that the existing operations on site are covered by suitable strategies, plans or programs at all times. • If the submission of any strategy, plan or program is to be staged, then the relevant strategy, plan or program must clearly describe the specific stage to which the strategy, plan or program applies, the relationship of this stage to any future stages, and the trigger for undation the strategy, plan or program **STRATEGIES, PLANS & PROGRAMS** Within 3 months of the submission of an: (a) incident report under condition 8 below; (b) Annual Review under condition 10 below; (c) audit report under condition 11 below; and (d) any modifications to this consent, the Applicant must review, and if necessary revise, the strategies, plans, and programs required under this consent, to the satisfaction of the Consentant. **Note: This is to ensure the strategies, plans and programs are updated on a regular basis, and incorporate any recommended measures to improve the environmental performance of the development. **NANGEMENT** The Applicant must assess and manage development-related risks to ensure that there are no exceedances of the criteria and/or performance measures in Schedule 3. Any exceedance of these criteria and/or performance measures in Schedule 3. Any exceedance of these criteria and/or performance measures constitutes a breach of this consent and may be subject to penalty or offence provisions under the EP&A Act or EP&A Regulation. Where any exceedance of these criteria and/or performance measures has occurred, the Applicant must, at the earliest opportunity: take all reasonable and feasible measures to ensure that the exceedance ceases and does not recur;	Annual Review 2020, 2021, 2022. Incident notifications to DPE dated 11 December 2023, 22 May 2023, 13 January 2023 Site interviews D. Egeonu Note. Note. Note. Annual Review 2020, 2021, 2022. Incident notifications to DPE dated 11 December 2023, 22 May 2023, 13 January 2023 Annual Review 2020, 2021, 2022.	following annual reviews. No evidence sighted of review of plans following incidents or previous audit. 2020 Annual Review notes an IEA Action plan is available as Appendix 3 of the document however is notes local funding initiatives not IEA actions Sighted AERs and DPE incident notification letters for the audit period, each of which shows actions taken to minimise/control/report on exceedances. Proportionate to the exceedance identified. Sighted AERs and DPE incident notification letters for the audit period, each of which shows	Compliant	NC12
6 (a)	consulting with all the parties nominated under the applicable conditions of consent. Notes: • While any strategy, plan or program may be submitted on a progressive basis, the Applicant will need to ensure that the existing operations on site are covered by suitable strategies, plans or programs at all times. • If the submission of any strategy, plan or program is to be staged, then the relevant strategy, plan or program must clearly describe the specific stage to which the strategy, plan or program applies, the relationship of this stage to any future stages, and the trigger for undation the strategy, plan or program applies, the relationship of this stage to any future stages, and the trigger for undational the strategy plan or program. **STRATEGIES, PLANS & PROGRAMS** Within 3 months of the submission of an: (a) incident report under condition 10 below; (b) Annual Review under condition 11 below; and (d) any modifications to this consent, the Applicant must review, and if necessary revise, the strategies, plans, and programs required under this consent, to the satisfaction of the Acceptage. Note: This is to ensure the strategies, plans and programs are updated on a regular basis, and incorporate any recommended measures to improve the environmental performance of the development. **NAGEMENT** The Applicant must assess and manage development-related risks to ensure that there are no exceedances of the criteria and/or performance measures in Schedule 3. Any exceedance of these criteria and/or performance measures constitutes a breach of this consent and may be subject to penalty or offence provisions under the FP&A Act or EP&A Regulation. Where any exceedance of these criteria and/or performance measures and does not recur; consider all reasonable and feasible options for remediation (where relevant) and submit a report to the Department describing those	Annual Review 2020, 2021, 2022. Incident notifications to DPE dated 11 December 2023, 22 May 2023, 13 January 2023 Site interviews D. Egeonu Note. Note. Note. Annual Review 2020, 2021, 2022. Incident notifications to DPE dated 11 December 2023, 22 May 2023, 13 January 2023 Annual Review 2020, 2021, 2022. Incident notifications to DPE dated 11 December 2023, 22 May 2023, 13 January 2023 Annual Review 2020, 2021, 2022. Incident notifications to DPE dated 11 December 2023, 22 May 2023, 13	following annual reviews. No evidence sighted of review of plans following incidents or previous audit. 2020 Annual Review notes an IEA Action plan is available as Appendix 3 of the document however is notes local funding initiatives not IEA actions Sighted AERs and DPE incident notification letters for the audit period, each of which shows actions taken to minimise/control/report on exceedances. Proportionate to the exceedance identified. Sighted AERs and DPE incident notification letters for the audit period, each of which shows actions taken to minimise/control/report on exceedances. Proportionate to the exceedance	Compliant	NC12
6 (a)	consulting with all the parties nominated under the applicable conditions of consent. Notes: * While any strategy, plan or program may be submitted on a progressive basis, the Applicant will need to ensure that the existing operations on site are covered by suitable strategies, plans or programs at all times. * If the submission of any strategy, plan or program is to be staged, then the relevant strategy, plan or program must clearly describe the specific stage to which the strategy, plan or program applies, the relationship of this stage to any future stages, and the trigger for lundation the strategy, plan or program applies, the relationship of this stage to any future stages, and the trigger for lundation the strategy and a program applies. The relationship of this stage to any future stages, and the trigger for lundation the strategy and the trigger for lundation the strategy of the submission of an: (a) incident report under condition 8 below; (b) Annual Review under condition 10 below; (c) audit report under condition 11 below; and (d) any modifications to this consent, the Applicant must review, and if necessary revise, the strategies, plans, and programs required under this consent, to the satisfaction of shock-corestance. Note: This is to ensure the strategies, plans and programs are updated on a regular basis, and incorporate any recommended measures to improve the environmental performance of the development. NAGEMENT The Applicant must assess and manage development-related risks to ensure that there are no exceedances of the criteria and/or performance measures in Schedule 3. Any exceedance of these criteria and/or performance measures constitutes a breach of this consent and may be subject to penalty or offence provisions under the EP&A Act or EP&A Regulation. Where any exceedance of these criteria and/or performance measures has occurred, the Applicant must, at the earliest opportunity: take all reasonable and feasible measures to ensure that the exceedance ceases and does not recur;	Annual Review 2020, 2021, 2022. Incident notifications to DPE dated 11 December 2023, 22 May 2023, 13 January 2023 Site interviews D. Egeonu Note. Note. Note. Annual Review 2020, 2021, 2022. Incident notifications to DPE dated 11 December 2023, 22 May 2023, 13 January 2023 Annual Review 2020, 2021, 2022. Incident notifications to DPE dated 11 December 2023, 22 May 2023, 13 January 2024	following annual reviews. No evidence sighted of review of plans following incidents or previous audit. 2020 Annual Review notes an IEA Action plan is available as Appendix 3 of the document however is notes local funding initiatives not IEA actions Sighted AERs and DPE incident notification letters for the audit period, each of which shows actions taken to minimise/control/report on exceedances. Proportionate to the exceedance identified. Sighted AERs and DPE incident notification letters for the audit period, each of which shows actions taken to minimise/control/report on exceedances. Proportionate to the exceedance identified.	Compliant	NC12
6 (a)	consulting with all the parties nominated under the applicable conditions of consent. Notes: * While any strategy, plan or program may be submitted on a progressive basis, the Applicant will need to ensure that the existing operations on site are covered by suitable strategies, plans or programs at all times. * If the submission of any strategy, plan or program is to be staged, then the relevant strategy, plan or program must clearly describe the specific stage to which the strategy, plan or program applies, the relationship of this stage to any future stages, and the trigger for undation the strategy plan or program applies, the relationship of this stage to any future stages, and the trigger for undation the strategy plans a PROGRAMS Within 3 months of the submission of an: (a) incident report under condition 8 below; (b) Annual Review under condition 10 below; (c) audit report under condition 11 below; and (d) any modifications to this consent, the Applicant must review, and if necessary revise, the strategies, plans, and programs required under this consent, to the satisfaction of the Sacrataus. Note: This is to ensure the strategies, plans and programs are updated on a regular basis, and incorporate any recommended measures to improve the environmental performance of the development. ANAGEMENT The Applicant must assess and manage development-related risks to ensure that there are no exceedances of the criteria and/or performance measures in Schedule 3. Any exceedance of these criteria and/or performance measures constitutes a breach of this consent and may be subject to penalty or offence provisions under the EPBA Act or EPBA Regulation. Where any exceedance of these criteria and/or performance measures has occurred, the Applicant must, at the earliest opportunity: take all reasonable and feasible measures to ensure that the exceedance ceases and does not recur; consider all reasonable and feasible options for remediation (where relevant) and submit a report to the Department describing those	Annual Review 2020, 2021, 2022. Incident notifications to DPE dated 11 December 2023, 22 May 2023, 13 January 2023 Site interviews D. Egeonu Note. Note. Note. Annual Review 2020, 2021, 2022. Incident notifications to DPE dated 11 December 2023, 22 May 2023, 13 January 2023 Annual Review 2020, 2021, 2022. Incident notifications to DPE dated 11 December 2023, 22 May 2023, 13 January 2024 Site interviews - D. Egeonu	following annual reviews. No evidence sighted of review of plans following incidents or previous audit. 2020 Annual Review notes an IEA Action plan is available as Appendix 3 of the document however is notes local funding initiatives not IEA actions Sighted AERs and DPE incident notification letters for the audit period, each of which shows actions taken to minimise/control/report on exceedances. Proportionate to the exceedance identified. Sighted AERs and DPE incident notification letters for the audit period, each of which shows actions taken to minimise/control/report on exceedances. Proportionate to the exceedance	Compliant	NC12
6 (a)	consulting with all the parties nominated under the applicable conditions of consent. Notes: * While any strategy, plan or program may be submitted on a progressive basis, the Applicant will need to ensure that the existing operations on site are covered by suitable strategies, plans or programs at all times. * If the submission of any strategy, plan or program is to be staged, then the relevant strategy, plan or program must clearly describe the specific stage to which the strategy, plan or program applies, the relationship of this stage to any future stages, and the trigger for lundation the strategy, plan or program applies, the relationship of this stage to any future stages, and the trigger for lundation the strategy and a program applies. The relationship of this stage to any future stages, and the trigger for lundation the strategy and the trigger for lundation the strategy of the submission of an: (a) incident report under condition 8 below; (b) Annual Review under condition 10 below; (c) audit report under condition 11 below; and (d) any modifications to this consent, the Applicant must review, and if necessary revise, the strategies, plans, and programs required under this consent, to the satisfaction of shock-corestance. Note: This is to ensure the strategies, plans and programs are updated on a regular basis, and incorporate any recommended measures to improve the environmental performance of the development. NAGEMENT The Applicant must assess and manage development-related risks to ensure that there are no exceedances of the criteria and/or performance measures in Schedule 3. Any exceedance of these criteria and/or performance measures constitutes a breach of this consent and may be subject to penalty or offence provisions under the EP&A Act or EP&A Regulation. Where any exceedance of these criteria and/or performance measures has occurred, the Applicant must, at the earliest opportunity: take all reasonable and feasible measures to ensure that the exceedance ceases and does not recur;	Annual Review 2020, 2021, 2022. Incident notifications to DPE dated 11 December 2023, 22 May 2023, 13 January 2023 Site interviews D. Egeonu Note. Note. Note. Annual Review 2020, 2021, 2022. Incident notifications to DPE dated 11 December 2023, 22 May 2023, 13 January 2023 Annual Review 2020, 2021, 2022. Incident notifications to DPE dated 11 December 2023, 22 May 2023, 13 January 2024	following annual reviews. No evidence sighted of review of plans following incidents or previous audit. 2020 Annual Review notes an IEA Action plan is available as Appendix 3 of the document however is notes local funding initiatives not IEA actions Sighted AERs and DPE incident notification letters for the audit period, each of which shows actions taken to minimise/control/report on exceedances. Proportionate to the exceedance identified. Sighted AERs and DPE incident notification letters for the audit period, each of which shows actions taken to minimise/control/report on exceedances. Proportionate to the exceedance identified.	Compliant	NC12
6 (a) 6 (b) 6 (c)	consulting with all the parties nominated under the applicable conditions of consent. Notes: * While any strategy, plan or program may be submitted on a progressive basis, the Applicant will need to ensure that the existing operations on site are covered by suitable strategies, plans or programs at all times. * If the submission of any strategy, plan or program is to be staged, then the relevant strategy, plan or program must clearly describe the specific stage to which the strategy, plan or program applies, the relationship of this stage to any future stages, and the trigger for undation the strategy plan or program applies, the relationship of this stage to any future stages, and the trigger for undation the strategy plans a PROGRAMS Within 3 months of the submission of an: (a) incident report under condition 8 below; (b) Annual Review under condition 10 below; (c) audit report under condition 11 below; and (d) any modifications to this consent, the Applicant must review, and if necessary revise, the strategies, plans, and programs required under this consent, to the satisfaction of the Sacrataus. Note: This is to ensure the strategies, plans and programs are updated on a regular basis, and incorporate any recommended measures to improve the environmental performance of the development. ANAGEMENT The Applicant must assess and manage development-related risks to ensure that there are no exceedances of the criteria and/or performance measures in Schedule 3. Any exceedance of these criteria and/or performance measures constitutes a breach of this consent and may be subject to penalty or offence provisions under the EPBA Act or EPBA Regulation. Where any exceedance of these criteria and/or performance measures has occurred, the Applicant must, at the earliest opportunity: take all reasonable and feasible measures to ensure that the exceedance ceases and does not recur; consider all reasonable and feasible options for remediation (where relevant) and submit a report to the Department describing those	Annual Review 2020, 2021, 2022. Incident notifications to DPE dated 11 December 2023, 22 May 2023, 13 January 2023 Site interviews D. Egeonu Note. Note. Note. Annual Review 2020, 2021, 2022. Incident notifications to DPE dated 11 December 2023, 22 May 2023, 13 January 2023 Annual Review 2020, 2021, 2022. Incident notifications to DPE dated 11 December 2023, 22 May 2023, 13 January 2024 Site interviews - D. Egeonu	following annual reviews. No evidence sighted of review of plans following incidents or previous audit. 2020 Annual Review notes an IEA Action plan is available as Appendix 3 of the document however is notes local funding initiatives not IEA actions Sighted AERs and DPE incident notification letters for the audit period, each of which shows actions taken to minimise/control/report on exceedances. Proportionate to the exceedance identified. Sighted AERs and DPE incident notification letters for the audit period, each of which shows actions taken to minimise/control/report on exceedances. Proportionate to the exceedance identified.	Compliant	NC12
5 ADAPTIVE N 6 6 (a) 6 (b) 6 (c) COMMUNIT	consulting with all the parties nominated under the applicable conditions of consent. Notes: * While any strategy, plan or program may be submitted on a progressive basis, the Applicant will need to ensure that the existing operations on site are covered by suitable strategies, plans or programs at all times. * If the submission of any strategy, plan or program is to be staged, then the relevant strategy, plan or program must clearly describe the specific stage to which the strategy, plan or program applies, the relationship of this stage to any future stages, and the trigger for undertains the strategy, plan or program applies, the relationship of this stage to any future stages, and the trigger for undertains the strategy, plan or program applies, the relationship of this stage to any future stages, and the trigger for undertains the strategy, plan or program applies, the relationship of this stage to any future stages, and the trigger for undertains the strategy, plan or program applies, the relationship of this stage to any future stages, and the trigger for undertains the strategies, plans of the stages, and the trigger for under this consent. Within 3 months of the submission of an: (a) incident report under condition 8 below; (b) Annual Review under condition 10 below; (c) audit report under condition 11 below; and (d) any modifications to this consent, the Applicant must review, and if necessary revise, the strategies, plans, and programs required under this consent, to the satisfaction of the strategies, plans and programs are updated on a regular basis, and incorporate any recommended measures to improve the environmental performance of the development. ANAGEMENT The Applicant must assess and manage development-related risks to ensure that there are no exceedances of the criteria and/or performance measures in Schedule 3. Any exceedance of these criteria and/or performance measures constitutes a breach of this consent and may be subject to penalty or offence provisions under the EP&A Act or E	Annual Review 2020, 2021, 2022. Incident notifications to DPE dated 11 December 2023, 22 May 2023, 13 January 2023 Site interviews D. Egeonu Note. Note. Note. Annual Review 2020, 2021, 2022. Incident notifications to DPE dated 11 December 2023, 22 May 2023, 13 January 2023 Annual Review 2020, 2021, 2022. Incident notifications to DPE dated 11 December 2023, 22 May 2023, 13 January 2024 Site interviews - D. Egeonu	following annual reviews. No evidence sighted of review of plans following incidents or previous audit. 2020 Annual Review notes an IEA Action plan is available as Appendix 3 of the document however is notes local funding initiatives not IEA actions Sighted AERs and DPE incident notification letters for the audit period, each of which shows actions taken to minimise/control/report on exceedances. Proportionate to the exceedance identified. Sighted AERs and DPE incident notification letters for the audit period, each of which shows actions taken to minimise/control/report on exceedances. Proportionate to the exceedance identified.	Compliant Compliant Not triggered	NC12
5 ADAPTIVE N 6 6 (a) 6 (b) 6 (c) COMMUNIT	consulting with all the parties nominated under the applicable conditions of consent. Notes: * While any strategy, plan or program may be submitted on a progressive basis, the Applicant will need to ensure that the existing operations on site are covered by suitable strategies, plans or programs at all times. * If the submission of any strategy, plan or program is to be staged, then the relevant strategy, plan or program must clearly describe the specific stage to which the strategy, plan or program applies, the relationship of this stage to any future stages, and the trigger for undefation the strategy, plan or program applies, the relationship of this stage to any future stages, and the trigger for undefation the strategy, plan or program applies, the relationship of this stage to any future stages, and the trigger for undefation the strategy, plan or program applies, the relationship of this stage to any future stages, and the trigger for undefation the strategy, plan or program applies, the relationship of this stage to any future stages, and the trigger for undefation the strategy, plan or program applies, the relationship of this stage to any future stages, and the trigger for undefation the strategy plan applies and the relationship of this stage to any future stages, and the trigger for undefationship of the strategies, plans and programs are undefationship of this stage to any future stages, and the trigger for undefation the strategies, plans and programs are undefation that for the plant must related this consent, the Applicant must related must assess and manage development. **ANAGEMENT** The Applicant must assess and manage development-related risks to ensure that there are no exceedances of the criteria and/or performance measures in Schedule 3. Any exceedance of these criteria and/or performance measures in Schedule 3. Any exceedance of these criteria and/or performance measures and does not recur; **Consultative Committee** **Consultative Committee** The Applicant must operate a Community	Annual Review 2020, 2021, 2022. Incident notifications to DPE dated 11 December 2023, 22 May 2023, 13 January 2023 Site interviews D. Egeonu Note. Note. Note. Annual Review 2020, 2021, 2022. Incident notifications to DPE dated 11 December 2023, 22 May 2023, 13 January 2023 Annual Review 2020, 2021, 2022. Incident notifications to DPE dated 11 December 2023, 22 May 2023, 13 January 2024 Site interviews - D. Egeonu Note.	following annual reviews. No evidence sighted of review of plans following incidents or previous audit. 2020 Annual Review notes an IEA Action plan is available as Appendix 3 of the document however is notes local funding initiatives not IEA actions Sighted AERs and DPE incident notification letters for the audit period, each of which shows actions taken to minimise/control/report on exceedances. Proportionate to the exceedance identified. Sighted AERs and DPE incident notification letters for the audit period, each of which shows actions taken to minimise/control/report on exceedances. Proportionate to the exceedance identified. No directions given during audit period.	Compliant	NC12
5 ADAPTIVE N 6 6 (a) 6 (b) 6 (c) COMMUNIT	consulting with all the parties nominated under the applicable conditions of consent. Notes: * While any strategy, plan or program may be submitted on a progressive basis, the Applicant will need to ensure that the existing operations on site are covered by suitable strategies, plans or programs at all times. * If the submission of any strategy, plan or program is to be staged, then the relevant strategy, plan or program must clearly describe the specific stage to which the strategy, plan or program applies, the relationship of this stage to any future stages, and the trigger for undatation the strategy, plan or program applies, the relationship of this stage to any future stages, and the trigger for undatation the strategy, plan or program applies, the relationship of this stage to any future stages, and the trigger for undatation the strategy, plan or program applies, the relationship of this stage to any future stages, and the trigger for undatation that strategy and a program applies, the relationship of this stage to any future stages, and the trigger for undatation that strategy and programs applies, the relationship of this stage to any future stages, and the trigger for undatation that strategy and the trigger for undatation that strategy and the trigger for under condition 10 below; (b) Annual Review under condition 10 below; (c) audit report under condition 10 below; (c) audit report under condition 10 below; (d) any modifications to this consent, the Applicant must review, and if necessary revise, the strategies, plans, and programs required under this consent, to the satisfaction of the development. **Note: This is to ensure the strategies, plans and programs are updated on a regular basis, and incorporate any recommended measures to improve the environmental performance of the development. **Note: This is to ensure the strategies, plans and programs are updated on a regular basis, and incorporate any recommended measures to improve the environmental performance of the development. **Note:	Note. Annual Review 2020, 2021, 2022. Incident notifications to DPE dated 11 December 2023, 22 May 2023, 13 January 2023 Site interviews D. Egeonu Note. Note. Note. Annual Review 2020, 2021, 2022. Incident notifications to DPE dated 11 December 2023, 22 May 2023, 13 January 2023 Annual Review 2020, 2021, 2022. Incident notifications to DPE dated 11 December 2023, 22 May 2023, 13 January 2024 Site interviews - D. Egeonu Note. Annual Review 2020, 2021, 2022.	following annual reviews. No evidence sighted of review of plans following incidents or previous audit. 2020 Annual Review notes an IEA Action plan is available as Appendix 3 of the document however is notes local funding initiatives not IEA actions Sighted AERs and DPE incident notification letters for the audit period, each of which shows actions taken to minimise/control/report on exceedances. Proportionate to the exceedance identified. Sighted AERs and DPE incident notification letters for the audit period, each of which shows actions taken to minimise/control/report on exceedances. Proportionate to the exceedance identified. No directions given during audit period.	Compliant Compliant Not triggered	NC12
5 ADAPTIVE N 6 6 (a) 6 (b) 6 (c) COMMUNIT	consulting with all the parties nominated under the applicable conditions of consent. Notes: * While any strategy, plan or program may be submitted on a progressive basis, the Applicant will need to ensure that the existing operations on site are covered by suitable strategies, plans or programs at all times. * If the submission of any strategy, plan or program is to be staged, then the relevant strategy, plan or program must clearly describe the specific stage to which the strategy, plan or program applies, the relationship of this stage to any future stages, and the trigger for undefation the strategy, plan or program applies, the relationship of this stage to any future stages, and the trigger for undefation the strategy, plan or program applies, the relationship of this stage to any future stages, and the trigger for undefation the strategy, plan or program applies, the relationship of this stage to any future stages, and the trigger for undefation the strategy, plan or program applies, the relationship of this stage to any future stages, and the trigger for undefation the strategy, plan or program applies, the relationship of this stage to any future stages, and the trigger for undefation the strategy plan applies and the relationship of this stage to any future stages, and the trigger for undefationship of the strategies, plans and programs are undefationship of this stage to any future stages, and the trigger for undefation the strategies, plans and programs are undefation that for the plant must related this consent, the Applicant must related must assess and manage development. **ANAGEMENT** The Applicant must assess and manage development-related risks to ensure that there are no exceedances of the criteria and/or performance measures in Schedule 3. Any exceedance of these criteria and/or performance measures in Schedule 3. Any exceedance of these criteria and/or performance measures and does not recur; **Consultative Committee** **Consultative Committee** The Applicant must operate a Community	Annual Review 2020, 2021, 2022. Incident notifications to DPE dated 11 December 2023, 22 May 2023, 13 January 2023 Site interviews D. Egeonu Note. Note. Note. Annual Review 2020, 2021, 2022. Incident notifications to DPE dated 11 December 2023, 22 May 2023, 13 January 2023 Annual Review 2020, 2021, 2022. Incident notifications to DPE dated 11 December 2023, 22 May 2023, 13 January 2024 Site interviews - D. Egeonu Note.	following annual reviews. No evidence sighted of review of plans following incidents or previous audit. 2020 Annual Review notes an IEA Action plan is available as Appendix 3 of the document however is notes local funding initiatives not IEA actions Sighted AERs and DPE incident notification letters for the audit period, each of which shows actions taken to minimise/control/report on exceedances. Proportionate to the exceedance identified. Sighted AERs and DPE incident notification letters for the audit period, each of which shows actions taken to minimise/control/report on exceedances. Proportionate to the exceedance identified. No directions given during audit period.	Compliant Compliant Not triggered	NC12
5 ADAPTIVE N 6 6 (a) 6 (b) 6 (c) COMMUNIT	consulting with all the parties nominated under the applicable conditions of consent. Notes: * While any strategy, plan or program may be submitted on a progressive basis, the Applicant will need to ensure that the existing operations on site are covered by suitable strategies, plans or programs at all times. * If the submission of any strategy, plan or program is to be staged, then the relevant strategy, plan or program must clearly describe the specific stage to which the strategy, plan or program applies, the relationship of this stage to any future stages, and the trigger for undatation the strategy, plan or program applies, the relationship of this stage to any future stages, and the trigger for undatation the strategy, plan or program applies, the relationship of this stage to any future stages, and the trigger for undatation the strategy, plan or program applies, the relationship of this stage to any future stages, and the trigger for undatation that strategy and a program applies, the relationship of this stage to any future stages, and the trigger for undatation that strategy and programs applies, the relationship of this stage to any future stages, and the trigger for undatation that strategy and the trigger for undatation that strategy and the trigger for under condition 10 below; (b) Annual Review under condition 10 below; (c) audit report under condition 10 below; (c) audit report under condition 10 below; (d) any modifications to this consent, the Applicant must review, and if necessary revise, the strategies, plans, and programs required under this consent, to the satisfaction of the development. **Note: This is to ensure the strategies, plans and programs are updated on a regular basis, and incorporate any recommended measures to improve the environmental performance of the development. **Note: This is to ensure the strategies, plans and programs are updated on a regular basis, and incorporate any recommended measures to improve the environmental performance of the development. **Note:	Note. Annual Review 2020, 2021, 2022. Incident notifications to DPE dated 11 December 2023, 22 May 2023, 13 January 2023 Site interviews D. Egeonu Note. Note. Note. Annual Review 2020, 2021, 2022. Incident notifications to DPE dated 11 December 2023, 22 May 2023, 13 January 2023 Annual Review 2020, 2021, 2022. Incident notifications to DPE dated 11 December 2023, 22 May 2023, 13 January 2024 Site interviews - D. Egeonu Note. Annual Review 2020, 2021, 2022.	following annual reviews. No evidence sighted of review of plans following incidents or previous audit. 2020 Annual Review notes an IEA Action plan is available as Appendix 3 of the document however is notes local funding initiatives not IEA actions Sighted AERs and DPE incident notification letters for the audit period, each of which shows actions taken to minimise/control/report on exceedances. Proportionate to the exceedance identified. Sighted AERs and DPE incident notification letters for the audit period, each of which shows actions taken to minimise/control/report on exceedances. Proportionate to the exceedance identified. No directions given during audit period.	Compliant Compliant Not triggered	NC12
5 ADAPTIVE N 6 6 (a) 6 (b) 6 (c) COMMUNIT	consulting with all the parties nominated under the applicable conditions of consent. Notes: * While any strategy, plan or program may be submitted on a progressive basis, the Applicant will need to ensure that the existing operations on site are covered by suitable strategies, plans or programs at all times. * If the submission of any strategy, plan or program is to be staged, then the relevant strategy, plan or program must clearly describe the specific stage to which the strategy, plan or program applies, the relationship of this stage to any future stages, and the trigger for undadation the strategy, plan or program applies, the relationship of this stage to any future stages, and the trigger for undadation the strategy, plan or program applies, the relationship of this stage to any future stages, and the trigger for undadation the strategy, plan or program applies, the relationship of this stage to any future stages, and the trigger for undadation the strategy plan or program applies, the relationship of this stage to any future stages, and the trigger for undadation the strategy plan or program applies, the relationship of this stage to any future stages, and the trigger for undadation the strategy plan or program applies, the relationship of this stage to any future stages, and the trigger for undadation the strategy plan or program applies, the relationship of this stage to any future stages, and the trigger for undadation the strategy plan or program applies, the relationship of this stage to any future stages, and the trigger for undadation the strategy plan or program applies, the relationship of this stage to any future stages, and the trigger for undadation the strategy plan or program applies, the relationship of this stage to any future stages, and the trigger for undadation to the stages and the stages and program applies, the relationship of this stage to any future stages, and the trigger for undadation fall reasonable and performance of the development. The Applicant must open and feasible	Note. Annual Review 2020, 2021, 2022. Incident notifications to DPE dated 11 December 2023, 22 May 2023, 13 January 2023 Site interviews D. Egeonu Note. Note. Note. Annual Review 2020, 2021, 2022. Incident notifications to DPE dated 11 December 2023, 22 May 2023, 13 January 2023 Annual Review 2020, 2021, 2022. Incident notifications to DPE dated 11 December 2023, 22 May 2023, 13 January 2024 Site interviews - D. Egeonu Note. Annual Review 2020, 2021, 2022.	following annual reviews. No evidence sighted of review of plans following incidents or previous audit. 2020 Annual Review notes an IEA Action plan is available as Appendix 3 of the document however is notes local funding initiatives not IEA actions Sighted AERs and DPE incident notification letters for the audit period, each of which shows actions taken to minimise/control/report on exceedances. Proportionate to the exceedance identified. Sighted AERs and DPE incident notification letters for the audit period, each of which shows actions taken to minimise/control/report on exceedances. Proportionate to the exceedance identified. No directions given during audit period.	Compliant Compliant Not triggered	NC12
5 ADAPTIVE N 6 6 (a) 6 (b) 6 (c) COMMUNIT	consulting with all the parties nominated under the applicable conditions of consent. Notes: • While any strategy, plan or program may be submitted on a progressive basis, the Applicant will need to ensure that the existing operations on site are covered by suitable strategies, plans or programs at all times. • If the submission of any strategy, plan or program is to be staged, then the relevant strategy, plan or program must clearly describe the specific stage to which the strategy, plan or program applies, the relationship of this stage to any future stages, and the trigger for underly describe the strategy plan or program applies, the relationship of this stage to any future stages, and the trigger for underly described the strategy plan or program applies, the relationship of this stage to any future stages, and the trigger for underly described the strategy plan or program applies, the relationship of this stage to any future stages, and the trigger for underly described the strategy plans and the strategy plans and the strategy plans and the relationship of this stage to any future stages, and the trigger for under condition 10 below; (a) administration of the strategy plans and programs are updated on a regular basis, and incorporate any recommended measures to improve the environmental performance of the development. **ANAGEMENT** The Applicant must assess and manage development-related risks to ensure that there are no exceedances of the criteria and/or performance measures in Schedule 3. Any exceedance of these criteria and/or performance measures in Schedule 3. Any exceedance of these criteria and/or performance measures constitutes a breach of this consent and may be subject to enalty or offence provisions under the EP&A Act or EP&A Regulation. Where any exceedance of these criteria and/or performance measures and does not recur; consider all reasonable and feasible options for remediation (where relevant) and submit a report to the Department describing those options and any preferred remedi	Note. Annual Review 2020, 2021, 2022. Incident notifications to DPE dated 11 December 2023, 22 May 2023, 13 January 2023 Site interviews D. Egeonu Note. Note. Note. Annual Review 2020, 2021, 2022. Incident notifications to DPE dated 11 December 2023, 22 May 2023, 13 January 2023 Annual Review 2020, 2021, 2022. Incident notifications to DPE dated 11 December 2023, 22 May 2023, 13 January 2024 Site interviews - D. Egeonu Note. Annual Review 2020, 2021, 2022.	following annual reviews. No evidence sighted of review of plans following incidents or previous audit. 2020 Annual Review notes an IEA Action plan is available as Appendix 3 of the document however is notes local funding initiatives not IEA actions Sighted AERs and DPE incident notification letters for the audit period, each of which shows actions taken to minimise/control/report on exceedances. Proportionate to the exceedance identified. Sighted AERs and DPE incident notification letters for the audit period, each of which shows actions taken to minimise/control/report on exceedances. Proportionate to the exceedance identified. No directions given during audit period.	Compliant Compliant Not triggered	NC12
5 ADAPTIVE N 6 6 (a) 6 (b) 6 (c) COMMUNIT	consulting with all the parties nominated under the applicable conditions of consent. Notes: • While any strategy, plan or program may be submitted on a progressive basis, the Applicant will need to ensure that the existing operations on site are covered by suitable strategies, plans or programs at all times. • If the submission of any strategy, plan or program is to be staged, then the relevant strategy, plan or program must clearly describe the specific stage to which the strategy, plan or program applies, the relationship of this stage to any future stages, and the trigger for lundational the strategy and or program applies, the relationship of this stage to any future stages, and the trigger for lundational the strategy and or program applies, the relationship of this stage to any future stages, and the trigger for lundational the strategy and strate	Note. Annual Review 2020, 2021, 2022. Incident notifications to DPE dated 11 December 2023, 22 May 2023, 13 January 2023 Site interviews D. Egeonu Note. Note. Note. Annual Review 2020, 2021, 2022. Incident notifications to DPE dated 11 December 2023, 22 May 2023, 13 January 2023 Annual Review 2020, 2021, 2022. Incident notifications to DPE dated 11 December 2023, 22 May 2023, 13 January 2024 Site interviews - D. Egeonu Note. Annual Review 2020, 2021, 2022.	following annual reviews. No evidence sighted of review of plans following incidents or previous audit. 2020 Annual Review notes an IEA Action plan is available as Appendix 3 of the document however is notes local funding initiatives not IEA actions Sighted AERs and DPE incident notification letters for the audit period, each of which shows actions taken to minimise/control/report on exceedances. Proportionate to the exceedance identified. Sighted AERs and DPE incident notification letters for the audit period, each of which shows actions taken to minimise/control/report on exceedances. Proportionate to the exceedance identified. No directions given during audit period.	Compliant Compliant Not triggered	NC12
5 ADAPTIVE N 6 6 (a) 6 (b) 6 (c) COMMUNIT	consulting with all the parties nominated under the applicable conditions of consent. Notes: • While any strategy, plan or program may be submitted on a progressive basis, the Applicant will need to ensure that the existing operations on site are covered by suitable strategies, plans or programs at all times. • If the submission of any strategy, plan or program is to be staged, then the relevant strategy, plan or program must clearly describe the specific stage to which the strategy, plan or program applies, the relationship of this stage to any future stages, and the trigger for undutation the strategy alian or program applies, the relationship of this stage to any future stages, and the trigger for undutation the strategy alian or program applies, the relationship of this stage to any future stages, and the trigger for undutation the strategy alian or program applies, the relationship of this stage to any future stages, and the trigger for undutation than the strategy and the strategy of this stage to any future stages, and the trigger for under thin stages and the trigger for under thin stages and the trigger for under thin stages and the trigger for under condition 10 below; (a) alicited report under condition 10 below; (b) Annual Review under condition 11 below; and (d) any modifications to this consent, the Applicant must review, and if necessary revise, the strategies, plans, and programs required under this consent, to the satisfaction of the source the strategies, plans and programs are updated on a regular basis, and incorporate any recommended measures to improve the ensure the strategies, plans and programs are updated on a regular basis, and incorporate any recommended measures to improve the ensuremental performance of the development. **ANACEMENT** The Applicant must assess and manage development-related risks to ensure that there are no exceedances of the criteria and/or performance measures in Schedule 3. Any exceedance of these criteria and/or performance measures in Schedule 3. Any exc	Note. Annual Review 2020, 2021, 2022. Incident notifications to DPE dated 11 December 2023, 22 May 2023, 13 January 2023 Site interviews D. Egeonu Note. Note. Note. Annual Review 2020, 2021, 2022. Incident notifications to DPE dated 11 December 2023, 22 May 2023, 13 January 2023 Annual Review 2020, 2021, 2022. Incident notifications to DPE dated 11 December 2023, 22 May 2023, 13 January 2024 Site interviews - D. Egeonu Note. Annual Review 2020, 2021, 2022.	following annual reviews. No evidence sighted of review of plans following incidents or previous audit. 2020 Annual Review notes an IEA Action plan is available as Appendix 3 of the document however is notes local funding initiatives not IEA actions Sighted AERs and DPE incident notification letters for the audit period, each of which shows actions taken to minimise/control/report on exceedances. Proportionate to the exceedance identified. Sighted AERs and DPE incident notification letters for the audit period, each of which shows actions taken to minimise/control/report on exceedances. Proportionate to the exceedance identified. No directions given during audit period.	Compliant Compliant Not triggered	NC12
5 ADAPTIVE N 6 6 (a) 6 (b) 6 (c) COMMUNIT	consulting with all the parties nominated under the applicable conditions of consent. Notes: • While any strategy, plan or program may be submitted on a progressive basis, the Applicant will need to ensure that the existing operations on site are covered by suitable strategies, plans or programs at all times. • If the submission of any strategy, plan or program is to be staged, then the relevant strategy, plan or program must clearly describe the specific stage to which the strategy, plan or program applies, the relationship of this stage to any future stages, and the trigger for lundational the strategy and or program applies, the relationship of this stage to any future stages, and the trigger for lundational the strategy and or program applies, the relationship of this stage to any future stages, and the trigger for lundational the strategy and strate	Annual Review 2020, 2021, 2022. Incident notifications to DPE dated 11 December 2023, 22 May 2023, 13 January 2023 Site interviews D. Egeonu Note. Note. Note. Annual Review 2020, 2021, 2022. Incident notifications to DPE dated 11 December 2023, 22 May 2023, 13 January 2023 Annual Review 2020, 2021, 2022. Incident notifications to DPE dated 11 December 2023, 22 May 2023, 13 January 2024 Site interviews - D. Egeonu Note. Annual Review 2020, 2021, 2022. CCC Meeting Minutes	following annual reviews. No evidence sighted of review of plans following incidents or previous audit. 2020 Annual Review notes an IEA Action plan is available as Appendix 3 of the document however is notes local funding initiatives not IEA actions Sighted AERs and DPE incident notification letters for the audit period, each of which shows actions taken to minimise/control/report on exceedances. Proportionate to the exceedance identified. Sighted AERs and DPE incident notification letters for the audit period, each of which shows actions taken to minimise/control/report on exceedances. Proportionate to the exceedance identified. No directions given during audit period.	Compliant Compliant Not triggered	NC12
5 ADAPTIVE N 6 6 (a) 6 (b) COMMUNIT 7	consulting with all the parties nominated under the applicable conditions of consent. Notes: * While any strategy, plan or program may be submitted on a progressive basis, the Applicant will need to ensure that the existing operations on site are covered by suitable strategies, plans or programs at all times. * If the submission of any strategy, plan or program is to be staged, then the relevant strategy, plan or program must clearly describe the specific stage to which the strategy, plan or program applies, the relationship of this stage to any future stages, and the trigger for undation the strategy along any applies are program applies, the relationship of this stage to any future stages, and the trigger for undation the strategy along any applies are program applies, the relationship of this stage to any future stages, and the trigger for undation the strategy along any applies are program applies, the relationship of this stage to any future stages, and the trigger for undation the strategy along and programs applies, the relationship of this stage to any future stages, and the trigger for undation the strategies, plan or program applies, the relationship of this stage to any future stages, and the trigger for undation the strategies and programs are undationship of this stage to any future stages, and the trigger for undation the strategies and programs are undated and programs required under this consent, to the satisfaction of the strategies, plans and programs are updated on a regular basis, and incorporate any recommended measures to improve the environmental performance of the development. **NAKEMENT** The Applicant must assess and manage development-related risks to ensure that there are no exceedances of the criteria and/or performance measures in Schedule 3. Any exceedance of these criteria and/or performance measures constitutes a breach of this consent and may be subject to penalty or offence provisions under the EPBA Act or EPBA Regulation. Where any exceedance of these criteria and/or per	Annual Review 2020, 2021, 2022. Incident notifications to DPE dated 11 December 2023, 22 May 2023, 13 January 2023 Site interviews D. Egeonu Note. Note. Note. Annual Review 2020, 2021, 2022. Incident notifications to DPE dated 11 December 2023, 22 May 2023, 13 January 2023 Annual Review 2020, 2021, 2022. Incident notifications to DPE dated 11 December 2023, 22 May 2023, 13 January 2024 Site interviews - D. Egeonu Note. Annual Review 2020, 2021, 2022. CCC Meeting Minutes	following annual reviews. No evidence sighted of review of plans following incidents or previous audit. 2020 Annual Review notes an IEA Action plan is available as Appendix 3 of the document however is notes local funding initiatives not IEA actions Sighted AERs and DPE incident notification letters for the audit period, each of which shows actions taken to minimise/control/report on exceedances. Proportionate to the exceedance identified. Sighted AERs and DPE incident notification letters for the audit period, each of which shows actions taken to minimise/control/report on exceedances. Proportionate to the exceedance identified. No directions given during audit period.	Compliant Compliant Not triggered	NC12

8	The Applicant must notify, at the earliest opportunity, the Secretary and any other relevant agencies of any incident that has caused, or			Compliant	
	threatens to cause, material harm to the environment. For any other incident associated with the development, the Applicant must notify				
	the Secretary and any other relevant agencies as soon as practicable after the Applicant becomes aware of the incident. Within 7 days of		Incidents appear to be managed as per the requirements. No incidents triggering the PRIMP		
	the date of the incident, the Applicant must provide the Secretary and any relevant agencies with a detailed report on the incident, and		or presenting material environmental harm identified during the audit period.		
	such further reports as may be requested.	Pollution Incident Response Management Plan	It is noted Lynwood Quarry failed to notify DPHI of monitoring event incidents, these		
		Annual Review 2020, 2021, 2022, 2023	failures to notify are captured within the indiduval monitoring consent conditions. This		
			1		
		Incident notifications to DPE dated 11 December 2023, 22 May 2023, 13	conditions is intrepretted as to relate to the triggering of the PIRMP or incidents which have		
DECLII AD D	PORTING	January 2024	caused or threaten to cause material environmental harm.		
negular r		Halaina Lunius ad Ouenn unahanna		Compliant	
3	its website, in accordance with the reporting arrangements in any plans or programs approved under the conditions of this consent.	Holcim Lynwood Quarry webpage (accessed 12/1/2024)		Compilant	
i		· · · · · · · · · · · · · · · · · · ·	Annual research annual tention data and annual release are arrayided on the Heleius		
		https://www.holcim.com.au/abou	Annual reports, monitoring data and management plans are provided on the Holcim		
ANNUAL RE		t-us/community link/Lynwood/planning-approvals reporting	website, along with community information.		
				Compliant	
10	By the end of September each year, or other timing as may be agreed by the Secretary, the Applicant must review the environmental performance of the development to the satisfaction of the Secretary.			Compliant	
	This review must:	Annual Review 2020, 2021, 2022.	The Annual Review reporting period is agreed to be 1 January to 1 December each year.		
10 (a)	(a) describe the development (including rehabilitation) that was carried out in the previous financial year, and the development that is			Compliant	
	proposed to be carried out over the current mandal year,	Annual Review 2020, 2021, 2022, 2023			
10 (b)	(b) include a comprehensive review of the monitoring results and complaints records of the development over the previous financial year,			Compliant	
	which includes a comparison of these results				
	against:				
	• the relevant statutory requirements, limits or performance measures/criteria;				
	 requirements of any plan or program required under this consent; the monitoring results of previous years; and 				
	the relevant predictions in the documents listed in condition 2(a) of Schodule 2: the relevant predictions in the documents listed in condition 2(a) of Schodule 2:	Annual Review 2020, 2021, 2022, 2023			
10 (c)	(c) identify any non-compliance over the last year, and describe what actions were (or are being) taken to ensure compliance;			Compliant	
	Invitage at the part of the pa	Annual Review 2020, 2021, 2022, 2023		2 !!	
10 (d)		Annual Review 2020, 2021, 2022, 2023		Compliant	
10 (e)	(e) identify any discrepancies between the predicted and actual impacts of the development, and analyse the potential cause of any	Annual Review 2020, 2021, 2022, 2023		Compliant	
10 (f)	significant discrepancies; (f) describe what measures will be implemented over the current financial year to improve the environmental performance of the	Alliludi Review 2020, 2021, 2022, 2023		Compliant	
10 (1)		Annual Review 2020, 2021, 2022, 2023		Compilant	
10 (g)	(g) describe the area of vegetation cleared as part of the development and identify the area proposed to be cleared over the next 5 years;	, , ,		Compliant	
		Annual Review 2020, 2021, 2022, 2023			
10 (h)	(h) calculate the number of additional BioBanking (or equivalent) credits that will need to be purchased, before that clearing can be done;	AI Daview 2020, 2021, 2022, 2022		Compliant	
10 (;)	and (i) court on the number of Bio Basking (or equivalent) godite that have been purchased to allow againg closing and completion of	Annual Review 2020, 2021, 2022, 2023		Compliant	
10 (i)	(i) report on the number of BioBanking (or equivalent) credits that have been purchased to allow ongoing clearing and completion of			Compliant	1
(1)	stages	Annual Review 2020, 2021, 2022, 2023		the state of the s	
10 (i)	stages. The Applicant must ensure that copies of the Annual Review are submitted to Council and are available to the Community Consultative	Annual Review 2020, 2021, 2022, 2023		Non-compliant	
	Stages.	Annual Review 2020, 2021, 2022, 2023	While the AERs are publicly available on the Holcim website, there is no evidence that that	Non-compliant	
	The Applicant must ensure that copies of the Annual Review are submitted to Council and are available to the Community Consultative	Annual Review 2020, 2021, 2022, 2023 Annual Review 2020, 2021, 2022, 2023	While the AERs are publicly available on the Holcim website, there is no evidence that that the AERs in the reporting period were submitted directly to Council.	Non-compliant	NC13
10 (i)	The Applicant must ensure that copies of the Annual Review are submitted to Council and are available to the Community Consultative			Non-compliant	NC13
10 (i)	The Applicant must ensure that copies of the Annual Review are submitted to Council and are available to the Community Consultative Committee (see condition 7 of Schedule 5) and any interested person upon request. NT ENVIRONMENTAL AUDIT By 30 September 2017, and every 3 years thereafter, unless the Secretary directs otherwise, the Applicant must commission and pay the			·	NC13
10 (i)	The Applicant must ensure that copies of the Annual Review are submitted to Council and are available to the Community Consultative Committee (see condition 7 of Schedule 5) and any interested person upon request.		the AERs in the reporting period were submitted directly to Council.	Non-compliant	NC13
10 (i)	The Applicant must ensure that copies of the Annual Review are submitted to Council and are available to the Community Consultative Committee (see condition 7 of Schedule 5) and any interested person upon request. NT ENVIRONMENTAL AUDIT By 30 September 2017, and every 3 years thereafter, unless the Secretary directs otherwise, the Applicant must commission and pay the		the AERs in the reporting period were submitted directly to Council. Audit commissioned 4 December 2023, and was originally scheduled for the week the 11th	Non-compliant	NC13
10 (i)	The Applicant must ensure that copies of the Annual Review are submitted to Council and are available to the Community Consultative Committee (see condition 7 of Schedule 5) and any interested person upon request. NT ENVIRONMENTAL AUDIT By 30 September 2017, and every 3 years thereafter, unless the Secretary directs otherwise, the Applicant must commission and pay the full cost of an Independent Environmental Audit of the development. This audit must: (a) be conducted by suitably qualified, experienced and independent team of experts whose appointment has been endorsed by the	Annual Review 2020, 2021, 2022, 2023 This audit.	the AERs in the reporting period were submitted directly to Council. Audit commissioned 4 December 2023, and was originally scheduled for the week the 11th of December 2023. However due to personal circumstances the auditor could not undertake	Non-compliant	
10 (i) INDEPENDE 11 11 (a)	The Applicant must ensure that copies of the Annual Review are submitted to Council and are available to the Community Consultative Committee (see condition 7 of Schedule 5) and any interested person upon request. NT ENVIRONMENTAL AUDIT By 30 September 2017, and every 3 years thereafter, unless the Secretary directs otherwise, the Applicant must commission and pay the full cost of an Independent Environmental Audit of the development. This audit must: (a) be conducted by suitably qualified, experienced and independent team of experts whose appointment has been endorsed by the Secretary;	Annual Review 2020, 2021, 2022, 2023 This audit. DPE Letter dated 1 December 2023, approving audit team.	the AERs in the reporting period were submitted directly to Council. Audit commissioned 4 December 2023, and was originally scheduled for the week the 11th of December 2023. However due to personal circumstances the auditor could not undertake	Non-compliant Compliant	
10 (i) INDEPENDE 11	The Applicant must ensure that copies of the Annual Review are submitted to Council and are available to the Community Consultative Committee (see condition 7 of Schedule 5) and any interested person upon request. NT ENVIRONMENTAL AUDIT By 30 September 2017, and every 3 years thereafter, unless the Secretary directs otherwise, the Applicant must commission and pay the full cost of an Independent Environmental Audit of the development. This audit must: (a) be conducted by suitably qualified, experienced and independent team of experts whose appointment has been endorsed by the	Annual Review 2020, 2021, 2022, 2023 This audit. DPE Letter dated 1 December 2023, approving audit team. Letter sent to relevant agencies and responses appended to the audit	the AERs in the reporting period were submitted directly to Council. Audit commissioned 4 December 2023, and was originally scheduled for the week the 11th of December 2023. However due to personal circumstances the auditor could not undertake	Non-compliant	
10 (i) INDEPENDE 11 11 (a) 11 (b)	The Applicant must ensure that copies of the Annual Review are submitted to Council and are available to the Community Consultative Committee (see condition 7 of Schedule 5) and any interested person upon request. NT ENVIRONMENTAL AUDIT By 30 September 2017, and every 3 years thereafter, unless the Secretary directs otherwise, the Applicant must commission and pay the full cost of an Independent Environmental Audit of the development. This audit must: (a) be conducted by suitably qualified, experienced and independent team of experts whose appointment has been endorsed by the Secretary; (b) include consultation with the relevant agencies and the CCC;	Annual Review 2020, 2021, 2022, 2023 This audit. DPE Letter dated 1 December 2023, approving audit team.	Audit commissioned 4 December 2023, and was originally scheduled for the week the 11th of December 2023. However due to personal circumstances the auditor could not undertake the audit till 11 January 2024.	Non-compliant Compliant Compliant	
10 (i) INDEPENDE 11 11 (a)	The Applicant must ensure that copies of the Annual Review are submitted to Council and are available to the Community Consultative Committee (see condition 7 of Schedule 5) and any interested person upon request. NT ENVIRONMENTAL AUDIT By 30 September 2017, and every 3 years thereafter, unless the Secretary directs otherwise, the Applicant must commission and pay the full cost of an Independent Environmental Audit of the development. This audit must: (a) be conducted by suitably qualified, experienced and independent team of experts whose appointment has been endorsed by the Secretary; (b) include consultation with the relevant agencies and the CCC;	Annual Review 2020, 2021, 2022, 2023 This audit. DPE Letter dated 1 December 2023, approving audit team. Letter sent to relevant agencies and responses appended to the audit	All conditions of consent (Mod 5), statement of commitments (SoC), and the EPL have been	Non-compliant Compliant Compliant	
10 (i) INDEPENDE 11 11 (a) 11 (b)	The Applicant must ensure that copies of the Annual Review are submitted to Council and are available to the Community Consultative Committee (see condition 7 of Schedule 5) and any interested person upon request. NT ENVIRONMENTAL AUDIT By 30 September 2017, and every 3 years thereafter, unless the Secretary directs otherwise, the Applicant must commission and pay the full cost of an Independent Environmental Audit of the development. This audit must: (a) be conducted by suitably qualified, experienced and independent team of experts whose appointment has been endorsed by the Secretary; (b) include consultation with the relevant agencies and the CCC; (c) assess the environmental performance of the development and whether it is complying with the relevant requirements in this consent and any relevant EPL and/or Water Licence	Annual Review 2020, 2021, 2022, 2023 This audit. DPE Letter dated 1 December 2023, approving audit team. Letter sent to relevant agencies and responses appended to the audit report.	All conditions of consent (Mod 5), statement of commitments (SoC), and the EPL have been audited, along with any assessment, plan or	Non-compliant Compliant Compliant	
10 (i) INDEPENDE 11 11 (a) 11 (b)	The Applicant must ensure that copies of the Annual Review are submitted to Council and are available to the Community Consultative Committee (see condition 7 of Schedule 5) and any interested person upon request. NT ENVIRONMENTAL AUDIT By 30 September 2017, and every 3 years thereafter, unless the Secretary directs otherwise, the Applicant must commission and pay the full cost of an Independent Environmental Audit of the development. This audit must: (a) be conducted by suitably qualified, experienced and independent team of experts whose appointment has been endorsed by the Secretary; (b) include consultation with the relevant agencies and the CCC; (c) assess the environmental performance of the development and whether it is complying with the relevant requirements in this consent and any relevant EPL and/or Water Licence (including any assessment, plan or program required under these approvals);	Annual Review 2020, 2021, 2022, 2023 This audit. DPE Letter dated 1 December 2023, approving audit team. Letter sent to relevant agencies and responses appended to the audit report. This audit.	Audit commissioned 4 December 2023, and was originally scheduled for the week the 11th of December 2023. However due to personal circumstances the auditor could not undertake the audit till 11 January 2024. All conditions of consent (Mod 5), statement of commitments (SoC), and the EPL have been audited, along with any assessment, plan or program required under these approvals	Non-compliant Compliant Compliant Compliant	
10 (i) INDEPENDE 11 11 (a) 11 (b) 11 (c)	The Applicant must ensure that copies of the Annual Review are submitted to Council and are available to the Community Consultative Committee (see condition 7 of Schedule 5) and any interested person upon request. NT ENVIRONMENTAL AUDIT By 30 September 2017, and every 3 years thereafter, unless the Secretary directs otherwise, the Applicant must commission and pay the full cost of an Independent Environmental Audit of the development. This audit must: (a) be conducted by suitably qualified, experienced and independent team of experts whose appointment has been endorsed by the Secretary; (b) include consultation with the relevant agencies and the CCC; (c) assess the environmental performance of the development and whether it is complying with the relevant requirements in this consent and any relevant EPL and/or Water Licence (including any assessment, plan or program required under these approvals); (d) review the adequacy of any approved strategy, plan or program required under the these approvals;	Annual Review 2020, 2021, 2022, 2023 This audit. DPE Letter dated 1 December 2023, approving audit team. Letter sent to relevant agencies and responses appended to the audit report.	All conditions of consent (Mod 5), statement of commitments (SoC), and the EPL have been audited, along with any assessment, plan or	Non-compliant Compliant Compliant Compliant	
10 (i) INDEPENDE 11 11 (a) 11 (b) 11 (c)	The Applicant must ensure that copies of the Annual Review are submitted to Council and are available to the Community Consultative Committee (see condition 7 of Schedule 5) and any interested person upon request. NT ENVIRONMENTAL AUDIT By 30 September 2017, and every 3 years thereafter, unless the Secretary directs otherwise, the Applicant must commission and pay the full cost of an Independent Environmental Audit of the development. This audit must: (a) be conducted by suitably qualified, experienced and independent team of experts whose appointment has been endorsed by the Secretary; (b) include consultation with the relevant agencies and the CCC; (c) assess the environmental performance of the development and whether it is complying with the relevant requirements in this consent and any relevant EPL and/or Water Licence (including any assessment, plan or program required under these approvals); (d) review the adequacy of any approved strategy, plan or program required under the these approvals; (e) recommend measures or actions to improve the environmental performance of the development, and/or any assessment, plan or	Annual Review 2020, 2021, 2022, 2023 This audit. DPE Letter dated 1 December 2023, approving audit team. Letter sent to relevant agencies and responses appended to the audit report. This audit. This audit.	Audit commissioned 4 December 2023, and was originally scheduled for the week the 11th of December 2023. However due to personal circumstances the auditor could not undertake the audit till 11 January 2024. All conditions of consent (Mod 5), statement of commitments (SoC), and the EPL have been audited, along with any assessment, plan or program required under these approvals The adequacy of approved strategies, plans and programs required under the these approva	Non-compliant Compliant Compliant Compliant	
10 (i) INDEPENDE 11 11 (a) 11 (b) 11 (c) 11 (d) 11 (e)	The Applicant must ensure that copies of the Annual Review are submitted to Council and are available to the Community Consultative Committee (see condition 7 of Schedule 5) and any interested person upon request. NT ENVIRONMENTAL AUDIT By 30 September 2017, and every 3 years thereafter, unless the Secretary directs otherwise, the Applicant must commission and pay the full cost of an Independent Environmental Audit of the development. This audit must: (a) be conducted by suitably qualified, experienced and independent team of experts whose appointment has been endorsed by the Secretary; (b) include consultation with the relevant agencies and the CCC; (c) assess the environmental performance of the development and whether it is complying with the relevant requirements in this consent and any relevant EPL and/or Water Licence (including any assessment, plan or program required under these approvals); (d) review the adequacy of any approved strategy, plan or program required under the these approvals; (e) recommend measures or actions to improve the environmental performance of the development, and/or any assessment, plan or program required under these approvals; and	Annual Review 2020, 2021, 2022, 2023 This audit. DPE Letter dated 1 December 2023, approving audit team. Letter sent to relevant agencies and responses appended to the audit report. This audit.	Audit commissioned 4 December 2023, and was originally scheduled for the week the 11th of December 2023. However due to personal circumstances the auditor could not undertake the audit till 11 January 2024. All conditions of consent (Mod 5), statement of commitments (SoC), and the EPL have been audited, along with any assessment, plan or program required under these approvals The adequacy of approved strategies, plans and programs required under the these approval Recommendations provided in the audit report.	Non-compliant Compliant Compliant Compliant Compliant Compliant	
10 (i) INDEPENDE 11 11 (a) 11 (b) 11 (c)	The Applicant must ensure that copies of the Annual Review are submitted to Council and are available to the Community Consultative Committee (see condition 7 of Schedule 5) and any interested person upon request. NT ENVIRONMENTAL AUDIT By 30 September 2017, and every 3 years thereafter, unless the Secretary directs otherwise, the Applicant must commission and pay the full cost of an Independent Environmental Audit of the development. This audit must: (a) be conducted by suitably qualified, experienced and independent team of experts whose appointment has been endorsed by the Secretary; (b) include consultation with the relevant agencies and the CCC; (c) assess the environmental performance of the development and whether it is complying with the relevant requirements in this consent and any relevant EPL and/or Water Licence (including any assessment, plan or program required under these approvals); (d) review the adequacy of any approved strategy, plan or program required under the these approvals; (e) recommend measures or actions to improve the environmental performance of the development, and/or any assessment, plan or program required under these approvals; and (f) be conducted and reported to the satisfaction of the Secretary.	Annual Review 2020, 2021, 2022, 2023 This audit. DPE Letter dated 1 December 2023, approving audit team. Letter sent to relevant agencies and responses appended to the audit report. This audit. This audit. This audit.	Audit commissioned 4 December 2023, and was originally scheduled for the week the 11th of December 2023. However due to personal circumstances the auditor could not undertake the audit till 11 January 2024. All conditions of consent (Mod 5), statement of commitments (SoC), and the EPL have been audited, along with any assessment, plan or program required under these approvals The adequacy of approved strategies, plans and programs required under the these approva	Non-compliant Compliant Compliant Compliant	
10 (i) INDEPENDE 11 11 (a) 11 (b) 11 (c) 11 (d) 11 (e) 11 (f)	The Applicant must ensure that copies of the Annual Review are submitted to Council and are available to the Community Consultative Committee (see condition 7 of Schedule 5) and any interested person upon request. NT ENVIRONMENTAL AUDIT By 30 September 2017, and every 3 years thereafter, unless the Secretary directs otherwise, the Applicant must commission and pay the full cost of an Independent Environmental Audit of the development. This audit must: (a) be conducted by suitably qualified, experienced and independent team of experts whose appointment has been endorsed by the Secretary; (b) include consultation with the relevant agencies and the CCC; (c) assess the environmental performance of the development and whether it is complying with the relevant requirements in this consent and any relevant EPL and/or Water Licence (including any assessment, plan or program required under these approvals); (d) review the adequacy of any approved strategy, plan or program required under the these approvals; (e) recommend measures or actions to improve the environmental performance of the development, and/or any assessment, plan or program required under these approvals; and (f) be conducted and reported to the satisfaction of the Secretary. Note: This audit team must be led by a suitably qualified auditor and include experts in any fields specified by the Secretary.	Annual Review 2020, 2021, 2022, 2023 This audit. DPE Letter dated 1 December 2023, approving audit team. Letter sent to relevant agencies and responses appended to the audit report. This audit. This audit.	Audit commissioned 4 December 2023, and was originally scheduled for the week the 11th of December 2023. However due to personal circumstances the auditor could not undertake the audit till 11 January 2024. All conditions of consent (Mod 5), statement of commitments (SoC), and the EPL have been audited, along with any assessment, plan or program required under these approvals The adequacy of approved strategies, plans and programs required under the these approval Recommendations provided in the audit report.	Non-compliant Compliant Compliant Compliant Compliant Compliant Compliant	
10 (i) INDEPENDE 11 11 (a) 11 (b) 11 (c) 11 (d) 11 (e)	The Applicant must ensure that copies of the Annual Review are submitted to Council and are available to the Community Consultative Committee (see condition 7 of Schedule 5) and any interested person upon request. NT ENVIRONMENTAL AUDIT By 30 September 2017, and every 3 years thereafter, unless the Secretary directs otherwise, the Applicant must commission and pay the full cost of an Independent Environmental Audit of the development. This audit must: (a) be conducted by suitably qualified, experienced and independent team of experts whose appointment has been endorsed by the Secretary; (b) include consultation with the relevant agencies and the CCC; (c) assess the environmental performance of the development and whether it is complying with the relevant requirements in this consent and any relevant EPL and/or Water Licence (including any assessment, plan or program required under these approvals); (d) review the adequacy of any approved strategy, plan or program required under the these approvals; (e) recommend measures or actions to improve the environmental performance of the development, and/or any assessment, plan or program required under these approvals; and (f) be conducted and reported to the satisfaction of the Secretary. Note: This audit team must be led by a suitably qualified auditor and include experts in any fields specified by the Secretary. Within 12 weeks of commencing this audit, or as otherwise agreed by the Secretary, the Applicant must submit a copy of the audit report	Annual Review 2020, 2021, 2022, 2023 This audit. DPE Letter dated 1 December 2023, approving audit team. Letter sent to relevant agencies and responses appended to the audit report. This audit. This audit. This audit.	Audit commissioned 4 December 2023, and was originally scheduled for the week the 11th of December 2023. However due to personal circumstances the auditor could not undertake the audit till 11 January 2024. All conditions of consent (Mod 5), statement of commitments (SoC), and the EPL have been audited, along with any assessment, plan or program required under these approvals The adequacy of approved strategies, plans and programs required under the these approval Recommendations provided in the audit report.	Non-compliant Compliant Compliant Compliant Compliant Compliant	
10 (i) INDEPENDE 11 11 (a) 11 (b) 11 (c) 11 (d) 11 (e) 11 (f)	The Applicant must ensure that copies of the Annual Review are submitted to Council and are available to the Community Consultative Committee (see condition 7 of Schedule 5) and any interested person upon request. NT ENVIRONMENTAL AUDIT By 30 September 2017, and every 3 years thereafter, unless the Secretary directs otherwise, the Applicant must commission and pay the full cost of an Independent Environmental Audit of the development. This audit must: (a) be conducted by suitably qualified, experienced and independent team of experts whose appointment has been endorsed by the Secretary; (b) include consultation with the relevant agencies and the CCC; (c) assess the environmental performance of the development and whether it is complying with the relevant requirements in this consent and any relevant EPL and/or Water Licence (including any assessment, plan or program required under these approvals); (d) review the adequacy of any approved strategy, plan or program required under the these approvals; (e) recommend measures or actions to improve the environmental performance of the development, and/or any assessment, plan or program required under these approvals; and (f) be conducted and reported to the satisfaction of the Secretary. Note: This audit team must be led by a suitably qualified auditor and include experts in any fields specified by the Secretary. Within 12 weeks of commencing this audit, or as otherwise agreed by the Secretary, the Applicant must submit a copy of the audit report to the Secretary, Council, EPA and any other NSW agency that requests it, together with its response to any recommendations contained	Annual Review 2020, 2021, 2022, 2023 This audit. DPE Letter dated 1 December 2023, approving audit team. Letter sent to relevant agencies and responses appended to the audit report. This audit. This audit. This audit.	Audit commissioned 4 December 2023, and was originally scheduled for the week the 11th of December 2023. However due to personal circumstances the auditor could not undertake the audit till 11 January 2024. All conditions of consent (Mod 5), statement of commitments (SoC), and the EPL have been audited, along with any assessment, plan or program required under these approvals The adequacy of approved strategies, plans and programs required under the these approval Recommendations provided in the audit report.	Non-compliant Compliant Compliant Compliant Compliant Compliant Compliant	
10 (i) INDEPENDE 11 11 (a) 11 (b) 11 (c) 11 (d) 11 (e) 11 (f)	The Applicant must ensure that copies of the Annual Review are submitted to Council and are available to the Community Consultative Committee (see condition 7 of Schedule 5) and any interested person upon request. NT ENVIRONMENTAL AUDIT By 30 September 2017, and every 3 years thereafter, unless the Secretary directs otherwise, the Applicant must commission and pay the full cost of an Independent Environmental Audit of the development. This audit must: (a) be conducted by suitably qualified, experienced and independent team of experts whose appointment has been endorsed by the Secretary; (b) include consultation with the relevant agencies and the CCC; (c) assess the environmental performance of the development and whether it is complying with the relevant requirements in this consent and any relevant EPL and/or Water Licence (including any assessment, plan or program required under these approvals); (d) review the adequacy of any approved strategy, plan or program required under the these approvals; (e) recommend measures or actions to improve the environmental performance of the development, and/or any assessment, plan or program required under these approvals; and (f) be conducted and reported to the satisfaction of the Secretary. Note: This audit team must be led by a suitably qualified auditor and include experts in any fields specified by the Secretary. Within 12 weeks of commencing this audit, or as otherwise agreed by the Secretary, the Applicant must submit a copy of the audit report	Annual Review 2020, 2021, 2022, 2023 This audit. DPE Letter dated 1 December 2023, approving audit team. Letter sent to relevant agencies and responses appended to the audit report. This audit. This audit. This audit.	Audit commissioned 4 December 2023, and was originally scheduled for the week the 11th of December 2023. However due to personal circumstances the auditor could not undertake the audit till 11 January 2024. All conditions of consent (Mod 5), statement of commitments (SoC), and the EPL have been audited, along with any assessment, plan or program required under these approvals The adequacy of approved strategies, plans and programs required under the these approvals Recommendations provided in the audit report. To be confirmed by DPHI following submission of the audit.	Non-compliant Compliant Compliant Compliant Compliant Compliant Compliant	
10 (i) INDEPENDE 11 11 (a) 11 (b) 11 (c) 11 (d) 11 (e) 11 (f)	The Applicant must ensure that copies of the Annual Review are submitted to Council and are available to the Community Consultative Committee (see condition 7 of Schedule 5) and any interested person upon request. NT ENVIRONMENTAL AUDIT By 30 September 2017, and every 3 years thereafter, unless the Secretary directs otherwise, the Applicant must commission and pay the full cost of an Independent Environmental Audit of the development. This audit must: (a) be conducted by suitably qualified, experienced and independent team of experts whose appointment has been endorsed by the Secretary; (b) include consultation with the relevant agencies and the CCC; (c) assess the environmental performance of the development and whether it is complying with the relevant requirements in this consent and any relevant EPL and/or Water Licence (including any assessment, plan or program required under these approvals); (d) review the adequacy of any approved strategy, plan or program required under the these approvals; (e) recommend measures or actions to improve the environmental performance of the development, and/or any assessment, plan or program required under these approvals; and (f) be conducted and reported to the satisfaction of the Secretary. Note: This audit team must be led by a suitably qualified auditor and include experts in any fields specified by the Secretary. Within 12 weeks of commencing this audit, or as otherwise agreed by the Secretary, the Applicant must submit a copy of the audit report to the Secretary, Council, EPA and any other NSW agency that requests it, together with its response to any recommendations contained in the audit report.	Annual Review 2020, 2021, 2022, 2023 This audit. DPE Letter dated 1 December 2023, approving audit team. Letter sent to relevant agencies and responses appended to the audit report. This audit. This audit. This audit.	Audit commissioned 4 December 2023, and was originally scheduled for the week the 11th of December 2023. However due to personal circumstances the auditor could not undertake the audit till 11 January 2024. All conditions of consent (Mod 5), statement of commitments (SoC), and the EPL have been audited, along with any assessment, plan or program required under these approvals The adequacy of approved strategies, plans and programs required under the these approvals Recommendations provided in the audit report. To be confirmed by DPHI following submission of the audit.	Non-compliant Compliant Compliant Compliant Compliant Compliant Compliant	
10 (i) INDEPENDE 11 11 (a) 11 (b) 11 (c) 11 (d) 11 (e) 11 (f) 12 ACCESS TO 13	The Applicant must ensure that copies of the Annual Review are submitted to Council and are available to the Community Consultative Committee (see condition 7 of Schedule 5) and any interested person upon request. NT ENVIRONMENTAL AUDIT By 30 September 2017, and every 3 years thereafter, unless the Secretary directs otherwise, the Applicant must commission and pay the full cost of an Independent Environmental Audit of the development. This audit must: (a) be conducted by suitably qualified, experienced and independent team of experts whose appointment has been endorsed by the Secretary; (b) include consultation with the relevant agencies and the CCC; (c) assess the environmental performance of the development and whether it is complying with the relevant requirements in this consent and any relevant EPL and/or Water Licence (including any assessment, plan or program required under these approvals; (d) review the adequacy of any approved strategy, plan or program required under the these approvals; (e) recommend measures or actions to improve the environmental performance of the development, and/or any assessment, plan or program required under these approvals; (e) recommend measures or actions to improve the environmental performance of the development, and/or any assessment, plan or program required under these approvals; (e) recommend measures or actions to improve the environmental performance of the development, and/or any assessment, plan or program required under these approvals; (e) recommend measures or actions to improve the environmental performance of the development, and/or any assessment, plan or program required under these approvals; (e) recommend measures or actions to improve the environmental performance of the development, and/or any assessment, plan or program required under these approvals; (e) recommend measures or actions to improve the environmental performance of the development, and/or any assessment, plan or program required under these approvals; (e) recommend measures o	Annual Review 2020, 2021, 2022, 2023 This audit. DPE Letter dated 1 December 2023, approving audit team. Letter sent to relevant agencies and responses appended to the audit report. This audit. This audit. This audit.	Audit commissioned 4 December 2023, and was originally scheduled for the week the 11th of December 2023. However due to personal circumstances the auditor could not undertake the audit till 11 January 2024. All conditions of consent (Mod 5), statement of commitments (SoC), and the EPL have been audited, along with any assessment, plan or program required under these approvals The adequacy of approved strategies, plans and programs required under the these approvals Recommendations provided in the audit report. To be confirmed by DPHI following submission of the audit.	Non-compliant Compliant Compliant Compliant Compliant Compliant Compliant	
10 (i) INDEPENDE 11 11 (a) 11 (b) 11 (c) 11 (d) 11 (e) 11 (f) 12 ACCESS TO 13	The Applicant must ensure that copies of the Annual Review are submitted to Council and are available to the Community Consultative Committee (see condition 7 of Schedule 5) and any interested person upon request. NT ENVIRONMENTAL AUDIT By 30 September 2017, and every 3 years thereafter, unless the Secretary directs otherwise, the Applicant must commission and pay the full cost of an Independent Environmental Audit of the development. This audit must: (a) be conducted by suitably qualified, experienced and independent team of experts whose appointment has been endorsed by the Secretary; (b) include consultation with the relevant agencies and the CCC; (c) assess the environmental performance of the development and whether it is complying with the relevant requirements in this consent and any relevant EPL and/or Water Licence (including any assessment, plan or program required under these approvals); (d) review the adequacy of any approved strategy, plan or program required under the these approvals; (e) recommend measures or actions to improve the environmental performance of the development, and/or any assessment, plan or program required under these approvals; and (f) be conducted and reported to the satisfaction of the Secretary. Note: This audit team must be led by a suitably qualified auditor and include experts in any fields specified by the Secretary. Within 12 weeks of commencing this audit, or as otherwise agreed by the Secretary, the Applicant must submit a copy of the audit report to the Secretary, Council, EPA and any other NSW agency that requests it, together with its response to any recommendations contained in the audit report. NPORNMATION By 30 November 2016, unless otherwise agreed by the Secretary, until the completion of all works, including rehabilitation and	Annual Review 2020, 2021, 2022, 2023 This audit. DPE Letter dated 1 December 2023, approving audit team. Letter sent to relevant agencies and responses appended to the audit report. This audit. This audit. This audit.	Audit commissioned 4 December 2023, and was originally scheduled for the week the 11th of December 2023. However due to personal circumstances the auditor could not undertake the audit till 11 January 2024. All conditions of consent (Mod 5), statement of commitments (SoC), and the EPL have been audited, along with any assessment, plan or program required under these approvals The adequacy of approved strategies, plans and programs required under the these approvals Recommendations provided in the audit report. To be confirmed by DPHI following submission of the audit.	Non-compliant Compliant Compliant Compliant Compliant Compliant Compliant	
10 (i) INDEPENDE 11 11 (a) 11 (b) 11 (c) 11 (d) 11 (e) 11 (f) 12 ACCESS TO 13	The Applicant must ensure that copies of the Annual Review are submitted to Council and are available to the Community Consultative Committee (see condition 7 of Schedule 5) and any interested person upon request. NT ENVIRONMENTAL AUDIT By 30 September 2017, and every 3 years thereafter, unless the Secretary directs otherwise, the Applicant must commission and pay the full cost of an Independent Environmental Audit of the development. This audit must: (a) be conducted by suitably qualified, experienced and independent team of experts whose appointment has been endorsed by the Secretary; (b) include consultation with the relevant agencies and the CCC; (c) assess the environmental performance of the development and whether it is complying with the relevant requirements in this consent and any relevant EPL and/or Water Licence (including any assessment, plan or program required under these approvals; (d) review the adequacy of any approved strategy, plan or program required under the these approvals; (e) recommend measures or actions to improve the environmental performance of the development, and/or any assessment, plan or program required under these approvals; (e) recommend measures or actions to improve the environmental performance of the development, and/or any assessment, plan or program required under these approvals; (e) recommend measures or actions to improve the environmental performance of the development, and/or any assessment, plan or program required under these approvals; (e) recommend measures or actions to improve the environmental performance of the development, and/or any assessment, plan or program required under these approvals; (e) recommend measures or actions to improve the environmental performance of the development, and/or any assessment, plan or program required under these approvals; (e) recommend measures or actions to improve the environmental performance of the development, and/or any assessment, plan or program required under these approvals; (e) recommend measures o	Annual Review 2020, 2021, 2022, 2023 This audit. DPE Letter dated 1 December 2023, approving audit team. Letter sent to relevant agencies and responses appended to the audit report. This audit. This audit. This audit. Note.	Audit commissioned 4 December 2023, and was originally scheduled for the week the 11th of December 2023. However due to personal circumstances the auditor could not undertake the audit till 11 January 2024. All conditions of consent (Mod 5), statement of commitments (SoC), and the EPL have been audited, along with any assessment, plan or program required under these approvals The adequacy of approved strategies, plans and programs required under the these approvals Recommendations provided in the audit report. To be confirmed by DPHI following submission of the audit.	Non-compliant Compliant Compliant Compliant Compliant Compliant Compliant Compliant	
10 (i) 11 (a) 11 (b) 11 (c) 11 (d) 11 (e) 11 (f) 12 ACCESS TO 13	The Applicant must ensure that copies of the Annual Review are submitted to Council and are available to the Community Consultative Committee (see condition 7 of Schedule 5) and any interested person upon request. NT ENVIRONMENTAL AUDIT By 30 September 2017, and every 3 years thereafter, unless the Secretary directs otherwise, the Applicant must commission and pay the full cost of an Independent Environmental Audit of the development. This audit must: (a) be conducted by suitably qualified, experienced and independent team of experts whose appointment has been endorsed by the Secretary; (b) include consultation with the relevant agencies and the CCC; (c) assess the environmental performance of the development and whether it is complying with the relevant requirements in this consent and any relevant EPL and/or Water Licence (including any assessment, plan or program required under these approvals; (d) review the adequacy of any approved strategy, plan or program required under the these approvals; (e) recommend measures or actions to improve the environmental performance of the development, and/or any assessment, plan or program required under these approvals; (e) recommend measures or actions to improve the environmental performance of the development, and/or any assessment, plan or program required under these approvals; (e) recommend measures or actions to improve the environmental performance of the development, and/or any assessment, plan or program required under these approvals; (e) recommend measures or actions to improve the environmental performance of the development, and/or any assessment, plan or program required under these approvals; (e) recommend measures or actions to improve the environmental performance of the development, and/or any assessment, plan or program required under these approvals; (e) recommend measures or actions to improve the environmental performance of the development, and/or any assessment, plan or program required under these approvals; (e) recommend measures o	Annual Review 2020, 2021, 2022, 2023 This audit. DPE Letter dated 1 December 2023, approving audit team. Letter sent to relevant agencies and responses appended to the audit report. This audit. This audit. This audit. Note. Holcim Lynwood Quarry webpage	Audit commissioned 4 December 2023, and was originally scheduled for the week the 11th of December 2023. However due to personal circumstances the auditor could not undertake the audit till 11 January 2024. All conditions of consent (Mod 5), statement of commitments (SoC), and the EPL have been audited, along with any assessment, plan or program required under these approvals The adequacy of approved strategies, plans and programs required under the these approvals Recommendations provided in the audit report. To be confirmed by DPHI following submission of the audit.	Non-compliant Compliant Compliant Compliant Compliant Compliant Compliant Compliant	
10 (i) 11 (a) 11 (b) 11 (c) 11 (d) 11 (e) 11 (f) 12 ACCESS TO 13	The Applicant must ensure that copies of the Annual Review are submitted to Council and are available to the Community Consultative Committee (see condition 7 of Schedule 5) and any interested person upon request. NT ENVIRONMENTAL AUDIT By 30 September 2017, and every 3 years thereafter, unless the Secretary directs otherwise, the Applicant must commission and pay the full cost of an Independent Environmental Audit of the development. This audit must: (a) be conducted by suitably qualified, experienced and independent team of experts whose appointment has been endorsed by the Secretary; (b) include consultation with the relevant agencies and the CCC; (c) assess the environmental performance of the development and whether it is complying with the relevant requirements in this consent and any relevant EPL and/or Water Licence (including any assessment, plan or program required under these approvals; (d) review the adequacy of any approved strategy, plan or program required under the these approvals; (e) recommend measures or actions to improve the environmental performance of the development, and/or any assessment, plan or program required under these approvals; (e) recommend measures or actions to improve the environmental performance of the development, and/or any assessment, plan or program required under these approvals; (e) recommend measures or actions to improve the environmental performance of the development, and/or any assessment, plan or program required under these approvals; (e) recommend measures or actions to improve the environmental performance of the development, and/or any assessment, plan or program required under these approvals; (e) recommend measures or actions to improve the environmental performance of the development, and/or any assessment, plan or program required under these approvals; (e) recommend measures or actions to improve the environmental performance of the development, and/or any assessment, plan or program required under these approvals; (e) recommend measures o	Annual Review 2020, 2021, 2022, 2023 This audit. DPE Letter dated 1 December 2023, approving audit team. Letter sent to relevant agencies and responses appended to the audit report. This audit. This audit. This audit. Note. Holcim Lynwood Quarry webpage (accessed 12/1/2024)	Audit commissioned 4 December 2023, and was originally scheduled for the week the 11th of December 2023. However due to personal circumstances the auditor could not undertake the audit till 11 January 2024. All conditions of consent (Mod 5), statement of commitments (SoC), and the EPL have been audited, along with any assessment, plan or program required under these approvals The adequacy of approved strategies, plans and programs required under the these approvals Recommendations provided in the audit report. To be confirmed by DPHI following submission of the audit.	Non-compliant Compliant Compliant Compliant Compliant Compliant Compliant Compliant	
10 (i) INDEPENDE 11 11 (a) 11 (b) 11 (c) 11 (d) 11 (e) 11 (f) 12 ACCESS TO 13	The Applicant must ensure that copies of the Annual Review are submitted to Council and are available to the Community Consultative Committee (see condition 7 of Schedule 5) and any interested person upon request. NT ENVIRONMENTAL AUDIT By 30 September 2017, and every 3 years thereafter, unless the Secretary directs otherwise, the Applicant must commission and pay the full cost of an Independent Environmental Audit of the development. This audit must: (a) be conducted by suitably qualified, experienced and independent team of experts whose appointment has been endorsed by the Secretary; (b) include consultation with the relevant agencies and the CCC; (c) assess the environmental performance of the development and whether it is complying with the relevant requirements in this consent and any relevant EPL and/or Water Licence (including any assessment, plan or program required under these approvals; (d) review the adequacy of any approved strategy, plan or program required under the these approvals; (e) recommend measures or actions to improve the environmental performance of the development, and/or any assessment, plan or program required under these approvals; (e) recommend measures or actions to improve the environmental performance of the development, and/or any assessment, plan or program required under these approvals; (e) recommend measures or actions to improve the environmental performance of the development, and/or any assessment, plan or program required under these approvals; (e) recommend measures or actions to improve the environmental performance of the development, and/or any assessment, plan or program required under these approvals; (e) recommend measures or actions to improve the environmental performance of the development, and/or any assessment, plan or program required under these approvals; (e) recommend measures or actions to improve the environmental performance of the development, and/or any assessment, plan or program required under these approvals; (e) recommend measures o	Annual Review 2020, 2021, 2022, 2023 This audit. DPE Letter dated 1 December 2023, approving audit team. Letter sent to relevant agencies and responses appended to the audit report. This audit. This audit. This audit. Note. Holcim Lynwood Quarry webpage (accessed 12/1/2024) https://www.holcim.com.au/abou	Audit commissioned 4 December 2023, and was originally scheduled for the week the 11th of December 2023. However due to personal circumstances the auditor could not undertake the audit till 11 January 2024. All conditions of consent (Mod 5), statement of commitments (SoC), and the EPL have been audited, along with any assessment, plan or program required under these approvals The adequacy of approved strategies, plans and programs required under the these approva Recommendations provided in the audit report. To be confirmed by DPHI following submission of the audit. Audit submitted within 12 weeks of site inspection.	Non-compliant Compliant Compliant Compliant Compliant Compliant Compliant Compliant	
10 (i) INDEPENDE 11 11 (a) 11 (b) 11 (c) 11 (d) 11 (e) 11 (f) 12 ACCESS TO 13	The Applicant must ensure that copies of the Annual Review are submitted to Council and are available to the Community Consultative Committee (see condition 7 of Schedule 5) and any interested person upon request. NERVIRONMENTAL AUDIT By 30 September 2017, and every 3 years thereafter, unless the Secretary directs otherwise, the Applicant must commission and pay the full cost of an Independent Environmental Audit of the development. This audit must: (a) be conducted by suitably qualified, experienced and independent team of experts whose appointment has been endorsed by the Secretary; (b) include consultation with the relevant agencies and the CCC; (c) assess the environmental performance of the development and whether it is complying with the relevant requirements in this consent and any relevant EPL and/or Water Licence (including any assessment, plan or program required under these approvals); (d) review the adequacy of any approved strategy, plan or program required under the these approvals; (e) recommend measures or actions to improve the environmental performance of the development, and/or any assessment, plan or program required under these approvals; and (f) be conducted and reported to the satisfaction of the Secretary. Note: This audit team must be led by a suitably qualified auditor and include experts in any fields specified by the Secretary. Within 12 weeks of commencing this audit, or as otherwise agreed by the Secretary, the Applicant must submit a copy of the audit report to the Secretary, Council, EPA and any other NSW agency that requests it, together with its response to any recommendations contained in the audit report. NOTEMATION By 30 November 2016, unless otherwise agreed by the Secretary, until the completion of all works, including rehabilitation and remediation, the Applicant must: a) make the following information publicly available on its website:	Annual Review 2020, 2021, 2022, 2023 This audit. DPE Letter dated 1 December 2023, approving audit team. Letter sent to relevant agencies and responses appended to the audit report. This audit. This audit. This audit. Note. Holcim Lynwood Quarry webpage (accessed 12/1/2024) https://www.holcim.com.au/abou t-us/community link/Lynwood/planning-approvals reporting	Audit commissioned 4 December 2023, and was originally scheduled for the week the 11th of December 2023. However due to personal circumstances the auditor could not undertake the audit till 11 January 2024. All conditions of consent (Mod 5), statement of commitments (SoC), and the EPL have been audited, along with any assessment, plan or program required under these approvals The adequacy of approved strategies, plans and programs required under the these approva Recommendations provided in the audit report. To be confirmed by DPHI following submission of the audit. Audit submitted within 12 weeks of site inspection.	Non-compliant Compliant Compliant Compliant Compliant Compliant Compliant Compliant Compliant Compliant	
10 (i) INDEPENDE 11 11 (a) 11 (b) 11 (c) 11 (d) 11 (e) 11 (f) 12 ACCESS TO 13	The Applicant must ensure that copies of the Annual Review are submitted to Council and are available to the Community Consultative Committee (see condition 7 of Schedule 5) and any interested person upon request. NERVIRONMENTAL AUDIT By 30 September 2017, and every 3 years thereafter, unless the Secretary directs otherwise, the Applicant must commission and pay the full cost of an Independent Environmental Audit of the development. This audit must: (a) be conducted by suitably qualified, experienced and independent team of experts whose appointment has been endorsed by the Secretary; (b) include consultation with the relevant agencies and the CCC; (c) assess the environmental performance of the development and whether it is complying with the relevant requirements in this consent and any relevant EPL and/or Water Licence (including any assessment, plan or program required under these approvals); (d) review the adequacy of any approved strategy, plan or program required under the these approvals; (e) recommend measures or actions to improve the environmental performance of the development, and/or any assessment, plan or program required under these approvals; and (f) be conducted and reported to the satisfaction of the Secretary. Note: This audit team must be led by a suitably qualified auditor and include experts in any fields specified by the Secretary. Within 12 weeks of commencing this audit, or as otherwise agreed by the Secretary, the Applicant must submit a copy of the audit report to the Secretary, Council, EPA and any other NSW agency that requests it, together with its response to any recommendations contained in the audit report. NOTEMATION By 30 November 2016, unless otherwise agreed by the Secretary, until the completion of all works, including rehabilitation and remediation, the Applicant must: a) make the following information publicly available on its website:	Annual Review 2020, 2021, 2022, 2023 This audit. DPE Letter dated 1 December 2023, approving audit team. Letter sent to relevant agencies and responses appended to the audit report. This audit. This audit. This audit. Note. Holcim Lynwood Quarry webpage (accessed 12/1/2024) https://www.holcim.com.au/abou t-us/community link/Lynwood/planning-approvals reporting Holcim Lynwood Quarry webpage	Audit commissioned 4 December 2023, and was originally scheduled for the week the 11th of December 2023. However due to personal circumstances the auditor could not undertake the audit till 11 January 2024. All conditions of consent (Mod 5), statement of commitments (SoC), and the EPL have been audited, along with any assessment, plan or program required under these approvals The adequacy of approved strategies, plans and programs required under the these approva Recommendations provided in the audit report. To be confirmed by DPHI following submission of the audit. Audit submitted within 12 weeks of site inspection.	Non-compliant Compliant Compliant Compliant Compliant Compliant Compliant Compliant Compliant Compliant	
10 (i) INDEPENDE 11 11 (a) 11 (b) 11 (c) 11 (d) 11 (e) 11 (f) 12 ACCESS TO 13	The Applicant must ensure that copies of the Annual Review are submitted to Council and are available to the Community Consultative Committee (see condition 7 of Schedule 5) and any interested person upon request. NERVIRONMENTAL AUDIT By 30 September 2017, and every 3 years thereafter, unless the Secretary directs otherwise, the Applicant must commission and pay the full cost of an Independent Environmental Audit of the development. This audit must: (a) be conducted by suitably qualified, experienced and independent team of experts whose appointment has been endorsed by the Secretary; (b) include consultation with the relevant agencies and the CCC; (c) assess the environmental performance of the development and whether it is complying with the relevant requirements in this consent and any relevant EPL and/or Water Licence (including any assessment, plan or program required under these approvals); (d) review the adequacy of any approved strategy, plan or program required under the these approvals; (e) recommend measures or actions to improve the environmental performance of the development, and/or any assessment, plan or program required under these approvals; and (f) be conducted and reported to the satisfaction of the Secretary. Note: This audit team must be led by a suitably qualified auditor and include experts in any fields specified by the Secretary. Within 12 weeks of commencing this audit, or as otherwise agreed by the Secretary, the Applicant must submit a copy of the audit report to the Secretary, Council, EPA and any other NSW agency that requests it, together with its response to any recommendations contained in the audit report. NOTEMATION By 30 November 2016, unless otherwise agreed by the Secretary, until the completion of all works, including rehabilitation and remediation, the Applicant must: a) make the following information publicly available on its website:	Annual Review 2020, 2021, 2022, 2023 This audit. DPE Letter dated 1 December 2023, approving audit team. Letter sent to relevant agencies and responses appended to the audit report. This audit. This audit. This audit. Note. Holcim Lynwood Quarry webpage (accessed 12/1/2024) https://www.holcim.com.au/abou t-us/community link/Lynwood/planning-approvals reporting Holcim Lynwood Quarry webpage (accessed 12/1/2024)	Audit commissioned 4 December 2023, and was originally scheduled for the week the 11th of December 2023. However due to personal circumstances the auditor could not undertake the audit till 11 January 2024. All conditions of consent (Mod 5), statement of commitments (SoC), and the EPL have been audited, along with any assessment, plan or program required under these approvals The adequacy of approved strategies, plans and programs required under the these approva Recommendations provided in the audit report. To be confirmed by DPHI following submission of the audit. Audit submitted within 12 weeks of site inspection.	Non-compliant Compliant Compliant Compliant Compliant Compliant Compliant Compliant Compliant Compliant	
10 (i) INDEPENDE 11 11 (a) 11 (b) 11 (c) 11 (d) 11 (e) 11 (f) 12 ACCESS TO 13	The Applicant must ensure that copies of the Annual Review are submitted to Council and are available to the Community Consultative Committee (see condition 7 of Schedule 5) and any interested person upon request. NT ENVIRONMENTAL AUDIT By 30 September 2017, and every 3 years thereafter, unless the Secretary directs otherwise, the Applicant must commission and pay the full cost of an Independent Environmental Audit of the development. This audit must: (a) be conducted by suitably qualified, experienced and independent team of experts whose appointment has been endorsed by the Secretary; (b) include consultation with the relevant agencies and the CCC; (c) assess the environmental performance of the development and whether it is complying with the relevant requirements in this consent and any relevant EPL and/or Water Licence (including any assessment, plan or program required under these approvals); (d) review the adequacy of any approved strategy, plan or program required under the these approvals; (e) recommend measures or actions to improve the environmental performance of the development, and/or any assessment, plan or program required under these approvals; and (f) be conducted and reported to the satisfaction of the Secretary. Note: This audit team must be led by a suitably qualified auditor and include experts in any fields specified by the Secretary. Within 12 weeks of commencing this audit, or as otherwise agreed by the Secretary, the Applicant must submit a copy of the audit report to the Secretary, Council, EPA and any other NSW agency that requests it, together with its response to any recommendations contained in the audit report. Noomation By 30 November 2016, unless otherwise agreed by the Secretary, until the completion of all works, including rehabilitation and remediation, the Applicant must: a) make the following information publicly available on its website:	Annual Review 2020, 2021, 2022, 2023 This audit. DPE Letter dated 1 December 2023, approving audit team. Letter sent to relevant agencies and responses appended to the audit report. This audit. This audit. This audit. Note. Holcim Lynwood Quarry webpage (accessed 12/1/2024) https://www.holcim.com.au/abou t-us/community link/Lynwood/planning-approvals reporting Holcim Lynwood Quarry webpage (accessed 12/1/2024) https://www.holcim.com.au/abou	Audit commissioned 4 December 2023, and was originally scheduled for the week the 11th of December 2023. However due to personal circumstances the auditor could not undertake the audit till 11 January 2024. All conditions of consent (Mod 5), statement of commitments (SoC), and the EPL have been audited, along with any assessment, plan or program required under these approvals The adequacy of approved strategies, plans and programs required under the these approva Recommendations provided in the audit report. To be confirmed by DPHI following submission of the audit. Audit submitted within 12 weeks of site inspection. Documents available online Documents available online	Non-compliant Compliant Compliant Compliant Compliant Compliant Compliant Compliant Compliant Compliant	
10 (i) INDEPENDE 11 11 (a) 11 (b) 11 (c) 11 (d) 11 (e) 11 (f) 12 ACCESS TO 13	The Applicant must ensure that copies of the Annual Review are submitted to Council and are available to the Community Consultative Committee (see condition 7 of Schedule 5) and any interested person upon request. NT ENVIRONMENTAL AUDIT By 30 September 2017, and every 3 years thereafter, unless the Secretary directs otherwise, the Applicant must commission and pay the full cost of an Independent Environmental Audit of the development. This audit must: (a) be conducted by suitably qualified, experienced and independent team of experts whose appointment has been endorsed by the Secretary; (b) include consultation with the relevant agencies and the CCC; (c) assess the environmental performance of the development and whether it is complying with the relevant requirements in this consent and any relevant EPL and/or Water Licence (including any assessment, plan or program required under these approvals); (d) review the adequacy of any approved strategy, plan or program required under the these approvals; (e) recommend measures or actions to improve the environmental performance of the development, and/or any assessment, plan or program required under these approvals; and (f) be conducted and reported to the satisfaction of the Secretary. Note: This audit team must be led by a suitably qualified auditor and include experts in any fields specified by the Secretary. Within 12 weeks of commencing this audit, or as otherwise agreed by the Secretary, the Applicant must submit a copy of the audit report to the Secretary, Council, EPA and any other NSW agency that requests it, together with its response to any recommendations contained in the audit report. Noomation By 30 November 2016, unless otherwise agreed by the Secretary, until the completion of all works, including rehabilitation and remediation, the Applicant must: a) make the following information publicly available on its website:	Annual Review 2020, 2021, 2022, 2023 This audit. DPE Letter dated 1 December 2023, approving audit team. Letter sent to relevant agencies and responses appended to the audit report. This audit. This audit. This audit. Note. Holcim Lynwood Quarry webpage (accessed 12/1/2024) https://www.holcim.com.au/abou t-us/community link/Lynwood/planning-approvals reporting Holcim Lynwood Quarry webpage (accessed 12/1/2024) https://www.holcim.com.au/abou t-us/community link/Lynwood/planning-approvals reporting t-us/community link/Lynwood/planning-approvals reporting t-us/community link/Lynwood/planning-approvals reporting	Audit commissioned 4 December 2023, and was originally scheduled for the week the 11th of December 2023. However due to personal circumstances the auditor could not undertake the audit till 11 January 2024. All conditions of consent (Mod 5), statement of commitments (SoC), and the EPL have been audited, along with any assessment, plan or program required under these approvals The adequacy of approved strategies, plans and programs required under the these approva Recommendations provided in the audit report. To be confirmed by DPHI following submission of the audit. Audit submitted within 12 weeks of site inspection. Documents available online Documents available online	Non-compliant Compliant	
10 (i) INDEPENDE 11 11 (a) 11 (b) 11 (c) 11 (d) 11 (e) 11 (f) 12 ACCESS TO 13	The Applicant must ensure that copies of the Annual Review are submitted to Council and are available to the Community Consultative Committee (see condition 7 of Schedule 5) and any interested person upon request. NT ENVIRONMENTAL AUDIT By 30 September 2017, and every 3 years thereafter, unless the Secretary directs otherwise, the Applicant must commission and pay the full cost of an Independent Environmental Audit of the development. This audit must: (a) be conducted by suitably qualified, experienced and independent team of experts whose appointment has been endorsed by the Secretary; (b) include consultation with the relevant agencies and the CCC; (c) assess the environmental performance of the development and whether it is complying with the relevant requirements in this consent and any relevant EPL and/or Water Licence (including any assessment, plan or program required under these approvals); (d) review the adequacy of any approved strategy, plan or program required under the these approvals; (e) recommend measures or actions to improve the environmental performance of the development, and/or any assessment, plan or program required under these approvals; and (f) be conducted and reported to the satisfaction of the Secretary. Note: This audit team must be led by a suitably qualified auditor and include experts in any fields specified by the Secretary. Within 12 weeks of commencing this audit, or as otherwise agreed by the Secretary, the Applicant must submit a copy of the audit report to the Secretary, Council, EPA and any other NSW agency that requests it, together with its response to any recommendations contained in the audit report. Noomation By 30 November 2016, unless otherwise agreed by the Secretary, until the completion of all works, including rehabilitation and remediation, the Applicant must: a) make the following information publicly available on its website:	Annual Review 2020, 2021, 2022, 2023 This audit. DPE Letter dated 1 December 2023, approving audit team. Letter sent to relevant agencies and responses appended to the audit report. This audit. This audit. This audit. Note. Holcim Lynwood Quarry webpage (accessed 12/1/2024) https://www.holcim.com.au/abou t-us/community link/Lynwood/planning-approvals reporting Holcim Lynwood Quarry webpage (accessed 12/1/2024) https://www.holcim.com.au/abou t-us/community link/Lynwood/planning-approvals reporting Holcim Lynwood Quarry webpage (accessed 12/1/2024) https://www.holcim.com.au/abou t-us/community link/Lynwood/planning-approvals reporting Holcim Lynwood Quarry webpage	Audit commissioned 4 December 2023, and was originally scheduled for the week the 11th of December 2023. However due to personal circumstances the auditor could not undertake the audit till 11 January 2024. All conditions of consent (Mod 5), statement of commitments (SoC), and the EPL have been audited, along with any assessment, plan or program required under these approvals The adequacy of approved strategies, plans and programs required under the these approva Recommendations provided in the audit report. To be confirmed by DPHI following submission of the audit. Audit submitted within 12 weeks of site inspection. Documents available online Documents available online	Non-compliant Compliant	
10 (i) INDEPENDE 11 11 (a) 11 (b) 11 (c) 11 (d) 11 (e) 11 (f) 12 ACCESS TO 13	The Applicant must ensure that copies of the Annual Review are submitted to Council and are available to the Community Consultative Committee (see condition 7 of Schedule 5) and any interested person upon request. NT ENVIRONMENTAL AUDIT By 30 September 2017, and every 3 years thereafter, unless the Secretary directs otherwise, the Applicant must commission and pay the full cost of an Independent Environmental Audit of the development. This audit must: (a) be conducted by suitably qualified, experienced and independent team of experts whose appointment has been endorsed by the Secretary; (b) include consultation with the relevant agencies and the CCC; (c) assess the environmental performance of the development and whether it is complying with the relevant requirements in this consent and any relevant EPL and/or Water Licence (including any assessment, plan or program required under these approvals); (d) review the adequacy of any approved strategy, plan or program required under the these approvals; (e) recommend measures or actions to improve the environmental performance of the development, and/or any assessment, plan or program required under these approvals; and (f) be conducted and reported to the satisfaction of the Secretary. Note: This audit team must be led by a suitably qualified auditor and include experts in any fields specified by the Secretary. Within 12 weeks of commencing this audit, or as otherwise agreed by the Secretary, the Applicant must submit a copy of the audit report to the Secretary, Council, EPA and any other NSW agency that requests it, together with its response to any recommendations contained in the audit report. Noomation By 30 November 2016, unless otherwise agreed by the Secretary, until the completion of all works, including rehabilitation and remediation, the Applicant must: a) make the following information publicly available on its website:	Annual Review 2020, 2021, 2022, 2023 This audit. DPE Letter dated 1 December 2023, approving audit team. Letter sent to relevant agencies and responses appended to the audit report. This audit. This audit. This audit. Note. Holcim Lynwood Quarry webpage (accessed 12/1/2024) https://www.holcim.com.au/abou t-us/community link/Lynwood/planning-approvals reporting Holcim Lynwood Quarry webpage (accessed 12/1/2024) https://www.holcim.com.au/abou t-us/community link/Lynwood/planning-approvals reporting Holcim Lynwood Quarry webpage (accessed 12/1/2024) https://www.holcim.com.au/abou t-us/community link/Lynwood/planning-approvals reporting Holcim Lynwood Quarry webpage (accessed 12/1/2024)	Audit commissioned 4 December 2023, and was originally scheduled for the week the 11th of December 2023. However due to personal circumstances the auditor could not undertake the audit till 11 January 2024. All conditions of consent (Mod 5), statement of commitments (SoC), and the EPL have been audited, along with any assessment, plan or program required under these approvals The adequacy of approved strategies, plans and programs required under the these approva Recommendations provided in the audit report. To be confirmed by DPHI following submission of the audit. Audit submitted within 12 weeks of site inspection. Documents available online Documents available online	Non-compliant Compliant	
10 (i) INDEPENDE 11 11 (a) 11 (b) 11 (c) 11 (d) 11 (e) 11 (f) 12 ACCESS TO	The Applicant must ensure that copies of the Annual Review are submitted to Council and are available to the Community Consultative Committee (see condition 7 of Schedule 5) and any interested person upon request. NT ENVIRONMENTAL AUDIT By 30 September 2017, and every 3 years thereafter, unless the Secretary directs otherwise, the Applicant must commission and pay the full cost of an Independent Environmental Audit of the development. This audit must: (a) be conducted by suitably qualified, experienced and independent team of experts whose appointment has been endorsed by the Secretary; (b) include consultation with the relevant agencies and the CCC; (c) assess the environmental performance of the development and whether it is complying with the relevant requirements in this consent and any relevant EPL and/or Water Licence (including any assessment, plan or program required under these approvals); (d) review the adequacy of any approved strategy, plan or program required under the these approvals; (e) recommend measures or actions to improve the environmental performance of the development, and/or any assessment, plan or program required under these approvals; and (f) be conducted and reported to the satisfaction of the Secretary. Note: This audit team must be led by a suitably qualified auditor and include experts in any fields specified by the Secretary. Within 12 weeks of commencing this audit, or as otherwise agreed by the Secretary, the Applicant must submit a copy of the audit report to the Secretary, Council, EPA and any other NSW agency that requests it, together with its response to any recommendations contained in the audit report. Noomation By 30 November 2016, unless otherwise agreed by the Secretary, until the completion of all works, including rehabilitation and remediation, the Applicant must: a) make the following information publicly available on its website:	Annual Review 2020, 2021, 2022, 2023 This audit. DPE Letter dated 1 December 2023, approving audit team. Letter sent to relevant agencies and responses appended to the audit report. This audit. This audit. This audit. Note. Holcim Lynwood Quarry webpage (accessed 12/1/2024) https://www.holcim.com.au/abou t-us/community link/Lynwood/planning-approvals reporting Holcim Lynwood Quarry webpage (accessed 12/1/2024) https://www.holcim.com.au/abou t-us/community link/Lynwood/planning-approvals reporting Holcim Lynwood Quarry webpage (accessed 12/1/2024) https://www.holcim.com.au/abou t-us/community link/Lynwood/planning-approvals reporting Holcim Lynwood Quarry webpage (accessed 12/1/2024) https://www.holcim.com.au/abou	Audit commissioned 4 December 2023, and was originally scheduled for the week the 11th of December 2023. However due to personal circumstances the auditor could not undertake the audit till 11 January 2024. All conditions of consent (Mod 5), statement of commitments (SoC), and the EPL have been audited, along with any assessment, plan or program required under these approvals The adequacy of approved strategies, plans and programs required under the these approva Recommendations provided in the audit report. To be confirmed by DPHI following submission of the audit. Audit submitted within 12 weeks of site inspection. Documents available online Documents available online	Non-compliant Compliant	
10 (i) INDEPENDE 11 11 (a) 11 (b) 11 (c) 11 (d) 11 (e) 11 (f) 12 ACCESS TO	The Applicant must ensure that copies of the Annual Review are submitted to Council and are available to the Community Consultative Committee (see condition 7 of Schedule 5) and any interested person upon request. WENTIRONMENTAL AUDIT By 30 September 2017, and every 3 years thereafter, unless the Secretary directs otherwise, the Applicant must commission and pay the full cost of an Independent Environmental Audit of the development. This audit must: (a) be conducted by suitably qualified, experienced and independent team of experts whose appointment has been endorsed by the Secretary; (b) include consultation with the relevant agencies and the CCC; (c) assess the environmental performance of the development and whether it is complying with the relevant requirements in this consent and any relevant EPL and/or Water Licence (including any assessment, plan or program required under these approvals); (d) review the adequacy of any approved strategy, plan or program required under the these approvals; (e) recommend measures or actions to improve the environmental performance of the development, and/or any assessment, plan or program required under these approvals; and (f) be conducted and reported to the satisfaction of the Secretary. Note: This audit team must be led by a suitably qualified auditor and include experts in any fields specified by the Secretary. Within 12 weeks of commencing this audit, or as otherwise agreed by the Secretary, the Applicant must submit a copy of the audit report to the Secretary, Council, EPA and any other NSW agency that requests it, together with its response to any recommendations contained in the audit report. **THIS MACHON** By 30 November 2016, unless otherwise agreed by the Secretary, until the completion of all works, including rehabilitation and remediation, the Applicant must: a) make the following information publicly available on its website: **the documents listed in condition 2(a) of Schedule 2;	Annual Review 2020, 2021, 2022, 2023 This audit. DPE Letter dated 1 December 2023, approving audit team. Letter sent to relevant agencies and responses appended to the audit report. This audit. This audit. This audit. Note. Holcim Lynwood Quarry webpage (accessed 12/1/2024) https://www.holcim.com.au/abou t-us/community link/Lynwood/planning-approvals reporting Holcim Lynwood Quarry webpage (accessed 12/1/2024) https://www.holcim.com.au/abou t-us/community link/Lynwood/planning-approvals reporting Holcim Lynwood Quarry webpage (accessed 12/1/2024) https://www.holcim.com.au/abou t-us/community link/Lynwood/planning-approvals reporting Holcim Lynwood Quarry webpage (accessed 12/1/2024) https://www.holcim.com.au/abou t-us/community link/Lynwood/planning-approvals reporting t-us/community link/Lynwood/planning-approvals reporting	Audit commissioned 4 December 2023, and was originally scheduled for the week the 11th of December 2023. However due to personal circumstances the auditor could not undertake the audit till 11 January 2024. All conditions of consent (Mod 5), statement of commitments (SoC), and the EPL have been audited, along with any assessment, plan or program required under these approvals The adequacy of approved strategies, plans and programs required under the these approva Recommendations provided in the audit report. To be confirmed by DPHI following submission of the audit. Audit submitted within 12 weeks of site inspection. Documents available online Documents available online	Non-compliant Compliant	
10 (i) INDEPENDE 11 11 (a) 11 (b) 11 (c) 11 (d) 11 (e) 11 (f) 12 ACCESS TO	The Applicant must ensure that copies of the Annual Review are submitted to Council and are available to the Community Consultative Committee (see condition 7 of Schedule 5) and any interested person upon request. WENTIRONMENTAL AUDIT By 30 September 2017, and every 3 years thereafter, unless the Secretary directs otherwise, the Applicant must commission and pay the full cost of an Independent Environmental Audit of the development. This audit must: (a) be conducted by suitably qualified, experienced and independent team of experts whose appointment has been endorsed by the Secretary; (b) include consultation with the relevant agencies and the CCC; (c) assess the environmental performance of the development and whether it is complying with the relevant requirements in this consent and any relevant EPL and/or Water Licence (including any assessment, plan or program required under these approvals); (d) review the adequacy of any approved strategy, plan or program required under the these approvals; (e) recommend measures or actions to improve the environmental performance of the development, and/or any assessment, plan or program required under these approvals; and (f) be conducted and reported to the satisfaction of the Secretary. Note: This audit team must be led by a suitably qualified auditor and include experts in any fields specified by the Secretary. Within 12 weeks of commencing this audit, or as otherwise agreed by the Secretary, the Applicant must submit a copy of the audit report to the Secretary, Council, EPA and any other NSW agency that requests it, together with its response to any recommendations contained in the audit report. **THIS MACHON** By 30 November 2016, unless otherwise agreed by the Secretary, until the completion of all works, including rehabilitation and remediation, the Applicant must: a) make the following information publicly available on its website: **the documents listed in condition 2(a) of Schedule 2;	Annual Review 2020, 2021, 2022, 2023 This audit. DPE Letter dated 1 December 2023, approving audit team. Letter sent to relevant agencies and responses appended to the audit report. This audit. This audit. This audit. Note. Holcim Lynwood Quarry webpage (accessed 12/1/2024) https://www.holcim.com.au/abou t-us/community link/Lynwood/planning-approvals reporting Holcim Lynwood Quarry webpage (accessed 12/1/2024) https://www.holcim.com.au/abou t-us/community link/Lynwood/planning-approvals reporting Holcim Lynwood Quarry webpage (accessed 12/1/2024) https://www.holcim.com.au/abou t-us/community link/Lynwood/planning-approvals reporting Holcim Lynwood Quarry webpage (accessed 12/1/2024) https://www.holcim.com.au/abou t-us/community link/Lynwood/planning-approvals reporting Holcim Lynwood Quarry webpage	Audit commissioned 4 December 2023, and was originally scheduled for the week the 11th of December 2023. However due to personal circumstances the auditor could not undertake the audit till 11 January 2024. All conditions of consent (Mod 5), statement of commitments (SoC), and the EPL have been audited, along with any assessment, plan or program required under these approvals The adequacy of approved strategies, plans and programs required under the these approva Recommendations provided in the audit report. To be confirmed by DPHI following submission of the audit. Audit submitted within 12 weeks of site inspection. Documents available online Documents available online	Non-compliant Compliant	

	• a summary of the monitoring results of the development, which have been reported in accordance with the various plans and programs	Holcim Lynwood Quarry webpage		Compliant	
	approved under the conditions of this	(accessed 12/1/2024)			
	consent;	https://www.holcim.com.au/abou			
			Documents available online		
	a complaints register, which is to be updated on a quarterly basis;		Documents available offilitie	Compliant	
	* a complaints register, which is to be updated on a quarterly basis,	Holcim Lynwood Quarry webpage		Compliant	
		(accessed 12/1/2024)			
		https://www.holcim.com.au/abou			
		t-us/community link/Lynwood/planning-approvals reporting	Documents available online		
	the Annual Reviews (over the last 5 years);	Holcim Lynwood Quarry webpage		Non-compliant	
		(accessed 12/1/2024)		·	
		https://www.holcim.com.au/abou			
		' ''	Only 2020, 2021 and 2022 AERs available online		NC15
		a soften many and a first second seco	Only 2020, 2021 and 2022 AERS available online		NC15
	any independent environmental audit, and the Applicant's response to the recommendations in any audit;	Holcim Lynwood Quarry webpage		Non-compliant	
		(accessed 12/1/2024)			
		https://www.holcim.com.au/abou			
		t-us/community link/Lynwood/planning-approvals reporting	2012, 2015, 2019, and 2020 IEAs available online. No response to audits available.		NC16
	any other matter required by the Secretary; and	Note.			
	keep this information up-to-date,	Holcim Lynwood Quarry webpage		Compliant	
		(accessed 12/1/2024)			
		https://www.holcim.com.au/abou			
			Wohsita up to data whan accessed 12 January 2022		
	to the extinfaction of the Socratory		Website up to date when accessed 12 January 2023.		
DDENS	to the satisfaction of the Secretary.	Note.			
PPENDIX 1	1: SCHEDULE OF LAND	No. 1			
		Note.			
	2: DEVELOPMENT LAYOUT [Map figure]				
	3. NOISE RECEIVER LOCATIONS [Map figure] 4. LOCATION OF SEDIMENT DAMS [Map figure]				
	4. LOCATION OF SEDIMENT DAMIS [Map figure] 5. CONSTRUCTION TRAFFIC ROUTES [Map figure]				
	6. CULTURAL HERITAGE MANAGEMENT ZONE [Map figure]				
	7: DETAILED HERITAGE CONDITIONS				
	These conditions apply to the portion of the State Heritage Register Area within the site that is impacted by the development.	l		<u> </u>	
		Note.		- "	-
1	The NSW Heritage Office must be informed in writing of the start of the archaeological investigation at least five (5) days prior to the	A		Compliant	
	commencement of, and within five (5) days of the completion of on-site archaeological work.	As per previous audit: LTR_Old Marulan_Sign off_Dec 2010.		0 1: .	
2	The Heritage Council and staff of the NSW Heritage Office authorised under section 148(1) of the 'Heritage Act, 1977' reserve the right to	As not provious audit. Site intensious (2012)	Inspection was conducted on 22/12/07	Compliant	
	inspect the site and records at all times, as well as access any relics recovered from the site.	As per previous audit: Site interviews (2012).	Inspection was conducted on 22/12/07	Compliant	
3	The Applicant must ensure that all personnel involved in excavation works attend a comprehensive briefing on the requirements of the	1		Compliant	
	'Heritage Act, 1977' in relation to archaeological relics and the proposed archaeological programme. The briefing is to be presented by the	1			
	Excavation Director nominated in the section 60 application and is to be undertaken prior to the commencement of on-site works. A copy	As per previous audit: Interview with the Excavation Director, T. Adams			
	of this approval and conditions of consent should be made available to all archaeological on-site staff.	(Umwelt) (6/6/12).			
4	The Applicant must ensure that if substantial intact archaeological deposits and/or State significant relics not identified in Environmental	(0		Compliant	
-	Impact Statement, Readymix Holding Pty Ltd Proposed Lynwood Quarry, Marulan, prepared by Umwelt Environmental Consultants, are			Compilant	
	discovered, work must cease in the affected area(s) and the Heritage Council of NSW must be notified. Additional assessment and	1			
	approval may be required prior to works continuing in the affected area(s) based on the nature of the discovery.		No substantial intact archaeological deposits and/or State significant relics identified in any		
	approval may be required prior to works continuing in the affected area(s) based on the nature of the discovery.	Site interview - W Beattie	reporting.		
5	The Heritage Council of NSW must approve any substantial deviations from the approved research design outlined in Environmental			Compliant	
	Impact Statement, Readymix Holding Pty Ltd Proposed Lynwood Quarry, Marulan , prepared by Umwelt Environmental Consultants,	1	As not provious audit. The SCEA variation 2007/SCE/11 which refers to the approval of the		
	including extent and techniques of excavations, as an application for the variation of an approval under section 65A or a new application		As per previous audit: The S65A variation 2007/S65/11 which refers to the approval of the		
	under section 60 of the 'Heritage Act, 1977'.	, ,	changed research design has not been sighted but subsequent DECC letters note this		
		S65_2009_65A_11 (27/10/10).	variation as occurring.		
6	The Applicant must ensure that the nominated Excavation Director is present at the site supervising all archaeological fieldwork activity	1	Previous audit sighted S65_2009_65A_13, s65 assist director and notification. It is	Compliant	
	likely to expose significant relics 100% of the duration of the archaeological activity. Should this not be possible, then the Applicant must				
	forward for the approval of the Heritage Council or Director of the NSW Heritage Office the details of a Site Director in charge for this		understood no further archaeological fieldwork occurred		
	_neriod		during the audit period.	Carraliant	
/	neriod. At all times during periods of archaeological excavation the Applicant must comply with any directions of the nominated Excavation		As per previous audit: Letter sighted shows that all archaeological salvage works are to be	Compliant	
/	Director in relation to works likely to impact on this resource. Where major issues arise the Excavation Director must consult with the		As per previous audit: Letter sighted shows that all archaeological salvage works are to be completed with involvement from archaeologist	Compliant	
/			As per previous audit: Letter sighted shows that all archaeological salvage works are to be	Compliant	
8	Director in relation to works likely to impact on this resource. Where major issues arise the Excavation Director must consult with the		As per previous audit: Letter sighted shows that all archaeological salvage works are to be completed with involvement from archaeologist	Compliant	
8	Director in relation to works likely to impact on this resource. Where major issues arise the Excavation Director must consult with the Director of the heritage Office prior to issuing directions.		As per previous audit: Letter sighted shows that all archaeological salvage works are to be completed with involvement from archaeologist		
8	Director in relation to works likely to impact on this resource. Where major issues arise the Excavation Director must consult with the Director of the heritage Office prior to issuing directions. Given the exceptional significance of the archaeological remains of the Old Marulan Township, the Applicant must ensure that the		As per previous audit: Letter sighted shows that all archaeological salvage works are to be completed with involvement from archaeologist		
8	Director in relation to works likely to impact on this resource. Where major issues arise the Excavation Director must consult with the Director of the heritage Office prior to issuing directions. Given the exceptional significance of the archaeological remains of the Old Marulan Township, the Applicant must ensure that the nominated Excavation Director, and archaeological excavation team, are given priority when allocating resources to allow thorough	As per previous audit: Holcim letter to OEH dated 15 June 2017	As per previous audit: Letter sighted shows that all archaeological salvage works are to be completed with involvement from archaeologist		
8	Director in relation to works likely to impact on this resource. Where major issues arise the Excavation Director must consult with the Director of the heritage Office prior to issuing directions. Given the exceptional significance of the archaeological remains of the Old Marulan Township, the Applicant must ensure that the nominated Excavation Director, and archaeological excavation team, are given priority when allocating resources to allow thorough archaeological excavation and full and detailed recording to be undertaken to the satisfaction of the Heritage Council. Where necessary, work schedules shall be adjusted to accommodate the approved archaeological works.	As per previous audit: Holcim letter to OEH dated 15 June 2017 As per previous audit: Heritage Branch sign off (16/12/2010).	As per previous audit: Letter sighted shows that all archaeological salvage works are to be completed with involvement from archaeologist		
8	Director in relation to works likely to impact on this resource. Where major issues arise the Excavation Director must consult with the Director of the heritage Office prior to issuing directions. Given the exceptional significance of the archaeological remains of the Old Marulan Township, the Applicant must ensure that the nominated Excavation Director, and archaeological excavation team, are given priority when allocating resources to allow thorough archaeological excavation and full and detailed recording to be undertaken to the satisfaction of the Heritage Council. Where necessary, work schedules shall be adjusted to accommodate the approved archaeological works. Throughout the archaeological excavation works and post-excavation analysis, the Applicant must ensure that:	As per previous audit: Holcim letter to OEH dated 15 June 2017 As per previous audit: Heritage Branch sign off (16/12/2010). Note.	As per previous audit: Letter sighted shows that all archaeological salvage works are to be completed with involvement from archaeologist	Compliant	
9 9(a)	Director in relation to works likely to impact on this resource. Where major issues arise the Excavation Director must consult with the Director of the heritage Office prior to issuing directions. Given the exceptional significance of the archaeological remains of the Old Marulan Township, the Applicant must ensure that the nominated Excavation Director, and archaeological excavation team, are given priority when allocating resources to allow thorough archaeological excavation and full and detailed recording to be undertaken to the satisfaction of the Heritage Council. Where necessary, work schedules shall be adjusted to accommodate the approved archaeological works.	As per previous audit: Holcim letter to OEH dated 15 June 2017 As per previous audit: Heritage Branch sign off (16/12/2010).	As per previous audit: Letter sighted shows that all archaeological salvage works are to be completed with involvement from archaeologist		
	Director in relation to works likely to impact on this resource. Where major issues arise the Excavation Director must consult with the Director of the heritage Office prior to issuing directions. Given the exceptional significance of the archaeological remains of the Old Marulan Township, the Applicant must ensure that the nominated Excavation Director, and archaeological excavation team, are given priority when allocating resources to allow thorough archaeological excavation and full and detailed recording to be undertaken to the satisfaction of the Heritage Council. Where necessary, work schedules shall be adjusted to accommodate the approved archaeological works. Throughout the archaeological excavation works and post-excavation analysis, the Applicant must ensure that:	As per previous audit: Holcim letter to OEH dated 15 June 2017 As per previous audit: Heritage Branch sign off (16/12/2010). Note. Site observations	As per previous audit: Letter sighted shows that all archaeological salvage works are to be completed with involvement from archaeologist	Compliant	
	Director in relation to works likely to impact on this resource. Where major issues arise the Excavation Director must consult with the Director of the heritage Office prior to issuing directions. Given the exceptional significance of the archaeological remains of the Old Marulan Township, the Applicant must ensure that the nominated Excavation Director, and archaeological excavation team, are given priority when allocating resources to allow thorough archaeological excavation and full and detailed recording to be undertaken to the satisfaction of the Heritage Council. Where necessary, work schedules shall be adjusted to accommodate the approved archaeological works. Throughout the archaeological excavation works and post-excavation analysis, the Applicant must ensure that:	As per previous audit: Holcim letter to OEH dated 15 June 2017 As per previous audit: Heritage Branch sign off (16/12/2010). Note. Site observations	As per previous audit: Letter sighted shows that all archaeological salvage works are to be completed with involvement from archaeologist (i.e. monitoring is to be undertaken by archaeologist).	Compliant	
9(a)	Director in relation to works likely to impact on this resource. Where major issues arise the Excavation Director must consult with the Director of the heritage Office prior to issuing directions. Given the exceptional significance of the archaeological remains of the Old Marulan Township, the Applicant must ensure that the nominated Excavation Director, and archaeological excavation team, are given priority when allocating resources to allow thorough archaeological excavation and full and detailed recording to be undertaken to the satisfaction of the Heritage Council. Where necessary, work schedules shall be adjusted to accommodate the approved archaeological works. Throughout the archaeological excavation works and post-excavation analysis, the Applicant must ensure that: Appropriate signage to explain the history of the site and the archaeological excavation works is placed at the site during the work,	As per previous audit: Holcim letter to OEH dated 15 June 2017 As per previous audit: Heritage Branch sign off (16/12/2010). Note. Site observations Site interview - W Beattie Site observations	As per previous audit: Letter sighted shows that all archaeological salvage works are to be completed with involvement from archaeologist (i.e. monitoring is to be undertaken by archaeologist). There are no signs. However, there are no appropriate publicly accessible locations to place to the complete signs.	Compliant Compliant Compliant	
9(a)	Director in relation to works likely to impact on this resource. Where major issues arise the Excavation Director must consult with the Director of the heritage Office prior to issuing directions. Given the exceptional significance of the archaeological remains of the Old Marulan Township, the Applicant must ensure that the nominated Excavation Director, and archaeological excavation team, are given priority when allocating resources to allow thorough archaeological excavation and full and detailed recording to be undertaken to the satisfaction of the Heritage Council. Where necessary, work schedules shall be adjusted to accommodate the approved archaeological works. Throughout the archaeological excavation works and post-excavation analysis, the Applicant must ensure that: Appropriate signage to explain the history of the site and the archaeological excavation works is placed at the site during the work, A local public information program is implemented including press releases to ensure the public is informed about the project and its outcomes,	As per previous audit: Holcim letter to OEH dated 15 June 2017 As per previous audit: Heritage Branch sign off (16/12/2010). Note. Site observations Site interview - W Beattie Site observations Site interview - W Beattie	As per previous audit: Letter sighted shows that all archaeological salvage works are to be completed with involvement from archaeologist (i.e. monitoring is to be undertaken by archaeologist).	Compliant Compliant Compliant	
9(a) 9(b)	Director in relation to works likely to impact on this resource. Where major issues arise the Excavation Director must consult with the Director of the heritage Office prior to issuing directions. Given the exceptional significance of the archaeological remains of the Old Marulan Township, the Applicant must ensure that the nominated Excavation Director, and archaeological excavation team, are given priority when allocating resources to allow thorough archaeological excavation and full and detailed recording to be undertaken to the satisfaction of the Heritage Council. Where necessary, work schedules shall be adjusted to accommodate the approved archaeological works. Throughout the archaeological excavation works and post-excavation analysis, the Applicant must ensure that: Appropriate signage to explain the history of the site and the archaeological excavation works is placed at the site during the work, A local public information program is implemented including press releases to ensure the public is informed about the project and its	As per previous audit: Holcim letter to OEH dated 15 June 2017 As per previous audit: Heritage Branch sign off (16/12/2010). Note. Site observations Site interview - W Beattie Site observations Site interview - W Beattie Site interview - W Beattie	As per previous audit: Letter sighted shows that all archaeological salvage works are to be completed with involvement from archaeologist (i.e. monitoring is to be undertaken by archaeologist). There are no signs. However, there are no appropriate publicly accessible locations to place to some activities occurred during reporting period. Considered compliant on basis of previous au	Compliant Compliant Compliant Compliant	
9(a) 9(b) 9(c)	Director in relation to works likely to impact on this resource. Where major issues arise the Excavation Director must consult with the Director of the heritage Office prior to issuing directions. Given the exceptional significance of the archaeological remains of the Old Marulan Township, the Applicant must ensure that the nominated Excavation Director, and archaeological excavation team, are given priority when allocating resources to allow thorough archaeological excavation and full and detailed recording to be undertaken to the satisfaction of the Heritage Council. Where necessary, work schedules shall be adjusted to accommodate the approved archaeological works. Throughout the archaeological excavation works and post-excavation analysis, the Applicant must ensure that: Appropriate signage to explain the history of the site and the archaeological excavation works is placed at the site during the work, A local public information program is implemented including press releases to ensure the public is informed about the project and its outcomes, Community participation in the archaeological works on the site is allowed for through the inclusion of volunteers on the archaeological team under the supervision of the Excavation Director,	As per previous audit: Holcim letter to OEH dated 15 June 2017 As per previous audit: Heritage Branch sign off (16/12/2010). Note. Site observations Site interview - W Beattie Site observations Site interview - W Beattie Site interview - W Beattie Site interview - W Beattie Old Marulan 2007 - Final Report	As per previous audit: Letter sighted shows that all archaeological salvage works are to be completed with involvement from archaeologist (i.e. monitoring is to be undertaken by archaeologist). There are no signs. However, there are no appropriate publicly accessible locations to place to the complete signs.	Compliant Compliant Compliant	
9(a) 9(b)	Director in relation to works likely to impact on this resource. Where major issues arise the Excavation Director must consult with the Director of the heritage Office prior to issuing directions. Given the exceptional significance of the archaeological remains of the Old Marulan Township, the Applicant must ensure that the nominated Excavation Director, and archaeological excavation team, are given priority when allocating resources to allow thorough archaeological excavation and full and detailed recording to be undertaken to the satisfaction of the Heritage Council. Where necessary, work schedules shall be adjusted to accommodate the approved archaeological works. Throughout the archaeological excavation works and post-excavation analysis, the Applicant must ensure that: Appropriate signage to explain the history of the site and the archaeological excavation works is placed at the site during the work, A local public information program is implemented including press releases to ensure the public is informed about the project and its outcomes, Community participation in the archaeological works on the site is allowed for through the inclusion of volunteers on the archaeological team under the supervision of the Excavation Director, A website addressing the archaeological works on the site must be created. This website must feature a history of the site, archaeological	As per previous audit: Holcim letter to OEH dated 15 June 2017 As per previous audit: Heritage Branch sign off (16/12/2010). Note. Site observations Site interview - W Beattie Site observations Site interview - W Beattie Site interview - W Beattie	As per previous audit: Letter sighted shows that all archaeological salvage works are to be completed with involvement from archaeologist (i.e. monitoring is to be undertaken by archaeologist). There are no signs. However, there are no appropriate publicly accessible locations to place to some activities occurred during reporting period. Considered compliant on basis of previous au	Compliant Compliant Compliant Compliant	
9(a) 9(b) 9(c)	Director in relation to works likely to impact on this resource. Where major issues arise the Excavation Director must consult with the Director of the heritage Office prior to issuing directions. Given the exceptional significance of the archaeological remains of the Old Marulan Township, the Applicant must ensure that the nominated Excavation Director, and archaeological excavation team, are given priority when allocating resources to allow thorough archaeological excavation and full and detailed recording to be undertaken to the satisfaction of the Heritage Council. Where necessary, work schedules shall be adjusted to accommodate the approved archaeological works. Throughout the archaeological excavation works and post-excavation analysis, the Applicant must ensure that: Appropriate signage to explain the history of the site and the archaeological excavation works is placed at the site during the work, A local public information program is implemented including press releases to ensure the public is informed about the project and its outcomes, Community participation in the archaeological works on the site is allowed for through the inclusion of volunteers on the archaeological team under the supervision of the Excavation Director, A website addressing the archaeological works on the site must be created. This website must feature a history of the site, archaeological methodology, updated information on the archaeological works, photographs of the site and significant archaeological remains	As per previous audit: Holcim letter to OEH dated 15 June 2017 As per previous audit: Heritage Branch sign off (16/12/2010). Note. Site observations Site interview - W Beattie Site observations Site interview - W Beattie Site interview - W Beattie Site interview - W Beattie Old Marulan 2007 - Final Report Holcim Lynwood Quarry webpage	As per previous audit: Letter sighted shows that all archaeological salvage works are to be completed with involvement from archaeologist (i.e. monitoring is to be undertaken by archaeologist). There are no signs. However, there are no appropriate publicly accessible locations to place to some activities occurred during reporting period. Considered compliant on basis of previous au	Compliant Compliant Compliant	
9(a) 9(b) 9(c)	Director in relation to works likely to impact on this resource. Where major issues arise the Excavation Director must consult with the Director of the heritage Office prior to issuing directions. Given the exceptional significance of the archaeological remains of the Old Marulan Township, the Applicant must ensure that the nominated Excavation Director, and archaeological excavation team, are given priority when allocating resources to allow thorough archaeological excavation and full and detailed recording to be undertaken to the satisfaction of the Heritage Council. Where necessary, work schedules shall be adjusted to accommodate the approved archaeological works. Throughout the archaeological excavation works and post-excavation analysis, the Applicant must ensure that: Appropriate signage to explain the history of the site and the archaeological excavation works is placed at the site during the work, A local public information program is implemented including press releases to ensure the public is informed about the project and its outcomes, Community participation in the archaeological works on the site is allowed for through the inclusion of volunteers on the archaeological team under the supervision of the Excavation Director, A website addressing the archaeological works on the site must be created. This website must feature a history of the site, archaeological methodology, updated information on the archaeological works, photographs of the site and significant archaeological remains uncovered, links to the archaeological reports and links to other relevant sites. Public feedback must also be allowed for in this section of	As per previous audit: Holcim letter to OEH dated 15 June 2017 As per previous audit: Heritage Branch sign off (16/12/2010). Note. Site observations Site interview - W Beattie Site observations Site interview - W Beattie Site interview - W Beattie Site interview - W Beattie Old Marulan 2007 - Final Report Holcim Lynwood Quarry webpage (accessed 12/1/2024)	As per previous audit: Letter sighted shows that all archaeological salvage works are to be completed with involvement from archaeologist (i.e. monitoring is to be undertaken by archaeologist). There are no signs. However, there are no appropriate publicly accessible locations to place to the control of	Compliant Compliant Compliant	
9(a) 9(b) 9(c)	Director in relation to works likely to impact on this resource. Where major issues arise the Excavation Director must consult with the Director of the heritage Office prior to issuing directions. Given the exceptional significance of the archaeological remains of the Old Marulan Township, the Applicant must ensure that the nominated Excavation Director, and archaeological excavation team, are given priority when allocating resources to allow thorough archaeological excavation and full and detailed recording to be undertaken to the satisfaction of the Heritage Council. Where necessary, work schedules shall be adjusted to accommodate the approved archaeological works. Throughout the archaeological excavation works and post-excavation analysis, the Applicant must ensure that: Appropriate signage to explain the history of the site and the archaeological excavation works is placed at the site during the work, A local public information program is implemented including press releases to ensure the public is informed about the project and its outcomes, Community participation in the archaeological works on the site is allowed for through the inclusion of volunteers on the archaeological team under the supervision of the Excavation Director, A website addressing the archaeological works on the site must be created. This website must feature a history of the site, archaeological methodology, updated information on the archaeological works, photographs of the site and significant archaeological remains uncovered, links to the archaeological reports and links to other relevant sites. Public feedback must also be allowed for in this section of the website. Updated information on the Open Day to be held during archaeological works at Old Marulan Township and an on-line	As per previous audit: Holcim letter to OEH dated 15 June 2017 As per previous audit: Heritage Branch sign off (16/12/2010). Note. Site observations Site interview - W Beattie Site observations Site interview - W Beattie Site interview - W Beattie Site interview - W Beattie Old Marulan 2007 - Final Report Holcim Lynwood Quarry webpage (accessed 12/1/2024) https://www.holcim.com.au/abou	As per previous audit: Letter sighted shows that all archaeological salvage works are to be completed with involvement from archaeologist (i.e. monitoring is to be undertaken by archaeologist). There are no signs. However, there are no appropriate publicly accessible locations to place to the complete of the complet	Compliant Compliant Compliant	
9(a) 9(b) 9(c)	Director in relation to works likely to impact on this resource. Where major issues arise the Excavation Director must consult with the Director of the heritage Office prior to issuing directions. Given the exceptional significance of the archaeological remains of the Old Marulan Township, the Applicant must ensure that the nominated Excavation Director, and archaeological excavation team, are given priority when allocating resources to allow thorough archaeological excavation and full and detailed recording to be undertaken to the satisfaction of the Heritage Council. Where necessary, work schedules shall be adjusted to accommodate the approved archaeological works. Throughout the archaeological excavation works and post-excavation analysis, the Applicant must ensure that: Appropriate signage to explain the history of the site and the archaeological excavation works is placed at the site during the work, A local public information program is implemented including press releases to ensure the public is informed about the project and its outcomes, Community participation in the archaeological works on the site is allowed for through the inclusion of volunteers on the archaeological team under the supervision of the Excavation Director, A website addressing the archaeological works on the site must be created. This website must feature a history of the site, archaeological methodology, updated information on the archaeological works, photographs of the site and significant archaeological remains uncovered, links to the archaeological reports and links to other relevant sites. Public feedback must also be allowed for in this section of the website. Updated information on the Open Day to be held during archaeological works at Old Marulan Township and an on-line hooking service must also be included.	As per previous audit: Holcim letter to OEH dated 15 June 2017 As per previous audit: Heritage Branch sign off (16/12/2010). Note. Site observations Site interview - W Beattie Site observations Site interview - W Beattie Site interview - W Beattie Site interview - W Beattie Old Marulan 2007 - Final Report Holcim Lynwood Quarry webpage (accessed 12/1/2024) https://www.holcim.com.au/abou t-us/community link/Lynwood/planning-approvals reporting	As per previous audit: Letter sighted shows that all archaeological salvage works are to be completed with involvement from archaeologist (i.e. monitoring is to be undertaken by archaeologist). There are no signs. However, there are no appropriate publicly accessible locations to place to the notivities occurred during reporting period. Considered compliant on basis of previous audit No activities occurred during reporting period. Considered compliant on basis of previous audit No activities occurred during reporting period. Considered compliant on basis of previous audit No works were undertaken during the audit period. Considered complaint on basis of final report and previous audit.	Compliant Compliant Compliant Compliant Compliant	
9(a) 9(b) 9(c)	Director in relation to works likely to impact on this resource. Where major issues arise the Excavation Director must consult with the Director of the heritage Office prior to issuing directions. Given the exceptional significance of the archaeological remains of the Old Marulan Township, the Applicant must ensure that the nominated Excavation Director, and archaeological excavation team, are given priority when allocating resources to allow thorough archaeological excavation and full and detailed recording to be undertaken to the satisfaction of the Heritage Council. Where necessary, work schedules shall be adjusted to accommodate the approved archaeological works. Throughout the archaeological excavation works and post-excavation analysis, the Applicant must ensure that: Appropriate signage to explain the history of the site and the archaeological excavation works is placed at the site during the work, A local public information program is implemented including press releases to ensure the public is informed about the project and its outcomes, Community participation in the archaeological works on the site is allowed for through the inclusion of volunteers on the archaeological team under the supervision of the Excavation Director, A website addressing the archaeological works on the site must be created. This website must feature a history of the site, archaeological methodology, updated information on the archaeological works, photographs of the site and significant archaeological remains uncovered, links to the archaeological reports and links to other relevant sites. Public feedback must also be allowed for in this section of the website. Updated information on the Open Day to be held during archaeological works at Old Marulan Township and an on-line	As per previous audit: Holcim letter to OEH dated 15 June 2017 As per previous audit: Heritage Branch sign off (16/12/2010). Note. Site observations Site interview - W Beattie Site observations Site interview - W Beattie Site interview - W Beattie Site interview - W Beattie Old Marulan 2007 - Final Report Holcim Lynwood Quarry webpage (accessed 12/1/2024) https://www.holcim.com.au/abou t-us/community link/Lynwood/planning-approvals reporting	As per previous audit: Letter sighted shows that all archaeological salvage works are to be completed with involvement from archaeologist (i.e. monitoring is to be undertaken by archaeologist). There are no signs. However, there are no appropriate publicly accessible locations to place to No activities occurred during reporting period. Considered compliant on basis of previous au No activities occurred during reporting period. Considered compliant on basis of previous au Old Marulan 2007 - Final Report details all works completed, available via Holcim website. No works were undertaken during the audit period. Considered complaint on basis of final report and previous audit. Previous audit identified that Videos are not able to be located and it is	Compliant Compliant Compliant	
9(a) 9(b) 9(c)	Director in relation to works likely to impact on this resource. Where major issues arise the Excavation Director must consult with the Director of the heritage Office prior to issuing directions. Given the exceptional significance of the archaeological remains of the Old Marulan Township, the Applicant must ensure that the nominated Excavation Director, and archaeological excavation team, are given priority when allocating resources to allow thorough archaeological excavation and full and detailed recording to be undertaken to the satisfaction of the Heritage Council. Where necessary, work schedules shall be adjusted to accommodate the approved archaeological works. Throughout the archaeological excavation works and post-excavation analysis, the Applicant must ensure that: Appropriate signage to explain the history of the site and the archaeological excavation works is placed at the site during the work, A local public information program is implemented including press releases to ensure the public is informed about the project and its outcomes, Community participation in the archaeological works on the site is allowed for through the inclusion of volunteers on the archaeological team under the supervision of the Excavation Director, A website addressing the archaeological works on the site must be created. This website must feature a history of the site, archaeological methodology, updated information on the archaeological works, photographs of the site and significant archaeological remains uncovered, links to the archaeological reports and links to other relevant sites. Public feedback must also be allowed for in this section of the website. Updated information on the Open Day to be held during archaeological works at Old Marulan Township and an on-line hooking service must also be included.	As per previous audit: Holcim letter to OEH dated 15 June 2017 As per previous audit: Heritage Branch sign off (16/12/2010). Note. Site observations Site interview - W Beattie Site observations Site interview - W Beattie Site interview - W Beattie Site interview - W Beattie Old Marulan 2007 - Final Report Holcim Lynwood Quarry webpage (accessed 12/1/2024) https://www.holcim.com.au/abou t-us/community link/Lynwood/planning-approvals reporting	As per previous audit: Letter sighted shows that all archaeological salvage works are to be completed with involvement from archaeologist (i.e. monitoring is to be undertaken by archaeologist). There are no signs. However, there are no appropriate publicly accessible locations to place to No activities occurred during reporting period. Considered compliant on basis of previous au No activities occurred during reporting period. Considered compliant on basis of previous au Old Marulan 2007 - Final Report details all works completed, available via Holcim website. No works were undertaken during the audit period. Considered complaint on basis of final report and previous audit. Previous audit identified that Videos are not able to be located and it is understood that photographs were taken instead.	Compliant Compliant Compliant Compliant Compliant	
9(a) 9(b) 9(c)	Director in relation to works likely to impact on this resource. Where major issues arise the Excavation Director must consult with the Director of the heritage Office prior to issuing directions. Given the exceptional significance of the archaeological remains of the Old Marulan Township, the Applicant must ensure that the nominated Excavation Director, and archaeological excavation team, are given priority when allocating resources to allow thorough archaeological excavation and full and detailed recording to be undertaken to the satisfaction of the Heritage Council. Where necessary, work schedules shall be adjusted to accommodate the approved archaeological works. Throughout the archaeological excavation works and post-excavation analysis, the Applicant must ensure that: Appropriate signage to explain the history of the site and the archaeological excavation works is placed at the site during the work, A local public information program is implemented including press releases to ensure the public is informed about the project and its outcomes, Community participation in the archaeological works on the site is allowed for through the inclusion of volunteers on the archaeological team under the supervision of the Excavation Director, A website addressing the archaeological works on the site must be created. This website must feature a history of the site, archaeological methodology, updated information on the archaeological works, photographs of the site and significant archaeological remains uncovered, links to the archaeological reports and links to other relevant sites. Public feedback must also be allowed for in this section of the website. Updated information on the Open Day to be held during archaeological works at Old Marulan Township and an on-line hooking service must also be included.	As per previous audit: Holcim letter to OEH dated 15 June 2017 As per previous audit: Heritage Branch sign off (16/12/2010). Note. Site observations Site interview - W Beattie Site observations Site interview - W Beattie Site interview - W Beattie Old Marulan 2007 - Final Report Holcim Lynwood Quarry webpage (accessed 12/1/2024) https://www.holcim.com.au/abou t-us/community link/Lynwood/planning-approvals reporting	As per previous audit: Letter sighted shows that all archaeological salvage works are to be completed with involvement from archaeologist (i.e. monitoring is to be undertaken by archaeologist). There are no signs. However, there are no appropriate publicly accessible locations to place to the control of	Compliant Compliant Compliant Compliant Compliant	
9(a) 9(b) 9(c) 9(d)	Director in relation to works likely to impact on this resource. Where major issues arise the Excavation Director must consult with the Director of the heritage Office prior to issuing directions. Given the exceptional significance of the archaeological remains of the Old Marulan Township, the Applicant must ensure that the nominated Excavation Director, and archaeological excavation team, are given priority when allocating resources to allow thorough archaeological excavation and full and detailed recording to be undertaken to the satisfaction of the Heritage Council. Where necessary, work schedules shall be adjusted to accommodate the approved archaeological works. Throughout the archaeological excavation works and post-excavation analysis, the Applicant must ensure that: Appropriate signage to explain the history of the site and the archaeological excavation works is placed at the site during the work, A local public information program is implemented including press releases to ensure the public is informed about the project and its outcomes, Community participation in the archaeological works on the site is allowed for through the inclusion of volunteers on the archaeological team under the supervision of the Excavation Director, A website addressing the archaeological works on the site must be created. This website must feature a history of the site, archaeological methodology, updated information on the archaeological works, photographs of the site and significant archaeological remains uncovered, links to the archaeological reports and links to other relevant sites. Public feedback must also be allowed for in this section of the website. Updated information on the Open Day to be held during archaeological works at Old Marulan Township and an on-line hooking service must also be included. The progress on the archaeological works on site is systematically video recorded,	As per previous audit: Holcim letter to OEH dated 15 June 2017 As per previous audit: Heritage Branch sign off (16/12/2010). Note. Site observations Site interview - W Beattie Site observations Site interview - W Beattie Site interview - W Beattie Site interview - W Beattie Old Marulan 2007 - Final Report Holcim Lynwood Quarry webpage (accessed 12/1/2024) https://www.holcim.com.au/abou t-us/community link/Lynwood/planning-approvals reporting Previous 2020 IEA Audit	As per previous audit: Letter sighted shows that all archaeological salvage works are to be completed with involvement from archaeologist (i.e. monitoring is to be undertaken by archaeologist). There are no signs. However, there are no appropriate publicly accessible locations to place to the control of	Compliant Compliant Compliant Compliant Compliant Non-compliant	NC17
9(a) 9(b) 9(c) 9(d) 9(e)	Director in relation to works likely to impact on this resource. Where major issues arise the Excavation Director must consult with the Director of the heritage Office prior to issuing directions. Given the exceptional significance of the archaeological remains of the Old Marulan Township, the Applicant must ensure that the nominated Excavation Director, and archaeological excavation team, are given priority when allocating resources to allow thorough archaeological excavation and full and detailed recording to be undertaken to the satisfaction of the Heritage Council. Where necessary, work schedules shall be adjusted to accommodate the approved archaeological works. Throughout the archaeological excavation works and post-excavation analysis, the Applicant must ensure that: Appropriate signage to explain the history of the site and the archaeological excavation works is placed at the site during the work, A local public information program is implemented including press releases to ensure the public is informed about the project and its outcomes, Community participation in the archaeological works on the site is allowed for through the inclusion of volunteers on the archaeological team under the supervision of the Excavation Director, A website addressing the archaeological works on the site must be created. This website must feature a history of the site, archaeological methodology, updated information on the archaeological works, photographs of the site and significant archaeological remains uncovered, links to the archaeological reports and links to other relevant sites. Public feedback must also be allowed for in this section of the website. Updated information on the Open Day to be held during archaeological works at Old Marulan Township and an on-line hooking service must also he included. The progress on the archaeological works on site is systematically video recorded,	As per previous audit: Holcim letter to OEH dated 15 June 2017 As per previous audit: Heritage Branch sign off (16/12/2010). Note. Site observations Site interview - W Beattie Site observations Site interview - W Beattie Site interview - W Beattie Old Marulan 2007 - Final Report Holcim Lynwood Quarry webpage (accessed 12/1/2024) https://www.holcim.com.au/abou t-us/community link/Lynwood/planning-approvals reporting	As per previous audit: Letter sighted shows that all archaeological salvage works are to be completed with involvement from archaeologist (i.e. monitoring is to be undertaken by archaeologist). There are no signs. However, there are no appropriate publicly accessible locations to place to the control of	Compliant Compliant Compliant Compliant Compliant Compliant Compliant Compliant	NC17
9(a) 9(b) 9(c) 9(d)	Director in relation to works likely to impact on this resource. Where major issues arise the Excavation Director must consult with the Director of the heritage Office prior to issuing directions. Given the exceptional significance of the archaeological remains of the Old Marulan Township, the Applicant must ensure that the nominated Excavation Director, and archaeological excavation team, are given priority when allocating resources to allow thorough archaeological excavation and full and detailed recording to be undertaken to the satisfaction of the Heritage Council. Where necessary, work schedules shall be adjusted to accommodate the approved archaeological works. Throughout the archaeological excavation works and post-excavation analysis, the Applicant must ensure that: Appropriate signage to explain the history of the site and the archaeological excavation works is placed at the site during the work, A local public information program is implemented including press releases to ensure the public is informed about the project and its outcomes, Community participation in the archaeological works on the site is allowed for through the inclusion of volunteers on the archaeological team under the supervision of the Excavation Director, A website addressing the archaeological works on the site must be created. This website must feature a history of the site, archaeological methodology, updated information on the archaeological works, photographs of the site and significant archaeological remains uncovered, links to the archaeological reports and links to other relevant sites. Public feedback must also be allowed for in this section of the website. Updated information on the Open Day to be held during archaeological works at Old Marulan Township and an on-line hooking service must also be included. The progress on the archaeological works on site is systematically video recorded,	As per previous audit: Holcim letter to OEH dated 15 June 2017 As per previous audit: Heritage Branch sign off (16/12/2010). Note. Site observations Site interview - W Beattie Site observations Site interview - W Beattie Site interview - W Beattie Old Marulan 2007 - Final Report Holcim Lynwood Quarry webpage (accessed 12/1/2024) https://www.holcim.com.au/abou t-us/community link/Lynwood/planning-approvals reporting Previous 2020 IEA Audit Previous audit sighted Old Marulan Archaeological Letter to DECC (27/10/10)	As per previous audit: Letter sighted shows that all archaeological salvage works are to be completed with involvement from archaeologist (i.e. monitoring is to be undertaken by archaeologist). There are no signs. However, there are no appropriate publicly accessible locations to place to No activities occurred during reporting period. Considered compliant on basis of previous au No activities occurred during reporting period. Considered compliant on basis of previous au Old Marulan 2007 - Final Report details all works completed, available via Holcim website. No works were undertaken during the audit period. Considered complaint on basis of final report and previous audit. Previous audit identified that Videos are not able to be located and it is understood that photographs were taken instead. Previous audit included action to discuss this matter with DPE. No evidence of action being addressed.	Compliant Compliant Compliant Compliant Compliant Non-compliant	NC17
9(a) 9(b) 9(c) 9(d) 9(e)	Director in relation to works likely to impact on this resource. Where major issues arise the Excavation Director must consult with the Director of the heritage Office prior to issuing directions. Given the exceptional significance of the archaeological remains of the Old Marulan Township, the Applicant must ensure that the nominated Excavation Director, and archaeological excavation team, are given priority when allocating resources to allow thorough archaeological excavation and full and detailed recording to be undertaken to the satisfaction of the Heritage Council. Where necessary, work schedules shall be adjusted to accommodate the approved archaeological works. Throughout the archaeological excavation works and post-excavation analysis, the Applicant must ensure that: Appropriate signage to explain the history of the site and the archaeological excavation works is placed at the site during the work, A local public information program is implemented including press releases to ensure the public is informed about the project and its outcomes, Community participation in the archaeological works on the site is allowed for through the inclusion of volunteers on the archaeological team under the supervision of the Excavation Director, A website addressing the archaeological works on the site must be created. This website must feature a history of the site, archaeological methodology, updated information on the archaeological works, photographs of the site and significant archaeological remains uncovered, links to the archaeological reports and links to other relevant sites. Public feedback must also be allowed for in this section of the website. Updated information on the Open Day to be held during archaeological works at Old Marulan Township and an on-line hooking service must also he included. The progress on the archaeological works on site is systematically video recorded,	As per previous audit: Holcim letter to OEH dated 15 June 2017 As per previous audit: Heritage Branch sign off (16/12/2010). Note. Site observations Site interview - W Beattie Site observations Site interview - W Beattie Site interview - W Beattie Old Marulan 2007 - Final Report Holcim Lynwood Quarry webpage (accessed 12/1/2024) https://www.holcim.com.au/abou t-us/community link/Lynwood/planning-approvals reporting Previous 2020 IEA Audit Previous audit sighted Old Marulan Archaeological Letter to DECC (27/10/10)	As per previous audit: Letter sighted shows that all archaeological salvage works are to be completed with involvement from archaeologist (i.e. monitoring is to be undertaken by archaeologist). There are no signs. However, there are no appropriate publicly accessible locations to place to the control of	Compliant Compliant Compliant Compliant Compliant Compliant Compliant Compliant	NC17

18 18 18 18 18 18 18 18	9(h)	All affected areas of the site are signed off by the Heritage Office prior to commencement of bulk excavation in those identified locations,			Compliant	
Part	0(i)	and	Previous 2020 IEA Audit: Heritage Branch sign off on 16/12/2010 prior to it	nitial bulk excavation.	Compliant	
Part	5(1)	interpretation programme for the Old Marulan Township precinct.	Previous 2020 IEA Audit: Umwelt letter to OEH, dated 29 June 2011 regard	ling Old Marulan Township - Road Reserve Works	Compilant	
For the Service for the Servic	10				Compliant	
Package Pack						
Here the second protects for t						
Manuscraft of the property of			Holcim Lynwood Quarry webpage			
			, , ,			
Page			1 11	·		
Heave the second of the second	11	An interpretation programme for the entire Old Marulan Township heritage precinct incorporating the results of the archaeological	t-us/community link/Lynwood/planning-approvals reporting	the audit period.	Compliant	
meters in any fire of the control of			Previous 2020 IFA Audit: letter from Heritage Branch, Well			
is the control of the			j =			
See the second programment for the proposed of the color proposed			with public interpretation	Considered closed following previous audit finding.		
Heave the first programment from the composition of	12				Compliant	
Part						
Second 1998						
Application and protection and pro			,			
Leg of the control of			, ,	Considered closed following previous audit finding.		
Legislation and the 15th students and 15th stude	13			· · · · ·	Compliant	
Fig. 12 Processes from the standard of the standard could be standard counter of the standard counter			Site interview - W Beattle	currently occurring.		
Property of the property of the second of		Photographic Recording of Heritage Items' (2004). One (1) copy of the photographic and archival recording shall be submitted to the				
August 1.5 Augu						
10 10 10 10 10 10 10 10	14		1		Compliant	
Manipulation and explanation designation designation designation and following information and	45	The Applicant work program that the site and a park of a fact that the site and a park of a fact that the site and a park of a fact that the site and a park of a fact that the site and a park of a fact that the site and a park of a fact that the site and a park of a fact that the site and a park of a fact that the site and a park of a fact that the site and a park of a fact that the site and a park of a fact that the site and a park of a fact that the site and a park of a fact that the site and a park of a fact that the site and a park of a fact that the site and a park of a fact that the site and a park of a fact that the site and a park of a fact that the site and a park of a fact that the site and a fact that	management policy is appropriate (7/9/09)		Compliant	
Part	15		Site observations	No continued archaeological excavation occurring. Areas of heritage interest are fenced and		
Sequence of the control of the state of the collaboration of the collabo	16	The Applicant must ensure that the nominated Excavation Director cleans, stabilises, labels, analyses, catalogues and stores any artefacts		<u> </u>		
Part		recovered from the site in a way that allows them to be retrieved according to both type and provenance.	,	No continued archaeological excavation occurring. Areas of heritage interest are fenced and		
Part	17	The Applicant must ensure that a summary of the results of the field work, up to 500 words in length, is submitted to the Heritage Council		0		
18 In A register must resure tests from fearenaben on the first field researcher register (or not if Pin III) and the first feel based exclusional classification of the first feel based exclusional classification in the first feel based exclusional classification in the first feel based and the first feel based and feel based a			·	Considered closed		
Accession of a Now Accessi	18		(2) (D. Gojak, Banksia Heritage + Archiaeology, 13/3/00).	considered closed.	Compliant	
Notice N			Previous 2020 IEA Audit: relevant pages of the Old Marulan 2007			
A continue time that out it is executed in a monitor of private and set to the continue time to the full period copies of the fund canadation may now with eletter of large copy with the first of large copy with the fund of l		by the Heritage Council of NSW.				
Part			,			
Description from the reserve that are 0.1.0 electronic support the final excessions required in southern with several All-Ville (Mineral Period) (Considered closed) Considered closed (Considered Closed)				Considered closed.		
Page of the Winter Organs contact of the fault accordance register and referrable ac	19	The Applicant must ensure that one (1) electronic copy of the final excavation report is submitted on CD to the Heritage Council of NSW			Compliant	
Second process of the second selection and second or second second second or second second or second second or second second or second seco		1 * ' ' ' ' ' ' ' ' ' ' ' ' ' ' ' ' ' '				
20 0 20 0				Considered closed.		
Constitution Cons		The Applicant must ensure that the information presented in a final excavation report includes the following:				
Second S	20(a)	(a) An executive summary,	, , , ,		Compliant	
Substitute Sub			[· · · · · · · · · · · · · · · · · · ·	Old Marulan 2007 - Final Report available online. No further works were conducted during		
20 0 (a) Poet redit to the client paying for the excavation on the title page, Holdim Lymwood Quarry webpage (occessed 121/12024) High-//www.holdim.com.au/abou the audit period. Compilant			[* **	·		
Internation	20(b)	(b) Due credit to the client paying for the excavation on the title page,			Compliant	
CAP accurate site location and site plan, Scape			[· · · · · · · · · · · · · · · · · · ·			
Example Compliant Holicim Lymwood Quarry webpage (accessed 12/1/2024) Holicim Lymwood Quarry w			1	·		
Compliant Conserving, sorting, cataloguing, labelling, sale photography and provided experience. Compliant Conserving, sorting, cataloguing, labelling, scale photography and provided experience. Compliant Conserving, sorting, cataloguing, labelling, scale photography and provided experience. Compliant Conserving, sorting, cataloguing, labelling, scale photography and provided experience. Compliant Conserving, sorting, cataloguing, labelling, scale photography and provided experience. Compliant Conserving, sorting, cataloguing, labelling, scale photography and provided experience. Compliant Conserving, sorting, cataloguing, labelling, scale photography and provided experience. Compliant Conserving, sorting, cataloguing, labelling, scale photography and provided experience. Compliant Conserving, sorting, cataloguing, labelling, scale photography and provided experience. Compliant Conserving, sorting, cataloguing, labelling, scale photography and provided experience. Compliant Conserving, sorting, cataloguing, labelling, scale photography and provided experience. Compliant Conserving, sorting, cataloguing, labelling, scale photography and provided experience. Compliant Conserving, sorting, cataloguing, labelling, scale photography and provided experience. Compliant Conserving, sorting, scale photography and provided experience. Compliant Conserving, sorting, scale photography and provided experience. Compliant Conserving, scale photography and provided experience. Compliant	20(c)	(c) An accurate site location and site plan,		the audit period.	Compliant	
thtps://www.holcim.com.au/abou bttps://www.holcim.com.au/abou	(0)	k.y				
20(e) (e) Detailed response to research questions, (f) Detailed response to research questions, (f) Detailed response to research questions, (g) Nominated repository for the items, (g) Nominated repository for the items, (d) Historical research, references, and bibliography, (d) Historical research, references, and bibliography, (d) Historical research, references, and bibliography, (accessed 12/1/2024) (b) Littys://www.holcim.com.au/abou t-us/community link/Lynwood/planning-approvals reporting the audit period. Compliant Compliant			https://www.holcim.com.au/abou	Old Marulan 2007 - Final Report available online. No further works were conducted during		
Caccessed 12/1/2024 https://www.holcim.com.au/abou tus/community link/Lynwood/planning-approvals reporting the audit period. Compliant consequence of caccessed 12/1/2024 https://www.holcim.com.au/abou tus/community link/Lynwood/planning-approvals reporting the audit period. Compliant consequence particles of the audit period. Com	201 "	(A) Uth delay a share		the audit period.	Constitut	
https://www.holcim.com.au/abou t.us/community link/Lynwood/planning-approvals reporting the audit period. 20(e) Detailed information on the excavation including the aim, the context for the excavation, procedures, treatment of artefacts (cleaning, conserving, sorting, cataloguing, labelling, scale photographs and/or drawings, location of repository) and analysis of the information retrieved, 20(f) Detailed response to research questions, (g) Nominated repository for the items, (g) Nominated repository for the items, (g) Nominated repository for the items, https://www.holcim.com.au/abou t.us/community link/Lynwood/planning-approvals reporting the audit period. https://www.holcim.com.au/abou t.us/community link/Lynwood/planning-approvals reporting the audit period. Holcim Lynwood Quarry webpage (accessed 12/1/2024) https://www.holcim.com.au/abou t.us/community link/Lynwood/planning-approvals reporting the audit period. 20(g) Nominated repository for the items, (g) Nominated repository for the items, Holcim Lynwood Quarry webpage (accessed 12/1/2024) https://www.holcim.com.au/abou Lus/community link/Lynwood/planning-approvals reporting the audit period. Holcim Lynwood Quarry webpage (accessed 12/1/2024) https://www.holcim.com.au/abou Holcim Lynwood Quarry webpage (acc	20(d)	(d) Historical research, references, and bibliography,	, , , ,		Compliant	
Lus/community link/Lynwood/planning-approvals reporting (e) Detailed information on the excavation including the aim, the context for the excavation, procedures, treatment of artefacts (cleaning conserving, sorting, cataloguing, labelling, scale photographs and/or drawings, location of repository) and analysis of the information retrieved, 20(f) (f) Detailed response to research questions, (g) Nominated repository for the items, (g) Nominated repository for the items, (e) Detailed information on the excavation including the aim, the context for the excavation, procedures, treatment of artefacts (cleaning, caccessed 12/1/2024) (b) Lotalled response to research questions, (f) Detailed response to research questions, (f) Detailed response to research questions, (g) Nominated repository for the items, (g) Nominated repository for the items				Old Marulan 2007 - Final Report available online. No further works were conducted during		
conserving, sorting, cataloguing, labelling, scale photographs and/or drawings, location of repository) and analysis of the information retrieved, 20(f) (f) Detailed response to research questions, (g) Nominated repository for the items, (
retrieved, https://www.holcim.com.au/abou t-us/community link/Lynwood/planning-approvals reporting the audit period. 20(f) (f) Detailed response to research questions, Holcim Lynwood Quarry webpage (accessed 12/1/2024) https://www.holcim.com.au/abou t-us/community link/Lynwood/planning-approvals reporting the audit period. 20(g) (g) Nominated repository for the items, Holcim Lynwood Quarry webpage (accessed 12/1/2024) https://www.holcim.com.au/abou thouse provided the audit period. 20(g) (g) Nominated repository for the items, (accessed 12/1/2024) https://www.holcim.com.au/abou Old Marulan 2007 - Final Report available online. No further works were conducted during the audit period. Compliant (accessed 12/1/2024) https://www.holcim.com.au/abou Old Marulan 2007 - Final Report available online. No further works were conducted during Old Marulan 2007 - Final Report available online. No further works were conducted during Old Marulan 2007 - Final Report available online. No further works were conducted during Old Marulan 2007 - Final Report available online. No further works were conducted during Old Marulan 2007 - Final Report available online. No further works were conducted during Old Marulan 2007 - Final Report available online. No further works were conducted during Old Marulan 2007 - Final Report available online.	20(e)				Compliant	
20(f) (f) Detailed response to research questions, Holcim Lynwood Quarry webpage (accessed 12/1/2024) https://www.holcim.com.au/abou 20(g) (g) Nominated repository for the items, (g) Nominated repository for the items, Holcim Lynwood Quarry webpage (accessed 12/1/2024) https://www.holcim.com.au/abou Did Marulan 2007 - Final Report available online. No further works were conducted during the audit period. Compliant the audit period. Old Marulan 2007 - Final Report available online. No further works were conducted during the audit period. Compliant (accessed 12/1/2024) https://www.holcim.com.au/abou Old Marulan 2007 - Final Report available online. No further works were conducted during Old Marulan 2007 - Final Report available online. No further works were conducted during Old Marulan 2007 - Final Report available online. No further works were conducted during Old Marulan 2007 - Final Report available online. No further works were conducted during				Old Manufac 2007. Final Depart qualishing as live No. C. albour and a control of the control of		
20(f) (f) Detailed response to research questions,		,, 				
(accessed 12/1/2024) https://www.holcim.com.au/abou t-us/community link/Lynwood/planning-approvals reporting the audit period. 20(g) Nominated repository for the items, Holcim Lynwood Quarry webpage (accessed 12/1/2024) https://www.holcim.com.au/abou Old Marulan 2007 - Final Report available online. No further works were conducted during the audit period. Compliant Old Marulan 2007 - Final Report available online. No further works were conducted during Old Marulan 2007 - Final Report available online. No further works were conducted during	20(f)	(f) Detailed response to research questions,		and dudit period.	Compliant	
t-us/community link/Lynwood/planning-approvals reporting the audit period. 20(g) (g) Nominated repository for the items, Holcim Lynwood Quarry webpage (accessed 12/1/2024) https://www.holcim.com.au/abou Old Marulan 2007 - Final Report available online. No further works were conducted during	-					
20(g) (g) Nominated repository for the items, Holcim Lynwood Quarry webpage (accessed 12/1/2024) https://www.holcim.com.au/abou Old Marulan 2007 - Final Report available online. No further works were conducted during						
(accessed 12/1/2024) https://www.holcim.com.au/abou Old Marulan 2007 - Final Report available online. No further works were conducted during	20/~\	(a) Nominated repository for the items		the audit period.	Compliant	
https://www.holcim.com.au/abou Old Marulan 2007 - Final Report available online. No further works were conducted during	∠∪(g)	IB) Nominated repository for the items,			Соприл	
				Old Marulan 2007 - Final Report available online. No further works were conducted during		
			1	·		

20(h)	(h) Conclusions from the archaeological programme. This information must include a reassessment of the site's heritage significance,	Holcim Lynwood Quarry webpage		Compliant	
	statement(s) on how archaeological investigations at this site have contributed to the community's understanding of the site and	(accessed 12/1/2024)			
	recommendations for the future management of the site, and	https://www.holcim.com.au/abou	Old Marulan 2007 - Final Report available online. No further works were conducted during		
		t-us/community link/Lynwood/planning-approvals reporting	the audit period.		
)(i)	(i) Details of how this information about this excavation has been publicly disseminated.	Holcim Lynwood Quarry webpage		Compliant	
		(accessed 12/1/2024)			
		https://www.holcim.com.au/abou	Old Marulan 2007 - Final Report available online. No further works were conducted during		
		t-us/community link/Lynwood/planning-approvals reporting	the audit period.		
NDIX 8	S. CONCEPTUAL REHABILITATION PLAN [Map figure]	t as/community may symbol planning approvals reporting	the dutil period.		
	9. HABITAT MANAGEMENT AREAS [Map figure]				
	10. NOISE COMPLIANCE ASSESSMENT				
able	Meteorological Conditions				
1	The noise criteria in Table 1 apply under all meteorological conditions except the following:	Note.			
(a)	monitoring locations for the collection of representative noise data;	Annual Review 2020, 2021, 2022.	AERs and Noise Monitoring Reports during the audit period demonstrate noise monitoring	Compliant	
		Site Observations	performed as required.		
		2023 Monitor data			
(b)	wind speeds greater than 3 metres/second at 10 metres above ground level; or	Annual Review 2020, 2021, 2022.	AERs and Noise Monitoring Reports during the audit period demonstrate noise monitoring	Compliant	
		Site Observations	performed as required.		
		2023 Monitor data	periorinea ao reganear		
(c)	stability category F temperature inversion conditions and wind speeds greater than 2 metres/second at 10 metres above ground level; or		AERs and Noise Monitoring Reports during the audit period demonstrate noise monitoring	Compliant	
(-)	,	Site Observations	performed as required.		
		2023 Monitor data	performed as required.		
(4)	stability category G temperature inversion conditions.		AFDs and Nation Manitestine Deposits of vitra the soudit provided deposits as a secretarion	Compliant	
(d)	stability Category & temperature inversion conditions.	Annual Review 2020, 2021, 2022.	0 1 1 1 1 0 1 1 0 1 1 1 1 1 1 1 1 1 1 1	Compilant	
		Site Observations	performed as required.		
		2023 Monitor data			
	tion of Meteorological Conditions				
2	Except for wind speed at microphone height, the data to be used for determining meteorological conditions must be that recorded by the		No reference in reports to reliance of meteorological station required under condition 1EA of	Non-compliant	NC18
liance	meteorological station required under condition 15A of Schedule 3. e Monitoring	Quarterly Noise Monitoring reports (Ramboll, MAC)	No reference in reports to reliance of meteorological station required under condition 15A or		NC10
3	Attended monitoring is to be used to evaluate compliance with the relevant conditions of this consent.	Note.			
	Attended monitoring is to be used to evaluate compliance with the relevant conditions of this consent.	Note.			
	University of the standing the Country of the deal country to the first test to be used to consider a with the colorest			Compliant	
4	Unless otherwise directed by the Secretary, attended quarterly monitoring is to be used to evaluate compliance with the relevant	Annual Review 2020, 2021, 2022.		Compliant	
4	conditions of this consent.	Annual Review 2020, 2021, 2022. Quarterly Noise Monitoring reports (Ramboll, MAC)	AERs and Noise Monitoring Reports during the audit period demonstrate noise monitoring p	Compliant	
4	conditions of this consent. Note: The Secretary may direct that the frequency of attended monitoring increase or decrease at any time during the life of the	Quarterly Noise Monitoring reports (Ramboll, MAC)	AERs and Noise Monitoring Reports during the audit period demonstrate noise monitoring p	Compliant	
4	conditions of this consent. Note: The Secretary may direct that the frequency of attended monitoring increase or decrease at any time during the life of the development.		AERs and Noise Monitoring Reports during the audit period demonstrate noise monitoring pr		
	conditions of this consent. Note: The Secretary may direct that the frequency of attended monitoring increase or decrease at any time during the life of the development. Unless otherwise agreed with the Secretary, this monitoring is to be carried out in accordance with the relevant requirements for	Quarterly Noise Monitoring reports (Ramboll, MAC)	AERs and Noise Monitoring Reports during the audit period demonstrate noise monitoring p	Compliant	
	conditions of this consent. Note: The Secretary may direct that the frequency of attended monitoring increase or decrease at any time during the life of the development.	Quarterly Noise Monitoring reports (Ramboll, MAC)	AERs and Noise Monitoring Reports during the audit period demonstrate noise monitoring activities are carried out in accordance with the Noise Policy for		
5	conditions of this consent. Note: The Secretary may direct that the frequency of attended monitoring increase or decrease at any time during the life of the development. Unless otherwise agreed with the Secretary, this monitoring is to be carried out in accordance with the relevant requirements for	Quarterly Noise Monitoring reports (Ramboll, MAC) Note.	Reports confirm monitoring activities are carried out in accordance with the Noise Policy for	Compliant	
5 (a)	conditions of this consent. Note: The Secretary may direct that the frequency of attended monitoring increase or decrease at any time during the life of the development. Unless otherwise agreed with the Secretary, this monitoring is to be carried out in accordance with the relevant requirements for reviewing performance set out in the INP (as amended from time to time), in particular the requirements relating to:	Quarterly Noise Monitoring reports (Ramboll, MAC) Note. Quarterly Noise Monitoring reports (Ramboll, MAC) Quarterly Noise Monitoring reports (Ramboll, MAC)	Reports confirm monitoring activities are carried out in accordance with the Noise Policy for The quarterly Noise Monitoring Reports describe the locations for the collection of noise data	Compliant	
5 (a) (b)	conditions of this consent. Note: The Secretary may direct that the frequency of attended monitoring increase or decrease at any time during the life of the development. Unless otherwise agreed with the Secretary, this monitoring is to be carried out in accordance with the relevant requirements for reviewing performance set out in the INP (as amended from time to time), in particular the requirements relating to: monitoring locations for the collection of representative noise data;	Quarterly Noise Monitoring reports (Ramboll, MAC) Note. Quarterly Noise Monitoring reports (Ramboll, MAC)	Reports confirm monitoring activities are carried out in accordance with the Noise Policy for	Compliant	
5 (a)	conditions of this consent. Note: The Secretary may direct that the frequency of attended monitoring increase or decrease at any time during the life of the development. Unless otherwise agreed with the Secretary, this monitoring is to be carried out in accordance with the relevant requirements for reviewing performance set out in the INP (as amended from time to time), in particular the requirements relating to: monitoring locations for the collection of representative noise data; meteorological conditions during which collection of noise data is not appropriate;	Quarterly Noise Monitoring reports (Ramboll, MAC) Note. Quarterly Noise Monitoring reports (Ramboll, MAC) Quarterly Noise Monitoring reports (Ramboll, MAC)	Reports confirm monitoring activities are carried out in accordance with the Noise Policy for The quarterly Noise Monitoring Reports describe the locations for the collection of noise dat. Reports confirm monitoring activities are carried out in accordance with the Noise Policy for	Compliant Compliant Compliant	
5 5 (a) 5 (b)	conditions of this consent. Note: The Secretary may direct that the frequency of attended monitoring increase or decrease at any time during the life of the development. Unless otherwise agreed with the Secretary, this monitoring is to be carried out in accordance with the relevant requirements for reviewing performance set out in the INP (as amended from time to time), in particular the requirements relating to: monitoring locations for the collection of representative noise data; meteorological conditions during which collection of noise data is not appropriate;	Quarterly Noise Monitoring reports (Ramboll, MAC) Note. Quarterly Noise Monitoring reports (Ramboll, MAC) Quarterly Noise Monitoring reports (Ramboll, MAC)	Reports confirm monitoring activities are carried out in accordance with the Noise Policy for The quarterly Noise Monitoring Reports describe the locations for the collection of noise data. Reports confirm monitoring activities are carried out in accordance with the Noise Policy for Reports confirm conformance with the following standards:	Compliant Compliant Compliant	
5 (a) (b)	conditions of this consent. Note: The Secretary may direct that the frequency of attended monitoring increase or decrease at any time during the life of the development. Unless otherwise agreed with the Secretary, this monitoring is to be carried out in accordance with the relevant requirements for reviewing performance set out in the INP (as amended from time to time), in particular the requirements relating to: monitoring locations for the collection of representative noise data; meteorological conditions during which collection of noise data is not appropriate;	Quarterly Noise Monitoring reports (Ramboll, MAC) Note. Quarterly Noise Monitoring reports (Ramboll, MAC) Quarterly Noise Monitoring reports (Ramboll, MAC)	Reports confirm monitoring activities are carried out in accordance with the Noise Policy for The quarterly Noise Monitoring Reports describe the locations for the collection of noise data. Reports confirm monitoring activities are carried out in accordance with the Noise Policy for Reports confirm conformance with the following standards: Australian Standard AS 1055:2018 Acoustics — Description and measurement of	Compliant Compliant Compliant	
5 (a) (b)	conditions of this consent. Note: The Secretary may direct that the frequency of attended monitoring increase or decrease at any time during the life of the development. Unless otherwise agreed with the Secretary, this monitoring is to be carried out in accordance with the relevant requirements for reviewing performance set out in the INP (as amended from time to time), in particular the requirements relating to: monitoring locations for the collection of representative noise data; meteorological conditions during which collection of noise data is not appropriate;	Quarterly Noise Monitoring reports (Ramboll, MAC) Note. Quarterly Noise Monitoring reports (Ramboll, MAC) Quarterly Noise Monitoring reports (Ramboll, MAC) Quarterly Noise Monitoring reports (Ramboll, MAC)	Reports confirm monitoring activities are carried out in accordance with the Noise Policy for The quarterly Noise Monitoring Reports describe the locations for the collection of noise data Reports confirm monitoring activities are carried out in accordance with the Noise Policy for Reports confirm conformance with the following standards: Australian Standard AS 1055:2018 Acoustics — Description and measurement of environmental noise (Standards Australia, 2018).	Compliant Compliant Compliant	
5 5 (a) 5 (b) 5 (c)	conditions of this consent. Note: The Secretary may direct that the frequency of attended monitoring increase or decrease at any time during the life of the development. Unless otherwise agreed with the Secretary, this monitoring is to be carried out in accordance with the relevant requirements for reviewing performance set out in the INP (as amended from time to time), in particular the requirements relating to: monitoring locations for the collection of representative noise data; meteorological conditions during which collection of noise data is not appropriate;	Quarterly Noise Monitoring reports (Ramboll, MAC) Note. Quarterly Noise Monitoring reports (Ramboll, MAC) Quarterly Noise Monitoring reports (Ramboll, MAC)	Reports confirm monitoring activities are carried out in accordance with the Noise Policy for The quarterly Noise Monitoring Reports describe the locations for the collection of noise data. Reports confirm monitoring activities are carried out in accordance with the Noise Policy for Reports confirm conformance with the following standards: Australian Standard AS 1055:2018 Acoustics — Description and measurement of	Compliant Compliant Compliant	

Table A.2 - DA 128-5-2005 Statement of Commitments (including Mod 1 (21/12/05), Mod 2 (22/3/11), Mod 3 (17/8/11), Mod 4 (5/2016) and Mod 5 (5/2017)

	- DA 128-5-2005 Statement of Commitments (including Mod 1 (21/12/05), Mod 2 (22/3/11), Mod 3 (17/8/12	Evidence collected	Independent Audit Findings and Recommendations	Compliance status	Unique Identification Non-compliance
spect					
PENDIX 11 - ST	TATEMENT OF COMMITMENTS (Final May 2016)				
	The Environmental Assessment for Modification Application DA 128-5-2005 MOD 4 (EA (MOD 4) in its entirety is the guiding document which provides context to the following commitments made by in relation to the Lynwood Extraction Area Modification Project. The EA (Mod 4) is to be used as the reference for interpreting how Holcim Australia will operate to implement these commitments.				
	Modification Project Management and Mitigation Measures	Note.			
/lanagement	Management Plans				
Plans	The approved Lynwood Quarry Environmental Management Strategy and environmental management plans will be revised and updated as part of the implementation of the Modification Project.	1. Air Quality Management Plan (August 2023) 2. Riparian Area Management Plan Lockyersleigh Creek Catchment Revision (June 2011) 3. Riparian Area Management Plan Marulan Creek Catchment Area (2011) 4. Noise Management Plan (February 2020) 5. Blast Management Plan (February 2020) 6. Environmental Management Strategy (February 2020) 7. Aboriginal Heritage Management Plan, Caring for Country Final (2022) 8. Rehabilitation and Landscape Management Plan (May 2018) 9. Water Management Plan (2020) 10. Waste Management and Minimisation Strategy (2019) 11. Pollution Incident Response Management Plan (September 2019) 12. Riparian Area Management Plan Joarimin Creek Catchment (2021). 13. Box Gum Woodland Management Plan (September 2013) 14. Groundwater Monitoring Program (2020) 15. Surface Water Monitoring Program (2020) Sighted correspondecne to DPE confirm reviews following Annual Reviews.	While not all management plans have been revised, all appear to have been reviewed. If deemed necessary they appear to have been revised following review.	Compliant	
Noise	Noise The design of the Modification Project incorporates the measures proposed in the 2004 Noise Impact Assessment (Heggies Australia, 2004) and 2010 modification (Umwelt, 2009a), where they are still applicable noting the proposed changes to Lynwood Quarry.	Noise Management Plan (February 2020)	Lynwood Quarry Noise Management Plan (NMP) was updated on September 2016 to incorporate Modification Project. It has since been reviewed and updated with the current version dated February 2020.	Compliant	
	in addition to the noise management measures (outlined in Appendix 4 of the EA (MOD 4)), the following measures are proposed to be incorporated into the routine operation of the quality over the life of the Modification Project to further minimise noise impacts:	Noise Management Plan (February 2020)	Lynwood Quarry Noise Management Plan (NMP) was updated on September 2016 to incorporate Modification Project. It has since been reviewed and updated with the current version dated February 2020.	Compliant	
	The use of broad band reversing alarms instead of beeper style alarms on all mobile equipment.	Site obersvations	Auditor sighted broad band reversing beacons on equipment	Compliant	
	• The management of mobile machines during adverse weather conditions when wind conditions or inversion conditions enhance the noise propagation towards sensitive receiver locations. This could include, but not be limited to: o ensuring the sales loader operates behind the product stockpile during adverse weather conditions in the evening and night time period; and/or o moving quarrying activities to locations deeper in the quarry pit during adverse weather conditions and ceasing operations in exposed areas (e.g. on the face of the overburden emplacement areas).	Noise Management Plan (February 2020) - Table 5 Sighted shift reports confirming modifications being made to operations during adverse weather conditions.		Compliant	
	Regular inspection and maintenance of noise attenuation systems on quarry equipment.	Noise Management Plan (February 2020) - Table 5 Site obersations of OEM inspections		Compliant	
	• Implementation of a process for periodic review of noise performance of equipment.	Noise Management Plan (February 2020) - Table 5		Compliant	
lasting	Blasting				
	Holcim Australia has an existing blast management and monitoring system in place at Lynwood Quarry which will be implemented for the Modification Project including:	Blast Management Plan (February 2020)		Compliant	
	• design of each blast to meet the required criteria and considering the particular needs, location, geological conditions of each blast. Appropriate blast initiation sequences will be used to minimise impacts with blast MIC limited as required to meet vibration and overpressure criteria	Blast Management Plan (February 2020) - Table 8		Compliant	
	• a pre-blast review of environmental conditions (including weather conditions) to avoid blasting in conditions which may significantly increase blasting impacts or dust impacts	Blast Management Plan (February 2020) - Table 8 Sighted pre-blast check list		Compliant	
	blasts are typically undertaken between 10 am and 3 pm noting that blasting is permitted to be undertaken between 9 am and 5 pm Monday to Saturday	Blast Management Plan (February 2020) - Table 8 Sighted pre-blast check list		Compliant	
	a blast monitoring system is in place at Lynwood Quarry with the results of monitoring used to assess compliance and feedback into the site blast model to provide for ongoing refinement of blast design. The blast monitoring program will be updated as part of the implementation of the Modification Project	Blast Management Plan (February 2020) - Table 8 Sighted pre-blast check list Sighted blast monitoring data		Compliant	
	• a blast notification process in accordance with Condition 10 of Schedule 3 of the development consent which requires Holcim Australia to notify residents of upcoming blasts, operate a blasting hotline and keep the community informed about this hotline.	Blast Management Plan (February 2020) - Table 8 Sighted pre-blast check list - incorportating prenotification requirements. Sighted blast notification signage.		Compliant	
	Holcim Australia will, subject to agreement of the landowner, commission a structural assessment of Lockyersleigh Homestead and the associated heritage structures to confirm the suitability of blast limits for these structures.	Conisdered complaint on basis of previous audit finding.		Compliant	
ir Quality	Air quality Holcim Australia will continue to implement the existing air quality management and monitoring system in place at Lynwood Quarry which includes both engineering and	Air Quality Management Plan (August 2023) - Section 6 and 7		Compliant	
	operations controls measures as outlined in Section 6.5.5 of the EA (MOD 4). The existing air quality monitoring program will be revised as operations commence in the Granite Pit with monitoring locations revised as indicated in Figure 2.5 of the Response to Submissions report. This monitoring program may be revised over the life of the Project with any changes outlined in the Air Quality Management Plan.	Air Quality Management Plan (August 2023) - Figure 1	Noting Depositional Dust Guage location update in consult with DPE.	Compliant	
iodiversity	Biodiversity				
	Holcim Australia will implement the following biodiversity controls:	Note.			
	• a robust tree felling procedure as outlined in Appendix 7 of the EA (MOD 4) will be implemented to minimise the potential for impacts on native fauna species (focusing on	Rehabilitation and Landscape Management Plan (September 2018) -	1	Compliant	1

_		Debelification and loaders At 101 (0 1 1 2017)	I		T
• r	nest boxes will be established in retained vegetation in proximity to the proposed disturbance footprint to mitigate the loss of hollow-bearing trees	Rehabilitation and Landscape Management Plan (September 2018) - Section 3.8.2		Compliant	
	targeted weed management measures including regular weed inspections and weed control and eradication techniques such as herbicides, physical removal and prompt evegetation of bare areas will be implemented in the Modification Project Area	Rehabilitation and Landscape Management Plan (September 2018) - Section 3.1.2		Compliant	
	targeted feral animal management measures will be implemented in accordance with Holcim Australia's existing Landscape Management Plan	Rehabilitation and Landscape Management Plan (September 2018) -		Compliant	
-	traffic control measures/speed limits/signage will be implemented on haul roads to minimise fauna injury/road kills, as much as possible.	Section 3.1.2 Site observations	Sighted signage, speed limits and exclusion fencing.	Compliant	
_	olcim Australia will deliver a Biodiversity Offset Strategy for the Modification Project in accordance with the NSW Biodiversity Offsets Policy for Major Projects.	Rehabilitation and Landscape Management Plan (September 2018) -	Sprice Signage, speed immediate exclusion retraing.		
		Section 3.8.1 Box Gum Woodland Management Plan (September 2013) - Section 2		Compliant	
urface Water Su					
Hc	olcim Australia will update the Lynwood Quarry Water Management Plan. This will include an update to the Lockyersleigh Creek Riparian Area Management Plan.	Water Management Plan (2020) Riparian Area Management Plan Lockyersleigh Creek Catchment (May 2018)	Water Management Plan (2020) - has been regualrly reviewed during the audite period. The Riparian Area Management Plan Lockyersleigh Creek Catchment (May 2018) document has beereviewed since its inception in 2011.	Compliant	
Κε	ey surface water management controls for the Modification Project will include:	Note.			
•	Erosion and sediment controls will set out and monitored during construction and operation in accordance with the Blue Book (Landcom, 2004 and DECC, 2008).	Water Management Plan (2020) - Section 6		Compliant	
	Monitoring of water imported to site, water used on site and water discharged following the guidelines for Water Reporting Requirements for Mines (NSW Office of Water, ndated), where applicable.	Water Management Plan (2020) - Section 3.2 and 5.5	The WMP (2020) states Holcim will monitor all water used on site, imported to site and overflows from sediment dams. The WMP (2011) does not state if this is in line with following the guidelines for Water Reporting Requirements for Mines (NSW Office of Water, undated). Section 3.2 refers to guidelines the WMP adheres to but does not refer to Water Reporting Requirements for Mines (NSW Office of Water, undated).		The revised WMP (2020) should state if the guidelines for Water Reporting Requirements for Mines (NSW Office of Water, undated) have been used in the WMP (2020) development.
	The existing surface water monitoring program will be updated to include four additional sites as shown in Figure 2.2 of the Response to Submissions report. The final details f the proposed surface water monitoring program will be contained within the updated Water Management Plan.	Water Management Plan (2020) Surface Water Monitoring Program (2020)	Figure 6 of the WMP identifies the four additional surface water montioring locations as per the MOD 4 Response to Submission Figure 2.2.	Compliant	
ob	The water quality parameters and frequency of sampling will remain as for the existing approved operations. Flow monitoring will continue to be undertaken by visual bservation of the flows during water quality sampling (flow, no-flow).	Water Management Plan (2020) Surface Water Monitoring Program (2020)		Compliant	
Ho we	roundwater olcim Australia will extend the current groundwater monitoring program, which includes both groundwater level and quality, to include the new monitoring piezometers that rere constructed for the Granite Pit during the exploration drilling phase. Details of these locations are provided in Appendix 9 of the EA (MOD 4). These bores will be nonitored until they are progressively removed by the progression of the Granite Pit or as otherwise refined via the Water Management Plan.	Water Management Plan (2020) Groundwater Monitoring Program (2020)		Compliant	
Social impact Sc	ocial Impact and Opportunities				
—	olcim Australia will implement the following measures in relation to mitigating social impacts and maximising opportunities:	Note.			
• (isual Ongoing liaison with interested members of the Towrang community with regard to lighting and other visual impacts as appropriate. Ongoing discussion with key residents in Marulan and surrounds. Implementation of the visual management measures outlined later in this section.	Site Interviews - W Beattie CCC Consultation Site Observations	Community engagement facilitated via the CCC. Visual mitigation works including visual bund and sials installed.	Compliant	
<u>La</u>	and Management Where appropriate, consult with neighbouring landholders when undertaking pest and weed management activities.	Sighted pest management notifications around boundaries Sighted evidence of engagement of vertbrate pest management services Pest management reported through Annual Reviews and CCC		Compliant	
	opulation Change (infrastructure and services) Continue implementation of the community fund.	Site Interviews - W Beattie	Site interview confirmed Holcim still continuing to implement community fund intiatioves	Compliant	
• (and Use and Industry Diversity Consider potential benefits to the local tourist industry when determining community contributions, in consultation with relevant community and business stakeholders as elevant throughout the life of operations.	Site Interviews - W Beattie	Local tourist industry considered when assessing commuity funding.	Compliant	
Tri •	rust and Reputation Existing engagement to continue as appropriate, with a focus on respectful, honest and open communications.	CCC Consultation		Compliant	
- o - rı	Continue to communicate regularly with nearby and interested stakeholders regarding: ongoing operations on site residents' experience of impacts such as dust, noise, blasting, traffic, heritage and impacts to water visual impacts, particularly with interested members of the Towrang community.	CCC Consultation		Compliant	
Co	Holcim Australia will periodically review the operation and membership of the CCC, in line with the 2007 Guidelines for establishing and operating Community Consultative ommittees for Mining Projects, to ensure that membership is appropriate for the issues discussed and that matters discussed and minutes are distributed (for example via mail) to all interested community stakeholders more widely	CCC Consultation		Compliant	
	Utilise additional communication channels such as local newsletter, updates and local blogs.	Holcim website, including general company and community updates. Sighted Holcim contributions to Marulan Messenger - a local monthly community newsletter.		Compliant	
	fonitoring Undertake social monitoring as outlined in Table 6.14 of the EA (MOD 4).	EA (MOD 4) - Table 6.14 CCC	Table 6.14 states the following will be completed in regard to social monitoring: • Completion of periodic community surveys to review community perception over time. • Continued implementation of community engagement program including seeking feedback on engagement effectiveness and on the community's preferred engagement mechanisms. • Continued effective operation of the CCC. • Newsletter content to focus on key community issues identified as of most interest to the community. • Community survey outcomes and feedback from the CCC to be used to inform and update engagement and broader business planning. No evidence sighted of periodic community surveys or newsletters during audit period. Its is noted CCC operated effectively.	Non-compliant	NC19

	• Amenity Bund – an approximately 12 metre high amenity bund (and 14 metres in spot locations, as required) will be constructed along the western boundary of the Granite Pit Area. This bund will be constructed as part of the initial establishment phases of the Granite Pit so that it is in place for the life of the quarry operations. The outer face of				
	the bund will be revegetated (through direct seeding or tube stock) as quickly as possible so that trees, over time, will contribute to the overall visual screening of the quarry operations.	Site observations	Sighted complete Amentity Bund.	Compliant	
L		en l		Constituti	
	Lighting – there will be no fixed lighting in the Granite Pit Area.	Site observations		Compliant	
- 1	• Lighting – quarry operations on the surface including topsoil stripping, overburden extraction and overburden emplacement will be daytime operations only (consistent with current development consent conditions) and therefore do not have any potential to result in lighting impacts.		Sighted shift reports confirming complaince	Compliant	
- ⊢	• Lighting – quarrying within the Granite Pit will occur in the evening period (up to 10 pm, consistent with current development consent conditions) but will be managed so	Shift reports			
	that extraction activities are undertaken in areas that are not visible from the potential viewing locations to the west (i.e. on lower benches or on the western face of the	Site observations			
- 1	quarry), with mobile lighting plant kept low and pointing down, facing away from western residences and kept to the minimum needed for operational safety.	Shift reports	Sighted shift reports confirming complaince	Compliant	
L		· ·			
- 1	• Lighting – a bund will be constructed along the western and southern faces of the haul road from the Granite Pit to the infrastructure area. The purpose of this bund will be				
- 1	o seek to screen the headlights of vehicles operating on the haul during the evening period (6pm to 10pm). The bunding will be	Site observations	Sithed complete bund.	Compliant	
	approximately 5 metres high. Overburden emplacement – Holcim Australia will seek to construct the outer edges of the overburden emplacement areas first, creating an approximate 5-10 metre high				
	bund behind which overburden emplacement activities will continue. This will provide visual screening of ongoing emplacement activities and allow timely rehabilitation of the	Site observations	Overburden emplacement area constructed prior to audit period,		
	outer face of the emplacement area to minimise visual impacts (noting that once rehabilitated the emplacement areas will start to blend into the existing environment and not		assumed complaint on basis of previous audit findings.	Compliant	
h	ne as visually prominent)				
	Overburden emplacement – emplacement areas will be rehabilitated as soon as practicable after final shaping, with progressive rehabilitation to be undertaken over the life	Site observations	Overburden emplacement areas still active, seeding has been		
	of the quarry so that the externally visible disturbed area is kept as small as practicable. Revegetation will be undertaken as discussed in Section 6.15 of the EA (MOD 4) to	Site observations	undertaken on areas which will be left in the current state for	Compliant	
re	result in mixed grassland and woodland vegetation that will be similar in visual character to the surrounding natural landscape.	Site interviews - W Beattie	extended periods of time.		
•	Overburden emplacement - the surface of the Southern Overburden Emplacement Area and the Lynwood Overburden Emplacement area will be shaped to have swales,			Not triggered	
SI	small drainage hollows and a locally irregular landform to resemble, where practicable, the natural surrounding landform.	Site observations	Final shaping yet to commence, overburden emplacement areas		
		Site Interviews - W Beattie	still active.		
•	• Quarry operations – the upper western facing benches of the Granite Pit (which are in overburden material) will be shaped and rehabilitated progressively as the quarry		Amenity bund will mask western facing benches. Benches have		
р	progresses. These areas will be visible from a small number of elevated properties in Towrang and so will be rehabilitated as soon as practicable to reduce visibility.	Site observations	been	Compliant	
		Site Interviews - W Beattie	contoured in preparation for rehab.		
•	• Maintenance – Holcim Australia will maintain the amenity bund and its vegetative cover so that it remains effective for the duration of the quarry operations.				REC3
		Site observations	Amentity bund seeded with well established vegetatation.	Compliant	
			Minor erosion sighted.		
٨	Note: as discussed in the EA, the priority for emplacement of overburden will be 1 - construction of haul roads to allow quarrying, 2 - construction of the visual bund, 3 -	Note.			
	construction of the outer faces of the overburden emplacement areas.	1000			
-	Aboriginal Cultural Heritage	10 11 11 11 11 11 11 11 11 11 11 11 11 1			
- 1	Holcim Australia will update the Aboriginal Cultural Heritage Management Plan (ACHMP) for Lynwood Quarry.	Lynwood Quarry Aboriginal Heritage Management Plan, Caring for County		Compliant	
_	Holcim Australia will implement the Aboriginal Cultural Heritage management actions detailed in Section 6.9.9 of the EA (MOD 4).	(Umwelt 2022)		·	
- ⊢	distoric Heritage				
	The historic heritage management measures to be implemented for the Modification Project are as follows:	Note.		Constitution (
	Blasting is to be designed so that vibration does not exceed 5 mm/s at the Lockyersleigh Homestead and outbuildings with blasts monitored to confirm compliance.	Blast Management Plan (February 2020)	Section 8, BMP addresses Condition 11 (b)	Compliant	
	Subject to agreement of the landowner, an inspection will be undertaken to confirm the structural integrity of Lockyersleigh Homestead and associated outbuildings to	Previous audit sighted: A & R Engineering Design Pty Ltd condition report		Compliant	
- 1	confirm that a maximum ground vibration limit with a peak particle velocity of 5 mm/s is appropriate.	(structural integrity report) dated 22 June 2016	Considered closed from previous audit		
•	In the unlikely event that unexpected archaeological remains or potential heritage items not identified as part of this report are discovered during the Modification Project,	,		Not triggered	
	all works in the immediate area will cease. The remains and potential impacts will be assessed by a qualified archaeologist or heritage consultant and, if necessary, the Heritage	Site Interviews - W Beattie		33	
	Branch. OEH notified in accordance with Section 146 of the Heritage Act 1977.				
	• If potential human remains are located following any surface disturbance, all works will halt in the immediate area to prevent any further impacts to the remains. The NSW Police will be contacted immediately.	Site Interviews - W Beattie		Not triggered	
	Conce will be Contracted infiniediately.	OUTSIDE AUDIT PERIOD			
	·				
G	The key technical control measures to be implemented as part of the Modification Project include:	Note.			
G T	The key technical control measures to be implemented as part of the Modification Project include: pipelines will be designed in accordance with relevant standards	Note.		Not triggered	
G T		Note. Site Interviews - W Beattie	No interaction with the Gas Pipeline during the audit period.	Not triggered	
G ⊤	pipelines will be designed in accordance with relevant standards	Site Interviews - W Beattie			
T •			No interaction with the Gas Pipeline during the audit period. No interaction with the Gas Pipeline during the audit period.	Not triggered Not triggered	
• •	pipelines will be designed in accordance with relevant standards	Site Interviews - W Beattie Site Interviews - W Beattie	No interaction with the Gas Pipeline during the audit period.		
G T •	pipelines will be designed in accordance with relevant standards geotechnical assessment will be undertaken to determine soil stability at pipeline crossing location prior to construction activities	Site Interviews - W Beattie		Not triggered	
•	pipelines will be designed in accordance with relevant standards geotechnical assessment will be undertaken to determine soil stability at pipeline crossing location prior to construction activities	Site Interviews - W Beattie Site Interviews - W Beattie Site Interviews - W Beattie	No interaction with the Gas Pipeline during the audit period. No interaction with the Gas Pipeline during the audit period.	Not triggered	
•	pipelines will be designed in accordance with relevant standards geotechnical assessment will be undertaken to determine soil stability at pipeline crossing location prior to construction activities civil design of the haul road/pipeline crossing will be undertaken so that the installed road meets load bearing capacity requirements and relevant standards	Site Interviews - W Beattie Site Interviews - W Beattie	No interaction with the Gas Pipeline during the audit period.	Not triggered Not triggered	
•	pipelines will be designed in accordance with relevant standards geotechnical assessment will be undertaken to determine soil stability at pipeline crossing location prior to construction activities civil design of the haul road/pipeline crossing will be undertaken so that the installed road meets load bearing capacity requirements and relevant standards use of appropriate equipment to minimise the impact on the pipes in the event of contact use of process and design controls including limited excavation depths, buffer distances and designated crossings to limit potential for contact with or overstress of the pipes	Site Interviews - W Beattie	No interaction with the Gas Pipeline during the audit period. No interaction with the Gas Pipeline during the audit period.	Not triggered Not triggered	
•	pipelines will be designed in accordance with relevant standards geotechnical assessment will be undertaken to determine soil stability at pipeline crossing location prior to construction activities civil design of the haul road/pipeline crossing will be undertaken so that the installed road meets load bearing capacity requirements and relevant standards use of appropriate equipment to minimise the impact on the pipes in the event of contact use of process and design controls including limited excavation depths, buffer distances and designated crossings to limit potential for contact with or overstress of the pipes during haul road construction.	Site Interviews - W Beattie	No interaction with the Gas Pipeline during the audit period. No interaction with the Gas Pipeline during the audit period.	Not triggered Not triggered Not triggered Compliant	
• d	pipelines will be designed in accordance with relevant standards geotechnical assessment will be undertaken to determine soil stability at pipeline crossing location prior to construction activities civil design of the haul road/pipeline crossing will be undertaken so that the installed road meets load bearing capacity requirements and relevant standards use of appropriate equipment to minimise the impact on the pipes in the event of contact use of process and design controls including limited excavation depths, buffer distances and designated crossings to limit potential for contact with or overstress of the pipes during haul road construction. The key non-technical safeguards and procedures to be implemented as part of the Modification Project for works in the vicinity of the gas pipeline will include:	Site Interviews - W Beattie Sighted internal permit system required to be completed prior to any	No interaction with the Gas Pipeline during the audit period. No interaction with the Gas Pipeline during the audit period.	Not triggered Not triggered Not triggered	
• • • • • • • • • • • • • • • • • • • •	pipelines will be designed in accordance with relevant standards geotechnical assessment will be undertaken to determine soil stability at pipeline crossing location prior to construction activities civil design of the haul road/pipeline crossing will be undertaken so that the installed road meets load bearing capacity requirements and relevant standards use of appropriate equipment to minimise the impact on the pipes in the event of contact use of process and design controls including limited excavation depths, buffer distances and designated crossings to limit potential for contact with or overstress of the pipes during haul road construction. The key non-technical safeguards and procedures to be implemented as part of the Modification Project for works in the vicinity of the gas pipeline will include: assessment of process designs, site layout and design changes	Site Interviews - W Beattie Sighted internal permit system required to be completed prior to any	No interaction with the Gas Pipeline during the audit period. No interaction with the Gas Pipeline during the audit period.	Not triggered Not triggered Not triggered Compliant	
• • • • • • • • • • • • • • • • • • • •	pipelines will be designed in accordance with relevant standards geotechnical assessment will be undertaken to determine soil stability at pipeline crossing location prior to construction activities civil design of the haul road/pipeline crossing will be undertaken so that the installed road meets load bearing capacity requirements and relevant standards use of appropriate equipment to minimise the impact on the pipes in the event of contact use of process and design controls including limited excavation depths, buffer distances and designated crossings to limit potential for contact with or overstress of the pipes during haul road construction. The key non-technical safeguards and procedures to be implemented as part of the Modification Project for works in the vicinity of the gas pipeline will include: assessment of process designs, site layout and design changes procedural control including APA Group's Daily Permit System, site inductions and other procedures	Site Interviews - W Beattie Sighted internal permit system required to be completed prior to any	No interaction with the Gas Pipeline during the audit period. No interaction with the Gas Pipeline during the audit period.	Not triggered Not triggered Not triggered Compliant	
• dd T	pipelines will be designed in accordance with relevant standards geotechnical assessment will be undertaken to determine soil stability at pipeline crossing location prior to construction activities civil design of the haul road/pipeline crossing will be undertaken so that the installed road meets load bearing capacity requirements and relevant standards use of appropriate equipment to minimise the impact on the pipes in the event of contact use of process and design controls including limited excavation depths, buffer distances and designated crossings to limit potential for contact with or overstress of the pipes during haul road construction. The key non-technical safeguards and procedures to be implemented as part of the Modification Project for works in the vicinity of the gas pipeline will include: assessment of process designs, site layout and design changes procedural control including APA Group's Daily Permit System, site inductions and other procedures operating procedures, including awareness and training	Site Interviews - W Beattie Sighted internal permit system required to be completed prior to any	No interaction with the Gas Pipeline during the audit period. No interaction with the Gas Pipeline during the audit period.	Not triggered Not triggered Not triggered Compliant	
•	pipelines will be designed in accordance with relevant standards geotechnical assessment will be undertaken to determine soil stability at pipeline crossing location prior to construction activities civil design of the haul road/pipeline crossing will be undertaken so that the installed road meets load bearing capacity requirements and relevant standards use of appropriate equipment to minimise the impact on the pipes in the event of contact use of process and design controls including limited excavation depths, buffer distances and designated crossings to limit potential for contact with or overstress of the pipes during haul road construction. The key non-technical safeguards and procedures to be implemented as part of the Modification Project for works in the vicinity of the gas pipeline will include: assessment of process designs, site layout and design changes procedural control including APA Group's Daily Permit System, site inductions and other procedures operating procedures, including awareness and training cessation of operations in adverse weather conditions and where practical covering of exposed pipelines	Site Interviews - W Beattie Sighted internal permit system required to be completed prior to any	No interaction with the Gas Pipeline during the audit period. No interaction with the Gas Pipeline during the audit period.	Not triggered Not triggered Not triggered Compliant	
• • • • • • • • • • • • • • • • • • • •	pipelines will be designed in accordance with relevant standards geotechnical assessment will be undertaken to determine soil stability at pipeline crossing location prior to construction activities civil design of the haul road/pipeline crossing will be undertaken so that the installed road meets load bearing capacity requirements and relevant standards use of appropriate equipment to minimise the impact on the pipes in the event of contact use of process and design controls including limited excavation depths, buffer distances and designated crossings to limit potential for contact with or overstress of the pipes during haul road construction. The key non-technical safeguards and procedures to be implemented as part of the Modification Project for works in the vicinity of the gas pipeline will include: assessment of process designs, site layout and design changes a procedural control including APA Group's Daily Permit System, site inductions and other procedures a operating procedures, including awareness and training a cessation of operations in adverse weather conditions and where practical covering of exposed pipelines a implementation of site speed limit, driver training, route selection and physical barriers where appropriate	Site Interviews - W Beattie Sighted internal permit system required to be completed prior to any distrubance.	No interaction with the Gas Pipeline during the audit period. No interaction with the Gas Pipeline during the audit period. No interaction with the Gas Pipeline during the audit period.	Not triggered Not triggered Not triggered Compliant	
• dd T	pipelines will be designed in accordance with relevant standards geotechnical assessment will be undertaken to determine soil stability at pipeline crossing location prior to construction activities civil design of the haul road/pipeline crossing will be undertaken so that the installed road meets load bearing capacity requirements and relevant standards use of appropriate equipment to minimise the impact on the pipes in the event of contact use of process and design controls including limited excavation depths, buffer distances and designated crossings to limit potential for contact with or overstress of the pipes during haul road construction. The key non-technical safeguards and procedures to be implemented as part of the Modification Project for works in the vicinity of the gas pipeline will include: assessment of process designs, site layout and design changes procedural control including APA Group's Daily Permit System, site inductions and other procedures operating procedures, including awareness and training cessation of operations in adverse weather conditions and where practical covering of exposed pipelines	Site Interviews - W Beattie Sighted internal permit system required to be completed prior to any distrubance.	No interaction with the Gas Pipeline during the audit period. No interaction with the Gas Pipeline during the audit period. No interaction with the Gas Pipeline during the audit period.	Not triggered Not triggered Not triggered Compliant	
• • • • • • • • • • • • • • • • • • •	pipelines will be designed in accordance with relevant standards geotechnical assessment will be undertaken to determine soil stability at pipeline crossing location prior to construction activities civil design of the haul road/pipeline crossing will be undertaken so that the installed road meets load bearing capacity requirements and relevant standards use of appropriate equipment to minimise the impact on the pipes in the event of contact use of process and design controls including limited excavation depths, buffer distances and designated crossings to limit potential for contact with or overstress of the pipes during haul road construction. The key non-technical safeguards and procedures to be implemented as part of the Modification Project for works in the vicinity of the gas pipeline will include: assessment of process designs, site layout and design changes procedural control including APA Group's Daily Permit System, site inductions and other procedures operating procedures, including awareness and training essation of operations in adverse weather conditions and where practical covering of exposed pipelines implementation of site speed limit, driver training, route selection and physical barriers where appropriate provision of physical controls including fencing of site during construction Imiliting access to authorised personnel only and implementation of security patrol if necessary appropriate training and supervision of operations	Site Interviews - W Beattie Sighted internal permit system required to be completed prior to any distrubance.	No interaction with the Gas Pipeline during the audit period. No interaction with the Gas Pipeline during the audit period. No interaction with the Gas Pipeline during the audit period.	Not triggered Not triggered Not triggered Compliant	
• • • • • • • • • • • • • • • • • • •	pipelines will be designed in accordance with relevant standards geotechnical assessment will be undertaken to determine soil stability at pipeline crossing location prior to construction activities civil design of the haul road/pipeline crossing will be undertaken so that the installed road meets load bearing capacity requirements and relevant standards use of appropriate equipment to minimise the impact on the pipes in the event of contact use of process and design controls including limited excavation depths, buffer distances and designated crossings to limit potential for contact with or overstress of the pipes during haul road construction. The key non-technical safeguards and procedures to be implemented as part of the Modification Project for works in the vicinity of the gas pipeline will include: assessment of process designs, site layout and design changes procedural control including APA Group's Daily Permit System, site inductions and other procedures procedures, including awareness and training cessation of operations in adverse weather conditions and where practical covering of exposed pipelines implementation of site speed limit, driver training, route selection and physical barriers where appropriate provision of physical controls including fencing of site during construction limiting access to authorised personnel only and implementation of security patrol if necessary	Site Interviews - W Beattie Sighted internal permit system required to be completed prior to any distrubance.	No interaction with the Gas Pipeline during the audit period. No interaction with the Gas Pipeline during the audit period. No interaction with the Gas Pipeline during the audit period.	Not triggered Not triggered Not triggered Compliant	
d T	pipelines will be designed in accordance with relevant standards geotechnical assessment will be undertaken to determine soil stability at pipeline crossing location prior to construction activities civil design of the haul road/pipeline crossing will be undertaken so that the installed road meets load bearing capacity requirements and relevant standards use of appropriate equipment to minimise the impact on the pipes in the event of contact use of process and design controls including limited excavation depths, buffer distances and designated crossings to limit potential for contact with or overstress of the pipes during haul road construction. The key non-technical safeguards and procedures to be implemented as part of the Modification Project for works in the vicinity of the gas pipeline will include: assessment of process designs, site layout and design changes procedural control including APA Group's Daily Permit System, site inductions and other procedures operating procedures, including awareness and training essation of operations in adverse weather conditions and where practical covering of exposed pipelines implementation of site speed limit, driver training, route selection and physical barriers where appropriate provision of physical controls including fencing of site during construction Imiliting access to authorised personnel only and implementation of security patrol if necessary appropriate training and supervision of operations	Site Interviews - W Beattie Sighted internal permit system required to be completed prior to any distrubance.	No interaction with the Gas Pipeline during the audit period. No interaction with the Gas Pipeline during the audit period. No interaction with the Gas Pipeline during the audit period.	Not triggered Not triggered Not triggered Compliant	
d T	pipelines will be designed in accordance with relevant standards geotechnical assessment will be undertaken to determine soil stability at pipeline crossing location prior to construction activities civil design of the haul road/pipeline crossing will be undertaken so that the installed road meets load bearing capacity requirements and relevant standards use of appropriate equipment to minimise the impact on the pipes in the event of contact use of process and design controls including limited excavation depths, buffer distances and designated crossings to limit potential for contact with or overstress of the pipes during haul road construction. sassessment of process designs, site layout and design changes procedural control including APA Group's Daily Permit System, site inductions and other procedures operating procedures, including awareness and training cessation of operations in adverse weather conditions and where practical covering of exposed pipelines implementation of site speed limit, driver training, route selection and physical barriers where appropriate provision of physical controls including fencing of site during construction limiting access to authorised personnel only and implementation of security patrol if necessary appropriate training and supervision of operations provision of ongoing maintenance and operation procedures.	Site Interviews - W Beattie Sighted internal permit system required to be completed prior to any distrubance.	No interaction with the Gas Pipeline during the audit period. No interaction with the Gas Pipeline during the audit period. No interaction with the Gas Pipeline during the audit period.	Not triggered Not triggered Not triggered Compliant	
d d T	e geotechnical assessment will be undertaken to determine soil stability at pipeline crossing location prior to construction activities e civil design of the haul road/pipeline crossing will be undertaken so that the installed road meets load bearing capacity requirements and relevant standards e use of appropriate equipment to minimise the impact on the pipes in the event of contact e use of process and design controls including limited excavation depths, buffer distances and designated crossings to limit potential for contact with or overstress of the pipes during haul road construction. The key non-technical safeguards and procedures to be implemented as part of the Modification Project for works in the vicinity of the gas pipeline will include: assessment of process designs, site layout and design changes procedural control including APA Group's Daily Permit System, site inductions and other procedures procedural control including awareness and training cessation of operations in adverse weather conditions and where practical covering of exposed pipelines implementation of site speed limit, driver training, route selection and physical barriers where appropriate provision of physical controls including fencing of site during construction limiting access to authorised personnel only and implementation of security patrol if necessary appropriate training and supervision of operations provision of ongoing maintenance and operations provision of fine Modification Project Holcim Australia will review opportunities for reducing energy consumption on an ongoing basis during the detailed design process and once the operation has commenced including:	Site Interviews - W Beattie Sighted internal permit system required to be completed prior to any distrubance.	No interaction with the Gas Pipeline during the audit period. No interaction with the Gas Pipeline during the audit period. No interaction with the Gas Pipeline during the audit period.	Not triggered Not triggered Not triggered Compliant Not triggered	
d T • • • • • • • • • • • • • • • • • •	e geotechnical assessment will be undertaken to determine soil stability at pipeline crossing location prior to construction activities e civil design of the haul road/pipeline crossing will be undertaken so that the installed road meets load bearing capacity requirements and relevant standards e use of appropriate equipment to minimise the impact on the pipes in the event of contact e use of process and design controls including limited excavation depths, buffer distances and designated crossings to limit potential for contact with or overstress of the pipes during haul road construction. The key non-technical safeguards and procedures to be implemented as part of the Modification Project for works in the vicinity of the gas pipeline will include: a sasessment of process designs, site layout and design changes procedural control including APA Group's Daily Permit System, site inductions and other procedures operating procedures, including awareness and training e cessation of operations in adverse weather conditions and where practical covering of exposed pipelines implementation of site speed limit, driver training, route selection and physical barriers where appropriate provision of physical controls including fencing of site during construction limiting access to authorised personnel only and implementation of security patrol if necessary appropriate training and supervision of operations provision of ongoing maintenance and operation procedures. Sreenhouse Gas and Energy As part of the Modification Project Holcim Australia will review opportunities for reducing energy consumption on an ongoing basis during the detailed design process and once the operation has commenced including: e setting energy use and greenhouse emission reduction targets	Site Interviews - W Beattie Sighted internal permit system required to be completed prior to any distrubance. Site Interviews - W Beattie Sighted internal permit system required to be completed prior to any distrubance.	No interaction with the Gas Pipeline during the audit period. No interaction with the Gas Pipeline during the audit period. No interaction with the Gas Pipeline during the audit period. No interaction with the Gas Pipeline during the audit period. No interaction with the Gas Pipeline during the audit period. There are a number of energy-saving programs on site including automatic lights.	Not triggered Not triggered Not triggered Compliant Not triggered Compliant	
d d T	e geotechnical assessment will be undertaken to determine soil stability at pipeline crossing location prior to construction activities e civil design of the haul road/pipeline crossing will be undertaken so that the installed road meets load bearing capacity requirements and relevant standards e use of appropriate equipment to minimise the impact on the pipes in the event of contact use of process and design controls including limited excavation depths, buffer distances and designated crossings to limit potential for contact with or overstress of the pipes during haul road construction. The key non-technical safeguards and procedures to be implemented as part of the Modification Project for works in the vicinity of the gas pipeline will include: assessment of process designs, site layout and design changes procedural control including APA Group's Daily Permit System, site inductions and other procedures operating procedures, including awareness and training cessation of operations in adverse weather conditions and where practical covering of exposed pipelines implementation of site speed limit, driver training, route selection and physical barriers where appropriate provision of physical controls including fencing of site during construction limiting access to authorised personnel only and implementation of security patrol if necessary appropriate training and supervision of operations provision of ongoing maintenance and operation procedures. Greenhouse Gas and Energy As part of the Modification Project Holcim Australia will review opportunities for reducing energy consumption on an ongoing basis during the detailed design process and none the operation has commenced including: setting energy use and greenhouse emission reduction targets using energy use and greenhouse emission reduction targets	Site Interviews - W Beattie Sighted internal permit system required to be completed prior to any distrubance. Site Interviews - W Beattie	No interaction with the Gas Pipeline during the audit period. No interaction with the Gas Pipeline during the audit period. No interaction with the Gas Pipeline during the audit period. No interaction with the Gas Pipeline during the audit period. No interaction with the Gas Pipeline during the audit period. There are a number of energy-saving programs on site including automatic lights. Holcim reports to the Department of the Environment and Energy	Not triggered Not triggered Not triggered Compliant Not triggered Compliant	
d T	e geotechnical assessment will be undertaken to determine soil stability at pipeline crossing location prior to construction activities e geotechnical assessment will be undertaken to determine soil stability at pipeline crossing location prior to construction activities e use of appropriate equipment to minimise the impact on the pipes in the event of contact e use of process and design controls including limited excavation depths, buffer distances and designated crossings to limit potential for contact with or overstress of the pipes during haul road construction. The key non-technical safeguards and procedures to be implemented as part of the Modification Project for works in the vicinity of the gas pipeline will include: a assessment of process designs, site layout and design changes procedural control including APA Group's Daily Permit System, site inductions and other procedures operating procedures, including awareness and training cessation of operations in adverse weather conditions and where practical covering of exposed pipelines implementation of site speed limit, driver training, route selection and physical barriers where appropriate provision of physical controls including fencing of site during construction limiting access to authorised personnel only and implementation of security patrol if necessary appropriate training and supervision of operations provision of ongoing maintenance and operation procedures. Foreign general was a supervision of operations in a procedure of the Modification Project Holcim Australia will review opportunities for reducing energy consumption on an ongoing basis during the detailed design process and once the operation has commenced including: setting energy use and greenhouse emission reduction targets using energy monitoring and auditing as a management to site personnel	Site Interviews - W Beattie Sighted internal permit system required to be completed prior to any distrubance. Site Interviews - W Beattie Sighted internal permit system required to be completed prior to any distrubance.	No interaction with the Gas Pipeline during the audit period. No interaction with the Gas Pipeline during the audit period. No interaction with the Gas Pipeline during the audit period. No interaction with the Gas Pipeline during the audit period. No interaction with the Gas Pipeline during the audit period. There are a number of energy-saving programs on site including automatic lights. Holcim reports to the Department of the Environment and Energy-National Pollution Inventory (NPI) with a list of all emissions	Not triggered Not triggered Not triggered Compliant Not triggered Compliant	
d d T	e geotechnical assessment will be undertaken to determine soil stability at pipeline crossing location prior to construction activities e geotechnical assessment will be undertaken to determine soil stability at pipeline crossing location prior to construction activities e civil design of the haul road/pipeline crossing will be undertaken so that the installed road meets load bearing capacity requirements and relevant standards • use of appropriate equipment to minimise the impact on the pipes in the event of contact • use of process and design controls including limited excavation depths, buffer distances and designated crossings to limit potential for contact with or overstress of the pipes during haul road construction. • the key non-technical safeguards and procedures to be implemented as part of the Modification Project for works in the vicinity of the gas pipeline will include: • assessment of process designs, site layout and design changes • procedural control including APA Group's Daily Permit System, site inductions and other procedures • procedural control including awareness and training • cessation of operations in adverse weather conditions and where practical covering of exposed pipelines • implementation of site speed limit, driver training, route selection and physical barriers where appropriate • provision of physical controls including fencing of site during construction • imiting access to authorised personnel only and implementation of security patrol if necessary • provision of ongoing maintenance and operation procedures. • appropriate training and supervision of operations • provision of ongoing maintenance and operation procedures. • appropriate training and supervision and operation procedures of the Modification Project Holcim Australia will review opportunities for reducing energy consumption on an ongoing basis during the detailed design process and once the operation has commenced including: • setting energy monitoring and auditing as a management tool • providing	Site Interviews - W Beattie Sighted internal permit system required to be completed prior to any distrubance. Site Interviews - W Beattie Sighted internal permit system required to be completed prior to any distrubance.	No interaction with the Gas Pipeline during the audit period. No interaction with the Gas Pipeline during the audit period. No interaction with the Gas Pipeline during the audit period. No interaction with the Gas Pipeline during the audit period. No interaction with the Gas Pipeline during the audit period. There are a number of energy-saving programs on site including automatic lights. Holcim reports to the Department of the Environment and Energy	Not triggered Not triggered Not triggered Compliant Not triggered Compliant	
d d T · · · · · · · · · · · · · · · · ·	pipelines will be designed in accordance with relevant standards geotechnical assessment will be undertaken to determine soil stability at pipeline crossing location prior to construction activities e civil design of the haul road/pipeline crossing will be undertaken so that the installed road meets load bearing capacity requirements and relevant standards use of appropriate equipment to minimise the impact on the pipes in the event of contact use of process and design controls including limited excavation depths, buffer distances and designated crossings to limit potential for contact with or overstress of the pipes during haul road construction. The key non-technical safeguards and procedures to be implemented as part of the Modification Project for works in the vicinity of the gas pipeline will include: assessment of process designs, site layout and design changes procedural control including APA Group's Daily Permit System, site inductions and other procedures operating procedures, including awareness and training essation of operations in adverse weather conditions and where practical covering of exposed pipelines implementation of site speed limit, driver training, route selection and physical barriers where appropriate provision of physical controls including fencing of site during construction limiting access to authorised personnel only and implementation of security patrol if necessary appropriate training and supervision of operations provision of ongoing maintenance and operation procedures. Genehouse Gas and Energy As part of the Modification Project Holcim Australia will review opportunities for reducing energy consumption on an ongoing basis during the detailed design process and more the operation has commenced including: setting energy use and greenhouse emission reduction targets using energy monitoring and auditing as a management tool providing training on energy management to site personnel monitoring the fuel efficiency of diesel equipment considering the energy effici	Site Interviews - W Beattie Sighted internal permit system required to be completed prior to any distrubance. Site Interviews - W Beattie Sighted internal permit system required to be completed prior to any distrubance.	No interaction with the Gas Pipeline during the audit period. No interaction with the Gas Pipeline during the audit period. No interaction with the Gas Pipeline during the audit period. No interaction with the Gas Pipeline during the audit period. No interaction with the Gas Pipeline during the audit period. There are a number of energy-saving programs on site including automatic lights. Holcim reports to the Department of the Environment and Energy-National Pollution Inventory (NPI) with a list of all emissions	Not triggered Not triggered Not triggered Compliant Not triggered Compliant	
d T · · · · · · · · · · · · · · · · · ·	pipelines will be designed in accordance with relevant standards geotechnical assessment will be undertaken to determine soil stability at pipeline crossing location prior to construction activities civil design of the haul road/pipeline crossing will be undertaken so that the installed road meets load bearing capacity requirements and relevant standards use of appropriate equipment to minimise the impact on the pipes in the event of contact use of process and design controls including limited excavation depths, buffer distances and designated crossings to limit potential for contact with or overstress of the pipes during haul road construction. The key non-technical safeguards and procedures to be implemented as part of the Modification Project for works in the vicinity of the gas pipeline will include: assessment of process designs, site layout and design changes procedural control including APA Group's Daily Permit System, site inductions and other procedures operating procedures, including awareness and training cessation of operations in adverse weather conditions and where practical covering of exposed pipelines implementation of site speed limit, driver training, route selection and physical barriers where appropriate provision of physical controls including fencing of site during construction limiting access to authorised personnel only and implementation of security patrol if necessary appropriate training and supervision of operations appropriate training and supervision of operations provision of ongoing maintenance and operation procedures. Greenhouse Gas and Energy As part of the Modification Project Holcim Australia will review opportunities for reducing energy consumption on an ongoing basis during the detailed design process and once the operation has commenced including: a setting energy use and greenhouse emission reduction targets using energy monitoring and auditing as a management tool providing training on energy management os site personnel monitoring the fuel efficie	Site Interviews - W Beattie Sighted internal permit system required to be completed prior to any distrubance. Site Interviews - W Beattie Sighted internal permit system required to be completed prior to any distrubance.	No interaction with the Gas Pipeline during the audit period. No interaction with the Gas Pipeline during the audit period. No interaction with the Gas Pipeline during the audit period. No interaction with the Gas Pipeline during the audit period. No interaction with the Gas Pipeline during the audit period. There are a number of energy-saving programs on site including automatic lights. Holcim reports to the Department of the Environment and Energy-National Pollution Inventory (NPI) with a list of all emissions	Not triggered Not triggered Not triggered Compliant Not triggered Compliant	
d d T · · · · · · · · · · · · · · · · ·	pipelines will be designed in accordance with relevant standards geotechnical assessment will be undertaken to determine soil stability at pipeline crossing location prior to construction activities civil design of the haul road/pipeline crossing will be undertaken so that the installed road meets load bearing capacity requirements and relevant standards use of appropriate equipment to minimise the impact on the pipes in the event of contact use of process and design controls including limited excavation depths, buffer distances and designated crossings to limit potential for contact with or overstress of the pipes during haul road construction. The key non-technical safeguards and procedures to be implemented as part of the Modification Project for works in the vicinity of the gas pipeline will include: assessment of process designs, site layout and design changes procedural control including APA Group's Daily Permit System, site inductions and other procedures appropriate procedures, including awareness and training cessation of operations in adverse weather conditions and where practical covering of exposed pipelines implementation of site speed limit, driver training, route selection and physical barriers where appropriate provision of physical controls including fencing of site during construction limiting access to authorised personnel only and implementation of security patrol if necessary appropriate training and supervision of operations provision of ongoing maintenance and operations procedures. Greenhouse Gas and Energy As part of the Modification Project Holcim Australia will review opportunities for reducing energy consumption on an ongoing basis during the detailed design process and once the operation has commenced including: setting energy use and greenhouse emission reduction targets using energy monitoring and auditing as a management tool providing training on energy management to site personnel monitoring the fuel efficiency of diesel equipment considering the energy eff	Site Interviews - W Beattie Sighted internal permit system required to be completed prior to any distrubance. Site Interviews - W Beattie Sighted internal permit system required to be completed prior to any distrubance.	No interaction with the Gas Pipeline during the audit period. No interaction with the Gas Pipeline during the audit period. No interaction with the Gas Pipeline during the audit period. No interaction with the Gas Pipeline during the audit period. No interaction with the Gas Pipeline during the audit period. There are a number of energy-saving programs on site including automatic lights. Holcim reports to the Department of the Environment and Energy-National Pollution Inventory (NPI) with a list of all emissions	Not triggered Not triggered Not triggered Compliant Not triggered Compliant	Nega
G A O O O O O O O O O O O O O O O O O O	pipelines will be designed in accordance with relevant standards geotechnical assessment will be undertaken to determine soil stability at pipeline crossing location prior to construction activities civil design of the haul road/pipeline crossing will be undertaken so that the installed road meets load bearing capacity requirements and relevant standards use of appropriate equipment to minimise the impact on the pipes in the event of contact use of process and design controls including limited excavation depths, buffer distances and designated crossings to limit potential for contact with or overstress of the pipes buring haul road construction. The key non-technical safeguards and procedures to be implemented as part of the Modification Project for works in the vicinity of the gas pipeline will include: assessment of process designs, site layout and design changes procedural control including APA Group's Daily Permit System, site inductions and other procedures operating procedures, including awareness and training cossation of operations in adverse weather conditions and where practical covering of exposed pipelines implementation of site speed limit, driver training, route selection and physical barriers where appropriate provision of physical controls including fencing of site during construction limiting access to authorised personnel only and implementation of security patrol if necessary appropriate training and supervision of operations provision of ongoing maintenance and operation procedures. Greenhouse Gas and Energy As part of the Modification Project Holcim Australia will review opportunities for reducing energy consumption on an ongoing basis during the detailed design process and nonce the operation has commenced including: setting energy wonlitoring and auditing as a management tool providing training on energy management to site personnel only appropriate training and energy management to site personnel only and implementation of the providing training on energy management to s	Site Interviews - W Beattie Sighted internal permit system required to be completed prior to any distrubance. Site Interviews - W Beattie Sighted overarching Holcim Greenhouse Gas Reduction Strategy Site Interviews - W Beattie	No interaction with the Gas Pipeline during the audit period. No interaction with the Gas Pipeline during the audit period. No interaction with the Gas Pipeline during the audit period. No interaction with the Gas Pipeline during the audit period. No interaction with the Gas Pipeline during the audit period. There are a number of energy-saving programs on site including automatic lights. Holcim reports to the Department of the Environment and Energy - National Pollution Inventory (NPI) with a list of all emissions leaving the site	Not triggered Not triggered Not triggered Compliant Not triggered Compliant Not triggered	NC20
6 T T • • • • • • • • • • • • • • • • •	pipelines will be designed in accordance with relevant standards geotechnical assessment will be undertaken to determine soil stability at pipeline crossing location prior to construction activities civil design of the haul road/pipeline crossing will be undertaken so that the installed road meets load bearing capacity requirements and relevant standards use of appropriate equipment to minimise the impact on the pipes in the event of contact use of process and design controls including limited excavation depths, buffer distances and designated crossings to limit potential for contact with or overstress of the pipes during haul road construction. The key non-technical safeguards and procedures to be implemented as part of the Modification Project for works in the vicinity of the gas pipeline will include: assessment of process designs, site layout and design changes procedural control including APA Group's Daily Permit System, site inductions and other procedures operating procedures, including awareness and training cessation of operations in adverse weather conditions and where practical covering of exposed pipelines implementation of site speed limit, driver training, route selection and physical barriers where appropriate provision of physical controls including fencing of site during construction limiting access to authorised personnel only and implementation of security patrol if necessary appropriate training and supervision of operations provision of ongoing maintenance and operation procedures. Greenhouse Gas and Energy As part of the Modification Project Holcim Australia will review opportunities for reducing energy consumption on an ongoing basis during the detailed design process and nece the operation has commenced including: setting energy use and greenhouse emission reduction targets using energy monitoring and auditing as a management tool providing training on energy management to site personnel monitoring the fuel efficiency of diesel equipment considering the energy efficiency of diesel	Site Interviews - W Beattie Sighted internal permit system required to be completed prior to any distrubance. Site Interviews - W Beattie Sighted overarching Holcim Greenhouse Gas Reduction Strategy Site Interviews - W Beattie	No interaction with the Gas Pipeline during the audit period. No interaction with the Gas Pipeline during the audit period. No interaction with the Gas Pipeline during the audit period. No interaction with the Gas Pipeline during the audit period. No interaction with the Gas Pipeline during the audit period. There are a number of energy-saving programs on site including automatic lights. Holcim reports to the Department of the Environment and Energy - National Pollution Inventory (NPI) with a list of all emissions leaving the site	Not triggered Not triggered Not triggered Compliant Not triggered Compliant Not triggered	NC20 REC4
6 T T O O O O O O O O O O O O O O O O O	pipelines will be designed in accordance with relevant standards geotechnical assessment will be undertaken to determine soil stability at pipeline crossing location prior to construction activities civil design of the haul road/pipeline crossing will be undertaken so that the installed road meets load bearing capacity requirements and relevant standards use of appropriate equipment to minimise the impact on the pipes in the event of contact use of process and design controls including limited excavation depths, buffer distances and designated crossings to limit potential for contact with or overstress of the pipes buring haul road construction. The key non-technical safeguards and procedures to be implemented as part of the Modification Project for works in the vicinity of the gas pipeline will include: assessment of process designs, site layout and design changes procedural control including APA Group's Daily Permit System, site inductions and other procedures operating procedures, including awareness and training cossation of operations in adverse weather conditions and where practical covering of exposed pipelines implementation of site speed limit, driver training, route selection and physical barriers where appropriate provision of physical controls including fencing of site during construction limiting access to authorised personnel only and implementation of security patrol if necessary appropriate training and supervision of operations provision of ongoing maintenance and operation procedures. Greenhouse Gas and Energy As part of the Modification Project Holcim Australia will review opportunities for reducing energy consumption on an ongoing basis during the detailed design process and nonce the operation has commenced including: setting energy wonlitoring and auditing as a management tool providing training on energy management to site personnel only appropriate training and energy management to site personnel only and implementation of the providing training on energy management to s	Site Interviews - W Beattie Sighted internal permit system required to be completed prior to any distrubance. Site Interviews - W Beattie Sighted overarching Holcim Greenhouse Gas Reduction Strategy Site Interviews - W Beattie Rehabilitation and Landscape Management Plan (2018) - Section 3.1	No interaction with the Gas Pipeline during the audit period. No interaction with the Gas Pipeline during the audit period. No interaction with the Gas Pipeline during the audit period. No interaction with the Gas Pipeline during the audit period. No interaction with the Gas Pipeline during the audit period. There are a number of energy-saving programs on site including automatic lights. Holcim reports to the Department of the Environment and Energy - National Pollution Inventory (NPI) with a list of all emissions leaving the site Section 3.1 of the Rehabilitation and Landscape Management Plan (20)	Not triggered Not triggered Not triggered Compliant Not triggered Compliant Not triggered	

• stripped topsoil will be placed in stockpiles in depths of up to approximately three metres and will seeded with a cover crop if they are to remain in place for longer than approximately six months	Isite observations	Sighted topsoil stockpile appear in compliance. It is noted the majority of top soil has been relied on to rehabilitate the amentity bund.	Compliant	
shaped areas will be covered with topsoil where practicable	Rehabilitation and Landscape Management Plan (2018) - Section 3.2.2 Site observations Site Interviews - W Beattie	Amentity bund covered with topsoil following construction.	Compliant	
• areas where topsoil has been replaced will be seeded with a native species and cover crop mix with intent of achieving mixed grassland and woodland native vegetation communities	Rehabilitation and Landscape Management Plan (2018) - Section 3.2.2 Site observations Site Interviews - W Beattie	Amentity bund deeded and direct planted.	Compliant	
• selected surface habitat features consisting of large rocks, logs and trees from clearing undertaken in the Modification Project Area will also be placed across the rehabilitated area, where practicable		Materials recovered and stockpiled for future rehabilitation activieis.	Compliant	
• upon closure of the quarry, unless an alternative use of the quarry infrastructure is identified, the infrastructure will be removed and the areas containing the surface infrastructure will be recontoured. The reshaped areas will then be seeded with a native species and cover crop mix with the intent of achieving mixed grassland and woodland native vegetation communities	Rehabilitation and Landscape Management Plan (2018)		Not triggered	
• upon closure of the quarry, the haul roads would also be removed and water management controls either removed or modified to assist in stabilisation of the final landform and to capture any sediment runoff from the rehabilitated areas.	Rehabilitation and Landscape Management Plan (2018)		Not triggered	

Table A.3 - EPL 12939 - Variation 27-Oct-2023

	. 12939 -	variation	27-Oct-2023	3		a Pro-	Term and the second	the state of the s		
ion						Audit team responsible for condition	Evidence collected r	Independent Audit Findings and Recommendations	Compliance status	Unique Identification compliance
	• .		of pollutants to the	identified in this licende air from the point.	e for the purposes of monitoring and/or					
EPA identi fication no		-	Air Type of Discharge Point	Location Description Dust deposition gauge id the map attached to the o "EPA Monitor Relocation 2020", received by EPA	locument titled Letter February			2021 All dust deposition (DD) gauges and high volume (HVAS) units were in operation. HVAS 1 failed to operate on 4 occasions during the year and HVAS 2 failed to operate on 1 occasion		
14	PM10 Dust			on 6 February 2020 (DO Dust deposition gauge la in Figure 1 Revised Moni received by EPA 8 Nover (DOC16/565661). Dust deposition gauge la	220/98576-1). belled as HVAS1 toring Locations, nber 2016		Annual Review 2020, 2021, 2022	during the year. (Lynwood Quarry 2021 Annual Review); 2022 All dust deposition (DD) gauges and high volume (HVAS) units were in operation. HVAS 1 failed to operate on 8 occasions during the year. (Lynwood Quarry 2022 Annual Review); 2023 - All dust deposition (DD) gauges and high volume (HVAS) units were in operation. HVA		
16	Dust Monito			in Figure 1 Revised Moni received by EPA 8 Nove (DOC16/565661). Dust deposition gauge la	nber 2016 belled as DD8 in		2023 Quarterly Monitoring Reports Site observations	2023 - All dust deposition (DD) gauges and high volume (HVAS) units were in operation. HV 1 failed to operate on 8 occasions during the year and HVAS 2 failed to operate on 2 occasions during the year (Lynwood (EPL 12939) - Live Monitoring Worksheet 2023.XLS).	Non-compliant	
17	Dust monito	oring		Figure 1 Revised Monitor received by EPA 8 Novel (DOC16/565661). Dust deposition of Monitor	nber 2016 belled as DD11 in			In general, all points were monitored during the three year period. Occasional failures occurred at the high volume samplers (reported as LOW NON-COMPLIANCE in 2021 and 202 Annual Reviews). Dust deposition gauges were not collected in June 2021 due to CV19	2	
18	Dust monito	oring		Figure 1 Revised Monitor received by EPA 8 Nover (DOC16/565661). Dust deposition gauge D in map supplied by Holci	mber 2016 D12, as identified			restrictions.		
19	Dust monito	oring		28 August 2019 (DOC19 Dust deposition gauge la Figure 1 Revised Monitor received by EPA 8 Novel (DOC16/565661).	belled as DD13 in ing Locations,					NC21
Noise gen	erated at the	premises mus	t not exceed the n	noise limits presented	in the table below:					NCZI
Noise Assess Location		1	Evening	Night	Night					
Locatio	n 1 35	eq (15 minute)	LAeq (15 minute)	LAeq (15 minute) 35	LA1 (1 minute) 45		2021 - attended monitoring undertaken 4 times in the year at 4 representative locations (closest receivers). All compliant with agreed noise criteria. (Lynwood	d		
Location Location Location	n 3 35		35	35	45		Quarry 2021 Annual Review / Noise Monitoring Assessment Quarterly Reports from 2021 (Muller Acoustic Consulting Pty Ltd (MAC)); 2022- attended monitoring undertaken 4 times in the year at 4 representative locations (closest receivers). All compliant with agreed noise criteria.(Lynwood Quarry 2022 Annual Review / Noise Monitoring Assessment Quarterly Reports from 2022 (Muller Acoustic Consulting Pty Ltd (MAC) / Ramboll); 2023 - attended monitoring undertaken 3 times in the year at 4 representative locations (closest receivers). All compliant with agreed noise criteria (Ramboll). (Lynwood (EPL 12939) - Live Monitoring Worksheet 2023.XLS / Noise	year. No exceedances of the noise limits set were recorded due to the quarry; however, attended monitoring found occasional exceedance caused by bird noise, road traffic noise and rail (train) noise. These noise events were excluded from the results.		
Location	n 5 35		35	35	46				Non-compliant	
Location	n 7 38		38	35	55					
Location			38	36 37	55			Icriteria of 35 LAeg (15min) dBA. The LA1 quarry contribution also exceeded the LA1(1min)		
Location			42 35	40 36	53 47					
Location			37 38	36 37	47 47		Monitoring Assessment Quarterly Reports from 2023 (Ramboll)). Exceedance noted within spreadsheet			
Locatio			35 35	35 35	47 47					
Location	n 16 35		35	35	45					NC22
2 Air Monito	oring Require	ments								
Partic		nits of measure rams per square metre onth	Frequency per Monthly	Sampling Method AM-19				2021 All dust deposition (DD) gauges were in operation to collect PM g/sqm/month and high volume (HVAS) units were in operation to collect a HV Sample of PM10 for 24 hours very 6 days. HVAS 1 failed to operate on 4 occasions during the year and HVAS 2 failed to operate		
POINT 14,15	5							on 1 occasion during the year. (Lynwood Quarry 2021 Annual Review); 2022 All dust deposition (DD) gauges were in operation to collect PM g/sqm/month and high		
PM10	0 m		Frequency etre Special Frequency				Annual Review 2020, 2021, 2022 (Lynwood (EPL 12939) - Live Monitoring Worksheet 2023.XLS	volume (HVAS) units were in operation to collect a HV Sample of PM10 for 24 hours very 6 days. HVAS 1 failed to operate on 8 occasions during the year. (Lynwood Quarry 2022 Annua Review);	Non-compliant	
	ne purposes of the t	able(s) above Specia	ii Frequency 1 means the	collection of samples over a 24	our		high volume (HVAS) units were in operation to collect a HV Sample of days. HVAS 1 failed to operate on 8 occasions during the year and	2023 - All dust deposition (DD) gauges were in operation to collect PM g/sqm/month and high volume (HVAS) units were in operation to collect a HV Sample of PM10 for 24 hours ver 6 days. HVAS 1 failed to operate on 8 occasions during the year and HVAS 2 failed to operate on 2 occasions during the year (Lynwood (EPL 12939) - Live Monitoring Worksheet 2023.XLS		
							Annual Review 2020, 2021, 2022, 2023 Site Incident management software package	No evidence of incidents or exceedances reported to EPA of EPL criteria during the audit period Notable this includes ongoing failures of air quality and noise monitoring events. It is noted that		NC23
Notificatio	ons must be n	nade by teleph	oning the Environ	ment Line service on	131 555.		Holcim website	incidents recorded within the information provided are unlikely to have caused environmental harm.	ion compliant	NC24
The license aware of t	ee must prov he incident. licensee or its ironment imn	ide written de s employees m	tails of the notifica	ation to the EPA within	n 7 days of the date on which they became dents causing or threatening material harn ent in accordance with the requirements of	1	Annual Review 2020, 2021, 2022, 2023 Site Incident management software package Holcim website	No evidence of incidents or exceedances reported to EPA of EPL criteria during the audit period Notable this includes ongoing failures of air quality and noise monitoring events. It is noted that incidents recorded within the information provided are unlikely to have caused environmental harm.		NC25

Monitoring must be under	ertaken at HVAS1 and HVAS 2 as described in Condition P1.2.		Annual Review 2020, 2021, 2022 2023 Quarterly Monitoring Reports Site observations	2021 All dust deposition (DD) gauges and high volume (HVAS) units were in operation. HVAS 1 failed to operate on 4 occasions during the year and HVAS 2 failed to operate on 1 occasion during the year. (Lynwood Quarry 2021 Annual Review); 2022 All dust deposition (DD) gauges and high volume (HVAS) units were in operation. HVAS 1 failed to operate on 8 occasions during the year. (Lynwood Quarry 2022 Annual Review); 2023 - All dust deposition (DD) gauges and high volume (HVAS) units were in operation. HVAS 1 failed to operate on 8 occasions during the year and HVAS 2 failed to operate on 2 occasions during the year (Lynwood (EPL 12939) - Live Monitoring Worksheet 2023.XLS). In general, all points were monitored during the three year period. Occasional failures occurred at the high volume samplers (reported as LOW NON-COMPLIANCE in 2021 and 2022 Annual Reviews). Dust deposition gauges were not collected in June 2021 due to CV19 restrictions.		NC26
U1.3 Monitoring must be under	ertaken using the same methodology as described in Condition M2.2.	I	Annual Review 2020, 2021, 2022 (Lynwood (EPL 12939) - Live Monitoring Worksheet 2023.XLS	2022 All dust deposition (DD) gauges were in operation to collect PM g/sqm/month and high volume (HVAS) units were in operation to collect a HV Sample of PM10 for 24 hours very 6 days. HVAS 1 failed to operate on 4 occasions during the year and HVAS 2 failed to operate on 1 occasion during the year. (Lynwood Quarry 2021 Annual Review); 2022 All dust deposition (DD) gauges were in operation to collect PM g/sqm/month and high volume (HVAS) units were in operation to collect a HV Sample of PM10 for 24 hours very 6 days. HVAS 1 failed to operate on 8 occasions during the year. (Lynwood Quarry 2022 Annual Review); 2023 - All dust deposition (DD) gauges were in operation to collect PM g/sqm/month and high volume (HVAS) units were in operation to collect a HV Sample of PM10 for 24 hours very 6 days. HVAS 1 failed to operate on 8 occasions during the year and HVAS 2 failed to operate on 2 occasions during the year (Lynwood (EPL 12939) - Live Monitoring Worksheet 2023.XLS).	Non-compliant	NC27

Appendix E

Site Inspection Photographs





Photograph E.1

Water fill point



Photograph E.2

Water cart in operation



Photograph E.3

IPC located outside of bunded areas



Photograph E.4

Pump station

E231253 | RP#1 | v1



Photograph E.5 Visual amenity wall



Photograph E.6 Water supply dam



Photograph E.7 Excess product stockpile



Photograph E.8 Amenity bund



Photograph E.9 Water supply dam






Photograph E.10 Granite Pit

Photograph E.11 Granite Pit







Photograph E.13 Sediment Dam G1 - Spillway



Photograph E.14

Sediment Dam G1



Photograph E.15

Water supply dam



Photograph E.16

Depositional Dust Guage



Photograph E.17

Sprayed black berry bush



Photograph E.18

Joarmin Creek



Photograph E.19

Joarmin Creek



Photograph E.20

Sediment Dam F



Photograph E.21

Workshop facilities



Photograph E.22 Excavator







Photograph E.24 Bunded oil container





Refuelling facilities



Photograph E.26

Sump



Photograph E.27

Sump oily water separator




Photograph E.28


Bunded hydrocarbon storage



Photograph E.29 Bunded container storages for hydrocarbons







Photograph E.31 Processing area



Photograph E.32

Workshop facilities



Photograph E.33

ph E.33 Administration area



Photograph E.34

Processing plant and stacker



Photograph E.35

Conveyors



Photograph E.36

Processing plant



Photograph E.37

Enclosed crusher



Photograph E.38

aph E.38 Active water sprays on processing facility



Photograph E.39

Stacker and stockpile



Photograph E.40

Stockpiles



Photograph E.41

Product stockpiles



Photograph E.42

h E.42 Product stockpiles



Photograph E.43

Dust suppressant and associated pump



Photograph E.44

Refuelling facility



Photograph E.45

Sediment Dam E



Photograph E.46 Sediment E



Photograph E.48 Internally bunded area of truck refuelling station



Photograph E.47 Truck weight station



Photograph E.49 Road vehicle refuelling station





Quarry signage on access road



Photograph E.51 Quarry blasting signage on access road

Australia

SYDNEY

Ground floor, 20 Chandos Street St Leonards NSW 2065 T 02 9493 9500

NEWCASTLE

Level 3, 175 Scott Street Newcastle NSW 2300 T 02 4907 4800

BRISBANE

Level 1, 87 Wickham Terrace Spring Hill QLD 4000 T 07 3648 1200

CANBERRA

Level 2, Suite 2.04 15 London Circuit Canberra City ACT 2601

ADELAIDE

Level 4, 74 Pirie Street Adelaide SA 5000 T 08 8232 2253

MELBOURNE

188 Normanby Road Southbank VIC 3006

PERTH

Level 9, Suite 9.02 109 St Georges Terrace Perth WA 6831

Canada

TORONTO

2345 Yonge Street, Suite 300 Toronto ON M4P 2E5

VANCOUVER

60 W 6th Ave Suite 200 Vancouver BC V5Y 1K1



