

Strength. Performance. Passion.

HumeSlab[®] system Technical manual



Humes 18 Little Cribb Street Milton 4064 Australia

Copyright[®] Smorgon Steel Group 1999

First published 2001 Second Edition 2001

All rights reserved. No part of this publication may be reproduced, stored in a retrieval system or transmitted in any form or by any means, electronic, mechanical, photocopying, recording or otherwise, without the prior written permission of Smorgon Steel Group. Every attempt has been made to trace and acknowledge copyright but in some cases this has not been possible. The Publishers apologise for any accidental infringements and would welcome any information to redress the situation.

HumeSlab[™] is a trademark of Humes.

The information and illustrations in this publication are provided as a general guide only. The publication is not intended as a substitute for professional advice which should be sought before applying any of the information to particular projects or circumstances. In the event of purchase of goods to which this publication relates, the publications does not form part of the contractual arrangements with Humes. The purchase of any goods is subject to the Humes terms and conditions of sale.

Humes reserves the right to alter the design or discontinue any of its goods or services without notice. Whilst every effort has been made to ensure the accuracy of the information and illustrations in this publication, a policy of continual research and development necessitates changes and refinements which may not be reflected in this publication. If in doubt please contact the nearest Humes sales office.

Preamble

This Technical Manual has been prepared by Smorgon Steel Group on behalf of Humes to facilitate the design of suspended concrete slabs covering a wide range of applications using the HumeSlab[™] flooring system. It is intended to be used as a technical guide for construction loading and it is a requirement of use that any designs prepared using this Technical Manual be examined and verified by a competent and qualified structural engineer.

The manual contains comprehensive data on the properties of HumeSlab[™] trusses and describes some of the typical details required to achieve an equivalent monolithic slab. The procedures are based on established design methods and material properties for conventional steel reinforced concrete structures. Design criteria relating to bending, shear capacity, anchoring of reinforcement, transverse reinforcement, support conditions and any general design and construction procedures shall be referred to and approved by an industry registered structural design engineer.

1.0	Introduction	. 1
2.0	The HumeSlab™ System	. 2
3.0	Advantages and applications	. 3
4.0 4.1 4.2 4.3 4.4 4.5	Material and product specifications Reinforcement. Panel concrete Polystyrene void formers Topping concrete Truss Specifications.	5 5 5 5 5 5 6 6
5.0 5.1 5.2 5.3 5.4 5.5 5.6 5.7 5.8	Design principles Design for bending Precast in-situ interface Vertical shear Load distribution Durability requirements and fire rating Support conditions Design for construction loads Deflection during construction	. 7 . 8 . 8 . 8 . 9 . 10 . 11 . 13
6.0	Final slab design	14
7.0 7.1 7.2 7.3 7.4	Seismic conditions Structural integrity Diaphragm action Detailing requirements for seismic loads Slab and band beam systems	15 15 16 17 17
8.0 8.1 8.2 8.3 8.4 8.5 8.6 8.7 8.8	Manufacture and installation Manufacture Delivery. Installation. Lifting and placing. Services and edge forms. Top reinforcement and in-situ concrete. Ceiling finish Construction practice	 18 18 18 19 20 20 20 20 20
9.0 9.1 9.2 9.3 9.4	HumeSlab bridge decking.Design detailsLoad distribution - panel to panel connectionBearing of bridge deck panelsConstruction practice for bridge decks	24 25 26 27
10.0	References	28
11.0	Appendices Appendix A - Typical construction details for multi-level building. Appendix B Design Examples Estimate Design & Detailed Design Appendix C Transpan™ HumeSlab™ design software output . Appendix D Quotation checklist	29 29 41 45 55

Further Information

For further technical information regarding HumeSlab[™], contact our sales Engineers or technical representatives at Humes. For contact details, refer to back cover.

1.0 Introduction

The **HumeSlab™ System** (also known as Transfloor[™] and by the name of the original licensors - ABE, Filigran, Kaiser-Omnia floor) has been widely used in Europe and elsewhere for over 40 years. Overseas trends indicate that this precast flooring system is a favoured method of construction for suspended concrete slabs and in some parts of Europe it accounts for 60% of all suspended work reaching production rates of 80 million square metres per year. As a precast flooring system it offers many advantages over cast in-situ floors while maintaining the full structural integrity and monolithic requirements of the slab.

In Australia this type of flooring has been in use since 1982 and in February 1988 Transfloor[™] was purchased by Smorgon Steel Group and traded as Transfloor[™] Australia Pty Ltd until 1991. Since 1992 the manufacture of Transfloor[™] has been licensed to a number of independent precast companies. Humes, as a licensee, markets Transfloor[™] as HumeSlab[™], using the same expertise and technical know how developed by Transfloor[™].



Figure 1: Placing a HumeSlab[™] panel

Humes and Smorgon Steel Group are committed to technical support and product development of HumeSlab™.

2.0 The HumeSlab[™] System

The HumeSlab[™] system uses a combination of precast conventionally reinforced concrete panels and a poured in-situ topping as a means of constructing a typical suspended concrete slab. The use of site placed steel reinforced concrete effectively ties all the precast elements together providing safety, rigidity and structural redundancy.

HumeSlab[™] Features

Size - A HumeSlab[™] panel is a factory made precast concrete slab of variable width up to a maximum of 2.5 metres and variable length, usually limited to about 12 metres for transport and handling purposes.

Thickness - The panel thickness can be varied and will depend on reinforcement size and concrete cover. For many applications a nominal thickness of 55 mm is satisfactory.

Reinforcement - The bottom reinforcement embedded in the panel can consist of a layer of fabric, the bottom chords of the trusses and additional reinforcing bars as required by the designer.

Handling - The HumeSlab[™] trusses provide strength and stiffness for handling and transport, allow panels to support construction loads with a minimum of temporary propping, contribute to the bottom steel and to the top steel and can also serve as continuous bar chairs to support the top reinforcement.

Weight Saving - Polystyrene void formers, added at the precast factory, allow for construction of voided slabs with a significant reduction in self weight (typically 30%).

Flexibility - In contrast with most other prefabricated systems, HumeSlab[™] imposes few restrictions on designers because there are no standard panel sizes. The length, width, thickness, plan geometry and reinforcement steel can be varied to suit design requirements and allow considerable flexibility for both the Architect and the Engineer.

ADJUST NUMBER AND TYPE OF TRUSSES TO SUIT CONSTRUCTION LOADS. 5 TRUSSES IS THE PRACTICAL MINIMUM FOR 2500 WIDE PANEL, FOR SLABS WITHOUT VOIDS ABOUT 18 TRUSSES ARE POSSIBLE USE MAXIMUM 31 RRUSSES IN CODED SLABS. THE PRACTICAL MINIMUM SLASSES IN CODED SLABS. DEPTH OF SITE PLACED CONCRETE ABOVE VOIDS AS REQUIRED BY DESIGN. 120 MINIMUM SLASSES IN CODED SLABS. 120 MINIMUM SLASSES IN CODE SLAPS. 120 MINIMUM RIB AT INTERNAL 120 MINIMUM RI
NOTE HUMESLAB UNITS CAN BE MADE TO ANY SIZE AND ANY SHAPE WITHIN THE LIMITS SHOWN ABOVE. SEMICIRCULAR OR RECTANGULAR CUT OUTS, SKEWED ENDS AND IRREGULAR SHAPES CAN BE MANUFACTURED TO SUIT PARTICULAR JOB REQUIREMENTS. CHARACTERISTICS OF HUMESLAB TM PANELS

Figure 2: Typical characteristics of a HumeSlab™ panel

3.0 Advantages and Applications

The HumeSlab[™] system is versatile and adaptable for use in a wide variety of structures including low-rise residential and commercial developments, high-rise steel and concrete framed structures, bridge decks, culverts and other civil applications. Generally suited to most suspended reninforced slabs.

Cost Effective Features

Faster construction - Up to 150 m² per hour can be placed by crane. Total building time can be reduced significantly (refer Table 1).

Eliminates formwork - Most of the traditional formwork can be eliminated. HumeSlab[™] panels provide both the working platform and part of the completed slab.

Reduced propping - Propping requirements are reduced when compared with traditional formwork which means less cluttering of the floor below and earlier access by following trades.

Clean and safe - Fewer trades are required resulting in a less cluttered, cleaner and safer building site. An immediate work platform is provided.

Lighter structure - Use of polystyrene void formers reduces the self weight of the slab and provides cost savings in foundations, columns and beams. The void formers also reduce the volume of in-situ concrete.

Soffit finish - A class 2 off-form grey finish is easily achieved, suitable for painting with minimum preparation (refer Figure 3). Panel joints do require filling if a flat soffit is desired (refer Figure 30).

Balcony Upstands - Can be provided as an integral part of the HumeSlab[™] panel. Eliminates costly edge formwork and scaffolds. Allows early installation of temporary or permanent balustrades. (Generally the standard size is 300mm high x 150mm wide. For other sizes please consult your Humes representative.)



Figure 3: High quality off form soffit finish

Advantages and Applications

Tradi	tional Formwork			HumeSlab™ System							
Activity	Labour	Day/s	Hours	Activity	Labour	Day/s	Hours				
Erect & prop wall panels	2 Dogman 2 Labourers	1 1	16 16	Erect and prop wall panels	2 Dogman 2 Labourers	1 1	16 16				
Grout wall panels	2 Labourers	1	16	Grout wall panels	2 Labourers	1	16				
Support frames	3 Scaffolders	2	48	Support frames	3 Scaffolders	1	24				
Place ply formwork	4 Carpenters 2 Labourers	3 3	96 48	Place HumeSlab™ panels	2 Dogman 2 Carpenters	1	16 16				
Place reinforcement	4 Steel Fixers	2	64	Place top reinforcement	4 Steel Fixers	1	32				
Pour concrete	8 Labourers	1	64	Pour concrete	8 Labourers	1	64				
Strip formwork and clean up	4 Carpenters 2 Scaffolders	2 2	64 32	Remove propping frames	2 Scaffolders	1	16				
Total Cycle (approximate ho	urs)		Total Cycle (approximate ho		216						
Typical Cycle		0.62	hrs/m²	Typical Cycle	0.29	hrs/m²					

Table 1: Comparison of cycle times and labour requirements for slab over precast walls-Brookland Apartments.



Figure 4: Column penetration in HumeSlab[™] panel



Figure 5: HumeSlab[™] on load bearing block walls

Flexibility in design - HumeSlab[™] is an engineered product made to suit individual project requirements. Penetrations, cantilevers and unusual panel shapes can be easily accommodated (refer Figure 4).

Eliminates bar chairs - If concrete cover and overall slab thickness are suited to the truss type, top reinforcement can be supported directly on the HumeSlab[™] trusses.

Four easy steps to build with HumeSlab™

- 1. At the time of planning, contact Humes to discuss the use of HumeSlab[™] for your application.
- 2. Supplier personnel will then assess and arrange for a preliminary design and prepare concept layout plans and a quotation.
- 3. Upon placement of the order a detailed layout plan is prepared based on the documentation provided. This information is returned to the builder and engineering consultant for checking and approval.
- 4. After approval has been obtained for dimensional accuracy and engineering integrity, the panels are produced and delivered to site at a time specified by the builder.



Figure 6: HumeSlab[™] panels placed on steel frame structures

4.1 Reinforcement

HumeSlab[™] trusses are fabricated from plain round hard drawn 500L grade bar conforming to AS4671. The diagonal bars of the truss are electronically welded to both the top and bottom chords. Weld tests are carried out at regular intervals as part of the Smorgon Steel Group Quality Assurance programme.

All fabric used in the panels is welded wire fabric, grade 500L conforming to AS4671 and all bar reinforcement is grade 500N conforming to AS4671.

4.2 Panel concrete

The panel concrete is Normal Class Concrete as defined in AS3600. A typical concrete specification is given below but the Engineer should also nominate special class concrete if used.

Minimum strength grade	N40
Slump	80 mm
Maximum size of aggregate	14 mm (nominal)
Cement	General purpose



Figure 7: Reinforcement in casting bed ready for concrete pour

4.3 Polystyrene void formers

The expanded polystyrene (EPS) void formers are made of a light weight cellular plastic material comprising 98% air. A class SL material is used having a density of 13.5 kg/m3. All other physical properties of the EPS are in accordance with AS1366, Part 3-1992. Designers should note that the EPS is produced with a fire retardant additive that allows it to self extinguish almost immediately after the fire source is removed. The level of toxicity of EPS in a fire situation is not greater than that of timber or other commonly used building materials.

4.4 Topping concrete

It is essential that the site concrete, whether placed over panels or over void formers, is of a high quality, and that placement and curing is of a satisfactory standard to minimise surface cracking due to plastic shrinkage or other causes.

In-situ concrete thickness over void formers will be governed by cover, quantity, size and laps of top reinforcement. A minimum of 70 mm should be used.

4.5 Truss specifications

Generic Truss Reference	CSR Humes Product Code	Top Chord Diameter	Height (H) (mm)	Mass (kg/m)
T80/10	TRUS8010C	9.5	82	1.77
T110/10	TRUS11010C	9.5	111	1.86
T150/10	TRUS15010	9.5	154	2.06
T190/10	TRUS19010C	9.5	191	2.21
T110/12	TRUS11012C	11.9	112	2.21
T150/12	TRUS15012C	11.9	155	2.41
T190/12	TRUS19012C	11.9	192	2.56

Typical Sections:



Figure 8: Truss properties and section details

The structural design of HumeSlab™, or any precast concrete floor system, should not only deal with the calculation of bending moment and shear force capacity of the separate units, but also with the total coherence of the floor. In the final stage, the individual components should be connected in a manner that ensures adequate overall capacity with interaction between the units and the supporting structure. Two distinct stages must be checked when designing with HumeSlab[™].

- 1. The non-composite panel during construction stresses occurring only in the precast units resulting from lifting, transportation and the weight of the wet concrete.
- 2. The composite floor slab after hardening of the in-situ concrete.

5.1 **Design for bending**



Figure 9: Biaxial trusses - panels engineered to suit project requirements

Note: Minimum slab thickness of 160mm.

Accepted principles of Ultimate Strength Theory applies to the design of HumeSlab[™] since the finished slab can be considered as monolithic. A prerequisite for this is that the uptake of shear forces at the interface between precast and in-situ concrete is proven. The shear capacity, at this interface, has been shown to be adequate by overseas research (Reference 1) and some early testing done at the University of Queensland (Reference 2).

The system is best suited to one way action, however, two way action can be achieved by eliminating void formers to allow placement of transverse bars. The transverse bars should be placed near the upper surface of the panel ensuring that in-situ concrete flows under the bars and anchorage is achieved. Note that a reduced effective depth for the transverse reinforcement will have to be used.

In a uniaxial design the precast panel will normally contain all of the bottom reinforcement required in the final design which can consist of a light fabric, truss bottom chords and additional bar reinforcement. It should be noted that the presence of voids will not usually result in design of the section as a tee beam since large amounts of steel are required to shift the neutral axis below the top of the void. Refer to Figure 10 for a general cross section of a finished slab.



Figure 10: General cross section of finished slab



Figure 11: Penetrations for services can be cast into panel **5.3**

Precast in-situ interface

The required capacity at the interface can be calculated in accordance with AS3600 Clause 8.4. The level of surface roughness is somewhat open to interpretation but can be considered as rough with small ridges and undulations. The surface roughness achieved during the casting process is satisfactory when, at the same time, truss web members are used as shear plane reinforcement.

If an intentionally roughened surface is specified, care should be taken not to disturb the grain structure of the concrete or dislodge aggregates near the surface. A vibrated level or light broom finish is all that is required.

Vertical shear

If a voided slab is used the shear forces can only be carried by the concrete in the rib sections. Voids must be terminated in regions of high shear (at supports and point loads) and will generally not be included within one slab depth from the section at which the ribs are just sufficient to resist the applied shear.

The overall slab thickness is not normally controlled by shear strength requirements but, when required, the diagonal wires of the trusses may be treated as inclined stirrups (Reference 1) provided the pitch of the wires does not exceed the depth of the slab, trusses extend through the full slab depth and truss spacing does not exceed the recommended stirrup spacing given in AS3600.

When the precast element is used to form a wide shallow beam (band beam/slab system on columns) and shear reinforcement is required, the ligatures should extend over the entire section depth and tie into the precast element. However, if the actual shear is less than the shear capacity and the beam depth is less than half the beam width, nominal shear ligatures can be incorporated as shown in Figure A8 in Appendix A.

5.4 Load distribution

When a slab is subjected to concentrated loads, the distribution of the load across longitudinal joints should be considered. The transverse load distribution in composite precast element floors is similar to cast in situ floors. Load distribution between precast elements is provided by the shear resistance of the in-situ concrete section at the joint (Figure 10). Where trusses are not located adjacent to the joint, additional transverse bars may be placed in the site concrete over the panel joints. The inclusion of transverse ribs (Figure 2) would also contribute to the load distribution capabilities.



Figure 12: Slab and band beam system

Panel Thickness	Panel Width
55mm	2502mm
60mm	2504mm
65mm	2506mm
70mm	2508mm

Table 2 Actual panel thickness and width

Table 3:	Standard trus	s thickness	and typical	l fire rating	for voided	slabs

Slab thickness	Fire rating
160mm	2 Hours
190mm	3 Hours
230mm	3 Hours
270mm	3 Hours
	Slab thickness 160mm 190mm 230mm 270mm

Note:

- 1. Table 3 is based on 20 mm cover to top and bottom reinforcement and minimum 65 mm topping concrete over polystyrene void formers.
- 2. The overall slab thickness is the minimum that can be used with the nominated truss type.
- 3. The actual panel width will depend on the panel thickness used due to the tapered edge forms.
- 4. Top reinforcement can be supported directly on trusses when the above slab/truss combinations are used and reinforcement is arranged as shown in Figure 10.

5.5 Durability requirements and fire rating

Since HumeSlab[™] panels are cast on rigid steel forms and are subjected to intense compaction the reinforcement cover requirements at the bottom of the slab can be reduced compared to in-situ slabs (AS3600 Table 4.10.3.4). If severe exposure conditions are specified the panel thickness is increased to allow for the increased cover requirements.

Fire resistance requirements for slabs constructed with HumeSlab[™] panels can be determined by referring to clause 5.5.1 (b) and 5.5.3 (a) of AS3600. If a voided slab is used the effective thickness of the slab is calculated as the net cross sectional area divided by the width of the cross section. Typical fire resistance periods are shown in Table 3. Higher fire ratings can be achieved with increased cover to reinforcement and decreased thickness of polystyrene voids.



Figure 13: panels connecting to precast walls

Support conditions

The correct detailing of precast concrete involves the consideration of the design, manufacture and construction requirements at the start of the project. It is important to consider detailing during the early design stages so as to obtain the full benefits of any precast system.

As with in-situ floors, when designing with HumeSlab[™], attention must be given to anchoring of steel reinforcement at the supports. Steel reinforcement end details are specified in AS3600 clause 9.1.3 and the amount of steel reinforcement to be carried into the support will depend on the end restraint condition.

Connections between HumeSlab[™] panels and supporting members present few problems since continuity can be provided by lapping the panel steel reinforcement with steel bars projecting from the supporting beams or walls. In general, it is sufficient to anchor 50% of the total positive moment steel reinforcement required at mid span. The bottom chords of the HumeSlab[™] trusses which end at the front edge of the support do not constitute part of this requirement. Therefore the details suggested in Figure 14 can be safely used provided the field steel reinforcement is satisfactorily anchored above the support.



Figure 14: Reinforcement end details conforming to AS3600

5.7

Figure 15: Unpropped HumeSlab™ panels on precast beams

Design for construction loads

Selecting a panel specification to support construction loads should provide a panel with sufficient strength and stiffness to carry the mass of wet concrete and construction live loads without exceeding safe limits for stress and/or deflection. The loading to be considered at this stage of the design is based on the Formwork Code AS3610 and will include:

- Precast panel self weight
- Dead load of wet in situ concrete
- Live loads due to stacked materials
- Live load due to workmen and equipment
- Localised mounding of in-situ concrete during placing.

Prop spacing during construction will be controlled by one of the following criteria.

• Bending moment capacity determined by limiting the tensile stress in the panel concrete to less than the characteristic tensile strength.

Truss	Overall		Truss spacing (mm)										
Туре	Slab Thk	565	450	320	200	565	450	320					
T80/10	160 180	2.1 2.0	2.2 2.1	2.3 2.2	2.5 2.4	2.3 2.2	2.3 2.3	2.3 2.4					
T110/10	190 200 220	2.2 2.2 2.1	2.3 2.2 2.2	2.5 2.4 2.3	2.7 2.7 2.6	2.5 2.4 2.4	2.5 2.5 2.5	2.7 2.6 2.6					
T150/10	230 250	2.4 2.3	2.6 2.5	2.8 2.7	3.1 3.0	2.8 2.8	3.0 2.9	3.1 3.1	ports (m)				
T190/10	270 300 320 350 400	2.6 2.5 2.4 2.3 2.2	2.8 2.6 2.6 2.5 2.3	3.0 2.9 2.8 2.7 2.5	3.4 3.3 3.2 3.1 2.9	3.2 3.1 3.1 3.0 2.9	3.3 3.2 3.2 3.1 3.0	3.5 3.4 3.3 3.3 3.1	veen temporary sup				
T110/12	190 200 220	2.4 2.4 2.3	2.5 2.5 2.4	2.7 2.7 2.6	3.1 3.0 2.9	2.7 2.7 2.7	2.8 2.8 2.8	3.0 3.0 2.9	um span betv				
T150/12	230 250	2.8 2.7	2.9 2.8	3.2 3.1	3.6 3.4	3.2 3.2	3.4 3.3	3.6 3.5	Maxim				
T190/12	270 300 320 350 400	3.0 2.9 2.8 2.7 2.4	3.2 3.0 2.9 2.8 2.7	3.5 3.3 3.2 3.1 2.9	3.9 3.7 3.6 3.5 3.3	3.7 3.6 3.5 3.5 3.4	3.8 3.7 3.7 3.6 3.5	4.0 3.9 3.8 3.7 3.6					
			Solid	l Slab	1		Voided Slab						

Table 4: Propping requirements - single span during construction

- Bending moment capacity may also be governed by the compressive stress in the top chord of the truss. This should be limited so that buckling of the top chord does not occur.
- Shear capacity will be determined by the buckling strength of the truss diagonal wires.

Load capacities and thus distance between temporary supports will depend on panel thickness, truss spacing and whether the slab is voided or solid. The unpropped spans given in Tables 4 and 5 have been calculated by analysing the HumeSlab[™] panel as an uncracked section using a transformed area method to determine stresses in concrete and steel during construction.

Since this is a serviceability limit state design, unfactored loads have been used. The tensile stress in the panel concrete is limited to $0.6 \sqrt{f'c}$ (AS3600, Clause. 6.1.1.2) and the compressive force in the truss wires is limited to AS4100 Clause. 6.1

Truss	Overall			Tru	iss spacing (m	ım)						
Туре	Slab Thk	565	450	320	200	565	450	320				
T80/10	160 180	2.4 2.3	2.5 2.4	2.6 2.5	2.8 2.7	2.6 2.5	2.7 2.6	2.8 2.7				
T110/10	190 200 220	2.5 2.5 2.4	2.6 2.6 2.5	2.8 2.7 2.6	3.1 3.0 2.9	2.8 2.8 2.8	2.9 2.9 2.8	3.1 3.0 3.0				
T150/10	230 250	2.8 2.7	2.9 2.8	3.2 3.0	3.6 3.4	3.3 3.2	3.4 3.3	3.6 3.5	ports (m)			
T190/10	270 300 320 350 400	2.7 2.5 2.4 2.6 1.9	3.1 3.0 2.8 2.8 2.3	3.4 3.3 3.2 3.0 2.9	3.9 3.7 3.6 3.4 3.2	3.6 3.6 3.5 3.4 3.3	3.8 3.7 3.6 3.6 3.4	4.0 3.9 3.8 3.8 3.6	ween temporary sup			
T110/12	190 200 220	2.8 2.7 2.6	2.9 2.8 2.7	3.1 3.1 2.9	3.5 3.4 3.3	3.1 3.1 3.1	3.2 3.2 3.1	3.4 3.4 3.3	um span betv			
T150/12	230 250	3.1 3.0	3.3 3.2	3.6 3.5	4.0 3.9	3.7 3.6	3.9 3.8	4.1 4.0	Maxim			
T190/12	270 300 320 350 400	2.7 2.5 2.4 2.2 1.9	3.3 3.0 2.8 2.6 2.3	3.9 3.8 3.6 3.5 3.1	4.4 4.2 4.1 3.9 3.7	4.1 3.9 3.8 3.7 3.4	4.4 4.2 4.2 4.1 3.9	4.6 4.5 4.4 4.3 4.1				
			Solic	l Slab			Voided Slab					
	SPAN SPAN											
		For a	SPAN more detailed des	sign, go to the VI	P section at www.	SPAN smorgonarc.com	au					



Tables 4 and 5 can be used to determine propping requirements, provided construction loads are specified as in AS3600, the HumeSlab[™] panel has a minimum thickness of 55 mm and is reinforced with at least SL62 fabric, and the load from stacked materials does not exceed 4 KPa prior to placement of top concrete.

Where special construction loads are specified and the above conditions do not apply, the determination of prop spacing is possible using the TranSpan[™] software. This software is available from Humes or can be accessed by visiting Smorgon Steel Group's web site on http://www.smorgonsteel.com.au/reinforcing

5.8 Deflection during construction

At typical propping spans of up to 2.7 m tests have shown that deflections under construction loads should not exceed 2 mm.

In cases where unpropped spans exceeding 3.0 m are proposed the deflection should be checked to ensure it does not exceed the limits set in AS3600. Conventional transformed section methods can be used to predict the elastic behaviour of a HumeSlab[™] panel but note that the load used to calculate deflections during construction should be the dead load only (wet concrete and panel).



Figure 16: Typical propping layout

6.0 Final Slab Design

Tables 6 and 7 can be used to to estimate values for the final slab design. However, it should be noted that this information is indicative and should only be used for estimating purposes and does not replace the need for a qualified design Engineer. The calculations are based on the following criteria.

- 1. Design is to AS3600 Clause 7.2 and Section 9.
- 2. Cover to reinforcement = 20 mm (exposure classification B1).
- 3. Concrete class: 32 MPa for in situ topping and 50 MPa for precast.
- 4. Bottom steel reinforcement content to include SL62 fabric (min).
- 5. Superimposed loads include a dead load of 0.5 KPa, the remainder is live load.
- 6. In-Situ concrete allows for polystyrene void formers and is given in m³/m²



Figure 17: Slab section relating to Tables 6 and 7

Slab	Depth	SW	Reinf.	(Kg/m ^²)	In situ	itu Superimposed load (KPa) for span (m)										
D	d	KPa	Тор	Bot.	Conc	8.5	8.0	7.5	7.0	6.5	6.0	5.5	5.0	4.5	4.0	3.5
160	55	3.3	3.1	4.3	0.080									2.2	4.1	5.9
190	55	3.6	3.1	5.4	0.090							2.0	3.5	5.2	7.3	10.5
230	55	3.9	3.1	6.5	0.104					2.5	3.7	5.0	6.7	9.1	12.3	
270	55	4.3	3.1	7.5	0.120			2.5	3.7	4.8	6.2	8.1	10.5	13.8		
300	55	4.6	3.1	7.9	0.130	2.0	2.8	3.7	4.7	6.1	7.8	10.0	12.8			

Table 6: Single simply supported span (voided slab)

Slab	Depth	SW	Reinf.	(Kg/m²)	In situ Superimposed load (KPa) for span (m)												
D	d	KPa	Тор	Bot.	Conc	9.	5	9.0	8.5	8.0	7.5	7.0	6.5	6.0	5.5	5.0	4.5
160	55	3.3	4.4	4.3	0.080										0.5	2.5	4.5
190	55	3.6	4.9	5.0	0.090								1.5	2.5	4.1	5.5	7.5
230	55	3.9	5.6	6.1	0.104						2.0	3.4	4.5	5.8	7.5	9.7	
270	55	4.3	6.1	6.8	0.120				2.5	3.3	4.3	5.4	6.8	8.6	10.9		
300	55	4.6	6.7	7.6	0.130	2.	5	3.2	4.0	5.0	6.2	7.6	9.4	11.7			

 Table 7: Multiple continuous span (voided slab)

Although Australia is classified as a "low risk" area, in terms of earthquake damage, the need for seismic design in building structure was highlighted by the Newcastle earthquake of 1989. Building structures are to be designed for earthquake loading depending on the "earthquake design category" as specified in AS1170.4.

Seismic considerations for HumeSlab[™] will follow the same design rules as for in-situ floors but will require adequate detailing to achieve seismic integrity at the connections. The main criteria to consider is:

- maintain structural integrity without collapse of all or a significant part of the structure;
- achieve ductility of both precast elements and their connections;
- provide structural continuity;
- design and detail structural elements such that they may be produced economically and erected easily.

7.1 Structural integrity

It has generally been found that in-situ floor slabs, acting monolithically with supporting beams, are very capable of transmitting lateral forces unless the number of large openings is excessive.

HumeSlab[™], acting monolithically, will adequately transmit lateral loads through diaphragm action. The strength and ductility of the overall structural system will depend on the integrity of the joint detailing and in particular, the connections between the floor (horizontal diaphragm) and the supporting structure.

The majority of reported damage (Reference 3.0) caused to precast construction during earthquakes is confined to the joints and connections and can be summarised as follows:



Figure 19: Actions in a typical diaphragm



Figure 18: HumeSlab connecting to precast walls

- Failure of connection between wall panel and roof system resulting in roof failure, tilting of wall panels and increased stresses in the lower level floor connections.
- Failure of connection between wall panel and floor system.
- Flexibility of thin cast in-situ topping slab that forms the horizontal diaphragm causing overstressing and cracking resulting in separation from the precast elements.

The 1988 earthquake in Armenia highlighted some of the problems caused by inadequately detailed precast construction (Reference 3). A common form of construction for medium rise residential buildings was to use precast concrete panels or frames for the vertical elements and precast concrete floor planks without the addition of a topping slab. These precast systems performed poorly due mainly to the inadequate provision of viable load paths through inadequate tying of the horizontal floor planks to the vertical elements and to each other for effective diaphragm action.

7.2 Diaphragm action

Horizontal loads from earthquakes are usually transmitted to the vertical cores or shear walls by the roof and floor acting as horizontal diaphragms. The floor can be analysed by the 'strut and tie' method or by considering the floor to act as a deep horizontal beam. The central core, shear walls or other stabilising components act as supports with the lateral loads being transmitted to them as shown in Figure 19.

As stated by Clough (Reference 4), "In zones of high seismic intensity, or with configurations which impose large in-plane compatibility forces under lateral load, diaphragms joined by cast in place reinforced concrete usually are satisfactory". It is essential to ensure that the topping is adequately bonded to the precast elements such as in precast element floors where the topping is bonded by mechanical connectors (wire truss as in-plane reinforcement). Without this, separation can occur and the topping may buckle when subject to diagonal compression from diaphragm action.



Figure 20: Detailing requirements for earthquake loading

7.3 Detailing requirements for seismic loads

Designers should ensure that not only is there an adequate load path for forces that need to be transferred between the diaphragm and any lateral force resisting elements, such as walls or frames, but that connections are detailed such that they adequately transfer the anticipated loads.

The comments in this section relate to 'Intermediate Moment Resisting Frames', defined in AS3600 (Reference 8) as 'moment resisting frames of ductile construction', complying with the additional requirements of 'Appendix A' in AS3600. The intent of these special detailing requirements is to improve the ductility and reduce the vulnerability of concrete structures in a manner consistent with the relatively low seismic hazard in Australia. The detailing requirements shown in Figure 20 are therefore not onerous and relate to steel reinforcement continuity, anchorage and lapping.

7.4 Slab and band beam systems

In high seismic regions building codes (ACI and New Zealand Standard) tend to discourage wide shallow beams by imposing limitations on the maximum beam width. Also, 75% of the longitudinal beam bars are required to be within the column width. Since the main difficulties with wide beams is placing all the required joint ties, Irvine and Hutchinson (Reference 5) recommend that the steel reinforcement ratio (Ast/bd) be restricted to 0.02 or less, so as to reduce this problem. The designer should ensure that the column has sufficient ductility to prevent a column side sway failure (soft storey collapse).

The above requirements apply to high seismic regions. The University of Melbourne has conducted research to investigate the behaviour of wide band beams in low seismic regions. At this stage the current requirements of AS3600 (Reference 8) can be used, see Figure 21.



Figure 21: Detailing requirements for earthquake loading

8.1



Figure 22: Concrete is discharged at a controlled rate by an electrically operated concrete spreader

Delivery

8.2



Figure 23: Lifting of HumeSlab panels from casting table

Panels are stacked and transported by semi-trailers in approximately 150 m² loads. Stacking bearers should be provided at approximately 1.5 m centres to minimise stresses during transport.

The laying sequence should be pre-determined and communicated to the HumeSlab[™] supplier prior to manufacture. This will enable stacks to be stored and then loaded in reverse order of placement so that the top panel on the stack is the first to be placed on site. The only exception being in the case of a load of mixed panel sizes when small panels are loaded on the top of the stack irrespective of the placing sequence. The erector should be prepared to site stack units delivered out of sequence due to loading requirements. However, such panels may be placed directly in position if their locations can be accurately fixed prior to commencement of panel placing.



Figure 24: Panels in storage ready for delivery to site

Installation

8.3

Where the HumeSlab[™] panels are not designed to sustain construction loads over the clear span without intermediate supports, a simple system of frames and props with timber headers is normally erected prior to arrival of panels on site (see Figure 16).

Prop spacing should be specified by the design engineer and will vary according to the type and number of trusses in the HumeSlab[™] panels and the construction loads to be supported. Tables 4 and 5 can be used to determine the required prop spacing or alternatively contact Humes for more information.

environment where a system of controls and checks ensures optimum product quality.

Manufacture

Panels are cast on steel forms using high strength concrete, externally vibrated, to ensure thorough compaction and uniform density.

The manufacture of HumeSlab[™] panels takes place in a factory

After an initial curing period of approximately 12 hours the panels are stripped, stacked and stored ready for delivery.



Figure 25: Site lifting - typical 4-point lift

Lifting and placing

Panels 55 mm thick have a typical weight of 145 to 160 kg/m². In cases where the spreader is used for lifting, the weight of the spreader (about 500 kg) must be added to the panel weight to determine the maximum load for lifting.

It is important to ensure that the crane selected has adequate capacity at the reach required to place all panels. If crane capacity is limited, it may be necessary to limit the size of panels to ensure that the load/reach capacity of the crane is not exceeded.

During production each panel is marked with an identification number corresponding to the panel numbers on the layout drawing. This ensures that panels are placed in the correct position in the structure.

Panels up to 8.5 metres in length can be lifted by crane using four chains*. The chain hooks must be attached to the top chord of the trusses as shown in Figure 26. The lifting capacity has been verified by testing for this method. Panels between 8.5 and 10 m long may require a lifting frame. Lifting point locations should be marked on shop drawings.

Placing rates of up to 10 panels per hour can be achieved with a crew of two men on the deck, crane driver and dogman. Where panels of 6 m length or greater are supplied, the placing rate can be approximately 150 m² per hour.



Figure 26: Lifting of HumeSlab[™] Panels

All bearing surfaces for HumeSlab[™] panels should be level to ensure alignment between units and to minimise twisting of panels. Where panels are to sit on block work or precast walls, the bearing surfaces may require levelling with concrete mortar. An alternative is to provide temporary, carefully aligned props immediately adjacent to the walls.

* This applies to standard panels only. For non-symmetrical panels, panels with block-outs, voids or other non-standard inclusions, contact Humes.



8.5

Figure 27: Temporary props are positioned prior to placing panels

Services and edge forms

Electrical junction boxes, fire collars for plumbing, ferrules etc, can be cast into the panels as detailed on architectural drawings These items need to be supplied by the contractor. A hot wire cutter is used to quickly cut polystyrene void formers to accommodate conduits. Generally penetrations are formed by using polystyrene edge forms in the factory. Smaller penetrations can be accommodated by casting in polystyrene blockouts or alternatively they can be core drilled onsite.

Fixing of edge forms can usually proceed while services are being installed. A turnbuckle engaging truss wires can be used as a connection device for edge forms. Appendix A, Figure A6, includes edge form details.



Figure 28: In-situ concrete is reduced by use of polystyrene void formers

8.6 Top reinforcement and in-situ concrete

Immediately following installation of services and edge forms, fixing of top reinforcement steel is carried out and the slab is then ready for pouring the top layer of concrete.

The thickness of topping concrete above polystyrene generally should not be less that 65 mm. Additional top steel reinforcement, fabric (mesh) laps, fabric (mesh) wire diameter and other factors may require this topping thickness to be increased to ensure that steel reinforcement is fully embedded and adequate cover is provided. This aspect should be considered at the design stage (refer to section 5.0, 'design principles').

8.7 Ceiling finish

HumeSlab[™] panels are manufactured in rigid steel beds and the soffit finish achieved is 'Class 2' as described in AS3600. The joint between panels, if left unfilled, is referred to as a shadow joint, in that a light and shade effect is created between the two prefabricated units. This type of ceiling finish requires no treatment and is quite acceptable as an off-form grey concrete finish. In fact, the surface finish achieved is quite superior to that achieved with conventional forming products.

Manufacture and Installation



In situations where the slab soffit is to be used as an exposed ceiling and a painted surface is required, then the joint can be filled and a textured paint finish applied directly to the panel. If the joints are subject to differential movement then the use of a cement based repair mortar with high bond strength should be used to fill the joint. If no differential movement were expected then the use of a plaster-based material would be acceptable. A flat paint finish is possible after a skim coat of plaster.

Figure 29: Unpainted soffit finish showing shadow joint



Figure 30: HumeSlab™ panel soffit joint

8.8 Construction Pratice

Delivery

Panels are delivered in stacks on semi-trailers, approximately 150m2 per load. Stacks are normally loaded onto the truck in reverse order of placement so that the top panel on the stack is the first to be placed on site. The only exception being in the case of a load of mixed panel sizes when small panels are loaded on the top of the stack irrespective of placing sequence. This should be the only circumstance which requires a panel to be grounded on site before placing. However, such panels may be placed directly in position if their location can be accurately fixed prior to commencement of panel placement.

Installation

Except in cases where the HumeSlab[™] panels are designed to sustain construction load over the clear span without propping, a simple system of frames and props with 150 x 100 timber headers is normally erected prior to arrival of panels on site. Prop spacing should be specified or shown on the engineer's drawing and will vary according to the type and number of trusses in the HumeSlab[™] panels and the construction loads to be supported. Prop spacing generally varying from 1.8 to 2.4 metres is typical for slabs.

Crane Capacity

HumeSlab[™] 55mm thick has an average weight of 145kg/m2. In cases where the spreader is used for lifting, the weight of the spreader (500kg) must be added to the panel weight to determine the maximum load for lifting. It is important to ensure that the crane selected has adequate capacity at the reach required to place all panels.

Alternatively, where crane capacity is limited it may be necessary to limit the size and weight of panels to ensure that the load/reach capacity of the crane is not exceeded.

Lifting and Placing

During production, each panel is marked with an Identification number corresponding to the panel layout drawing so that the placement of each panel in its correct position in the structure is simplified.

Most panels up to about 8 metres in length containing truss types T110 or T150 can be lifted by crane using four chains, the hooks being attached to the top bars of the HumeSlab[™] trusses. See Fig 26, page 19 for correct hook placement.

In windy conditions it may be preferable to lift long panels using a 16 hook spreader.

For lifting and placing panels a crew of two men on the deck should achieve a placing rate of approximately 10 panels per hour.

Services

After a reasonable area of floor has been covered with panels a stable deck is available for following trades to commence work. Conduits for electrical and communications services and water reticulation pipes are installed as for in-situ concrete slabs. A hot wire cutter is used to quickly chase into polystyrene void formers to accommodate conduits.

Most penetrations can be accommodated during the panel design. However, small penetrations such as those required for waste pipes and electrical outlets can be made by core drilling through the 55mm HumeSlab[™].

Cracking of Panel

The HumeSlab[™] panel may exhibit cracking for a number of reasons, eg.

- Incorrect loading of stacking on site.
- Poor handling techniques.
- Inadequate propping.

Minor cracking will not affect the structural Integrity of the final slab, however, if more severe cracking (I.e. crack widths greater than 0.2mm) has occurred it should be inspected by a suitably qualified engineer.

Top Steel and In-Situ Concrete

Immediately following Installation of services, fixing of top steel is carried out and the slab is then ready for pouring of site placed concrete.

The thickness of topping concrete above polystyrene will be shown on drawings, but generally should not be less than 70mm, additional top reinforcement fabric wire diameter and other factors may require this topping thickness to be increased in some cases, to ensure that reinforcement is fully embedded and adequate cover provided.

Edge Forms

Fixing of edge forms can usually proceed while services are being installed. A turn buckle engaging truss wires may be used as a connection device for edge forms.

9.0 HumeSlab[™] Bridge Decking

HumeSlab[™] is used in composite bridge construction and has been approved by most state road authorities, providing safer and more efficient construction of bridge superstructures. Figure 31 shows a typical bridge deck section constructed with HumeSlab[™] panels (70 to 90 mm thick) which, when topped with in-situ concrete, become an integral part of the deck slab. Panels are made with trusses and steel reinforcement uninterrupted but with full-length gaps or continuous concrete block-outs, which coincide with beam locations to accommodate the shear connectors. This allows placement of panels directly over precast concrete or steel beams.

The HumeSlab[™] panel can cover the entire width of a bridge, including the cantilever beyond the external beams, thus eliminating the need for formwork and additional scaffolding. This application for HumeSlab[™] has been widely accepted and shown to be very cost effective in terms of speed of erection, safety in construction (instant safe working platform), efficient use of materials (no lost formwork) and significantly reduced traffic interference.



Figure 31: Ready made bridges - HumeSlab™ bridge deck panel being lifted into position

9.1 Design details

The design can be carried out assuming full composite action between the precast panel, in situ topping and the supporting beams. The in-situ concrete topping fills the gaps over the beams and ensures an effective connection with ligatures on precast beams or shear studs on steel beams. During construction HumeSlab[™] trusses provide the cantilever strength and negative moment strength over the beams.

The slab reinforcing steel can be designed in accordance with the Austroads Bridge Design Code and, in view of the discontinuity at panel joints, the slab could be considered as spanning one way transversely over the beams. However, research carried out by Buth et al (Reference 6), for similar precast systems, has demonstrated that using this approach is conservative and that the joints can be disregarded.

HumeSlab™ Bridge Decking



9.2

Figure 27: Temporary props are positioned prior to placing panels

Load distribution - panel to panel connection

A commonly debated topic of past and current research has been the ability of similar deck systems to distribute wheel loads in the longitudinal direction and the corresponding effect of the joints between adjacent panels.

Continuity at the joint is provided by the in-situ portion of the deck and research results indicate that the presence of the joint is not detrimental to the load distribution performance of the bridge deck system (Reference 6,9 and 10).

Test results on two systems of longitudinal reinforcement:

- 1. longitudinal reinforcement placed directly on top of panels, and
- 2. splice bars, on top of panels and across joints,

in addition to the normal longitudinal steel reinforcement indicated the in-situ concrete topping successfully transferred wheel loads across joints. The supplementary joint reinforcing steel did not improve the performance and in all tests with wheel loads near the panel joint, the mode of failure was punching shear (Reference 6). Even at failure loads there were no tensile cracking observed at the bottom of the in-situ topping directly over the panel joints.



Figure 33: Typical bridge deck details

HumeSlab[™] Bridge Decking



Figure 34: Thomson River Bridge - Victoria

Further research and testing (Reference 10) has indicated a tendency for shrinkage and thermal cracks to form directly over the panel joints but these cracks do not adversely affect the ability of the deck slab to transfer wheel loads across joints. Since these cracks extend down approximately half way through the topping slab, it was concluded that the distribution reinforcement performs better when placed toward the top to control shrinkage and thermal cracking than when placed at the bottom of the topping slab in an attempt to control flexural cracking.

American studies on in-service bridges (Reference 10) have indicated that a level of transverse reinforcement (reinforcement in the same direction as beams) equivalent to 230 mm²/m is satisfactory. AASHTO has adopted 230 mm²/m as the minimum transverse steel reinforcement in deck panels of similar decking systems. The level of this steel reinforcing content should be left to the discretion of the design Engineer. However, it should be noted that projects in Australia have been completed with the steel reinforcement content between 230 and 985 mm²/m.

9.3 Bearing of bridge deck panels

Composite bridge deck panels must be supported on the bridge girders by a permanent bearing material providing continuous and solid support. The permanent bearing material should consist of mortar, grout, concrete or steel. Use of soft fibrous material may lead to the bridge deck acting as simple spans over girders rather than continuous spans and delamination at the ends of the precast panels may occur.



Figure 35: Temporary bearing detail for bridge deck panels

HumeSlab[™] Bridge Decking



Figure 36: Cantilever portion of bridge **9.4** deck is unpropped during construction

If grout or concrete is used as the permanent bearing, a temporary bearing system must be used to support the panels during construction. Temporary bearing systems designed to remain in place include continuous strips of compressible material such as high density polystyrene and bituminous fibreboard. Rigid material such as hard plastic shims, which are left in place, will continue to provide the primary support for deck panels should the permanent grout or concrete shrink. This may result in undesirable cracking over these rigid bearing points.

Construction practice for bridge decks

- 1. Temporary bearing materials, which are designed to remain in place, must be compressible.
- 2. The height of the temporary bearing strip must be adequate to allow grout or concrete to flow under the panel.
- 3. Deck panels should extend a minimum of 40 mm beyond the temporary bearing material.
- 4. Venting is required when grout or concrete is used. This can be accomplished by leaving small gaps in the bearing strips at approximately 1200 mm intervals.
- 5. The top concrete should first be placed in continuous strips over girders and allowed to flow under panels before being placed on the remaining deck. This procedure improves the flow of concrete under panel ends, helps eliminate air pockets and places concrete under panel ends before the temporary bearing strips are compressed due to the weight of wet concrete.



Figure 37: Placing bridge deck panels

10.0 References

- 1. Hartmut Koblenz, "Precast Concrete Floors, Part 2" Betonwerk Fertigteil - Tecknik, (BFT), Bauverlag GmbH, Concrete Precasting Plant and Technology, issue 6/1994.
- 2. J. Glynn, "Test of HumeSlab™ Precast Floor Units", Glynn Tucker and Associates, University of Queensland, Report No. 7650, 1981.
- Sanders P.T. (et al), "Seismic Behaviour of load Bearing Precast Construction in Australia", Steel Reinforcement Institute of Australia, 1995.
- Clough D.P., "Considerations in the Design of Precast Concrete for Earthquake loads", Journal of Prestressed Concrete Institute, Vol. 27, No. 2. pp 78-107.
- 5. Irvine H.M. and Hutchinson G.L., "Australian Earthquake Engineering Manual" 3rd Edition, Techbooks, 1993.
- 6. Buth, Eugene, Furr H.L., and Jones H.L., "Evaluation of a Prestressed Panel, Cast in Place Concrete Bridge", Research Report 145-3, Texas Transportation Institute.
- Furr H.L. and Ingram L.L., "Cyclic Load Tests of Composite Prestressed-Reinforced Concrete Panels", Research Report 145-4F, Texas Transportation Institute.
- 8. Standards Australia, "AS3600 2001 Concrete Structures".
- 9. Kluge, Ralph W. and Sawyer H.A., "Interacting Pretensioned Concrete Form Panels for Bridge Decks", PCI Journal, Vol. 20, No. 3.
- 10. Jones H.L. and Furr H.L., "Study of In Service Bridges Constructed with Prestressed Panel Sub-decks", Research Report 145-1, Texas Transportation Institute.



Figure A1: Typical, but not restricted to, reinforcement arrangements in slabs



Figure A2: Typical, but not restricted to, reinforcement arrangements in slabs



Figure A3: Typical, but not restricted to, reinforcement arrangements in slabs



Figure A4: Typical, but not restricted to, reinforcement arrangements in slabs



Figure A5: Typical panel layout diagram



Figure A6: Band beam edge form options



HumeSlab[™] Precast Flooring System



Figure A8: Band beam with ligatures





Figure A10: Typical beam details



HumeSlab[™] Precast Flooring System



Figure A12: Change in slab soffit level



Figure A13: Cantilever and balcony details



Figure A14: Typical wall connection details



B
Ľ.
D
Ð
dd
A

B1 - EXAMPLE CALCULATION - ESTIMATE	E DESIGN	Estimate	e Design & Detailed Design	
Effective span (continuous slab) Superimposed dead load Live Load Deflection limit Cover to reinforcement	6000 0.5 L/250 20	mm kPa mm		
From Table 7: Overall slab thickness Panel thickness Polystyrene void former thickness Slab self weight Average bottom reinforcement Average top reinforcement Average in-situ concrete	190 55 3.6 5.0 0.090	mm mm kPa kg/m² m3/m²	(from Appendix A)	
B2 - EXAMPLE CALCULATION - DETAILED	D DESIGN			
Effective span (continuous slab) Overall slab thickness Cover to reinforcement In-situ concrete strength	6000 190 32	mm MPa MPa		
Panel length Panel Width Panel Thickness	6000 2500 55	um mm		
Polystyrene voids length Polystyrene voids width Polystyrene voids thickness Number of Polystyrene voids Polystyrene volume	5525 440 65 0.0421	mm mm m³/m²		
Slab self weight Superimposed dead load Live load Ultimate load	3.62 0.5 8.15	кРа кРа кРа	1.25DL + 1.5LL	

Appendix **B**

DEFLECTION CRITERIA Short term factor Xs Long term factor X1 Deflection limit Span/depth Lef/d	0.7 0.4 0.004 39.2		span/250	
SLAB DESIGN MINIMUM THICKNESS L _n /D _s 70(1/wK) ^{1/3}	31.58 32.06		L _n /D _S < 70(1/wK) ^{1/3}	
BOTTOM REINFORCEMENT BENDING Ultrimate design bending moment	26 68 2		wi2/11	
Effective depth d F _{sy}	500 32 32	mm MPa MPa		AS3600-2001 CI 8.1.2.2 (b)
gamma A _{st}	0.822 449 1000	mm²/m mm		
Mu phi Mu Ası∕bd	33.37 26.96 0.00284	kNm kNm kNm	phi $M_u \ge M^*$	
0.22(D/d)² f' _{ci} /f _{sy} k _u d _n	0.00216 0.0636 8.25 mm		Ast/db > 0.22(D/d)² f' _{ci} /f _{sy} <0.4 gamma k _u d	AS3600-2001 CI 8.1.4.1 AS3600-2001 CI 8.1.3 AS3600-2001 CI 8.1.2.2 (b)
TOP REINFORCEMENT BENDING Ultimate design bending moment Effective depth d	29.35 159	kNm mm	wl2/10	
f _{sv} gamma bst	500 50 0.696 480 1000	MPa MPa mm²/m	Humeslab panel strength	AS3600-2001 CI 8.1.2.2 (b)
Mu	36.72	kNm		

			Appendix B	
bhi Mu An An	29.38 0.00202	kNm	phi M _u ≥ M*	
Set Dd 22 (D/d)² f' _{ci} /f _{sy} u	0.00267 0.00267 5.65	ш Ш	Ast/db> 0.22(D/d)² f' _{c/} /f _{sy} <0.4 gamma k _u d	AS3600-2001 CI 8.1.4.1 AS3600-2001 CI 8.1.3 AS3600-2001 CI 8.1.2.2 (b)
SHEAR Jltimate Shear Force at support V _s * / _{uc} Jltimate Shear Force of void V _v *	28.13 127.53 89.27 26.19	Z Z Z Z X X X X	1.15 wl/ ² B ₁ B ₂ B ₃ b ₄ d ₆ (A _{st} f' ₆ /b ₄ d ₆). ³³³ phi V _{uc} \geq V s 1.15 wl/ ²	AS3600-2001 CI 8.2.7.1
ې ره hi V _{uc}	296 56.62 39.63	E Z Z	$B_1B_2B_3b_vd_o(A_{st} f'_o/b_v d_o)^{.333}$ phi $V_{uc} \ge V_v^*$	AS3600-2001 CI 8.2.7.1
DEFLECTION _{ee} /d ₅₃ k₄ ((delta/l _{er}) E _c /F _{d.er})0.333	37.74 39.05		L _{el} /d <k<sub>3 k₄ ((delta/l_{el}) E_c/F_{d.el})0.333</k<sub>	AS3600-2001 CI 9.3.4.1
CRACK CONTROL dueri dueri	6.12 5.52	kPa kPa	G + 1xQ G + Xs x Q	AS3600-2001 CI 9.4.1(a)
A* s.1 bottom A* ser bottom h.uncr Acrit	20.04 18.07 97.38 5.52E+08 17.43 M* _{s.1} > Mcrit	kNm kNm mm ⁴ kNm so critical tens	wl2/11 wl2/11 bD3/12 3 Ig/(D/2) ile zone	AS3600-2001 CI 9.4.1(a)
<i>A</i> ax bar spacing Actual bar spacing	200 200		EGU CONTRACTOR OF THE	AS3600-2001 CI 9.4.1(b) III
A* 1 top A*ser top dcrit	22.04 19.88 5.72E+08 $M^{s,1}$ > Mcrit Assuming wi tiled floor fini wider cracks	kNm kNm mm ⁴ kNm so critical tens der cracks can shes. (If carpe could be toler	wl2/10 wl2/10 bD3/12 3 I _g /(D/2) ile zone 1 not be tolerated, for example with ted floor or timber floating floor, then ated)	AS3600-2001 CI 9.4.1(a)

HumeslabTM Precast Flooring System

			Appendix B	
A _{st.min} Max bar spacing Max steel stress E _c h d _n f _{scr} Max steel stress f _{fscr}	570 300 300 28600 6.99 6.48E+07 6.48E+07 4.44E+08 5.8 3.00 3.43E+08 8.3 8.3 8.3	MPa MPa MPa MPa MPa MPa MPa MPa MPa MPa	$\begin{array}{c} 3 k_{s}A_{cr}/f_{s} \\ E_{s}/E_{c} \\ 0.5 b d_{n}^{2}=nA_{st} (d-d_{n}) \\ 0.33 b d_{n}^{3}+n A_{st} (d-d_{n})^{2} \\ l_{cr} + (l_{9} - l_{cr})(M_{sr}/M_{ser})^{3} \\ M y/l \\ \leq f_{scr} \\ l_{cr} + (l_{9} - l_{cr})(M_{cr}/M_{s.1})^{3} \\ M y/l \\ \leq f_{scr} \end{array}$	AS3600-2001 CI 9.4.1(b) ii AS3600-2001 CI 9.4.1(b) iii AS3600-2001 CI 9.4.1(b) Note 2 AS3600-2001 CI 9.4.4 (b) iv AS3600-2001 CI 9.4.4 (b) v
PROPPING DURING CONSTRUCTION From Table 5: Truss Type Voided Slab-Truss spacings Span between props	T110/0 320 3.1	E E	190 thick slab	
320 mm truss spacings selected to reduce pro reduce void width by 40 mm to 400 mm to aco REINFORCEMENT PANEL (BOTTOM REINFORCEMENT) Required from design	ppping of 6 m spa commodate the 8 449	n to a single pro trusses required mm²/m	op mid-span of the panel d for the 2500 wide panel Ultimate Bending	
Provided in Panel 8 T110/10 trusses over 2500 mm RF92 Total	181 287 468	mm²/m mm²/m mm²/m		
IN-SITU SLAB (TOP REINFORCEMENT OVE Required from design Provide N12-175 If wider cracks can be tolerated in the top of th	:R SUPPORTS) 570 628 ne slab, the reinfo	mm²/m mm²/m rcement could t	Flexural Crack Control Governs oe reduced to 480mm ² (N12-225)	

Transpan[™] HumeSlab[™] Design Software Output

Introduction The purpose of the following calculations is to determine the maximum simply supported double span for a HumeSlab panel given structural properties and construction loads.



The panel must comply with the stability, strength and service limit state criteria specified in AS3610-1995 Formwork for Concrete (Ref. [2]).

Stability The panel must resist overturning, uplift and sliding under the action of all the appropriate load combintions:

a) Overturning: In the case of a simply supported span overturning is not applicable

b) *Uplift*: The panel must resist forces from the appropriate load combination causing uplit Uplift is commonly cause by wind loads that are beyond the scope of this analysis and the fore uplift is not considered.

c) *Sliding*: The panel and its supports must resist forces from the appropriate load combination causing sliding.

AS3610 requires that formwork resist an applied horizontal live load of 1 kN/m plus the lat pressure of concrete.

Stage II - during placement of concrete.

$$1.5Q_{uh}^{C} + 1.5P^{C} < 0.8G^{R} + (fR)$$
⁽¹⁾

Strength The Panel must resist the bending and shear action effects from all the appropriate load combinations. In the case of a simply supported panel the following load combinations an appropriate:

Stage I – prior to placement of concrete.

1.25G + 1.5Q _{uv} + 1.5M ₁	(2)
--	-----

$$1.25G + 1.25G_{c} + 1.5Q_{UV} + 1.5M_{2} \tag{3}$$

$$1.25G + 1.25G_{c} + Q_{c}$$
 (4)

Stage III - after placement of concrete.

$$1.25G + 1.5G_{\rm C} + 1.5Q_{\rm UV} + 1.5M_3 \tag{5}$$

Stiffness The panel stiffness must be such that the deformation under the appropriate load combination does not exceed the limits specified in Ref. [2]. In the case of a simply supported panel the following load combinations are appropriate:

Stage II – during placement of concrete.	
G + G _c	(6)
Stage III – after placement of concrete.	
$G + G_c + M_3$	(7)

Surface Finish

sh The surface finish of the panel soffit conforms with the physical quality of a "Class 2" surface finish as specified in Ref. [2].

Panel Capacity The strength and stiffness of the panel is dependent on the truss, panel size and geometry. During construction the applied loads are resisted by the action of the truss members and panel concrete. The resistance provided by any mesh or additional reinforcement bars is ignored.

The following structural checks are performed:

Stability	a) Sliding b) Overturning
Strength	 a) Top Chord Tension b) Top Chord Tension c) Bottom Chord Compression d) Bottom Chord Tension e) Concrete Compression f) Diagonal Compression
Service	a) Deflection b) Cracking

The limit state resistance is calculated for each case.

Maximum Span The maximum span is selected on the basis that the design action, calculated from the factored load combinations, does not exceed the capacity of the panel.

A summary of the calculations showing the maximum span for each action is given in the table below:

Design	Max. Span
Action	(m)
Positive Bending	3.25
Negative Bending	3.20
Shear	14.18
Cracking	3.60
Deflection	3.54

The Maximum span for the given configuration is therefore:

Maximum Span	3.20	mm	

Stability The formwork assembly including the HumeSlab panel, falsework and connections are required to be designed to transfer the following limit state design load to anchorage or reaction points:

Limit State Sliding Load, H* 1.5

Stacked Materials

The maximum span is based on the live load for stacked materials, before and after placement of concrete, being limited to a maximum of 2.0 kPa.

This load must be clearly indicated in the formwork documentation and construction control put in place to ensure it is not exceeded.

kN/m

ored.

- **2** The value for stacked materials during Stage I (M_1) applies also to Stage III (M_3) and during Stage II the value for stacked materials (M_2) is 0 kPa.
- **3** The effects of form face deflection and construction tolerances can be ignored.
- **4** The deviations specified for surface undulation, in Ref[2], will be interpreted as the deflection criteria for the panel as per the following table:

Surface Quality Class	Surface Undulation Tolerance (mm)	Span/Defelection Ratio
2	3	500
3	5	300
4	8	188

- **5** The welds connecting the diagonal wires to the top and bottom chord of the truss are capable of transmitting the full design action effects.
- **6** Truss geometry is as per the following table:

Truss	Wire Size (mm)					
Туре	Тор	Bottom Diagonal Height				
T80/10	10	6.3	6.3	82		
T110/10	10	6.3	6.3	111		
T150/10	10	6.3	6.3	154		
T190/10	10	6.3	6.3	191		
T110/12	12.5	6.3	6.3	112		
T150/12	12.5	6.3	6.3	155		
T190/12	12.5	6.3	6.3	192		

Panel Properties			
	Overall Slab Thickness, d	190	mm
	Minimum Cover to Bottom Reinforcement	20	mm
	Concrete Density, r	2500	kg/m ³
	Concrete Strength at Loading, f cm	50	mPa
	Concrete Modulus of Elasticity, E cj	38007	mPa
	Panel Width, b	2500	mm
	Panel Thickness, t_{p}	55	mm
	Number of Truss per Panel, n_{t}	8	
	Number of Voids, n_V	4	
	Void Width, b _v	400	mm
	Void Thickness, t_{V}	75	mm
	Class of Surface Finish	2	
Construction Loads			
	Panel Dead Load, G	1.3	kPa
	Insitu Slab Dead Load, G _C	2.1	kPa
	Construction Live Load, Q _{uv}	1.0	kPa
	Concrete Mounding Load, Q _c	3.0	kPa
	Stacked Materials, <i>M</i> ₁	2.0	kPa
	Stacked Materials, M_2 Stacked Materials, M_3	0.0 2.0	kPa kPa

Load Combinations

Stage	Load Combination	Load	Unit	Equation
II	Stability 1.5 Q_{uh}^{C} + 1.5 P^{C} < 0.8 G^{R} + (ϕR)			(1)
 	Strength 1.25G + 1.5Q $_{\rm uv}$ +1.5 M_1^{**} 1.25G + 1.25G $_{\rm c}$ + 1.5 $Q_{\rm uv}$ +1.5 M_2^{**} 1.25G + 1.25G $_{\rm c}$ +Q $_{\rm c}^{*}$ 1.25G + 1.25G $_{\rm c}$ + 1.5 $Q_{\rm uv}$ +1.5 M_3^{**}	6.2 5.9 7.4 8.9	kPa kPa kPa kPa	(2) (3) (4) (5)
 	Stifness G + G _C G + G _C + M_3^{**}	3.5 5.5	kPa kPa	(6) (7)

(7) * Although AS3610 specifies that Q_c will apply over an area of 1.6 m x 1.6 m, it has been applied over the full area of the panel.

** - The loads from stacked materials (M) may apply to one span only.

Design Load

Therefore the design loads are as follows:

Strength, w*	8.9	kPa	
Service, w _s *	5.5	kPa	

Truss Properties				
	HumeSlab Truss Type, <i>T</i>	T110/10		
	Average Truss Spacing, T_{S}	312	mm	Ref.[1]
	Truss Height <i>, T_h</i>	111	mm	
	Truss Bar Yield Strength, <i>f_{syt}</i>	450	mPa	
Top Chord	Bar Diameter, d _t	10	mm	
	Area, A _t	628	mm ²	
	Strut Length, <i>L_t</i>	200	mm	
	Effective Length, It	180	mm	
	Radius of Gyration, r_t	3	mm	
	Slenderness Ratio, I_t / r_t	72		ОК
Diagona	Bar Diameter, d _W	6.3	mm	
	Area, A _W	499	mm ²	
	Angle of Web, <i>q</i>	48	degrees	
	Strut Length, <i>L_W</i>	149	mm	
	Effective Length, I _W	120	mm	
	Radius of Gyration, r_W	1.6	mm	
	Slenderness Ratio, I_W / r_W	76		ОК
Bottom Chord	Bar Diameter, d _b	6.3	mm	
	Area, A _b	499	mm ²	
	Strut Length, <i>L_b</i>	200	mm	
	Effective Length, <i>I_b</i>	180	mm	
	Radius of Gyration, r _b	1.6	mm	
	Slenderness Ratio, Ib /rb	114		ОК
Mesl	Mesh Size	F62		
Transformed	Wire Diameter, d _m Area, A _m	6.3 390	mm ²	
Section	For serviceability limit state the panel is analys	sed as an unc	cracked section	using the
	Transformed Area method to determine the s	tresses in the	steel and conc	rete.
	Steel Elastic Modulus, Es	200000	mPa	
	Concrete Elastic Modulus, E _{ci}	38007	mPa	
	Modular Ratio, <i>n</i>	5.3		
	Distance from Soffit to Top Chord	140	mm	
	Transformed Top Chord Area	3306	mm2	
	Distance from Soffit to Bottom Chord	29	mm	
	Transformed Bottom Chord Area	2625	mm	

Panel Concrete Area

Distance to the Neutral Axis, y_g

Second Moment of Inertia, I_g

137500

30.1

7.59E+07

mm

mm mm⁴

Capacity Calculations				
Top Chord Compression	In accordance with AS4100 – 1998 Steel S	structures (Re	ef.[3]), Clause 6.1	
	$N^* \leq$	$\phi \alpha_c N_s$		
	where ϕ	0.9		
	Section Jcapacity, $N_s = A_t f_{svt}$	283	kN	
	λ _n	96.6		
	α _a	17.6		
	α _b	-1.0		
	λ	79.0		
	η	0.2		
	ε	1.3		
	α_{c}	0.7		
	Limit State Capacity, $\phi \alpha_{C} N_{S}$	175.0	kN	
	Truss Height, <i>T_h</i>	111	mm	
	Limit State Moment Capacity, M^*_{tc}	19.4	kNm	
Top Chord Tension	In accordance with AS4100 – 1998 Steel Structures (Ref.[3]), Clause 7.1			
	$N^* \leq$	ф ^A g ^f у		
	where ϕ	0.9		
	Limit State Capacity, $\phi A_g f_y$	254.5	kN	
	Truss Height, <i>T_h</i>	111	mm	
Pottom Chard	Limit State Moment Capacity, M^*_{tt}	28.2	kNm	
Compression	In accordance with AS4100 – 1998 Steel S	Structures (Re	ef.[3]), Clause 6.1	
	$N^* \leq$	$\phi \alpha_c N_s$		
	where ϕ	0.9		
	Section Capacity, $N_s = A_b f_{syt}$	224.4	kN	
	λ _n	153.3		
	α _a	12.6		
	α _b	-1.0		
	λ	140.7		
	η	0.4		
	ε	0.8		
	α_{c}	0.3		
	Limit State Capacity, $\phi lpha_{C} N_{S}$	66.0	kN	
	Truss Height, T _h	111	mm	
	Limit State Moment Capacity, $M^*_{\ bc}$	7.3	kNm	

Bottom Chord Tension	In accordance with AS4100 – 1998 Steel S	Structures (Re	ef.[3]), Clause 7.1
	N^*	$\leq \phi A g^f y$	
	where ϕ	0.9	
	Limit State Capacity, $\phi A_g f_y$	202.0	kN
	Truss Height, <i>T_h</i>	111	mm
	Limit State Moment Capacity, $M^*{}_b$	22.4	kNm
Compression	The maximum concrete compressive force N^*	e is given by: $\leq 0.68 f_{cm} t_p$	b
	therefore		
	Limit State Capacity, N_{C}^{*}	4675.0	kN
	Truss Height <i>, T_h</i>	111	mm
_ . /	Limit State Moment Capacity, M^*_{PC}	518.9	kNm
Diagonai Compression	In accordance with AS4100 – 1998 Steel S	Structures (Re	ef.[3]), Clause 6.1
	N^*	$\leq \phi \alpha_c N_s$	
	where ø	0.9	
	Section Capacity, $N_s = A_b f_{syt}$	224.4	kN
	λ _n	101.8	
	α _a	17.1	
	α _b	-1.0	
	λ	84.7	
	η	0.2	
	3	1.2	
	α_{c}	0.6	
	Limit State Capacity, N*	130.8	kNm

Tensile Cracking AS3600, Ref[4] requires the maximum flexural stress in the concrete under short term service loads to be limited to

$$0.5\sqrt{f'_{c}}$$

The limit state service moment can be calculated from:

$$M^* = \frac{0.5\sqrt{f_{\rm cm} I_{\rm g}}}{y_{\rm g}}$$

therefore Limit State Service Moment Capacity, M*_C 8.9 kNm or AS3600 also provides an alternative of limiting the increment in steel stress to 150 mPa. Steel Stress 150 mPa mm² Area of Bottom Chord Steel, Ab 499 mm² Area of Mesh, Am 390 mm² Total Area of Steel 889 Equivalent Axial Force, N* kΝ 133.3 Truss Height, Th 111 mm Stability Check Limit State Service Moment Capacity, M*_C 14.8 kNm Sliding The force causing sliding must be transferred to an anchorage or reaction point on the permanent structure or foundation.

Limit state horizontal live load, Q _{uh}	1.0	kN/m
Limit state lateral concrete pressure, P	0.1	kN/m
Limit State horizontal design load, <i>H</i> *	1.5	kN/m

Span				
Calculations				
Positive Bending	The positive moment capacity of the panel	is given by th	ne following:	
	Top Chord Compression, M^*_{tC}	19.4	kNm	
	Bottom Chord Tension, M^*_{bt}	22.4	kNm	
	Design Moment, <i>M</i> *	19.4	kNm	
	-			
	The maximum span can be calculated from	n the following	g equation:	
	$S_{h=1}\sqrt{12M^*}$			
	^{-b} V wb			
	therefore			
	Positive Bending Maximum Span, S _b	3.25	m	
Negative Bending	The negative moment capacity of the pane	l is given by t	he following:	
	Top Chord Tension, ${\sf M^*_{tt}}$	28.2	kNm	
	Compression of Concrete Panel, M*pc	518.9	kNm	
	Bottom Chord Compression, M ⁻ bc	7.3	KNM	Ignored in this calculation
	Negative Bending Design Moment, M*	28.2	kNm	Calculation
	The maximum span can be calculated from	n the following	g equation:	
	$S_{b} = \sqrt{\frac{8M^{*}}{wb}}$			
	V W.5			
		0.00		
	Negative Bending Maximum Span, S b	3.20	m	
Shear	The shear capacity of the panel is governed	d by the com	pression of th	e truss diagonal
	The maximum span can be derived from th	ne followina e	quation:	
	The maximum span can be derived from the following equation:			

$$S_{v} = \left(\frac{2N*\sin\theta}{w_{s}b}\right)$$

therefore

Shear Maximum Span, S_V 14.18 m

Cracking The moment capacity of the panel is given by the following:

Flexural Cracking, M^{*} _C 14.8 kNm

The maximum span can be calculated from the following equation:

$$S_c = \sqrt{\frac{12M}{w_s b}}^*$$

therefore

Cracking Maximum Span, S_C 3.60 m

Deflection The maximum deflection of the panel can be calculated from the following equation:

$$\Delta = \frac{0.0074 w_s b S^4}{E_{ch} I_g}$$

To maintain the specified class the following Span/Deflection ratio must be achieved:

Span/Deflection Ratio, β 500

Therefore the maximum span can be calculated from:

$$S_{d} = \left(\frac{135E_{cj}I_g}{\beta w_s b}\right)$$

therefore

Deflection Maximum Span, S_d 3.54 m

References 1 Smorgon Steel Group, *Transfloor™ Technical Manual,* Smorgon Steel Group, Melbourne.

- **2** Standards Association of Australia, *AS3610-1995 Formwork for Concrete*, Standards Association of Australia, Sydney, 1995.
- **3** Standards Association of Australia, *AS4100-1998 Steel Structures*, Standards Association of Australia, Sydney, 1998.
- **4** Standards Association of Australia, *AS3600-1994 Concrete Structures*, Standards Association of Australia, Sydney, 1994.

Appendix D

HumeSlab™ Quotation Checklist

HumeSlab™	= \$ As quoted	per m²
Crane Hire	= \$	per m ²
Typically 10 panels can be placed per hour after the located	e crane is conven	iently
Propping See quotation for propping centres.	= \$	per m²
Labour Typically 2 men are required to place the above 10	= \$ panels/hr.	per m²
Topping concrete *See quotation for topping thickness estimate	= \$	per m²
Top steel See quotation for top steel mass estimate.	= \$	per m²
Labour for steel and concrete placement	= \$	per m²
Edge Boards	= \$	per m ²
Pumps, Buckets, etc	= \$	per m ²
Sealing the joint between the panel See Figure 30 for details.	= \$	per m²
Total Cost per m ²	= \$	per m ²
Total Area	= \$	m²
Total Cost	= \$	
	HumeSlab [™] Crane Hire Typically 10 panels can be placed per hour after the located Propping See quotation for propping centres. Labour Typically 2 men are required to place the above 10 Topping concrete *See quotation for topping thickness estimate Top steel See quotation for top steel mass estimate. Labour for steel and concrete placement Edge Boards Pumps, Buckets, etc Sealing the joint between the panel See Figure 30 for details. Total Cost per m ² Total Area Total Cost	HumeSlab TM

End of Report

Humes

National sales 1300 361 601 humes.com.au info@humes.com.au

A Division of Holcim Australia

This publication supersedes all previous literature on this subject. As the specifications and details contained in this publication may change please check with Humes Customer Service for confirmation of current issue. This publication provides general information only and is no substitute for professional engineering advice. No representations or warranty is made regarding the accuracy, completeness or relevance of the information provided. Users must make their own determination as to the suitability of this information and any Humes' product for their specific circumstances. Humes accepts no liability for any loss or damage resulting from any reliance on the information provided in this publication. Humes is a registered business name and registered trademark of Holcim (Australia) Pty Ltd (Holcim). HumeSlab is a registered trademark of Holcim. HumeSpan and "Strength. Performance. Passion." are trademarks of Holcim.

© February 2016 Holcim (Australia) Pty Ltd ABN 87 099 732 297. All rights reserved. This guide or any part of it may not be reproduced without prior written consent of Holcim.